AQA GCSE Physics | 8463

SPECIFICATION POINT 4.4.3.1

Background radiation

Mark schemes and examiner comments

Tier	**Higher**
Question groups	**18**
Available paper years	**2003–2023**

Using this booklet

1. Booklet answer numbers match the question booklet.
2. Use the original question number within marking tables.
3. Examiner comments are included where available.

Name: _____ **Date:** _____

Where a precise marking extract is unavailable, the full source document is included in an appendix. Any missing mark scheme is explicitly identified.

4.4.3.1 Background radiation

Answer 01 · Mark scheme June 2003 | 3451H | Original Q3 | Legacy

The full source mark scheme begins on page 30. Follow original question 3 in that document.

Answer 02 · Mark scheme June 2003 | 3462H3 | Original Q3 | Legacy

The full source mark scheme begins on page 52. Follow original question 3 in that document.

Answer 03 · Mark scheme June 2006 | 3451 | Original Q10 | Legacy

The full source mark scheme begins on page 69. Follow original question 10 in that document.

Answer 04 · Mark scheme June 2006 | 3462 | Original Q8 | Legacy

The full source mark scheme begins on page 89. Follow original question 8 in that document.

Answer 05 · Mark scheme November 2007 | PHY1B | Original Q3 | Legacy

Three	**1**	**1**	**4**	**1**

Answer 06 · Mark scheme June 2008 | PHY1BP | Original Q7 | Legacy

Seven	**2**	**2**	**3**	**3**

4.4.3.1 Background radiation

Answer 07 · Mark scheme June 2008 | PHY2H | Original Q2 | Legacy

Question 2

	answers	extra information	mark
(a)(i)	protons neutrons	answers may be in either order	1 1
(ii)	86		1
(iii)	two **fewer** protons and two **fewer** neutrons **or** 84 protons 134 neutrons	do **not** accept two fewer protons and neutrons do **not** accept 218 protons and neutrons	1
(b)(i)	0.4	accept $\frac{2}{5}$ / accept 40 % for 2 marks allow **1** mark for correct totalling = 1.8 allow **1** mark for a clearly correct method with a clearly incorrect total	2
(ii)	any **one** from: • nuclear weapon testing • nuclear power (stations) • nuclear accidents • medical	do **not** accept nuclear accept nuclear/ radioactive waste accept X-rays	1
(c)(i)	2	accept 2:1 accept twice as big ignore units	1

Question 2 continues on the next page

4.4.3.1 Background radiation

PHY2H

Question 2 continued

	answers	extra information	mark
(ii)	No with a reasonable reason explained only going for two weeks so **or** even staying for a year		1
	total exposure well under lowest limit for causing cancer **or**	**1** mark is for a time frame **1** mark is for correctly relating to a dose	1
	Yes with a reasonable reason explained all levels of radiation are (potentially) hazardous (1) harm caused by lower doses may not have been recorded (1) **or** evidence may not be complete **or** insufficient research into effect of small doses	accept low doses could still cause cancer accept all levels affect you do **not** accept radiation dose is high(er) do **not** accept level of background radiation is higher in Germany	
total			10

4.4.3.1 Background radiation

Answer 07 · Mark scheme June 2008 | PHY2H | Original Q2 | Legacy

PHY2H

Answer 08 · Mark scheme June 2009 | PHY1BP | Original Q7 | Legacy

Seven	**4**	**1**	**3**	**4**

4.4.3.1 Background radiation

Answer 09 · Mark scheme

Question 2

question	answers	extra information	mark
2(a)(i)	2.5		1
2(a)(ii)	The radiation dose from natural sources is much greater than from artificial sources.		1
2(b)(i)	other factors may be involved	accept a specific suggestion eg they may be exposed to other types of radiation accept cannot be sure (in many cases) that the cause of death is radon (poisoning)	1
2(b)(ii)	any **one** from: • different concentrations in different rooms • to average out daily fluctuations	accept to find an average accept to make the result (more) reliable / valid do **not** accept to make more accurate on its own	1
2(b)(iii)	average level (much) higher (in **C** and **D**) some homes have very high level (in **C** and **D**) **or** maximum level in some homes (in **C** and **D**) is very high	accept converse accept maximum level in **A** and **B** is low accept higher radiation levels (in **C** and **D**) for **1** mark	1 1
Total			**6**

4.4.3.1 Background radiation

Answer 09 · Mark scheme June 2010 | PHY2H | Original Q2 | Legacy

PHY2H

4.4.3.1 Background radiation

Answer 10 · Mark scheme

Question 3

question	answers	extra information	mark
3(a)(i)	any **one** from: • food / drink • rocks / building materials • cosmic rays / rays from space	accept correctly named example	1
3(a)(ii)	any **one** from: • nuclear power / coal power (stations) • nuclear accidents • nuclear weapons testing	accept nuclear waste accept named accident eg Chernobyl accept named medical procedure which involves a radioactive source accept radiotherapy nuclear activity / radiation is insufficient do **not** accept CT scans	1
3(a)(iii)	different number of / fewer protons **or** different atomic number	accept does not have 86 protons accept only has 84 protons do **not** accept bottom number different reference to mass number negates this mark	1

Question 3 continues on the next page . . .

PHY2H

Question 3 continued . . .

question	answers	extra information	mark
3(b)	168	accept 169 if clear, correct method is shown allow **1** mark for a correct dose ratio involving the spine eg 2:140 etc **or** ratio of days to dose is 1.2 **or** ratio of dose to days is 0.83	2
3(c)(i)	<table><tr><th>Group A</th><th>Group B</th></tr><tr><td>J M O</td><td>K L N</td></tr></table>	all correct any order within each group	1
3(c)(ii)	similar (number) / same (number) / large (number)	accept the same specific number in each group eg three reference to other factors such as age is neutral	1
3(c)(iii)	how many people in each group developed cancer	a clear comparison is required	1

Question 3 continues on the next page . . .

4.4.3.1 Background radiation

PHY2H

Question 3 continued . . .

question	answers	extra information	mark
3(c)(iv)	**Yes** the benefit of having the scan is greater than the risk **or** the risk is (very) small (compared to the chance from natural causes) **No** no additional risk is acceptable	there are no marks for **Yes** or **No** the mark is for the reason accept the risk is much greater from natural causes	1
Total			**9**

4.4.3.1 Background radiation

Answer 10 · Mark scheme January 2011 | PHY2H | Original Q3 | Legacy

PHY2H

4.4.3.1 Background radiation

Answer 11 · Mark scheme

June 2012 | PH1HP | Original Q8 | Legacy

Question 8

question	answers	extra information	mark
8(a)	any **three** from: • red-shift shows galaxies are moving away (from each other / the Earth) • more distant galaxies show bigger red-shift **or** more distant galaxies show a greater increase in wavelength • (in all directions) more distant galaxies are moving away faster • suggests single point of origin (of the universe)	accept correct reference to frequency in place of wavelength accept (suggests) universe is expanding	3
8(b)(i)	(radiation produced shortly after) 'Big Bang'	accept beginning of time / beginning of the universe for 'Big Bang'	1
8(b)(ii)	any **one** from: • can only be explained by 'Big Bang' • existence predicted by 'Big Bang' • provides (further) evidence for 'Big Bang'	ignore proves 'Big Bang' (theory) ignore reference to red-shift	1

Question 8 continues on the next page

4.4.3.1 Background radiation

Answer 11 · Mark scheme

PH1HP

Question 8 continued

question	answers	extra information	mark
8(b)(iii)	increase universe continues to accelerate outwards **or** greater red-shift	accept becomes radio waves accept as universe continues to expand	1 1
Total			**7**

UMS Conversion Calculator www.aqa.org.uk/umsconversion

4.4.3.1 Background radiation

Answer 12 · Mark scheme

June 2012 | PH2HP | Original Q2 | Legacy

Question 2

question	answers	extra information	mark
2(a)(i)	1.25 (mSv)		1
2(a)(ii)	any **two** from: • (frequent) flying • living at altitude • living in areas with high radon concentrations • living in a building made from granite (blocks) • having more than the average number of X-rays or having a CT scan • working in a nuclear power station	accept stated occupation that involves flying accept a specific area, eg Cornwall accept more medical treatments accept any suggestion that could reasonably increase the level from a specific source	2
2(b)(i)	to be able to see the effect of exposure (to radon gas) **or** as a control	accept to compare (the effect of) exposure (with no exposure)	1
2(b)(ii)	increased levels of exposure increases the risk (of developing cancer) smoking increases the (harmful) effect of radon	accept exposure (to radon gas) increases the risk answers that simply reproduce statistics are insufficient	1 1
2(c)	LNT model – risk increases with increasing radiation (dose) level Radiation hormesis – low radiation (dose) levels reduce the risk	accept in (direct) proportion accept low doses increase the risk	1 1

Question 2 continues on the next page . . .

4.4.3.1 Background radiation

PH2HP

Question 2 continued

question	answers	extra information	mark
2(d)	two valid points made – examples: • animals have no choice and so should not be used • should not make animals suffer • better to experiment on animals than humans • experiments lead to a better understanding / new knowledge • experiments may lead to health improvement / cures for humans	results for animals may not apply to humans is insufficient	2
Total			**10**

4.4.3.1 Background radiation

Answer 12 · Mark scheme

June 2012 | PH2HP | Original Q2 | Legacy

PH2HP

4.4.3.1 Background radiation

Answer 13 · Mark scheme

January 2013 | PH2HP | Original Q2 | Legacy

Question 2

question	answers	extra information	mark
2(a)(i)	any **one** from: • nuclear power (stations) • nuclear weapons (testing) • nuclear accidents	accept nuclear waste accept coal power stations accept nuclear bombs / fallout accept named accident, eg Chernobyl or Fukushima accept named medical procedure which involves a radioactive source accept radiotherapy accept X-rays accept specific industrial examples that involve a radioactive source nuclear activity / radiation is insufficient smoke detectors is insufficient	1
2(a)(ii)	(radioactive decay) is a random process	accept an answer in terms of background / radiation varies (from one point in time to another)	1
2(b)	any **one** from: • (maybe) other factors involved • evidence may not be valid • may not have (a complete) understanding of the process (involved)	accept a named 'sensible' factor, eg smoking accept not enough data	1

Question 2 continues on the next page . . .

4.4.3.1 Background radiation

PH2HP

Question 2 continued . . .

question	answers	extra information	mark
2(c)(i)	2 2		1 1
2(c)(ii)	218 84	correct order only	1 1
2(d)	3.8 (days)	allow **1** mark for showing correct method using the graph provided no subsequent steps correct answers obtained using numbers other than 800 and 400 gain **2** marks provided the method is shown	2
Total			**9**

4.4.3.1 Background radiation

Answer 13 · Mark scheme

January 2013 | PH2HP | Original Q2 | Legacy

PH2HP

4.4.3.1 Background radiation

Answer 14 · Mark scheme

June 2013 | PH1HP | Original Q8 | Legacy

Question 8

question	answers	extra information	mark
8(a)(i)	origin of the Universe	accept (why) the Universe is expanding do **not** accept origin of the Earth	1
8(a)(ii)	provided more evidence to support the 'Big Bang' theory		1
8(b)(i)	red-shift	accept Doppler (shift)	1
8(b)(ii)	(at the point in time shown the observed spectrum from) star A (shows it) is moving away from the Earth light from star B shows a decrease in wavelength so star B is moving towards Earth	accept star A is moving away star A shows red-shift is insufficient accept light from star B shows blue-shift accept light from star B shows an increase in frequency	1 1 1
Total			**6**

UMS Conversion Calculator: www.aqa.org.uk/umsconversion

4.4.3.1 Background radiation

Answer 15 · Mark scheme June 2017 | PH2HP | Original Q2 | Legacy

Question	Answers	Extra information	Mark	AO / Spec. Ref.
2(a)(i)	15 (%)	accept an answer of 0.15 for both marks allow **1** mark for (total radiation dose =) 2 (.00)	2	AO2 2.5.2b
2(a)(ii)	any one from: • living at altitude • pilot or aircrew • mountaineer • (very frequent) flyer	accept any answer that involves living or working at a height above sea level spending more time outdoors is insufficient ignore references to ozone layer	1	AO2 2.5
2(a)(iii)	any one from: • nuclear power (stations) • nuclear weapons (testing) • nuclear accidents • X rays or CT scan	accept nuclear/radioactive waste accept nuclear bombs/fallout accept named accident eg Chernobyl or Fukushima accept radiotherapy or medical treatments involving radioactive sources nuclear activity/radiation is insufficient smoke detectors is insufficient industrial tracers is insufficient	1	AO1 2.5.2b
2(b)	(radioactive decay) is a random process	accept an answer in terms of background/radiation varies (from one point in time to another) readings taken in different locations is insufficient	1	AO1 2.5.2a

4.4.3.1 Background radiation

Answer 15 · Mark scheme

2(c)(i)	**ROUTE A** as thickness increases the count (in one minute) decreases **or** the count (in one minute) falls to background (because) beta radiation is absorbed by the aluminium **ROUTE B** it cannot be alpha because that would be stopped by aluminium (1) it cannot be gamma as that would not be reduced by aluminium (1)	Award highest score from **either** Route A or Route B accept count rate or reading for count (in one minute) accept (because) beta is stopped by aluminium	1 1	AO3 2.5.2e
2(c)(ii)	replace the aluminium with paper/card **or** remove the aluminium and increase the distance (between source and GM tube) will decrease the count (in one minute)	do not accept thin gold foil for paper second mark point is dependent on scoring the first mark point accept count rate or reading for counts (in one minute)	1 1	AO3 2.5.2e
Total			**9**	

4.4.3.1 Background radiation

Answer 15 · Mark scheme

June 2017 | PH2HP | Original Q2 | Legacy



4.4.3.1 Background radiation

Answer 16 · Mark scheme June 2018 | 8463/1H | Original Q2

Question	Answers	Extra information	Mark	AO/ Spec. Ref
02.1	count rate = $\frac{819}{60}$ count rate = 13.65 corrected count rate = 13.35 (per second)	an answer of 13.35 (per second) scores **3** marks an answer of 13.95 (per second) scores **2** marks an answer of 801 (per second) scores **2** marks allow an answer of background = 0.30 × 60 = 18 (per minute) corrected count rate = 819 – 18 corrected count rate = 801 per minute	1 1 1	AO2 4.4.2.1 4.4.3.1
02.2	activity = 1250 × 180 activity = 225 000 (Bq)	an answer of 225 000 (Bq) scores **2** marks	1 1	AO2 4.4.2.1
02.3	yearly dose = 0.003 × 365 which is << 100 (mSv) **or** (well) below the lowest dose with evidence of causing cancer / harm	allow yearly dose = 1.095 (mSv)	1 1	AO3 4.4.3.1

4.4.3.1 Background radiation

Answer 16 · Mark scheme

June 2018 | 8463/1H | Original Q2

Question	Answers	Extra information	Mark	AO/ Spec. Ref
02.4	people are able to compare a radiation risk / dose / hazard to the radiation dose from (eating) bananas		1	AO3 4.4.2.4
Total			**8**	

4.4.3.1 Background radiation

Answer 17 · Mark scheme

November 2020 | 8463/1H | Original Q5

Question 5

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.1	Any **one** from: • (medical) x-rays • radiotherapy • nuclear weapons (testing) • named nuclear disaster eg Chernobyl / Fukushima / Three Mile Island.	allow CT scans allow nuclear fallout ignore radioactive / nuclear waste	1	AO1 4.4.3.1
05.2	uranium / plutonium	ignore any number given allow thorium	1	AO1 4.4.4.1
05.3	neutron absorbed by a uranium nucleus nucleus splits into two parts and (2 / 3) neutrons (are released) and gamma rays (are emitted)	allow an atom splits into two parts if 1st marking point doesn't score	1 1 1 1	AO1 4.4.4.1
05.4	lighter nuclei join to form heavier nuclei some of the mass (of the nuclei) is converted to energy (of radiation)	allow specific examples	1 1	AO1 4.4.4.2
05.5	activity decreases quickly risk of harm decreases quickly	allow nuclei / waste will decay at a greater rate ignore waste is radioactive for less time allow burial site doesn't need to be monitored for as long **or** doesn't need to be buried underground for as long **or** may not need to be buried underground	1 1	AO3 4.4.2.3
Total			**10**	

4.4.3.1 Background radiation

Answer 18 · Mark scheme

June 2023 | 8463/1H | Original Q5

Question 5

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.1	Similarities: • same number of protons **or** same atomic number • same number of electrons Difference: • different number of neutrons **or** different mass number	 allow both atoms / nuclei contain 6 protons allow carbon-12 has 6 neutrons **and** carbon-14 has 8 neutrons	 1 1 1	AO1 4.4.1.1

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.2	the time it takes for the number of nuclei (in a radioactive sample) to halve (is 5700 years) **or** the time it takes for the activity (of a radioactive sample) to halve (is 5700 years) **or** the time it takes for the radiation emitted (by a radioactive sample) to halve (is 5700 years) **or** the time it takes for the count rate (of a radioactive sample) to halve (is 5700 years) **or** the time it takes for the mass of carbon-14 (in a sample) to halve (is 5700 years)	allow atoms for nuclei ignore radioactivity	1	AO1 4.4.2.3

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.3	2 half-lives 128.74 (s)	 allow 129 (s)	1 1	AO2 4.4.2.3

4.4.3.1 Background radiation

Answer 18 · Mark scheme June 2023 | 8463/1H | Original Q5

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.4	nitrogen-18		1	AO3 4.4.2.1
	greatest activity	MP2 and MP3 dependent on scoring MP1 allow emits most radiation per second allow emits most radiation in a given time period ignore shortest half-life	1	4.4.3.3
	(so) greatest dose of radiation absorbed (per second)		1	

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.5	irradiation is the exposure of an object / person to radiation	allow 'absorption of radiation' for 'exposure' allow specific examples of ionising radiation	1	AO1 4.4.2.4
	(while) contamination is the (unwanted) presence of radioactive material / atoms on an object / person	allow 'inside a person' for 'on an object / person'	1	

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.6	any **one** from: • cancer / tumours • DNA / genetic mutation • damages / kills cells • radiation poisoning / sickness / burns	ignore mutates cells ignore death	1	AO3 4.4.3.3

4.4.3.1 Background radiation

Answer 18 · Mark scheme

June 2023 | 8463/1H | Original Q5

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.7	some radioactive materials emit alpha radiation which has a (very) short range (in air)	 MP2 dependent on scoring MP1 allow weakly penetrating for short range (in air)	1 1	AO3 4.4.2.1

Question	Answers	Extra information	Mark	AO / Spec. Ref.
05.8	pilot's dose in 24 hours = 0.072 (mSv) number of days = $\frac{0.072}{0.00050}$ number of days = 144 OR nuclear power worker hourly dose = 0.0000208… (mSv) (1) number of days = $\frac{0.0030}{0.0000208}$ (1) number of days = 144 (1) OR $\frac{\text{hourly dose}}{\text{daily dose}} = \frac{0.0030}{0.00050} = 6$ (1) number of days = 6 × 24 (1) number of days = 144 (1)		1 1 1	AO2 4.4.3.1

Total Question 5	17

4.4.3.1 Background radiation

AQA
ASSESSMENT and QUALIFICATIONS ALLIANCE

Mark scheme June 2003

GCSE

Physics

3451

Foundation

Copyright © 2003 AQA and its licensors. All rights reserved.

The Assessment and Qualifications Alliance (AQA) is a company limited by guarantee registered in England and Wales 3644723 and a registered charity number 1073334
Registered address: Addleshaw Booth & Co., Sovereign House, PO Box 8, Sovereign Street, Leeds LS1 1HQ
Kathleen Tattersall: *Director General*

4.4.3.1 Background radiation

INFORMATION FOR EXAMINERS

1. General

The mark scheme for each question shows:

- the marks available for each part of the question;
- the total marks available for the question;
- the typical answer or answers which are expected;
- extra information to help the Examiner make his or her judgement and help to delineate what is acceptable or not worthy of credit or, in discursive answers, to give an overview of the area in which a mark or marks may be awarded.

The extra information is aligned to the appropriate answer in the left-hand part of the mark scheme and should only be applied to that item in the mark scheme.

At the beginning of a part of a question a reminder may be given, for example:
where consequential marking needs to be considered in a calculation;
or the answer may be on the diagram or at a different place on the script.

In general the right hand side of the mark scheme is there to provide those extra details which confuse the main part of the mark scheme yet may be helpful in ensuring that marking is straightforward and consistent.

2. Emboldening

2.1 In a list of acceptable answers where more than one mark is available 'any **two** from' is used, with the number of marks emboldened. Each of the following lines is a potential mark.

2.2 A bold **and** is used to indicate that both parts of the answer are required to award the mark.

2.3 Alternative answers acceptable for a mark are indicated by the use of **or**. (Different terms in the mark scheme are shown by a / ; e.g. allow smooth / free movement.)

3. Marking points

3.1 Marking of Quality of Written Communication

Examiners are reminded of the need to assess QoWC by the following statement appearing in the appropriate parts of the mark scheme:

The answer to this question requires ideas in good English in a sensible order with correct use of scientific terms. Quality of written communication should be considered in crediting points in the mark scheme.

The maximum marks available to a candidate whose answer is not well expressed will be (the number of marks available –1).

4.4.3.1 Background radiation

3.2 Marking of lists

This applies to questions requiring a set number of responses, but for which candidates have provided extra responses. The general principle to be followed in such a situation is that 'right + wrong = wrong'.

Each error/contradiction negates each correct response. So, if the number of error/contradictions equals or exceeds the number of marks available for the question, no marks can be awarded.

However, responses considered to be neutral (indicated as * in example 1) are not penalised.

Example 1: What is the pH of an acidic solution? (1 mark)

Candidate	Response	Marks awarded
1	4,8	0
2	green, 5	0
3	red*, 5	1
4	red*, 8	0

Example 2: Name two planets in the solar system. (2 marks)

Candidate	Response	Marks awarded
1	Pluto, Mars, Moon	1
2	Pluto, Sun, Mars, Moon	0

3.3 Use of chemical symbols/formulae

If a candidate writes a chemical symbol/formula instead of a required chemical name, full credit can be given if the symbol/formula is correct and if, in the context of the question, such action is appropriate.

3.4 The marking of quantitative relationships

Full credit can be given for a correct quantitative relationship expressed in:

- named units;
- physical quantities;
- standard symbols;
- a combination of physical quantities and units.

No credit can be given for any quantitative relationship expressed in terms of:

- a combination of physical quantities, units and symbols;
- a diagram, e.g. the ohm's law triangle, unless the rest of the answer shows clearly that the candidate understands the relationships involved.

3.5 Marking procedure for calculations

3.5.1 Full marks can be given for a correct numerical answer, as shown in the column 'answers', without any working shown. However, if the answer is incorrect, mark(s) can be gained by correct substitution/working and this is shown in the 'extra information' column.

4.4.3.1 Background radiation

3.5.2 Where calculations are based on incorrectly recalled relationships, neither the incorrectly recalled relationship, nor the resulting calculation based on the incorrect relationship, will be credited.

3.6 Interpretation of 'it'

Answers using the word 'it' should be given credit only if it is clear that the 'it' refers to the correct subject.

3.7 Errors carried forward

There should be no error carried forward from a previous answer which has been based on wrong science. Any error in the answers to a structured question should be penalised once only.

Examples

(a) A candidate who calculates average speed using speed = time/distance **and** then proceeds to use this incorrect answer to calculate an acceleration based on the correct quantitative relationship should be given credit for the use of the correct acceleration relationship but none for either numerical answer.

(b) A candidate who incorrectly calculates average speed using speed = distance/time and then proceeds to use this incorrect value to calculate an acceleration based on the correct quantitative relationship, should be given credit for the use of both correct quantitative relationships **and** for the correct substitution and use of the incorrect value in the calculation of the rate of acceleration.

Papers should be constructed in such a way that the number of times errors can be carried forward are kept to a minimum. Allowances for errors carried forward are most likely to be restricted to calculation questions and should be shown by the abbreviation e.c.f. in the marking scheme.

3.8 Phonetic spelling

The phonetic spelling of correct scientific terminology should be credited **unless** there is a possible confusion with another technical term.

3.9 Brackets

(…..) is used to indicate information which is not essential for the mark to be awarded but is included to help the examiner identify the sense of the answer required.

3.10 Unexpected Correct Answers not in the Mark Scheme

The Examiner should use professional judgement to award credit where a candidate has given an unexpected correct answer which is not covered by the mark scheme. The Examiner should consult with the Team Leader to confirm the judgement. The Team Leader should pass this answer on to the Principal Examiner with a view to informing all examiners.

4.4.3.1 Background radiation

3451/F Q1

question	answers	extra information	mark
(a)	circuit symbol for a lamp correct 	accept  accept any standard of drawing providing circuit would work	1
	circuit symbol for a cell correct 		1
	2 lamps drawn in parallel with 3 cells	polarity of cells must be correct (+ to –) but cells may be either way around	1
(b)	4.5		1
(c)	the same as	accept any clear indication of the correct answer	1
total			5

4.4.3.1 Background radiation

3451/F Q2

question	answers	extra information	mark
(a)	gas		1
(b)	fuel burning stations produce electricity at any time / all the time	accept fuel available all the time	1
	wind generator can only produce when the wind is strong enough	accept it's not always windy	1
(c)	no fuel is burnt **or** no fuel is used **or** uses only energy from wind **or** does not emit harmful gases / soot / smoke	do **not** accept wind is natural / environmentally friendly / renewable answer must be in terms of wind, **not** negative of fuel burning specific examples of gases CO_2, SO_2, acid rain and greenhouse gases can be accepted ozone negates credit	1
total			4

4.4.3.1 Background radiation

3451/F Q3

question	answers	extra information	mark
(a)(i)	microwaves		1
(ii)	infra red		1
(iii)	ultrasonic		1
(b)(i)	B		1
(ii)	A		1
(c)	disturbance / vibration / movement direction	accept motion / force do **not** accept energy	1 1
(d)	sound wave	accept any clear indication of the correct answer	1
total			8

4.4.3.1 Background radiation

3451/F Q4

question	answers	extra information	mark
(a)(i)	heat		1
(ii)	temperature increases **or** (cause) convection (currents)	accept gets warmer accept gets hotter	1
(iii)	60% **or** 0.6	60 without % scores **1** mark 0.6 with a unit scores **1** mark 60 with incorrect unit scores **1** mark **or** correct substitution $\frac{120}{200}$ for **1** mark	2
(b)	street more (energy transferred as) light **or** less (energy transferred as) heat **or** useful energy output the highest	 can only score this mark if first mark scored all efficiencies calculated correctly score 2nd mark point	1 1
total			6

4.4.3.1 Background radiation

3451/F Q5

question	answers	extra information	mark
(a)	MN	accept 5.8, 8 seconds must include unit	1
(b)	LM	accept 0.8, 5.8 seconds must include unit	1
(c)(i)	0.8		1
(ii)	drinking alcohol		1
(d)	straight (by eye) line starting at 0.8 seconds line drawn steeper than LM starting before L	 ignore lines going beyond 2 seconds but line must exceed 2.5 metres per second before terminating	1 1
total			6

4.4.3.1 Background radiation

3451/F Q6

question	answers	extra information	mark
(a)(i)	each correct label scores 1 mark  		3
(ii)	neutron		1
(iii)	7 number of protons and neutrons **or** number of nucleons **or** number of particles in the nucleus	 accept number of particles in the centre only if first answer = 7	1 1
(b)(i)	50 ± 5		1
(ii)	50 ± 5	accept their (b)(i)	1
(iii)	less	accept any way of indicating the correct answer	1
total			9

4.4.3.1 Background radiation

3451/F Q7

question	answers	extra information	mark
(a)	each correct line scores 1 mark  	if more than 3 lines are drawn mark incorrect ones first, to a maximum of 3 lines	3
(b)	toaster	accept 1.2 kW	1
(c)(i)	400		1
(ii)	£24 **or** 2400p	full credit for their (c)(i) × 6p for full credit the correct numerical answer must have the correct unit an answer of 24 or 2400 with no unit or the incorrect unit scores **1** mark (c)(i) × 6 incorrectly evaluated scores **1** mark	2
(d)	6	allow 6000 for **1** mark allow 3 × 2 for **1** mark	2
total			9

4.4.3.1 Background radiation

3451/F Q8

question	answers	extra information	mark
(a)(i)	point where the rays cross	do not credit if ambiguous	1
(ii)	converging (lens)	do **not** accept convex	1
(b)(i)	point where the rays appear to diverge from	this should appear to be within 10mm in front of the back of the arrows on the approximate centre line need not be accurately constructed using a ruler	1
(ii)	diverging (lens)	do **not** accept concave	1
(c)	converging film smaller than nearer to	accept any clear indication of the correct response e.g. ticking, ringing, writing in after a mistake	1 1 1 1
(d)(i)	(image) bigger than object / enlarge	accept just 'made bigger'	1
(ii)	it / real image can be put on a screen **or** real image on the opposite side of the lens to the object	accept 'not an imaginary or virtual image' assume 'it' refers to a real image do **not** credit 'it can be seen'	1
(e)	**either** (the converging lens is) thick in the middle thin(ner) at the edge **or** (both) sides bend outwards (1) in the middle (1) **or** one side bends in the middle (1) more than the other side bends inwards (in the middle) (1)	thickest in the middle gains **2** marks convex gains **2** marks suitable diagrams gains **2** marks	1 1
total			12

4.4.3.1 Background radiation

3451/F Q9

question	answers	extra information	mark
(a)(i)	off off on	all correct	1
(ii)	AND (gate)	accept and (gate)	1
(iii)	on on on	all correct	1
(iv)	OR (gate)	accept or (gate)	1
(b)(i)	1 0 **or** 0 1 0 1 1 0	do **not** credit on / off responses	1
(ii)		accept mirror image accept  accept with either or both parts shaded accept line through as shading	1
(c)		accept off for 0 and on for 1 throughout	
	0 0	both correct	1
	0 1	both correct	1
	1 1	both correct	1
	1 1	both correct	1

4.4.3.1 Background radiation

3451/F Q9 continued

(d)(i)		accept mirror image **or** inverted do **not** credit  **or**  or similar	1
(ii)	resistance decreases / increases / changes current (through it) increases / decreases / changes **or** temperature changes / increases / decreases (1) resistance changes / decreases / increases (1) (NTC thermistor) both marks independent but must be compatible to score **2** marks accept 'voltage across it decreases' for **2** marks but only if it is made clear that this refers to a thermistor in series		1 1
total			13

4.4.3.1 Background radiation

3451/F Q10

question	answers	extra information	mark
(a)(i)	friction	accept any way of indicating the correct answer	1
(ii)	gravity	accept any way of indicating the correct answer	1
(b)(i)	accelerates **or** speed / velocity increases	accept faster and faster (**1** mark) do **not** accept faster pace / falls faster or suggestions of a greater but constant speed	1
	downwards / falls	accept towards the Earth / ground this may score in part (b)(ii) if it does not score here and there is no contradiction between the two parts	1
(ii)	constant speed / velocity **or** terminal velocity / speed **or** zero acceleration	stays in the same place negates credit	1
total			5

4.4.3.1 Background radiation

3451/F Q11

question	answers	extra information	mark
(a)(i)	X – mantle		1
	Y – inner core	do **not** accept solid core	1
(ii)	different to the crust **or** contains a lot of (heavy) metals	accept iron and nickel for metals	1
	higher (average) density **or** denser	density higher than 5500 (kg/m^3) gets **2** marks	1
(b)	animals were able to move from one continent to the other		1
	(when bridge broke) animals evolved differently	accept animals adapted differently	1
(c)(i)	earthquakes occur at the boundary between plates **or** earthquakes occur where plates push against each other		1
	there are no plate boundaries running through Britain	accept Britain is not near the edge of a plate	1
(ii)	convection currents (in the mantle) **or** heat released by (natural) radioactive processes		1
total			9

4.4.3.1 Background radiation

3451/F Q12

question	answers	extra information	mark
(a)(i)	outside the Earth **or** not from the Earth	accept alien accept life from / on another planet / space accept our planet for Earth	1
(ii)	radio telescope(s)	do **not** accept telescopes do **not** accept satellite dishes do **not** accept radio receivers **or** transmitters	1
(b)(i)	galaxies	do **not** accept stars	1
(ii)	any **one** from: the pulses were regular pulses from space are usually random (scientists) thought technology had been used to produce the pulses neutron stars were unknown signals from a single point	 accept signals / beats for pulses accept noise for random pulses idea of regular but not continuous	1
(iii)	neutron star is (the matter / mass) left behind after a star / red giant explodes (as a super nova)	 accept after a super nova (explosion) neutron star causing super nova gets no credit	1 1
(c)(i)	carried on the balloon / equipment	accept carried by a rocket / aircraft / satellite birds negates credit	1
(ii)	on comets or meteors	accept meteorites / shooting stars accept returning space craft accept solar wind ignore asteroids accept ufo do **not** accept solar flares do **not** accept satellites	1
total			8

4.4.3.1 Background radiation

3451/F Q13

question	answers	extra information	mark
(a)	silver is a (good) reflector of <u>heat</u> (radiation) **or** silver reflects the heat (radiation)	fact heat = infra red ignore references to light accept shiny for silver good radiator negates the mark ignore references to good conductor do **not** accept bounce back	1
	less heat is lost through the board **or** more heat is retained by the shirt	explanation accept both sides of shirt heated reflects heat back up gets **1** mark only ignore mention of friction	1
(b)	metal soleplate	accept soleplate / bottom / metal do **not** accept outside / case	1
(c)	plastic **or** rubber	accept any named plastic do **not** accept wood	1
	it is a (good) insulator **or** it is a poor conductor	ignore mention of heat if in conjunction with electricity	1
(d)	**Quality of written communication** *The answer to this question requires ideas in good English in a sensible order with correct use of scientific terms. Quality of written communication should be considered in crediting points in the mark scheme.*	*Maximum of **2** marks if ideas not well expressed.*	
	pulls iron bolt down **or** attracts the iron bolt **or** moves bolt out of plunger	answers in terms of charges attracting or repelling gain no credit	1
	plunger pushed / moved to the right (by spring) **or** plunger released		1
	push switch opens / goes to off / goes to right	accept circuit is broken for maximum credit the points must follow a logical sequence 3 correct points but incorrect sequence scores **2** marks only ignore reset action	1
total			8

4.4.3.1 Background radiation

3451/F Q14

question	answers	extra information	mark
(a)(i)	any **one** from: the ground the air radon (gas) building materials buildings rocks / granite food cosmic rays **or** solar rays X-rays nuclear weapons testing nuclear power stations / accidents	 do **not** accept mobile phones accept from outer space accept sun but **not** sunlight accept medical uses	1
(ii)	2	allow $\frac{1200}{60\times10}$ **or** $\frac{1200}{600}$ **or** 120 for **1** mark	2
(b)	 alpha: the count rate is (greatly) reduced by the card **or** the card absorbs alphas but not betas beta: the count rate is (greatly) reduced by the metal **or** the thin metal absorbs alphas and betas **or** the thin metal absorbs all of the radiation (from the source) gamma: would pass through the thin metal but count rate is background **or** no radiation passing through **or** a higher reading would be recorded **or** to reduce the count to 2 would require much more than 3 mm of metal	answers must be comparative accept converse answers throughout accept paper for the card accept aluminium for the metal accept aluminium for the metal accept lead / aluminium for the metal	 1 1 1
total			6

4.4.3.1 Background radiation

3451/F Q15

question	answers	extra information	mark
(a)(i)	weight = mass × g.f.s.	accept w = m × g accept gravity for gfs accept  provided subsequent use of Δ correct do **not** accept N = kg × N/kg	1
(ii)	675	75 × 9 for **1** mark	2
(iii)	g.(f.s.) is higher (on Earth than Venus)	accept gravity for g.f.s. do **not** accept g.f.s. is lower unless answer states on Venus	1
(iv)	orbit time for Jupiter is <u>longer</u> / longest (than for the other planets)	do **not** give any credit for an answer that includes a comparison of diameter **or** a comparison of g.f.s.	1
(b)	**Quality of written communication** *The answer to this question requires ideas in good English in a sensible order with correct use of scientific terms. Quality of written communication should be considered in crediting points in the mark scheme.* any **two** from: dust <u>and</u> gas **or** remnants of a super nova pulled together by (force of) <u>gravity</u> nuclear fusion starts	*Maximum of **1** mark if ideas not well expressed.* accept hydrogen for dust and gas do **not** accept hydrogen burns although candidates may include more detail these points are essential to score the credit	2
total			7

4.4.3.1 Background radiation

3451/F Q16

question	answers	extra information	mark
(a)(i)	upright with the contacts at the bottom and still in place and unbent	no need for labels but incorrect label(s) cancel the mark accept a freehand drawing no need for details such as correct dimensions	1
	one blob of mercury touching <u>both</u> contacts	do **not** award mark if contacts bent to touch	1
(b)(i)	(X is a) battery	do **not** credit cell accept (set of) cells accept power supply do **not** accept power pack	1
	(Y is a) LED	**or** light emitting diode	1
(ii)	longer (time)	do **not** accept 'slower time'	1
(iii)	any **two** from: current less (so) rate of flow of charge less **or** less coulombs per second (so) discharge is slower	 do **not** accept current slower accept capacitor has charge for longer **or** charge lasts longer **or** (so total of) electrons take longer to travel round circuit	2
(c)	4200	 translation correct (= 4000) but percentage addition incorrect gains **1** mark translation incorrect but 5% addition is correct gains **1** mark accept 422.1 **or** 42.2 **or** 6.3 for **1** mark	2
	ohms **or** Ω	 4.2 kilohms **or** 4.2 kΩ gains all **3** marks	1
total			10

4.4.3.1 Background radiation

3451/F Q17

question	answers	extra information	mark
(a)	point at which its mass (seems to) act **or** point at which gravity (seems to) act	accept …its weight acts accept correct statements if the intent is clear e.g. … if suspended, the centre of gravity will be directly under the point of suspension e.g. … (if the object is symmetrical), the centre of gravity is on the **or** an axis (of symmetry) do **not** credit just 'it is a point'	1
(b)	**Quality of written communication** *The answer to this question requires good English in a sensible order with correct use of scientific terms. Quality of written communication should be considered in crediting points in the mark scheme.* any **five** from: clamp (steel) rod (horizontally) hang plastic / sheet by rod through (one) hole hang plumb line from rod mark ends of plumb line on the sheet and use the ruler to draw a straight line repeat with other hole centre of mass is where the lines cross check by balancing at this point	*maximum of **4** marks if ideas not well expressed* **no** marks if method quite unworkable maximum of **3** marks if no 'repeat with other hole'	5
(c)(i)	(turning) effect **or** moment force distance	all three correct accept weight accept length	1
(ii)	17.6 Nm **or** newton metre(s)	allow 44 × 0.4 **or** 0.4 × 44 for **1** mark do **not** accept N/m **or** N/cm 1760 Ncm gains all **3** marks	2 1
total			10

4.4.3.1 Background radiation

ASSESSMENT and QUALIFICATIONS ALLIANCE

Mark scheme June 2003

GCSE

Science: Double Award Co-ordinated

3462

Paper 3F

Copyright © 2003 AQA and its licensors. All rights reserved.

The Assessment and Qualifications Alliance (AQA) is a company limited by guarantee registered in England and Wales 3644723 and a registered charity number 1073334
Registered address: Addleshaw Booth & Co., Sovereign House, PO Box 8, Sovereign Street, Leeds LS1 1HQ
Kathleen Tattersall: *Director General*

4.4.3.1 Background radiation

INFORMATION FOR EXAMINERS

1. General

The mark scheme for each question shows:

- the marks available for each part of the question;
- the total marks available for the question;
- the typical answer or answers which are expected;
- extra information to help the Examiner make his or her judgement and help to delineate what is acceptable or not worthy of credit or, in discursive answers, to give an overview of the area in which a mark or marks may be awarded.

The extra information is aligned to the appropriate answer in the left-hand part of the mark scheme and should only be applied to that item in the mark scheme.

At the beginning of a part of a question a reminder may be given, for example:
where consequential marking needs to be considered in a calculation;
or the answer may be on the diagram or at a different place on the script.

In general the right hand side of the mark scheme is there to provide those extra details which confuse the main part of the mark scheme yet may be helpful in ensuring that marking is straightforward and consistent.

2. Emboldening

2.1 In a list of acceptable answers where more than one mark is available 'any **two** from' is used, with the number of marks emboldened. Each of the following lines is a potential mark.

2.2 A bold **and** is used to indicate that both parts of the answer are required to award the mark.

2.3 Alternative answers acceptable for a mark are indicated by the use of **or**. (Different terms in the mark scheme are shown by a / ; e.g. allow smooth / free movement.)

3. Marking points

3.1 Marking of Quality of Written Communication

Examiners are reminded of the need to assess QoWC by the following statement appearing in the appropriate parts of the mark scheme:

The answer to this question requires ideas in good English in a sensible order with correct use of scientific terms. Quality of written communication should be considered in crediting points in the mark scheme.

The maximum marks available to a candidate whose answer is not well expressed will be (the number of marks available –1).

4.4.3.1 Background radiation

3.2 Marking of lists

This applies to questions requiring a set number of responses, but for which candidates have provided extra responses. The general principle to be followed in such a situation is that 'right + wrong = wrong'.

Each error/contradiction negates each correct response. So, if the number of error/contradictions equals or exceeds the number of marks available for the question, no marks can be awarded.

However, responses considered to be neutral (indicated as * in example 1) are not penalised.

Example 1: What is the pH of an acidic solution? (1 mark)

Candidate	Response	Marks awarded
1	4,8	0
2	green, 5	0
3	red*, 5	1
4	red*, 8	0

Example 2: Name two planets in the solar system. (2 marks)

Candidate	Response	Marks awarded
1	Pluto, Mars, Moon	1
2	Pluto, Sun, Mars, Moon	0

3.3 Use of chemical symbols/formulae

If a candidate writes a chemical symbol/formula instead of a required chemical name, full credit can be given if the symbol/formula is correct and if, in the context of the question, such action is appropriate.

3.4 The marking of quantitative relationships

Full credit can be given for a correct quantitative relationship expressed in:

- named units;
- physical quantities;
- standard symbols;
- a combination of physical quantities and units.

No credit can be given for any quantitative relationship expressed in terms of:

- a combination of physical quantities, units and symbols;
- a diagram, e.g. the ohm's law triangle, unless the rest of the answer shows clearly that the candidate understands the relationships involved.

3.5 Marking procedure for calculations

3.5.1 Full marks can be given for a correct numerical answer, as shown in the column 'answers', without any working shown. However, if the answer is incorrect, mark(s) can be gained by correct substitution/working and this is shown in the 'extra information' column.

4.4.3.1 Background radiation

3.5.2 Where calculations are based on incorrectly recalled relationships, neither the incorrectly recalled relationship, nor the resulting calculation based on the incorrect relationship, will be credited.

3.6 Interpretation of 'it'

Answers using the word 'it' should be given credit only if it is clear that the 'it' refers to the correct subject.

3.7 Errors carried forward

There should be no error carried forward from a previous answer which has been based on wrong science. Any error in the answers to a structured question should be penalised once only.

Examples

(a) A candidate who calculates average speed using speed = time/distance **and** then proceeds to use this incorrect answer to calculate an acceleration based on the correct quantitative relationship should be given credit for the use of the correct acceleration relationship but none for either numerical answer.

(b) A candidate who incorrectly calculates average speed using speed = distance/time and then proceeds to use this incorrect value to calculate an acceleration based on the correct quantitative relationship, should be given credit for the use of both correct quantitative relationships **and** for the correct substitution and use of the incorrect value in the calculation of the rate of acceleration.

Papers should be constructed in such a way that the number of times errors can be carried forward are kept to a minimum. Allowances for errors carried forward are most likely to be restricted to calculation questions and should be shown by the abbreviation e.c.f. in the marking scheme.

3.8 Phonetic spelling

The phonetic spelling of correct scientific terminology should be credited **unless** there is a possible confusion with another technical term.

3.9 Brackets

(…..) is used to indicate information which is not essential for the mark to be awarded but is included to help the examiner identify the sense of the answer required.

3.10 Unexpected Correct Answers not in the Mark Scheme

The Examiner should use professional judgement to award credit where a candidate has given an unexpected correct answer which is not covered by the mark scheme. The Examiner should consult with the Team Leader to confirm the judgement. The Team Leader should pass this answer on to the Principal Examiner with a view to informing all examiners.

4.4.3.1 Background radiation

Double Award
Foundation Tier 3462/3F

3462/3F Q1

question	answers	extra information	mark
(a)	circuit symbol for a lamp correct 	accept  accept any standard of drawing providing circuit would work	1
	circuit symbol for a cell correct 		1
	2 lamps drawn in parallel with 3 cells	polarity of cells must be correct (+ to –) but cells may be either way around	1
(b)	4.5		1
(c)	the same as	accept any clear indication of the correct answer	1
total			5

4.4.3.1 Background radiation

3462/3F Q2

question	answers	extra information	mark
(a)	gas		1
(b)	fuel burning stations produce electricity at any time / all the time	accept fuel available all the time	1
	wind generator can only produce when the wind is strong enough	accept it's not always windy	1
(c)	no fuel is burnt **or** no fuel is used **or** uses only energy from wind **or** does not emit harmful gases / soot / smoke	do **not** accept wind is natural / environmentally friendly / renewable answer must be in terms of wind, **not** negative of fuel burning specific examples of gases CO_2, SO_2, acid rain and greenhouse gases can be accepted ozone negates credit	1
total			4

4.4.3.1 Background radiation

3462/3F Q3

question	answers	extra information	mark
(a)(i)	microwaves		1
(ii)	infra red		1
(iii)	ultrasonic		1
(b)(i)	B		1
(ii)	A		1
(c)	disturbance / vibration / movement direction	accept motion / force do **not** accept energy	1 1
(d)	sound wave	accept any clear indication of the correct answer	1
total			8

4.4.3.1 Background radiation

3462/3F Q4

question	answers	extra information	mark
(a)(i)	heat		1
(ii)	temperature increases **or** (cause) convection (currents)	accept gets warmer accept gets hotter	1
(iii)	60% **or** 0.6	60 without % scores **1** mark 0.6 with a unit scores **1** mark 60 with incorrect unit scores **1** mark **or** correct substitution $\frac{120}{200}$ for **1** mark	2
(b)	street more (energy transferred as) light **or** less (energy transferred as) heat **or** useful energy output the highest	 can only score this mark if first mark scored all efficiencies calculated correctly score 2nd mark point	1 1
total			6

4.4.3.1 Background radiation

3462/3F Q5

question	answers	extra information	mark
(a)	MN	accept 5.8, 8 seconds must include unit	1
(b)	LM	accept 0.8, 5.8 seconds must include unit	1
(c)(i)	0.8		1
(ii)	drinking alcohol		1
(d)	straight (by eye) line starting at 0.8 seconds line drawn steeper than LM starting before L	 ignore lines going beyond 2 seconds but line must exceed 2.5 metres per second before terminating	1 1
total			6

4.4.3.1 Background radiation

3462/3F Q6

question	answers	extra information	mark
(a)(i)	each correct label scores 1 mark  		3
(ii)	neutron		1
(iii)	7 number of protons and neutrons **or** number of nucleons **or** number of particles in the nucleus	 accept number of particles in the centre only if first answer = 7	1 1
(b)(i)	50 ± 5		1
(ii)	50 ± 5	accept their (b)(i)	1
(iii)	less	accept any way of indicating the correct answer	1
total			9

4.4.3.1 Background radiation

3462/3F Q7

question	answers	extra information	mark
(a)	each correct line scores 1 mark  	if more than 3 lines are drawn mark incorrect ones first, to a maximum of 3 lines	3
(b)	toaster	accept 1.2 kW	1
(c)(i)	400		1
(ii)	£24 **or** 2400p	full credit for their (c)(i) × 6p for full credit the correct numerical answer must have the correct unit an answer of 24 or 2400 with no unit or the incorrect unit scores **1** mark (c)(i) × 6 incorrectly evaluated scores **1** mark	2
(d)	6	allow 6000 for **1** mark allow 3 × 2 for **1** mark	2
total			9

4.4.3.1 Background radiation

3462/3F Q8

question	answers	extra information	mark
(a)(i)	friction	accept any way of indicating the correct answer	1
(ii)	gravity	accept any way of indicating the correct answer	1
(b)(i)	accelerates **or** speed / velocity increases	accept faster and faster (**1** mark) do **not** accept faster pace / falls faster or suggestions of a greater but constant speed	1
	downwards / falls	accept towards the Earth / ground this may score in part (b)(ii) if it does not score here and there is no contradiction between the two parts	1
(ii)	constant speed / velocity **or** terminal velocity / speed **or** zero acceleration	stays in the same place negates credit	1
total			5

4.4.3.1 Background radiation

3462/3F Q9

question	answers	extra information	mark
(a)(i)	X – mantle		1
	Y – inner core	do **not** accept solid core	1
(ii)	different to the crust **or** contains a lot of (heavy) metals	accept iron and nickel for metals	1
	higher (average) density **or** denser	density higher than 5500 (kg/m^3) gets **2** marks	1
(b)	animals were able to move from one continent to the other		1
	(when bridge broke) animals evolved differently	accept animals adapted differently	1
(c)(i)	earthquakes occur at the boundary between plates **or** earthquakes occur where plates push against each other		1
	there are no plate boundaries running through Britain	accept Britain is not near the edge of a plate	1
(ii)	convection currents (in the mantle) **or** heat released by (natural) radioactive processes		1
total			9

4.4.3.1 Background radiation

3462/3F Q10

question	answers	extra information	mark
(a)(i)	outside the Earth **or** not from the Earth	accept alien accept life from / on another planet / space accept our planet for Earth	1
(ii)	radio telescope(s)	do **not** accept telescopes do **not** accept satellite dishes do **not** accept radio receivers **or** transmitters	1
(b)(i)	galaxies	do **not** accept stars	1
(ii)	any **one** from: the pulses were regular pulses from space are usually random (scientists) thought technology had been used to produce the pulses neutron stars were unknown signals from a single point	 accept signals / beats for pulses accept noise for random pulses idea of regular but not continuous	1
(iii)	neutron star is (the matter / mass) left behind after a star / red giant explodes (as a super nova)	 accept after a super nova (explosion) neutron star causing super nova gets no credit	1 1
(c)(i)	carried on the balloon / equipment	accept carried by a rocket / aircraft / satellite birds negates credit	1
(ii)	on comets or meteors	accept meteorites / shooting stars accept returning space craft accept solar wind ignore asteroids accept ufo do **not** accept solar flares do **not** accept satellites	1
total			8

4.4.3.1 Background radiation

3462/3F Q11

question	answers	extra information	mark
(a)	silver is a (good) reflector of heat (radiation) **or** silver reflects the heat (radiation)	fact heat = infra red ignore references to light accept shiny for silver good radiator negates the mark ignore references to good conductor do **not** accept bounce back	1
	less heat is lost through the board **or** more heat is retained by the shirt	explanation accept both sides of shirt heated reflects heat back up gets **1** mark only ignore mention of friction	1
(b)	metal soleplate	accept soleplate / bottom / metal do **not** accept outside / case	1
(c)	plastic **or** rubber	accept any named plastic do **not** accept wood	1
	it is a (good) insulator **or** it is a poor conductor	ignore mention of heat if in conjunction with electricity	1
(d)	**Quality of written communication** *The answer to this question requires ideas in good English in a sensible order with correct use of scientific terms. Quality of written communication should be considered in crediting points in the mark scheme.*	*Maximum of **2** marks if ideas not well expressed.*	
	pulls iron bolt down **or** attracts the iron bolt **or** moves bolt out of plunger	answers in terms of charges attracting or repelling gain no credit	1
	plunger pushed / moved to the right (by spring) **or** plunger released		1
	push switch opens / goes to off / goes to right	accept circuit is broken for maximum credit the points must follow a logical sequence 3 correct points but incorrect sequence scores **2** marks only ignore reset action	1
total			8

4.4.3.1 Background radiation

3462/3F Q12

question	answers	extra information	mark
(a)(i)	any **one** from: the ground the air radon (gas) building materials buildings rocks / granite food cosmic rays **or** solar rays X-rays nuclear weapons testing nuclear power stations / accidents	 do **not** accept mobile phones accept from outer space accept sun but **not** sunlight accept medical uses	1
(ii)	2	allow $\frac{1200}{60\times10}$ **or** $\frac{1200}{600}$ **or** 120 for **1** mark	2
(b)	 alpha: the count rate is (greatly) reduced by the card **or** the card absorbs alphas but not betas beta: the count rate is (greatly) reduced by the metal **or** the thin metal absorbs alphas and betas **or** the thin metal absorbs all of the radiation (from the source) gamma: would pass through the thin metal but count rate is background **or** no radiation passing through **or** a higher reading would be recorded **or** to reduce the count to 2 would require much more than 3 mm of metal	answers must be comparative accept converse answers throughout accept paper for the card accept aluminium for the metal accept aluminium for the metal accept lead / aluminium for the metal	 1 1 1
total			6

4.4.3.1 Background radiation

3462/3F Q13

question	answers	extra information	mark
(a)(i)	weight = mass × g.f.s.	accept w = m × g accept gravity for gfs accept  provided subsequent use of Δ correct do **not** accept N = kg × N/kg	1
(ii)	675	75 × 9 for **1** mark	2
(iii)	g.(f.s.) is higher (on Earth than Venus)	accept gravity for g.f.s. do **not** accept g.f.s. is lower unless answer states on Venus	1
(iv)	orbit time for Jupiter is <u>longer</u> / longest (than for the other planets)	do **not** give any credit for an answer that includes a comparison of diameter **or** a comparison of g.f.s.	1
(b)	**Quality of written communication** *The answer to this question requires ideas in good English in a sensible order with correct use of scientific terms. Quality of written communication should be considered in crediting points in the mark scheme.* any **two** from: dust <u>and</u> gas **or** remnants of a super nova pulled together by (force of) <u>gravity</u> nuclear fusion starts	*Maximum of **1** mark if ideas not well expressed.* accept hydrogen for dust and gas do **not** accept hydrogen burns although candidates may include more detail these points are essential to score the credit	2
total			7

Version 1.0: 0906

ASSESSMENT and QUALIFICATIONS ALLIANCE

General Certificate of Secondary Education

Physics 3451/F
Specification B

Mark Scheme

2006 examination - June series

Mark schemes are prepared by the Principal Examiner and considered, together with the relevant questions, by a panel of subject teachers. This mark scheme includes any amendments made at the standardisation meeting attended by all examiners and is the scheme which was used by them in this examination. The standardisation meeting ensures that the mark scheme covers the candidates' responses to questions and that every examiner understands and applies it in the same correct way. As preparation for the standardisation meeting each examiner analyses a number of candidates' scripts: alternative answers not already covered by the mark scheme are discussed at the meeting and legislated for. If, after this meeting, examiners encounter unusual answers which have not been discussed at the meeting they are required to refer these to the Principal Examiner.

It must be stressed that a mark scheme is a working document, in many cases further developed and expanded on the basis of candidates' reactions to a particular paper. Assumptions about future mark schemes on the basis of one year's document should be avoided; whilst the guiding principles of assessment remain constant, details will change, depending on the content of a particular examination paper.

Copyright © 2006 AQA and its licensors. All rights reserved.

4.4.3.1 Background radiation

Physics (Specification B)
Foundation Tier 3451/F

3451/F Q1

question	answers	extra information	mark
(a)	4 correct lines drawn  	**1** mark for each correct line if more than 4 lines are drawn mark incorrect ones first. Mark only 4 lines	4
(b)	4		1
(c)(i)	nuclear		1
(ii)	(natural) gas	do **not** accept natural	1
total			7

4.4.3.1 Background radiation

3451/F Q2

question	answers	extra information	mark
(a)(i)	ultra violet		1
(ii)	kill the cells	accept destroys the cells accept makes cells cancerous accept damage cells accept harms cells accept changes DNA accept cause cells to mutate accept skin cells for cells accept cause cancer do **not** accept skin for cells do **not** accept burns the cells	1
(b)(i)	the sunbed uses an alternating current (a.c.) supply		1
(ii)	10.8	accept **1** mark for correct substitution of power in W or kW and time in hours or seconds	2
total			5

4.4.3.1 Background radiation

3451/F Q3

question	answers	extra information	mark
(a)(i)	M		1
(ii)	K		1
(iii)	J		1
(iv)	O		1
(b)(i)	billions of years		1
(ii)	red giant	any answer in terms of explosion or supernova is **incorrect**	1
	contracts / shrinks to	incorrect reference to black hole negates **1** mark	1
	white dwarf		1
total			8

4.4.3.1 Background radiation

3451/F Q4

question	answers	extra information	mark
(a)(i)	A and C	**both** answers must be correct in either order	1
(ii)	A and B	**both** answers must be correct in either order	1
(iii)	same number of protons plus neutrons **or** same number of nucleons	accept number of particles in nucleus the same do **not** accept they add up to 6 unless qualified	1
(b)(i)	any **two** from: • boron - 12 • carbon - 14 • oxygen - 15 • lead - 209	**both** required both name **and** number must be given	1
(ii)	any **two** from: • boron - 11 • carbon - 12 • oxygen - 16 • lead - 207	**both** required both name **and** number must be given	1
(c)	alpha		1
total			6

4.4.3.1 Background radiation

3451/F Q5

question	answers	extra information	mark
(a)	(good) insulator	accept does not conduct (electricity) accept does not conduct heat or electricity do **not** accept does not conduct heat outside is tough is insufficient	1
(b)	fuse		1
(c)	connect the green and yellow / earth wire	accept wires must be connected to screws	1
	swap the brown and blue wires round		1
total			4

3451/F Q6

question	answers	extra information	mark
(a)	fossils	answers can be in either order	1
	water		1
(b)	increased		1
(c)	radio telescope		1
total			4

4.4.3.1 Background radiation

3451/F Q7

question	answers	extra information	mark
(a)(i)	electrical		1
	kinetic	accept movement	1
(ii)	heat	answers can be in either order	1
	sound		1
(b)(i)	360	accept **1** mark for correct substitution	2
(ii)	watt		1
(c)	the stairlift is not moving the stairlift is moving at constant speed	**both** answers are required for the mark	1
total			8

3451/F Q8

question	answers	extra information	mark
(a)(i)	(up) further **or** (up) faster	any reference to downwards movement loses credit accept <u>with</u> more force accept motion would increase	1
(ii)	down	accept the opposite way accept drop	1
(b)(i)	direct current		1
(ii)	Z		1
total			4

4.4.3.1 Background radiation

3451/F Q9

question	answers	extra information	mark
(a)	level of radiation (detected) will not change	ignore reference to particles	1
	if thickness of aluminium changes	accept for **both** marks a specific example eg if the aluminium gets thicker the level of radiation detected stays the same. accept for **1** mark gamma will pass through aluminium	1
	QoWC for 2 points in a sensible sequence		1
(b)	S W T V	all in correct order accept **2** marks for 2 correct accept **1** mark for 1 correct	3
total			6

4.4.3.1 Background radiation

3451/F Q10

<table>
<tr><th>question</th><th>answers</th><th>extra information</th><th>mark</th></tr>
<tr><td>(a)</td><td>thermistor(s)
LDR(s)
switch(es)
LED(s)
buzzer(s)
motor(s)</td><td>1 mark each
or light dependent resistor(s)
or light emitting diode(s)</td><td>6</td></tr>
<tr><td>(b)(i)</td><td><table><tr><th>1st input</th><th>2nd input</th><th>Output</th></tr><tr><td>0</td><td>0</td><td>0</td></tr><tr><td>1</td><td>0</td><td>0</td></tr><tr><td>0</td><td>1</td><td>0</td></tr><tr><td>1</td><td>1</td><td>1</td></tr></table></td><td>all correct</td><td>1</td></tr>
<tr><td>(ii)</td><td><table><tr><th>Input</th><th>Output</th></tr><tr><td>0</td><td>1</td></tr><tr><td>1</td><td>0</td></tr></table></td><td>both correct</td><td>1</td></tr>
<tr><td>(iii)</td><td><table><tr><th>1st input</th><th>2nd input</th><th>Output</th></tr><tr><td>0</td><td>0</td><td>0</td></tr><tr><td>1</td><td>0</td><td>1</td></tr><tr><td>0</td><td>1</td><td>1</td></tr><tr><td>1</td><td>1</td><td>1</td></tr></table></td><td>all correct</td><td>1</td></tr>
<tr><td>(c)(i)</td><td></td><td>do not credit any attempt which could equally well be a poorly drawn attempt at the symbol for a cell</td><td>1</td></tr>
<tr><td>(ii)</td><td>charge

increases</td><td>accept ‘electrons’
accept ‘energy
or gets bigger/larger</td><td>1

1</td></tr>
<tr><td>total</td><td></td><td></td><td>12</td></tr>
</table>

4.4.3.1 Background radiation

3451/F Q11

question	answers	extra information	mark
(a)(i)	A		1
(ii)	B		1
(iii)	mass is larger	credit if the response is clear by some other means e.g. it is ringed	1
	wire is shorter	credit if the response is clear by some other means e.g. it is ringed	1
(b)	moment		1
	distance		1
(c)(i)	1		1
(ii)	5		1
(iii)	any **two** from • remove slotted mass(es) • slide (slotted) masses / weights nearer pivot • slide forcemeter away from the pivot • slide rod to the left	 **or** ….. to the left **or** ….. to the right **or** …. so that the slotted masses side is shorter **or** …. so that the forcemeter side is longer	2
(d)	centre of the rectangle	accept *2*mm tolerance any direction	1
	centre of the circle	accept *2*mm tolerance any direction	1
	on centre line and 10mm above base	accept *2*mm tolerance any direction	1
total			13

4.4.3.1 Background radiation

3451/F Q12

question	answers	extra information	mark
(a)	0.05 (A)	ignore incorrect units if given accept 'the same' / 'the same as K' / 'the same as the other ammeter' do **not** accept 'same as the other meter'	1
(b)(i)	any **two** from: • two cells are joined + to +	answers in terms of current gain no marks accept one cell in the wrong way accept two cells are joined back-to-back accept two cells are joined – to – accept battery for cell do **not** accept answers in terms of all the cells or in terms of energy only	2
	• some of the cells potential difference is across the diode / ammeters / wires **or** the pd of the cells is shared by all components	accept voltage for pd do **not** accept using up pd	
	• the other components have a resistance	accept a named component / components / wire has a resistance	
	• cells not fully charged **or** cells partially run down	do **not** accept voltage of cells is less than 1.5 unless explained do **not** accept cells are not as powerful unless explained	
	• cells have an internal resistance		
(ii)	the diode has a (very) high resistance (in the reverse direction)		1
	a diode only conducts / allows current to flow in one direction	accept little / no current flows do **not** accept blocks / cuts flow	1

Continued

4.4.3.1 Background radiation

Physics B – AQA GCSE Mark Scheme, 2006 June series

3451/F Q12

question	answers	extra information	mark
(c)	**QoWC** for the use of the word resistance	annotate Q✓ Q✗ accept resistant	1
	accept increase / change / decrease throughout question but a contradiction loses **one** mark with change as neutral		
	as the pd / current increases / changes	accept voltage for pd must be correctly linked to at least one of the following points accept	1
	the temperature of the filament increases / changes	lamp / bulb for filament accept filament becomes hotter	1
	increasing / changing the **resistance** of the lamp		1
		accept for **1** mark only the filament lamp does not obey Ohm's law	
total			9

4.4.3.1 Background radiation

3451/F Q13

question	answers	extra information	mark
(a)	0.5		1
	hertz	accept Hz but **not** HZ / hz / hZ accept (waves) per second **or** / sec **or** / s **or** s^{-1} **or** sec^{-1}	1
(b)	any **one** from: • any named part of the electromagnetic spectrum • S – waves / secondary waves • wave on a rope	 do **not** accept seismic waves / earthquake do **not** accept slinky unless clearly described	1
(c)	transverse – disturbance / vibration is perpendicular to the direction of energy transfer / wave travel	accept a correctly labelled diagram	1
	longitudinal – disturbance / vibration is parallel to the direction of energy transfer / wave travel	accept a correctly labelled diagram part explanation of the difference between transverse **and** longitudinal gains **1** mark	1
(d)(i)	TIR shown	needs to stay inside water jet ignore number of reflections **or** arrow heads lines straight by eye	1
(ii)	bigger than	any indication of correct answer	1
total			7

4.4.3.1 Background radiation

3451/F Q14

question	answers	extra information	mark
(a)	W		1
	has only two states **or** is either on or off	accept discrete values only do **not** credit answer purely in terms of shape	1
(b)	any **one** from:		1
	• higher quality	accept clearer do **not** accept easier to read ignore faster accept <u>less</u> distortion **or** <u>less</u> weakening of signal strength do **not** accept no distortion / weakening on its own	
	• increased carrying capacity	accept more information can be sent **or** more channels	
	• errors can be rectified		
total			3

4.4.3.1 Background radiation

3451/F Q15

question	answers	extra information	mark
(a)(i)	all points plotted accurately	accept **1** mark for 5 correct plots ± ½ small square on stopping distance	2
	line of best fit must be continuous	accept attempt at a reasonable curve does not need to go through 0 0 do **not** accept a straight line do **not** accept dot-to-dot	1
(ii)	4 to 6 (metres)	accept ecf from (a)(i) accept **1** mark for value taken correctly from graph at 25mph **or** correct method shown	2
(b)(i)	0.7 (s)	incorrect unit = 0 marks	1
(ii)	constant speed / velocity	accept (continued as) 30mph accept did not change / stayed the same accept no acceleration	1
(iii)	3.3(s)	penalise incorrect unit once only	1
(iv)	reaction time <u>increases</u> / is <u>longer</u> **or** thinking distance <u>increases</u>	do **not** accept reaction time slower **or** reactions are slower	1
	stopping distance / it <u>increases</u>	do **not** accept travels at constant speed for longer	1
(c)(i)	work done = force (applied) × distance (moved)	accept W = F × s or W = F × d accept  provided subsequent method is correct	1

Continued

4.4.3.1 Background radiation

Physics B – AQA GCSE Mark Scheme, 2006 June series

3451/F Q15

question	answers	extra information	mark
(ii) **E**	2100	accept 2.1 kilo accept **1** mark for using 7000 N	2
(iii)	2100 (joules)	accept their (c)(ii)	1
total			14

4.4.3.1 Background radiation

3451/F Q16

question	answers	extra information	mark
(a)(i)	refraction		1
(ii)	it changes speed **or** change in density	accept it speeds up do **not** accept it slows down do **not** accept air is more dense than glass	1
(b)(i)	sound / waves <u>diffract</u> through the gap (in the wall) **or** over the wall **or** because the gate is open	do **not** accept reflection this only scores if first marking point is given accept for **1** mark only sound / waves go through the gap and <u>spread out</u> **or** diagram showing wave fronts spreading out from open gates if diagram is labelled as diffraction both marks can be scored	1 1
(ii)	less diffraction	accept no diffraction accept gates <u>absorb</u> sound / noise / waves accept gates <u>reflect</u> sound / noise / waves do **not** accept rebounds / stops / blocks out	1
total			5

4.4.3.1 Background radiation

3451/F Q17

question	answers	extra information	mark
(a)	both rays brought to a focus at F on the right	do **not** have to be continued beyond F	1
	lines have been drawn **accurately** with a ruler	only credit if 1st mark credited do **not** credit if contradictory arrow(s) added	1
(b)	rays seem to come from a focus at G on the left and continued to the right of the lens	this mark is for the current idea of divergence	1
	lines have been drawn **accurately** with a ruler	only credit if 1st mark credited do **not** credit if contradictory arrow(s) added	1
(c)	…lens… …image… …object… …image… ...object… …lens…	lens as 1st and 6th words (1) image and object in the correct order 2nd and 3rd words (1) image and object in correct order 4th and 5th words (1)	max 3
(d)(i)	correct statement about real image real rays intersect / cross to form a real image **or** a real image can be formed on a screen **or** real image is (always) on the opposite side (of the lens) **or** real image is (always) upside down (to the object)	may be credited from a correct diagram	1
	correct statement about virtual / imaginary image virtual / imaginary rays intersect / cross to form a virtual image **or** a virtual / imaginary image cannot **or** virtual / imaginary image is (always) on the same side (of the lens) **or** virtual / imaginary image is (always) same way up (as the object)	may be credited from a correct diagram	1

Continued

4.4.3.1 Background radiation

3451/F Q17

question	answers	extra information	mark
(ii)	**either** image needs to fall on / affect the film **or** image needs to fall on / affect the light sensors / charged coupled devices (CCDs) (in a digital camera / mobile phone) **or** image needs to cause a chemical reaction (in / on the film)		1
total			10

4.4.3.1 Background radiation

3451/F Q18

<table>
<tr><th>question</th><th>answers</th><th>extra information</th><th>mark</th></tr>
<tr><td>(a)</td><td>AND (gate)

OR (gate)

NOT (gate)

LED or light emitting diode</td><td>accept ‘and’

accept ‘or’

accept ‘not’ or invert gate

accept ‘led’</td><td>1

1

1

1</td></tr>
<tr><td>(b)(i)</td><td>NOT (gate) and AND (gate)</td><td>both in either order or ‘(the) gates’

any additions lose the mark</td><td>1</td></tr>
<tr><td>(ii)</td><td><table><tr><th>Switch for fire</th><th>Tilt switch</th><th>Signal to relay</th></tr><tr><td>0</td><td>0</td><td>…0…</td></tr><tr><td>0</td><td>1</td><td>…0…</td></tr><tr><td>1</td><td>0</td><td>…1…</td></tr><tr><td>1</td><td>1</td><td>…0…</td></tr></table></td><td>all correct

allow off or no
off no
on yes
off no</td><td>1</td></tr>
<tr><td>(iii)</td><td>(relay) acts as / is a switch

either
small current from the electronic / control circuit / system (1)

large current through the output / (electric) fire (1)

or

full current through electronic control system (1)

may damage components / lead to overheating / electric shock (1)

QoWC for correct use of the scientific term ‘current’</td><td>accept implication that it works as a switch e.g. ‘turns on fire’

or ‘small current through the coil (of the relay)’

do not accept small current is turned into a large current

annotate Q✓ Q×

if answer in terms of voltage isolation / voltage/ p.d. accept QoWC mark for correct use</td><td>1

1

1

1</td></tr>
<tr><td>total</td><td></td><td></td><td>10</td></tr>
</table>

Version 1.0: 0906

ASSESSMENT and QUALIFICATIONS ALLIANCE

General Certificate of Secondary Education

Science: Double Award 3462/3F
Specification B

Mark Scheme

2006 examination - June series

Mark schemes are prepared by the Principal Examiner and considered, together with the relevant questions, by a panel of subject teachers. This mark scheme includes any amendments made at the standardisation meeting attended by all examiners and is the scheme which was used by them in this examination. The standardisation meeting ensures that the mark scheme covers the candidates' responses to questions and that every examiner understands and applies it in the same correct way. As preparation for the standardisation meeting each examiner analyses a number of candidates' scripts: alternative answers not already covered by the mark scheme are discussed at the meeting and legislated for. If, after this meeting, examiners encounter unusual answers which have not been discussed at the meeting they are required to refer these to the Principal Examiner.

It must be stressed that a mark scheme is a working document, in many cases further developed and expanded on the basis of candidates' reactions to a particular paper. Assumptions about future mark schemes on the basis of one year's document should be avoided; whilst the guiding principles of assessment remain constant, details will change, depending on the content of a particular examination paper.

Copyright © 2006 AQA and its licensors. All rights reserved.

4.4.3.1 Background radiation

Science: Double Award (Co-ordinated) – AQA GCSE Mark Scheme, 2006 June series

Double Award (Co-ordinated)
Foundation Tier 3462/3F

3462/3F Q1

question	answers	extra information	mark
(a)	4 correct lines drawn  	**1** mark for each correct line if more than 4 lines are drawn mark incorrect ones first. Mark only 4 lines	4
(b)	4		1
(c)(i)	nuclear		1
(ii)	(natural) gas	do **not** accept natural	1
total			7

4.4.3.1 Background radiation

3462/3F Q2

question	answers	extra information	mark
(a)(i)	ultra violet		1
(ii)	kill the cells	accept destroys the cells accept makes cells cancerous accept damage cells accept harms cells accept changes DNA accept cause cells to mutate accept skin cells for cells accept cause cancer do **not** accept skin for cells do **not** accept burns the cells	1
(b)(i)	the sunbed uses an alternating current (a.c.) supply		1
(ii)	10.8	accept **1** mark for correct substitution of power in W or kW and time in hours or seconds	2
total			5

4.4.3.1 Background radiation

Science: Double Award (Co-ordinated) – AQA GCSE Mark Scheme, 2006 June series

3462/3F Q3

question	answers	extra information	mark
(a)(i)	M		1
(ii)	K		1
(iii)	J		1
(iv)	O		1
(b)(i)	billions of years		1
(ii)	red giant	any answer in terms of explosion or supernova is **incorrect**	1
	contracts / shrinks to	incorrect reference to black hole negates **1** mark	1
	white dwarf		1
total			8

4.4.3.1 Background radiation

3462/3F Q4

question	answers	extra information	mark
(a)(i)	A and C	**both** answers must be correct in either order	1
(ii)	A and B	**both** answers must be correct in either order	1
(iii)	same number of protons plus neutrons **or** same number of nucleons	accept number of particles in nucleus the same do **not** accept they add up to 6 unless qualified	1
(b)(i)	any **two** from: • boron - 12 • carbon - 14 • oxygen - 15 • lead - 209	**both** required both name **and** number must be given	1
(ii)	any **two** from: • boron - 11 • carbon - 12 • oxygen - 16 • lead - 207	**both** required both name **and** number must be given	1
(c)	alpha		1
total			6

4.4.3.1 Background radiation

Science: Double Award (Co-ordinated) – AQA GCSE Mark Scheme, 2006 June series

3462/3F Q5

question	answers	extra information	mark
(a)	(good) insulator	accept does not conduct (electricity) accept does not conduct heat or electricity do **not** accept does not conduct heat outside is tough is insufficient	1
(b)	fuse		1
(c)	connect the green and yellow / earth wire	accept wires must be connected to screws	1
	swap the brown and blue wires round		1
total			4

3462/3F Q6

question	answers	extra information	mark
(a)	fossils	answers can be in either order	1
	water		1
(b)	increased		1
(c)	radio telescope		1
total			4

4.4.3.1 Background radiation

3462/3F Q7

question	answers	extra information	mark
(a)(i)	electrical		1
	kinetic	accept movement	1
(ii)	heat	answers can be in either order	1
	sound		1
(b)(i)	360	accept **1** mark for correct substitution	2
(ii)	watt		1
(c)	the stairlift is not moving the stairlift is moving at constant speed	**both** answers are required for the mark	1
total			8

3462/3F Q8

question	answers	extra information	mark
(a)(i)	(up) further **or** (up) faster	any reference to downwards movement loses credit accept <u>with</u> more force accept motion would increase	1
(ii)	down	accept the opposite way accept drop	1
(b)(i)	direct current		1
(ii)	Z		1
total			4

4.4.3.1 Background radiation

Science: Double Award (Co-ordinated) – AQA GCSE Mark Scheme, 2006 June series

3462/3F Q9

question	answers	extra information	mark
(a)	level of radiation (detected) will not change	ignore reference to particles	1
	if thickness of aluminium changes	accept for **both** marks a specific example eg if the aluminium gets thicker the level of radiation detected stays the same. accept for **1** mark gamma will pass through aluminium	1
	QoWC for 2 points in a sensible sequence		1
(b)	S W T V	all in correct order accept **2** marks for 2 correct accept **1** mark for 1 correct	3
total			6

4.4.3.1 Background radiation

3462/3F Q10

question	answers	extra information	mark
(a)	0.05 (A)	ignore incorrect units if given accept 'the same' / 'the same as K' / 'the same as the other ammeter' do **not** accept 'same as the other meter'	1
(b)(i)	any **two** from: • two cells are joined + to +	answers in terms of current gain no marks accept one cell in the wrong way accept two cells are joined back-to-back accept two cells are joined – to – accept battery for cell do **not** accept answers in terms of all the cells or in terms of energy only	2
	• some of the cells potential difference is across the diode / ammeters / wires **or** the pd of the cells is shared by all components	accept voltage for pd do **not** accept using up pd	
	• the other components have a resistance	accept a named component / components / wire has a resistance	
	• cells not fully charged **or** cells partially run down	do **not** accept voltage of cells is less than 1.5 unless explained do **not** accept cells are not as powerful unless explained	
	• cells have an internal resistance		
(ii)	the diode has a (very) high resistance (in the reverse direction)		1
	a diode only conducts / allows current to flow in one direction	accept little / no current flows do **not** accept blocks / cuts flow	1

Continued

4.4.3.1 Background radiation

Science: Double Award (Co-ordinated) – AQA GCSE Mark Scheme, 2006 June series

3462/3F Q10

question	answers	extra information	mark
(c)	**QoWC** for the use of the word resistance	annotate Q✓ Q✗ accept resistant	1
	accept increase / change / decrease throughout question but a contradiction loses **one** mark with change as neutral		
	as the pd / current increases / changes	accept voltage for pd must be correctly linked to at least one of the following points accept	1
	the temperature of the filament increases / changes	lamp / bulb for filament accept filament becomes hotter	1
	increasing / changing the **resistance** of the lamp	accept for **1** mark only the filament lamp does not obey Ohm's law	1
total			9

4.4.3.1 Background radiation

3462/3F Q11

question	answers	extra information	mark
(a)	0.5		1
	hertz	accept Hz but **not** HZ / hz / hZ accept (waves) per second **or** / sec **or** / s **or** s^{-1} **or** sec^{-1}	1
(b)	any **one** from: • any named part of the electromagnetic spectrum • S – waves / secondary waves • wave on a rope	 do **not** accept seismic waves / earthquake do **not** accept slinky unless clearly described	1
(c)	transverse – disturbance / vibration is perpendicular to the direction of energy transfer / wave travel	accept a correctly labelled diagram	1
	longitudinal – disturbance / vibration is parallel to the direction of energy transfer / wave travel	accept a correctly labelled diagram part explanation of the difference between transverse **and** longitudinal gains **1** mark	1
(d)(i)	TIR shown	needs to stay inside water jet ignore number of reflections **or** arrow heads lines straight by eye	1
(ii)	bigger than	any indication of correct answer	1
total			7

4.4.3.1 Background radiation

Science: Double Award (Co-ordinated) – AQA GCSE Mark Scheme, 2006 June series

3462/3F Q12

question	answers	extra information	mark
(a)	W		1
	has only two states **or** is either on or off	accept discrete values only do **not** credit answer purely in terms of shape	1
(b)	any **one** from:		1
	• higher quality	accept clearer do **not** accept easier to read ignore faster accept <u>less</u> distortion **or** <u>less</u> weakening of signal strength do **not** accept no distortion / weakening on its own	
	• increased carrying capacity	accept more information can be sent **or** more channels	
	• errors can be rectified		
total			3

4.4.3.1 Background radiation

3462/3F Q13

question	answers	extra information	mark
(a)(i)	all points plotted accurately	accept **1** mark for 5 correct plots ± ½ small square on stopping distance	2
	line of best fit must be continuous	accept attempt at a reasonable curve does not need to go through 0 0 do **not** accept a straight line do **not** accept dot-to-dot	1
(ii)	4 to 6 (metres)	accept ecf from (a)(i) accept **1** mark for value taken correctly from graph at 25mph **or** correct method shown	2
(b)(i)	0.7 (s)	incorrect unit = 0 marks	1
(ii)	constant speed / velocity	accept (continued as) 30mph accept did not change / stayed the same accept no acceleration	1
(iii)	3.3(s)	penalise incorrect unit once only	1
(iv)	reaction time increases / is longer **or** thinking distance increases	do **not** accept reaction time slower **or** reactions are slower	1
	stopping distance / it increases	do **not** accept travels at constant speed for longer	1
(c)(i)	work done = force (applied) × distance (moved)	accept W = F × s or W = F × d accept  provided subsequent method is correct	1
(ii)	2100	accept 2.1 kilo accept **1** mark for using 7000 N	2
(iii)	2100 (joules)	accept their (c)(ii)	1
total			14

4.4.3.1 Background radiation

Science: Double Award (Co-ordinated) – AQA GCSE Mark Scheme, 2006 June series

3462/3F Q14

question	answers	extra information	mark
(a)(i)	refraction		1
(ii)	it changes speed **or** change in density	accept it speeds up do **not** accept it slows down do **not** accept air is more dense than glass	1
(b)(i)	sound / waves <u>diffract</u> through the gap (in the wall) **or** over the wall **or** because the gate is open	do **not** accept reflection this only scores if first marking point is given accept for **1** mark only sound / waves go through the gap and <u>spread out</u> **or** diagram showing wave fronts spreading out from open gates if diagram is labelled as diffraction both marks can be scored	1 1
(ii)	less diffraction	accept no diffraction accept gates <u>absorb</u> sound / noise / waves accept gates <u>reflect</u> sound / noise / waves do **not** accept rebounds / stops / blocks out	1
total			5

4.4.3.1 Background radiation

Answer 17 · Examiner comments

November 2020 | 8463/1H | Original Q5

Question 5 (Standard/High demand)

05.1 40% of student scored a mark on this question. Electronics, microwaves, phones and food and drink were common incorrect responses. Man-made doesn't mean 'made by man' in this context it refers to the radiation source being artificial rather than naturally occurring. Incorrect answers commonly seen included things which are not man-made, eg sunlight, cosmic rays, other types of radiation which do not contribute to background radiation like microwaves or infrared.

05.2 74% of students could name a nuclear fuel. The most popular answer being 'uranium'. Commonly seen incorrect answers included coal, oil, gas and petrol.

05.3 Only 6% of students scored all 4 marks. To score the first marking point, students needed to indicate that the neutron becomes part of the U-235 nucleus, it was insufficient to only say that the neutron collides with the nucleus. Very few students scored the 4th marking point. Many students hadn't revised the process, evidenced by their meandering discussion of different radiation types and gold sheets. Whilst many students had some idea of the nuclear fission process, they often failed to gain marks because their answers lacked detail or were imprecise, eg neutrons being absorbed by 'atoms' rather than 'nuclei', a nucleus 'splitting' without the detail of two daughter nuclei being produced. A number of students went on to describe the chain reaction and / or the process of electricity generation which was unnecessary.

05.4 Only 8% of students scored both marks, with 29% of students scoring 1 mark. Elements fuse or atoms fuse was insufficient. Nuclei fuse was insufficient unless they said to form a larger / heavier nucleus. Very few knew that some of the mass of the nuclei was converted into energy. Some students fell back on their knowledge of chemical reactions and mentioned breaking bonds and exothermic reactions.

05.5 Only 8% of students scored 2 marks, 39% of students scored 1 mark. Very few students linked the short half-life to how the activity of the waste would change with time. Most students who scored the first marking point did so for saying the radioactive waste would decay quicker. Students tended to score the second marking point rather than the first, although vague statements like less harm/damage to the environment were insufficient.

4.4.3.1 Background radiation

Answer 18 · Examiner comments

June 2023 | 8463/1H | Original Q5

Question 5 (Standard/high Demand)

05.1 This question discriminated well with 43 % of students scoring 3 marks, 18 % of students scoring 2 marks and 17 % of students scoring 1 mark. There is evident confusion about the significance of the mass number and the atomic number and what they represent. Lots of students 'shot themselves in the foot' by making statements about incorrect numbers of particles. e.g. 'Number of neutrons in carbon-12 is different from carbon-14, it's 12 in carbon-12 and 14 in carbon-14', would score no marks. Any numbers given as examples had to be correct to score marks.

05.2 'Time for radioactivity to halve' was insufficient to score, which was a commonly seen answer. If a student specified 'the time to halve' they needed to be clear what was halving: mass, number of nuclei, activity, etc. 47% of students scored the mark for this question.

05.3 Students struggled to realise that if ¼ remained two half-lives had passed. Subsequently, any calculation they did scored no marks. 32% of students scored 2 marks. For only 1 mark to score the words '2 half-lives' needed to be seen, it was not sufficient to see the number '2'.

05.4 Most students incorrectly chose Fluorine-18 as causing the biggest risk, believing that its long half-life would cause the most harm. Students who chose nitrogen-18 were often imprecise in their explanation and used 'more radiation emitted' without indicating the time period over which the more radiation was emitted. 'Decays the fastest' was insufficient to score the 2nd marking point. Less than 1% of students scored 3 marks, 7% scored 2 marks and 15% scored 1 mark.

05.5 Students who had learned the definitions as stated in the specification scored well, with 18% of students scoring 2 marks. Many students were unclear of the difference between the two terms and gave vague answers about 'radiation being around you versus in you', which were insufficient to score. It was evident that many students don't appreciate that radioactive materials emit radiation and gave confused answers mixing the terms 'radiation' and 'radioactive'.

05.6 90% of students answered correctly, scoring a mark. The most common correct answer was 'cancer'. 'Death' was ignored as working with nuclear radiation would cause other specific harm before death occurred. 'Damage to tissues / organs' was also creditworthy, as they are made up of cells. As ionisation occurs at an atomic level, this was not sufficient to score a mark. A commonly seen incorrect answer was 'ionises cells'.

05.7 38% of students scored 2 marks on this question, while 3% of students scored 1 mark. Students who didn't mention alpha radiation / particles would not have scored marks. Some students thought that standing close to the radiation detector would help to rule out radiation due to background radiation, which was not creditworthy.

05.8 82% of students scored 3 marks usually for using the first method given in the mark scheme. Some students calculated 144 (days) but thought they had calculated hours so divided by 24 and wrote an answer of 6. They scored 2 marks, as their final answer was treated as a unit error.