Chhetri Academy

chhetriacademy.com

GCSE MATHS

Algebra

Edexcel 1MA1 | Subtopic collection Topic 18

Solving quadratic equations

Higher tier

Answers and examiner comments

59	2003-2023	Higher
question groups	available papers	tier

Using this booklet

1. Answer numbers match the companion question booklet.
2. Follow the original question number on marking tables.
3. Examiner comments are included where available.

Name _____ **Date** _____

Some entries use full source marking material in an appendix. Any unavailable mark schemes are identified beside the relevant answer.

Original question 13

The full source mark scheme begins on page 95. Use the original paper code, tier and question number shown above.

Original question 9

No matching mark scheme was available in the supplied archive for this question.

Original question 7

No matching mark scheme was available in the supplied archive for this question.

Original question 15

No matching mark scheme was available in the supplied archive for this question.

Original question 19

The full source mark scheme begins on page 149. Use the original paper code, tier and question number shown above.

Original question 15

The full source mark scheme begins on page 200. Use the original paper code, tier and question number shown above.

Question		Working	Answer	Mark	Notes
25	(a)	$x^2+(x+2)^2=(x+4)^2$ $x^2+x^2+4x+4=x^2+8x+16$ $x^2+4x-8x+4-16=0$	Proof	3	M1 for $x^2 + (x + 2)^2 = (x + 4)^2$ oe A1 for $x^2+x^2+4x+4 = x^2+8x+16$ A1 for completing the proof
	b)(i)	$(x-6)(x+2)=0$ $x-6=0$ or $x+2=0$ or $x=\frac{--4\pm\sqrt{(-4)^2-4\times1\times-12}}{2\times1}$ $x=\frac{4\pm\sqrt{64}}{2}$ $(x - 2)^2 - 16 = 0$ $x - 2 = \pm\sqrt{16}$ $x = 2 \pm\sqrt{16}$	6, -2	4	M1 for $(x \pm 6)(x \pm 2)$ (= 0) OR $\frac{--4\pm\sqrt{(-4)^2-4\times1\times-12}}{2\times1}$ allow ±4 for b and ±12 for c OR $(x - 2)^2 - 16 = 0$ A1 $x = 6$ cao A1 $x = -2$ cao [SC: B1 for 1 correct solution if MO scored]
	(ii)		10		B1 ft from (b)(i), provided x is a positive value [Note: an answer of 10 and 2 gets B0]

1380_3H
Summer 2010

19	(a)		$(x-2)(x-5)$	2	M1 for $(x \pm 2)(x \pm 5)$ A1 for $(x-2)(x-5)$
	(b)		$x = 2$, $x = 5$	1	B1 cao or ft from (a)

Question	Working	Answer	Mark	Notes
23 (a)	$x^2 - 3x + 5x - 15$	$x^2 + 2x - 15$	2	M1 for four correct terms with or without signs, or 3 out of no more than 4 terms with correct signs. The terms may be in an expression or in a table A1 cao
(b)	$(x + 9)(x - 1) = 0$ OR a = 1, b = 8, c = − 9 $x = \frac{-8 \pm \sqrt{8^2 - 4 \times 1 \times -9}}{2 \times 1}$ $= \frac{-8 \pm \sqrt{100}}{2}$ OR $(x + 4)^2 - 16 - 9$ $(x + 4)^2 = 25$ $x = -4 \pm \sqrt{25}$	$x = 1$ or $x = -9$	3	M2 for $(x + 9)(x - 1)$ (M1 for $(x \pm 9)(x \pm 1)$) A1 cao **or** M1 for correct substitution in formula of 1, 8, ±9 M1 for reduction to $\frac{-8 \pm \sqrt{100}}{2}$ A1 cao **or** M1 for $(x + 4)^2$ M1 for $-4 \pm \sqrt{25}$ A1 cao SC: if no marks score then award B1 for 1 correct root, B3 for both correct roots.

1380_3H

1380/3H

28	(a)		Circle, centre O, radius 3	2	M1 for a complete circle centre (0, 0) A1 for a correct circle within guidelines
	(b)		$x = 2.6$, $y = -1.6$ or $x = -1.6$, $y = 2.6$	3	M1 for $x + y = 1$ drawn M1 (dep) ft from (a) for attempt to find coordinates for any one point of intersection with a curve or circle A1 for $x = 2.6$, $y = -1.6$ **and** $x = -1.6$, $y = 2.6$ all ± 0.1

1380_3H

Question		Working	Answer	Mark	Notes
27		$\frac{x\times2(x+1)}{2}-\frac{2\times2(x+1)}{x+1}=1\times2(x+1)$ $x(x+1)-4=2(x+1)$ $x^2+x-4=2x+2$ $x^2-x-6=0$ $(x-3)(x+2)=0$	$x = 3, -2$	4	M1 for an attempt to multiply one term of the equation by 2 or $x + 1$ or $2(x+1)$ or $2\times x + 1$ with or without cancelling or attempt to write LHS with a common denominator M1 for attempt to multiply all terms by $2(x + 1)$ with or without cancelling e.g. $\frac{x\times2(x+1)}{2}-\frac{2\times2(x+1)}{x+1}=1\times2(x+1)$ Or $x(x + 1) – 4 = 2(x + 1)$ A1 for $x^2 + x – 4 = 2x + 2$ or $x^2 – x – 6 = 0$ A1 cao for 3 and – 2

<table>
<tr><th colspan="2">Question</th><th>Working</th><th>Answer</th><th>Mark</th><th>Notes</th></tr>
<tr><td>18</td><td>(a)</td><td></td><td>c^8k^{20}</td><td>1</td><td>B1</td></tr>
<tr><td></td><td>(b)</td><td>$12x^2 - 3x + 20x - 5$
OR
<table><tr><td>×</td><td>3x</td><td>(+) 5</td></tr><tr><td>4x</td><td>$12x^2$</td><td>(+)20x</td></tr><tr><td>−1</td><td>−3x</td><td>−5</td></tr></table></td><td>$12x^2 + 17x - 5$</td><td>2</td><td>B2 for fully correct
(B1 for 3 out of 4 terms correct in working including signs OR 4 terms correct, ignore signs. In a grid the 20x need not be signed)</td></tr>
<tr><td></td><td>(c)</td><td>$(x - 5)(x + 2) = 0$</td><td>5 and −2</td><td>3</td><td>M1 for $(x \pm 5)(x \pm 2)$
A1 for $(x - 5)(x + 2)$ (= 0)
B1 ft (dep on M1) for $x = 5$ and −2
or
M1 for correct substitution in formula allow sign errors in b and c
M1 for reduction to $\frac{3 \pm \sqrt{49}}{2}$
A1 for 5 and −2
or
M1 for $(x - \frac{3}{2})^2 - \left(\frac{3}{2}\right)^2 - 10 = 0$
M1 for $\frac{3}{2} \pm \sqrt{\frac{49}{4}}$
A1 for 5 and −2
or
T&I B3 both roots
(B1 one root)</td></tr>
</table>

1380_4H

20	(a)	$2x^2 - 9x + 4 = (2x - 1)(x - 4)$	$(2x - 1)(x - 4)$	2	M1 $(2x \pm 1)(x \pm 4)$ A1 cao
	(b)	$(2x - 1)(x - 4) = (2x - 1)^2$ $2x - 1 = 0$ or $x - 4 = 2x - 1$ for $x = ½$ or $x = -3$ OR $2x^2 - 9x + 4 = 4x^2 - 4x + 1$ $2x^2 + 5x - 3 = 0$ $(2x - 1)(x + 3) = 0$ OR $(2x - 1)(x - 4) = (2x - 1)^2$ $(2x - 1)[2x - 1 - (x - 4)] = 0$ $(2x - 1)(x + 3) = 0$	$x = \frac{1}{2}, -3$	4	M1 '$(2x - 1)(x - 4)$' $= (2x - 1)^2$ M1 dep for $2x - 1 = 0$ or for $x - 4 = 2x - 1$ oe A1 for $x = ½$ or $x = -3$ A1 cao OR M1 attempts to expand RHS (at least 3 terms with two correct) M1 dep attempts to get $ax^2 + bx + c = 0$ (allow one error) or $2x^2 + 5x - 3$ seen A1 $(2x - 1)(x + 3)$ seen or correct substitution into the quadratic formula A1 cao OR M1 '$(2x - 1)(x - 4)$' $= (2x - 1)^2$ M1 dep attempt to factorise $(2x - 1)[2x - 1 - (x - 4)]$ A1 $(2x - 1)(x + 3)$ seen A1 cao [SC: Answer of -3 or ½, no working, scores B1]

1380_3H

Question		Working	Answer	Mark	Notes
19		$x^2 + 3 = 7x$ $x^2 - 7x + 3 = 0$ $x = \frac{-(-7) \pm \sqrt{(-7)^2 - 4\times 3}}{2}$ OR $(x - 3.5)^2 = 3.5^2 - 3 = 9.25$ $x - 3.5 = \pm\sqrt{9.25}$	$= \frac{7 \pm \sqrt{37}}{2}$ OR $3.5 \pm\sqrt{9.25}$	3	M1 for $x^2 + 3 = 7x$ oe **or** clear intention to multiply all terms by x M1 for $x = \frac{-(-7) \pm \sqrt{(-7)^2 - 4\times 3}}{2}$ ft from a quadratic equation of the form $ax^2 + bx + c = 0$ where $a,b,c \neq 0$; condone wrong signs for a, b, c in substitution A1 for $= \frac{7 \pm \sqrt{49 - 12}}{2}$ or for $= \frac{7 \pm \sqrt{37}}{2}$ as the final exact solution **OR** M1 for $x^2 + 3 = 7x$ oe **or** clear intention to multiply all terms by x M1 for $(x - 3.5)^2 - 3.5^2 + 3 = 0$ ft from a quadratic equation of the form $ax^2 + bx + c = 0$ where $a,b,c \neq 0$ A1 for $3.5 \pm\sqrt{9.25}$ SC : B2 for both 6.54(1381265..) **and** 0.458(6187349…)

1380_4H

Question		Working	Answer	Mark	Notes
14	(a)	$p^2 - 4p + 9p - 36$	$p^2 + 5p - 36$	2	M1 for all 4 terms correct (condone incorrect signs) or 3 out of 4 terms correct with correct signs A1 cao
	(b)	$5w - 8 = 3(4w + 2)$ $5w - 8 = 12w + 6$ $-8 - 6 = 12w - 5w$ $-14 = 7w$	-2	3	M1 for attempting to multiply both sides by 3 as a first step (this can be implied by equations of the form $5w - 8 = 12w + ?$ or $5w - 8 = ?w + 6$ i.e. the LHS must be correct M1 for isolating terms in w and the number terms correctly from $aw + b = cw + d$ A1 cao **OR** M1 for $\frac{5w}{3} - \frac{8}{3} = 4w + 2$ M1 for isolating terms in w and the number terms correctly A1 cao
	(c)		$(x + 7)(x - 7)$	1	B1 cao
	(d)		$3x^4y^{\frac{3}{2}}$	2	B2 for $3x^4y^{\frac{3}{2}}$ or $3x^4y^{1.5}$ or $3x^4y^{1\frac{1}{2}}$ (B1 for any two terms correct in a product eg. $3x^4y^n$)

<table>
<tr><th colspan="6">1MA0_2H</th></tr>
<tr><th colspan="2">Question</th><th>Working</th><th>Answer</th><th>Mark</th><th>Notes</th></tr>
<tr><td>*15</td><td></td><td>180 × 365 =65700
65700 ÷1000 =65.7
65.7 × 91.22 =5993.154
5993.154÷100 + 28.20 =88.13...

<table><tr><td>D</td><td>U</td><td>C</td><td>T</td></tr><tr><td>366</td><td>65880</td><td>6010</td><td>88.30</td></tr><tr><td>365</td><td>65700</td><td>5993</td><td>88.13</td></tr><tr><td></td><td>65000</td><td>5929</td><td>87.49</td></tr><tr><td></td><td>66000</td><td>6020</td><td>88.40</td></tr><tr><td>364</td><td>65520</td><td>5976</td><td>87.96</td></tr><tr><td>360</td><td>64800</td><td>5911</td><td>87.31</td></tr><tr><td><s>336</s></td><td><s>60480</s></td><td>5517</td><td>83.37</td></tr></table></td><td>Decision (Should have a water meter installed)</td><td>5</td><td>Per year
M1 for 180 × ‘365’ (= 65700)
M1 for ‘65700’ ÷ 1000 (= 65.7 or 65 or 66)
M1 for ‘65.7’ × 91.22 (= 5993...)
A1 for answer in range (£)87 to (£)89
C1 (dep on at least M1) for conclusion following from working seen

OR (per day)
M1 for 107 ÷ ‘365’ (= 0.293…)
M1 for 180 ÷ 1000 × 91.22 (= 16.4196)
M1 for 28.2 ÷ ‘365’ + ‘0.164196’ (units must be consistent)
A1 for 29 – 30(p) and 24 – 24.3(p) oe
C1 (dep on at least M1) for conclusion following from working seen

OR
M1 for (107 – 28.20) ÷ 0.9122 (= 86.384..)
M1 for ‘86.384..’× 1000 (= 86384.5…)
M1 for ‘365’ × 180 (= 65700)
A1 for 65700 and 86384.5...
C1 (dep on at least M1) for conclusion following from working seen

NB : Allow 365 or 366 or 52×7 (=364) or 12 × 30 (=360) or 365¼ for number of days</td></tr>
</table>

1MA0_2H

Question		Working	Answer	Mark	Notes
22		$a = 3, b = -4, c = -2$ $x = \frac{--4 \pm \sqrt{(-4)^2 - 4\times3\times-2}}{2\times3}$ $= \frac{4 \pm \sqrt{16+24}}{6} = \frac{4 \pm \sqrt{40}}{6}$ = 1.72075922 or = – 0.3874258867 OR $x^2 - \frac{4}{3}x - \frac{2}{3} = 0$ $\left(x - \frac{2}{3}\right)^2 - \left(\frac{2}{3}\right)^2 - \frac{2}{3} = 0$ $x - \frac{2}{3} = \sqrt{\left(\frac{2}{3}\right)^2 + \frac{2}{3}}$ $x = \frac{2}{3} \pm \sqrt{\frac{10}{9}}$	1.72, –0.387	3	M1 for $\frac{--4 \pm \sqrt{(-4)^2 - 4\times3\times-2}}{2\times3}$ (condone incorrect signs for –4 and –2) M1 for $\frac{4 \pm \sqrt{40}}{6}$ or $\frac{2 \pm \sqrt{10}}{3}$ A1 for one answer in the range 1.72 to 1.721 and one answer in the range – 0.387 to – 0.38743 **OR** M1 for $\left(x - \frac{2}{3}\right)^2$ oe M1 for method leading to $\frac{2}{3} \pm \sqrt{\frac{10}{9}}$ oe A1 for one answer in the range 1.72 to 1.721 and one answer in the range – 0.387 to – 0.38743

1MA0_2H

Question		Working	Answer	Mark	Notes
22	(a)	$x = \frac{-9 \pm \sqrt{9^2 - 4\times 2\times -7}}{2\times 2} = \frac{-9 \pm \sqrt{137}}{4}$	0.676, − 5.18	3	M1 $\frac{-9 \pm \sqrt{9^2 - 4\times 2\times -7}}{2\times 2}$ allow substitution of ±7 for c M1 $\frac{-9 \pm \sqrt{137}}{4}$ A1 answers in ranges 0.67 - 0.68 **and** − 5.17 to − 5.18 **OR** M1 $(x + \frac{9}{4})^2$ oe M1 for method leading to $\pm\sqrt{\frac{137}{16}} - \frac{9}{4}$ A1 answers in ranges 0.67 - 0.68 **and** − 5.17 to − 5.18
	(b)	Put $y = \frac{1}{x}$ and use part (a) Or $7y^2 - 9y - 2 = 0$ $y = \frac{--9 \pm \sqrt{(-9)^2 - 4\times 7\times (-2)}}{2\times 7}$ $\frac{9 \pm \sqrt{137}}{14}$	1.48, − 0.193	2	M1 $y = \frac{1}{x}$ **or** $x = \frac{1}{y}$ A1 (ft) answers in range 1.47 - 1.48 **and** − 0.19 to − 0.194 **OR** M1 fully correct method which leads to $7y^2 - 9y - 2 = 0$ **or** $-7y^2 + 9y + 2 = 0$ with correct method to solve (condone sign errors in substitution) A1 (ft) answers in range 1.47 - 1.48 **and** − 0.19 to − 0.194

1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
23	(a)	Let O be the centre of the base. $OB^2 + OC^2 = 10^2$; $OB^2 = 50$ $AO^2 = AB^2 - OB^2 = 50$ Vol = $\frac{1}{3}\times 10^2 \times \sqrt{50}$ **OR** Let M be the midpt of side BC and let O be the centre of the base. $AM^2+MC^2 = 10^2$; $AM^2 = 75$ $AO^2 = AM^2 - MO^2 = 50$ Vol = $\frac{1}{3}\times 10^2 \times \sqrt{50}$	236	4	M1 correct method to start to find BD or BO using triangle OBC or triangle BCD (oe) Eg. $OB^2 + OC^2 = 10^2$ **or** $BO^2 = 50$ **or** $BO = \sqrt{50}$ (=7.07..) **or** $BO = \frac{\sqrt{200}}{2}$ **or** $10^2 + 10^2 = BD^2$ **or** $BD^2 = 200$ **or** $BD = \sqrt{200}$ (=14.1..) M1 (dep) correct method to find height of pyramid using triangle AOB Eg. $AO^2 = 10^2 - '\sqrt{50}'^2$ **or** $AO^2 = 50$ **or** $AO = \sqrt{50}$ (=7.07..) M1 (indep) $\frac{1}{3}\times 10^2 \times '\sqrt{50}'$ (but **not** $\frac{1}{3}\times 10^2 \times 10$) A1 235 – 236 **OR** M1 correct method to start to find height of a face using triangle AMC (oe) Eg. $AM^2 + 5^2 = 10^2$ **or** $AM^2 = 75$ **or** $AM = \sqrt{75}$ (=8.66...) M1 (dep) correct method to find height of pyramid using triangle AOM Eg. $AO^2 = '\sqrt{75}'^2 - 5^2$ **or** $AO^2 = 50$ **or** $AO = \sqrt{50}$ (=7.07..) M1 (indep) $\frac{1}{3}\times 10^2 \times '\sqrt{50}'$ (but **not** $\frac{1}{3}\times 10^2 \times 10$) A1 235 – 236

1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
23 cont.	(a)				**OR** M1 for $\sin 45 = \frac{x}{10}$ **or** $\cos 45 = \frac{x}{10}$ M1 for $h = 10 \times \sin 45$ **or** $h = 10 \times \cos 45$ (=7.07..) M1 (indep) $\frac{1}{3} \times 10^2 \times$ '7.07...' (but **not** $\frac{1}{3} \times 10^2 \times 10$) A1 235 – 236

1MA0_2H

Question		Working	Answer	Mark	Notes
20	(a)(i)		$(x - 9)(x - 3)$	3	M1 for $(x \pm 9)(x \pm 3)$ A1 for $(x - 9)(x - 3)$
	(ii)		$x = 9$, $x = 3$		B1 cao
	(b)		$(y + 10)(y - 10)$	1	B1 for $(y + 10)(y - 10)$
*21		$(n + 1)^2 - n^2$ $= n^2 + 2n + 1 - n^2 = 2n + 1$ $(n + 1) + n = 2n + 1$ OR $(n + 1)^2 - n^2$ $= (n + 1 + n)(n + 1 - n)$ $= (2n + 1)(1) = 2n + 1$ $(n + 1) + n = 2n + 1$ OR $n^2 - (n + 1)^2 = n^2 - (n^2 + 2n + 1) = -2n - 1 = -(2n + 1)$ Difference is $2n + 1$ $(n + 1) + n = 2n + 1$	proof	4	M1 for any two consecutive integers expressed algebraically eg n and $n + 1$ M1(dep on M1) for the difference between the squares of 'two consecutive integers' expressed algebraically eg $(n + 1)^2 - n^2$ A1 for correct expansion and simplification of difference of squares, eg $2n + 1$ C1 (dep on M2A1) for showing statement is correct, eg $n + n + 1 = 2n + 1$ and $(n + 1)^2 - n^2 = 2n + 1$ from correct supporting algebra

25			$1 + \sqrt{5}$	5	M1 for $\frac{1}{2} \times x \times x \times \sin 30°$ oe M1 for $\frac{1}{2}(x-2)(x+1)$ oe **or** $\frac{1}{2} \times (x-2) \times (x+1) \times \sin 90$ M1 (dep on at least one previous M1) for formation of equation from equating areas with x as the only variable A1 for $x^2 - 2x - 4 = 0$ oe in the form $ax^2 + bx + c = 0$ or $ax^2 + bx = c$ A1 cao

Original question 20

The full source mark scheme begins on page 261. Use the original paper code, tier and question number shown above.

Original question 15

The full source mark scheme begins on page 276. Use the original paper code, tier and question number shown above.

Question		Working	Answer	Mark	Notes
18			0.27 and –1.47	3	M1 for $\frac{-6 \pm \sqrt{6^2 - 4 \times 5 \times -2}}{2 \times 5}$, allow substitution of 2 or –2 for c M1 for $\frac{-6 \pm \sqrt{76}}{10}$ A1 for 0.27(17797…) and –1.47(17797…)

PAPER: 1MA0_2H

Question	Working	Answer	Mark	Notes
22 (a)		'show'	2	M1 for $\frac{1}{2} \times (x - 4 + x + 5) \times 2$ **or** $2x \times (x - 4) + \frac{1}{2} \times 2x \times 9$ A1 for completion with correct processes seen
(b)		13	3	M1 for $\frac{-1 \pm \sqrt{1^2 - 4 \times 2 \times -351}}{2 \times 2}$ condone incorrect sign for 351 M1 for $\frac{-1 \pm \sqrt{2809}}{4}$ A1 for 13 NB for either M mark accept + only in place of ± **OR** M2 for $(2x + 27)(x - 13)$ (M1 for $(2x \pm 27)(x \pm 13)$) A1 for 13

9	(a)	x –1 0 1 2 3 4 5 y **9** 3 –1 **–3** –3 **–1** 3	9, –3, –1	2	B2 for a fully correct table of values (B1 for at least one correct extra entry)
	(b)		Correct graph	2	B1 (dep on at least B1 in (a)) for all of their points correctly plotted B1 (dep on previous B1) for smooth curve through all 7 of their points
	(c)		0.7, 4.3	2	B1 for an answer rounding to 0.7 or ft their graph B1 for an answer rounding to 4.3 or ft their graph

PAPER: 5MB3H_01

Question	Working	Answer	Mark	Notes
20		4.5, –0.75 oe	3	M2 for $(2x – 9)(4x + 3)$ oe (M1 for $(2x \pm 9)(4x \pm 3)$) oe A1 for 4.5, –0.75 oe [SC: B1 for 4.5 and –0.75 oe, found by any other method]

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5º
Measurements of length: ±5 mm

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q1	(a)	2cm grid	
	(b)	2cm grid. Triangle A to be rotated about the point (0,1).	
Q6		July peak / off peak in a different format. Information the same.	Standard mark scheme
Q7		Dashed line to join Alford and Bancroft. A to B – 7.5cm.	Standard mark scheme
Q9		1 ½ cm grid.	Standard mark scheme
Q12		2cm grid.	Standard mark scheme
Q13		Measurement arrows taken out.	Standard mark scheme
Q16		Model and diagram	Standard mark scheme

9	(a)	x –1 0 1 2 3 4 5 y **9** 3 –1 **–3** –3 **–1** 3	9, –3, –1	2	B2 for a fully correct table of values (B1 for at least one correct extra entry)
	(b)		Correct graph	2	B1 (dep on at least B1 in (a)) for all of their points correctly plotted B1 (dep on previous B1) for smooth curve through all 7 of their points
	(c)		0.7, 4.3	2	B1 for an answer rounding to 0.7 or ft their graph B1 for an answer rounding to 4.3 or ft their graph

PAPER: 5MB3H_01

Question	Working	Answer	Mark	Notes
20		4.5, –0.75 oe	3	M2 for $(2x – 9)(4x + 3)$ oe (M1 for $(2x \pm 9)(4x \pm 3)$) oe A1 for 4.5, –0.75 oe [SC: B1 for 4.5 and –0.75 oe, found by any other method]

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5º
Measurements of length: ±5 mm

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q1	(a)	2cm grid	
	(b)	2cm grid. Triangle A to be rotated about the point (0,1).	
Q6		July peak / off peak in a different format. Information the same.	Standard mark scheme
Q7		Dashed line to join Alford and Bancroft. A to B – 7.5cm.	Standard mark scheme
Q9		1 ½ cm grid.	Standard mark scheme
Q12		2cm grid.	Standard mark scheme
Q13		Measurement arrows taken out.	Standard mark scheme
Q16		Model and diagram	Standard mark scheme

PAPER: 1MA0_1H

Question		Working	Answer	Mark	Notes
15	(a)		2, –1, 2, 7	2	B2 for all correct (B1 for 2 or 3 correct)
	(b)		Correct graph	2	M1 (dep on at least B1) for at least 6 points from their table plotted correctly A1 cao for fully correct graph
	(c)	$x^2 - 3x - 4 = 0$ $(x - 4)(x + 1) = 0$	–1, 4	2	M1 for line $y = x + 3$ drawn correctly or for reduction to correct 3 term quadratic (=0) and : $(x \pm 1)(x \pm 4)$ or formula using $a = 1$, $b = -3$ and $c = -4$, allow one sign error in the formula, or $\left(x - \frac{3}{2}\right)^2 = 4 + \left(\frac{3}{2}\right)^2$ A1 cao

26		$y(5y + 24) = 0$ $\frac{-24 \pm \sqrt{(24^2)}}{10}$	$x = 6, y = 0$ $x = -3.6, y = -4.8$	5	M1 for substitution for elimination eg $(2y + 6)^2 + y^2 = 36$ M1 (dep on M1) for expansion eg $4y^2 + 12y + 12y + 36$ (3 out of 4 terms correct) A1 for $4y^2 + 24y + 36 + y^2 = 36$ oe M1 for a correct attempt to solve a 2 or 3 term quadratic equation eg by factorising or correct substitution into a quadratic formula A1 for $x = 6$, $y = 0$ and $x = -3.6$ oe, $y = -4.8$ oe SC: B1 (if M0 scored) for all 4 values mis-associated or one correct pair of values.

PAPER: 1MA0_2H

PAPER: 1MA0_1H

Question		Working	Answer	Mark	Notes
12	(a)		$e(3e + 5)$	1	B1 for $e(3e + 5)$
	(b)		4	3	M1 for intention to expand brackets, eg $7k - 21$ or division of all terms on RHS by 7 as first step, eg $\frac{3}{7}k - \frac{5}{7}$ M1 for correct method to isolate terms in k in an equation A1 cao
	(c)		$2x^2 - 13x - 24$	2	M1 for 4 terms correct ignoring signs or 3 out of no more than 4 terms correct A1 cao
	(d)		$-\frac{1}{3}$	3	M1 for clear intention to multiply both sides by 4 or split into individual fractions on LHS M1 for correct method to isolate term in f in an equation, ft from equations of form $a + bf = c$, where a, b, $c \neq 0$ A1 cao

PAPER: 1MA0_2H

Question		Working	Answer	Mark	Notes
20			1.85 and – 0.180	3	M1 for $\frac{--5\pm\sqrt{-5^2-4\times3\times-1}}{2\times3}$ (condone one sign error) M1 for $\frac{5\pm\sqrt{37}}{6}$ (=1.8 to1.85 or −0.18 to −0.181) A1 for answers in the ranges 1.8 to1.85, and −0.18 to −0.181

14	(a)		±7	2	M1 for 147 ÷ 3 (= 49) or 7 A1 cao
	(b)		18.2	3	M1 for correct method to deal with denominators (condone one error in arithmetic) M1 (dep) for correct method to write in the form $ay = b$ A1 for 18.2 or $18\frac{1}{5}$

18			−2.87, 0.87	3	M1 for substitution into formula; allow sign errors in b and c M1 for reduction to $\frac{-4-\sqrt{56}}{4}$ or $\frac{-4+\sqrt{56}}{4}$ A1 for 0.87 to 0.88 and −2.87 to −2.88 OR M1 for $(x+1)^2$ M1 for reduction to $\sqrt{\frac{7}{2}}-1$ or $-\sqrt{\frac{7}{2}}-1$ A1 for 0.87 to 0.88 and −2.87 to −2.88

PAPER: 5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
*19		eg $2a + 3c = 28.2$ $3a + 5c = 44.75$ $6a + 9c = 84.6$ $6a + 10c = 89.5$ $c = 4.9$ $2a + 14.7 = 28.2$ $2a = 13.5$ $a = 6.75$	Adult ticket £6.75 Child ticket £4.90	5	M1 for correctly stating both equations algebraically M1 for correct process to eliminate one variable (condone one arithmetic error) M1 (dep) for correct substitution of their found value to find other variable OR (indep) correct process to eliminate second variable (condone one error in arithmetic) A1 for 6.75 or 4.9 C1 for Adult ticket £6.75 and Child ticket £4.90 in correct money notation

19	(a)		Proof	3	M1 for $\frac{6}{n}$ or $\frac{5}{n-1}$ M1 for $\frac{6}{n} \times \frac{5}{n-1} \left(= \frac{1}{3}\right)$ A1 for fully correct algebra leading to $n^2 - n - 90 = 0$
	(b)		10	3	M1 for correct start to a solution, eg. $(n \pm 10)(n \pm 9)$ or substitution into the quadratic formula, condoning one sign error or $(n - 0.5)^2 - 0.25 - 90$ A1 for $(n - 10)(n + 9)$ or for 10 and –9 or $\frac{1 \mp 19}{2}$ oe A1 for 10 only

25		$\frac{-4\pm\sqrt{4^2-4\times3\times-12}}{2\times3}$	1.44 and −2.77	3	M1 for substitution of $a = 3$, $b = 4$, $c = -12$ into the formula (condone one sign error) or for completing the square M1 for $\frac{-4\pm\sqrt{160}}{6}$ or in simplified form A1 for answers in the ranges 1.43 to1.45 and −2.76 to −2.78

PAPER: 1MA0_2H

11	(a)		±7	2	M1 for intent to divide both sides by 3 as a first step or answer of 7 or -7 A1 ±7
	(b)		0.125 or $\frac{1}{8}$	1	B1 cao
	(c)		$27x^6$	2	M1 for either 27 or x^6 in a two term product A1 cao
	(d)		$p = \frac{w + 16}{4}$	2	M1 for ÷ 4 throughout or adding 16 to both sides as a first step A1 $p = \frac{w+16}{4}$ oe

PAPER: 1MA0_2H

22			$2x^2 + 7x + 4 = 0$	3	M1 for finding a correct coefficient M1 for a method to find a and c or b and c A1 $2x^2 + 7x + 4 = 0$ or $a = 2$, $b = 7$, $c = 4$

18			$-\frac{3}{2}, \frac{5}{3}$	3	M1 for $(2x \pm 3)(3x \pm 5)$ M1 for $(2x + 3)(3x - 5)$ A1 for $-\frac{3}{2}$ and $\frac{5}{3}$ oe accept 1.66 – 1.67 OR M1 for $\frac{-(-1)\pm\sqrt{(-1)^2-4\times6\times-15}}{2\times6}$, condone one sign error M1 for $\frac{1\pm\sqrt{361}}{12}$ A1 for $-\frac{3}{2}$ and $\frac{5}{3}$ oe accept 1.66 – 1.67 OR M1 for $\left(x - \frac{1}{12}\right)^2 \pm \left(\frac{1}{12}\right)^2 \pm a = 0$ M1 for $\left(x - \frac{1}{12}\right)^2 = b$ A1 for $-\frac{3}{2}$ and $\frac{5}{3}$ oe accept 1.66 – 1.67

22		2, 6	3	M1 for $(x^2 =)\quad 4(x^2 - 6x + 9)$ or $4x^2 - 24x + 36$ oe or for $\frac{x^2}{4} = x^2 - 6x + 9$ M1 (dep) for $3x^2 - 24x + 36 = 0$ or $3(x^2 - 8x + 12) = 0$ or $(x - 2)(x - 6) = 0$ or $(3x - 6)(x - 6) = 0$ oe A1 cao OR M1 for $x = (\pm)2(x - 3)$ or $\frac{x}{2} = (\pm)(x - 3)$ M1(dep) for correct solution of one equation A1 cao

PAPER: 1MA0_1H

20		$\frac{-6 \pm \sqrt{6^2 - 4 \times 3 \times -2}}{2 \times 3}$ $(x + 1)^2 - 1 - \frac{2}{3} = 0$	0.29 and – 2.29	3	M1 for substitution of $a = 3$, $b = 6$, $c = -2$ into the formula or for completing the square (condone **one** sign error) M1 for $\frac{-6 \pm \sqrt{60}}{6}$ or $-1 \pm \sqrt{\frac{5}{3}}$ or in simplified form A1 for answers in the range 0.29 to 0.292 and – 2.292 to – 2.29

Question	Working	Answer	Mark	Notes
19 (a)		$y^2 + 7y + 10$	2	M1 for all 4 terms (and no additional terms) correct ignoring signs **or** 3 terms correct A1 for $y^2 + 7y + 10$
(b)		$(e - 3)(e + 4)$	2	M1 for $(e \pm 3)(e \pm 4)$ A1 for $(e - 3)(e + 4)$
(c)		0.77, –0.43	3	M1 for $\frac{--1 \pm \sqrt{(-1)^2 - 4 \times 3 \times -1}}{2 \times 3}$ (condone one sign error) M1 for $\frac{1 \pm \sqrt{13}}{6}$ A1 for one answer in the range 0.767 to 0.77 and one answer in the range –0.43 to –0.4343

PAPER: 5MB3H_01

Question	Working	Answer	Mark	Notes
19 (a)		5 and −7	3	M1 for $(x \pm 5)(x \pm 7)$ M1 for $(x - 5)(x + 7)$ A1 cao OR M1 for correct substitution into formula M1 for reduction to $\frac{-2 \pm \sqrt{144}}{2}$ A1 cao
(b)		$\pm\sqrt{3}$	4	M1 for multiplying through by a common denominator eg by $(x + 1)(2x + 3)$ M1 (dep) for reduction eg to $4x + 6 + x^2 + x$ or $2x^2 + 3x + 2x + 3$ M1 for $x^2 - 3 (= 0)$ A1 cao for both answers; accept decimals to at least 2 dp

21	$\frac{-3\pm\sqrt{3^2-4\times2\times-7}}{2\times2}$	1.27, −2.77	3	M1 for substitution of $a = 2$, $b = 3$, $c = -7$ (condone one sign error) M1 for $\frac{-3\pm\sqrt{65}}{4}$ A1 for solutions in range 1.26 to 1.27 **and** –2.76 to –2.77

Question	Working	Answer	Mark	Notes
15		2.63	P1	for setting up the expression $\frac{1}{2}(x+3)(2x-1)\sin 45$ (may be seen in an equation)
			P1	(dep) for expanding the brackets in the expression or for the equation $\frac{1}{2}(x+3)(2x-1)\sin 45 = 6\sqrt{2}$ oe
			P1	(dep) for the process to set up the equation and rearrange to the form $ax^2+bx+c=d$ e.g. to $2x^2 + 5x - 27 = 0$ or $24 = 2x^2 + 5x - 3$
			P1	(dep) for substitution into the quadratic formula e.g. $\frac{-5\pm\sqrt{5^2-4\times2\times-27}}{4}$
			A1	for 2.63(10436…)

19		$x < -2, x > \frac{1}{2}$	M1 A1 A1	for a first step to solve the quadratic e.g. factorisation: $(2x + 4)(x - \frac{1}{2})$ or $(2x - 1)(x + 2)$ or using the formula $\frac{-3 \pm \sqrt{3^2 - 4 \times 2 \times (-2)}}{2 \times 2}$ for -2 and $\frac{1}{2}$

Question	Answer	Mark	Mark scheme	Additional guidance
19	$\frac{5}{3}$	P1	for process to derive an equation in x, eg $\frac{x}{4x-1}=\frac{6x+5}{12x+31}$	
		P1	for complete process to remove fractions, eg $x(12x + 31) = (6x + 5)(4x – 1)$	Must be correct use of brackets
		P1	for process to reduce to a quadratic equation, eg $12x^2 – 17x – 5 = 0$	Award for correct LHS only.
		P1	for process to solve the quadratic equation by factorisation or use of quadratic formula, eg $(4x + 1)(3x – 5) = 0$	Award for correct LHS only. Accept substitution into the formula; $\frac{--17\pm\sqrt{(-17)^2-4\times12\times-5}}{2\times12}$
		A1	for $\frac{5}{3}$ oe	Accept answers in the range 1.66 to 1.67 as equivalent

Paper: 1MA1/3H

Question	Answer	Mark	Mark scheme	Additional guidance
9 (a)	$2x^3 + x^2 - 7x - 6$	M1	for a method to find the product of two linear expressions eg 3 correct terms out of 4 terms or 4 terms ignoring signs	Note that (eg) $-x-6$ in expansion of $(x-2)(2x+3)$ is to be regarded as 3 correct terms.
		M1	for a complete method to obtain all terms, half of which are correct (ft their first product) eg $2x^3 - x^2 - 6x + 2x^2 - x - 6$	First product must be quadratic but need not be simplified or may be simplified incorrectly
		A1	cao	
(b)	-5	M1	for beginning to combine indices eg $4+n$ or y^{-3+2}	
		A1	cao	
(c)	1.27 and −0.472	M1	for substitution into the formula	Condone one sign error in the substitution Accept -4^2 or $(-4)^2$
		M1	for simplifying to the form $\frac{-b\pm\sqrt{N}}{k}$ eg $\frac{4\pm\sqrt{76}}{10}$ **or** 1.27 to 1.28 **or** −0.48 to −0.47	
		A1	for 1.27 to 1.28 **and** −0.48 to −0.47	

Paper: 1MA1/3H

17	–1, 2.5	P1 P1 P1 A1	for process to form an equation, eg $\frac{x^2}{3x+5}=\frac{1}{2}$ **or** $2x^2 = 3x + 5$ for writing in a suitable form ready for solution, eg $2x^2 – 3x – 5$ (= 0) **or** $– 2x^2 + 3x + 5$ (= 0) (dep 1st P1) for process to solve quadratic equation of form $ax^2 + bx + c$ (= 0) eg $(2x – 5)(x + 1)$ (= 0) **or** $\frac{--3 \pm \sqrt{(-3)^2 - 4 \times 2 \times -5}}{2 \times 2}$ for –1, 2.5 oe	

Paper: 1MA1/1H

Question	Answer	Mark	Mark scheme	Additional guidance
18 (a)	$6x^3 + 35x^2 + 58x + 21$	M1	for a method to find the product of two linear expressions, 3 correct terms out of 4 terms e.g. $2x^2 + x + 6x + 3$ or $3x^2 + 7x + 9x + 21$ or $6x^2 + 14x + 3x + 7$	Note that, for example, $7x + 3$ is regarded as three terms in the expansion of $(2x + 1)(x + 3)$
		M1	for a complete method to obtain all terms, at least half of which are correct (ft their first product) e.g. $6x^3 + 32x^2 + 42x + 3x^2 + 16x + 21$	First product must be a 3 or 4 term quadratic but need not be simplified or may be simplified incorrectly
		A1	cao	Accept $a = 6$, $b = 35$, $c = 58$, $d = 21$
(b)	$\frac{2}{5} < x < 1\frac{3}{5}$	M1	for first step of finding the square root of both sides eg $1 - x < \pm\frac{3}{5}$ **OR** for writing in the form $ax^2 + bx + c$ (< 0) eg $x^2 - 2x + \frac{16}{25}$ (< 0) or $25x^2 - 50x + 16$ (< 0)	Condone use of an "=" sign; accept one square root (eg $\frac{3}{5}$) only shown.
		M1	for showing critical values $\frac{2}{5}$ (= 0.4) and $1\frac{3}{5}$ (= 1.6) oe	Critical values can be stated, or shown in an expression (which may have incorrect inequality symbols)
		A1	for $\frac{2}{5} < x < 1\frac{3}{5}$ oe	Could be written as two separate expressions eg $x > \frac{2}{5}$ and $x < 1\frac{3}{5}$ oe

Paper: 1MA1/3H

Question	Answer	Mark	Mark scheme	Additional guidance
14	5	P1	for process to find the area of the triangle, eg. $0.5 \times (x + 4)(x - 2)$ oe OR for process to find the area of rectangle and 27.5×2, eg. $(x + 4)(x - 2)$ and 55	Trial and improvement methods must be fully correct identifying the value of x as 7 (3 marks) or the shortest side as 5 (4 marks)
		P1	(dep P1) for process to expand the brackets and derive a quadratic equation, eg. $x^2 + 4x - 2x - 8 = 55$ or $0.5(x^2 + 4x - 2x - 8) = 27.5$ oe	
		P1	(dep P2) for complete process to solve the quadratic equation $x^2 + 2x - 63 = 0$ eg $(x - 7)(x + 9)$ (= 0) or $\frac{-2 \pm \sqrt{2^2 - 4 \times 1 \times -63}}{2 \times 1}$ or $(x + 1)^2 - 1 - 63$ (= 0)	
		A1	cao SC: B1 for $x^2 + 4x - 2x - 8 = 27.5$	An answer of 5 with no supportive working gets no marks

Paper: 1MA1/1H

6	(a)	−2, 4	B1	cao	
	(b)	0.55 to 0.65, 3.35 to 3.45	M1	for correct method, eg marking intercepts with *x*-axis or one correct answer or both solutions given as a coordinate eg (0.6, 3.4) or (0.6, 0) (3.4, 0)	If answers are stated as coordinates, award M1 for both coordinates and M0 for one coordinate.
			A1	for answers in the ranges 0.55 to 0.65 and 3.35 to 3.45	With no extras

Question	Answer	Mark	Mark scheme	Additional guidance
8	8 and –3	M1	for rearranging to get $x^2 - 5x - 24 (= 0)$ **or** $-x^2 + 5x + 24 (= 0)$	Can be implied by $(x - 8)(x + 3)$ or $(-x + 8)(x + 3)$
		M1	for $(x \pm 8)(x \pm 3)$ **or** $(x + a)(x + b)$ where $ab = -24$ or $a + b = -5$ **or** substitution into formula, condoning one sign error eg $(x =) \dfrac{--5 \pm \sqrt{(-5)^2 - 4 \times 1 \times -24}}{2 \times 1}$	
		A1	for 8 **and** –3	

Question	Answer	Mark	Mark scheme	Additional guidance
16	Shown (supported)	M1	for eliminating y or x, eg $x^2 + 3x - 3 = 5x - 4$	
		M1	for rearranging, collecting terms and setting to 0 eg $x^2 - 2x + 1 (= 0)$	
		M1	for factorising or solving eg $(x - 1)^2 (= 0)$	
		C1	for statement confirming only 1 point in common eg only 1 root **or** only 1 value of x so only 1 set of coordinates	There must be a statement in words for the award of this mark

Paper: 1MA1/1H

Question	Answer	Mark	Mark scheme	Additional guidance
19	$\frac{5\pm\sqrt{15}}{2}$	M1	for using a common denominator eg $\frac{x-1}{(2x-1)(x-1)}+\frac{3(2x-1)}{(2x-1)(x-1)}$ (= 1) **or** $(x-1)+3(2x-1)=(2x-1)(x-1)$	
		M1	for expanding and rearranging to get $2x^2-10x+5$ (= 0)	Note we don't need to see "= 0"; just the LHS is sufficient Accept other forms of the 3 term quadratic, eg $2x^2-10x=-5$
		M1	(dep M1) ft for a method to solve their 3 term quadratic equation eg $\frac{10\pm\sqrt{(-10)^2-4\times2\times5}}{2\times2}$ or $\frac{10\pm\sqrt{60}}{4}$ **or** $2\left[\left(x-\frac{5}{2}\right)^2-\left(\frac{5}{2}\right)^2\right]+5=0$ oe	Correct use of formula or completing the square
		A1	cao	

Paper: 1MA1/1H

Paper: 1MA1/3H

Question	Answer	Mark	Mark scheme	Additional guidance
22	(– 3 , – 11) and (5.5, 6)	M1	for method to eliminate one variable, eg $(2x – 5)^2 = 6x^2 – 25x – 8$ or $y^2 = 6\left(\frac{y+5}{2}\right)^2 – 25\left(\frac{y+5}{2}\right) – 8$	
		M1	for expanding the square to give, eg. $4x^2 – 20x + 25 = 6x^2 – 25x – 8$ or $y^2 = 6\left(\frac{y^2+10y+25}{4}\right) – 25\left(\frac{y+5}{2}\right) – 8$	
		M1	for method to solve equation $2x^2 – 5x – 33 (= 0)$, eg $(2x – 11)(x + 3) (= 0)$ or $x = \frac{--5\pm\sqrt{(-5)^2-4\times2\times-33}}{2\times2}$ or –3, 5.5 oe or for method to solve equation $2y^2 + 10y – 132 (= 0)$, eg. $(2y + 22)(y – 6) (= 0)$ or $y = \frac{-10\pm\sqrt{10^2-4\times2\times-132}}{2\times2}$ or –11, 6	
		A1	for (– 3, – 11)	
		A1	for (5.5, 6) oe	

Modifications to the mark scheme for Modified Large Print (MLP) papers: 1MA1 3H

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme. Notes apply to both MLP papers and Braille papers unless otherwise stated.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5°
Measurements of length: ±5 mm

PAPER: 1MA1_3H			
Question		**Modification**	**Mark scheme notes**
1		Wording added 'Look at the diagram for Question 1 in the Diagram Booklet. It shows a right-angled triangle, ABC.' Diagram enlarged. The diagram labelled ABC. Wording added: 'AB = 4 cm AC = 8.5 cm BC = x cm'. Wording added 'Angle ABC is a right angle.' The right angle made more obvious.	Standard mark scheme
2	(b)	The letter 'd' changed to 'n'	Standard mark scheme but note the change of letter
3		Wording added 'Look at the information for Question 3 in the Diagram Booklet.' Wording added 'as shown in the ratio.'	Standard mark scheme
4		Wording added 'Look at the information for Question 4 in the Diagram Booklet.' Wording added 'The information in the Diagram Booklet shows the cost…'. Diagram enlarged. The information stacked vertically.	Standard mark scheme
5		Wording added 'Look at the diagram for Question 5 in the Diagram Booklet. It shows a frequency polygon.' Wording added 'The table below…'. Wording added 'Amos draws the frequency polygon in the Diagram Booklet…'. Diagram enlarged. Open headed arrows. Change the crosses to dots. The axes labels moved to the top of the vertical axis and to the left of the horizontal axis.	Standard mark scheme
7		The letter x changed to y. Wording added 'Look at the diagram for Question 7 in the Diagram Booklet. It shows…'. Wording added: 'TQ = 2y cm, TS = 4y cm, SR = 3y cm, RV = 5 cm' Wording added 'The trapezium QUVR is shaded.' Diagram enlarged. Open headed arrows. The text moved out of the arrows. Shading changed.	Standard mark scheme
8		Wording added 'Look at the diagram for Question 8 in the Diagram Booklet. It shows a graph.' Wording added 'David uses the graph in the Diagram Booklet…'. Diagram enlarged. Right axes labelled. Open headed arrows. Remove the small squares. The axes labels moved to the top of the vertical axis and to the left of the horizontal axis.	Standard mark scheme

12		Wording added 'Look at the diagram for Question 12 in the Diagram Booklet.' Wording added '…are right-angled triangles with a common side AC.' Wording added 'Angle ACD and angle ACB are right-angles.' Diagram enlarged. The angles moved outside of the angle arcs and the angle arcs made smaller.	Standard mark scheme
15		Wording added 'Look at the diagram for Question 15 in the Diagram Booklet.' Diagram enlarged.	Standard mark scheme
16		Letter 'e' changed to 't'. Letter 'f' changed to 'u'.	Standard mark scheme but note change of letters.
17	(a)	The values changed: 48 changed to 50. 22 changed to 30. 8 changed to 20. 12 changed to 20. Wording added 'Look at the diagram for Question 17(a) in the Diagram Booklet. It shows a grid.' Wording added 'The table below…'. 'On the grid in the Diagram Booklet…'. Diagram enlarged. Small squares removed. Open headed arrows. Grid reduced in size. Axes labels moved to the top of the vertical axis and to the left of the horizontal axis.	Standard mark scheme but note change in values: relative heights: 90, 100, 60, 20, 10

17	(b)	Wording added 'Look at the diagram for Question 17(b) in the Diagram Booklet. It is a histogram which shows…'. The values changed: 0.5 – 1 moved up to 30 small squares (6 squares high); 1– 2 moved up to 25 small squares (5 squares high); 3 – 5 moved up to 5 small squares (1 square high) Diagram enlarged. Small squares removed. Open headed arrows. Shading changed. The axes labels moved to the top of the vertical axis and to the left of the horizontal axis. Question 17(b)  	**M1** for comparing the heights of the bars of the two intervals, showing them in the ratio 5 : 2, eg. height of 1 - 2 = 5 units and height of 3 - 5 = 1 unit or compares areas of bars, eg 10 and 4 **A1** for $0.4n$ oe

18		Open-fronted model provided with a dowel from S to T and D to T. A wedge placed at DTS. DC is labelled with 14 cm. Wording added 'Look at Diagram 1 and Diagram 2 for Question 18 in the Diagram Booklet. You may be provided with a model.' Wording added 'Diagram 1 and the model show a prism ABCDSPQR.' '…a trapezium of area 147 cm^2 as shown in Diagram 2'; 'CD = 14cm.' Diagram 1 to show the original diagram. The line 'DT' joined with a dotted line and an angle arc added. Diagram 2 to show SRCD with 12 cm, 14 cm and two right angles marked. Diagrams enlarged. The dashed lines made longer and thicker. Braille: For **ALL** candidates, provide a **simplified 2D diagram** of the cross section SRCD. Wording added: "Look at the diagram for Question 18 in the separate Diagram Booklet. The diagram is NOT accurately drawn. The diagram is a simplified 2D diagram of the cross section of the prism."	Standard mark scheme
20		Wording added 'Look at the table for Question 20 in the Diagram Booklet.' Wording added 'The table in the Diagram Booklet…'. Table turned vertical.	Standard mark scheme
21		Wording added 'Look at the diagram for Question 21 in the Diagram Booklet. It shows Ray's nine cards numbered 1 to 9.' Diagram enlarged. Braille: Text frames removed and the numbers listed. Words changed to "Ray has nine cards numbered 1 to 9, as listed below."	Standard mark scheme

Paper: 1MA1/1H

Question	Answer	Mark	Mark scheme	Additional guidance
19	$-\frac{1}{2}\pm\frac{1}{2}\sqrt{2}$	P1	for using a common denominator, eg $\frac{x+1}{x(x+1)}-\frac{x}{x(x+1)}$ (= 4) or $\frac{x+1-x}{x(x+1)}$ (= 4) **or** $x+1-x=4x(x+1)$	
		P1	for expanding and rearranging to get $4x^2+4x-1$ (= 0)	Note we don't need to see "= 0"; just the LHS is sufficient Accept other forms of the 3 term quadratic, eg $4x^2+4x=1$
		P1	(dep P1) ft for a method to solve their 3 term quadratic equation, eg $\frac{-4\pm\sqrt{4^2-4\times4\times-1}}{2\times4}$ or $4\left[\left(x+\frac{1}{2}\right)^2-\left(\frac{1}{2}\right)^2\right]-1=0$ oe	Correct use of formula or completing the square
		A1	for values of x, eg $\frac{-4\pm\sqrt{32}}{8}$ or $\pm\sqrt{\frac{1}{2}}-\frac{1}{2}$ oe	
		A1	for $-\frac{1}{2}\pm\frac{1}{2}\sqrt{2}$ oe in the form $a\pm b\sqrt{2}$ where are a and b are fractions	Accept $a=-\frac{1}{2}$, $b=\frac{1}{2}$ or $a=-\frac{1}{2}$, $b=-\frac{1}{2}$

Paper: 1MA1/1H

19	$-\frac{3}{2}$ and $\frac{2}{3}$	M1 M1 A1	for $(2x \pm 3)(3x \pm 2)$ **or** $(6x \pm 4)(x \pm \frac{9}{6})$ **or** $(6x \pm 4)(x \pm \frac{3}{2})$ **or** correct substitution into the quadratic formula, eg $\frac{-5 \pm \sqrt{5^2-4\times6\times(-6)}}{2\times6}$ $(2x + 3)(3x - 2)$ $(6x - 4)(x + \frac{9}{6})$ **or** $(6x - 4)(x + \frac{3}{2})$ **or** $\frac{-5 \pm \sqrt{169}}{12}$ **or** one correct answer oe accept answers of −1.5 and in the range 0.66 to 0.67	

Paper: 1MA1/2H

17	(a)	$(2x + 1)(3x – 4)$	M1	for $(2x \pm 1)(3x \pm 4)$ oe or for brackets which when expanded give 2 out of 3 terms correct	
			A1	cao	
	(b)	$-\frac{1}{2} < x < \frac{4}{3}$	M1	for two critical values with at least one correct, $-\frac{1}{2}$ **or** $\frac{4}{3}$ **or** ft their critical values from (a)	
			A1	for $-\frac{1}{2} < x < \frac{4}{3}$ oe eg $x < \frac{4}{3}$, $x > -\frac{1}{2}$	

Paper: 1MA1/1H

Question	Answer	Mark	Mark scheme	Additional guidance
17 (a)(i)	$(x-4)^2-13$	M1	for start to method of completing the square, eg $(x-4)^2$...	
		A1	cao	
(ii)	$(4, -13)$	B1	ft from answer of form $(x-a)^2-b$	This mark is dependent on a completed square form given in (a)(i)
(b)	0.449 and −1.59	M1	for substitution into quadratic formula, eg $\frac{-8\pm\sqrt{8^2-4\times7\times-5}}{2\times7}$ oe	Condone one sign error
		M1	for simplification to $\frac{-8\pm\sqrt{204}}{14}$ or $\frac{-4\pm\sqrt{51}}{7}$ oe or for one correct solution in decimal form.	One correct solution in the required form out of two solutions given scores 2 marks.
		A1	for 0.448 to 0.449 and −1.59 to −1.6(0)	If an answer is shown in the range in working and then incorrectly rounded award full marks.
(c)	Explanation	C1	for explanation **Acceptable** He hasn't considered the coefficient of 3 He forgot about the 3 The answer $x = 2$ should be $x = \frac{2}{3}$ The first bracket was not $k-2$ $k = 2$ is wrong, he should have divided by 3 **Not acceptable** One of the answers is wrong The solutions are not correct He should have written $3(k-2)(k+4)$ The $3k$ should not be inside the bracket 2 added to –4 does not give 10 $k = 2$ is wrong	

Paper: 1MA1/3H

GCSE

Mark Scheme

Mathematics A (1387)

June 2003

Edexcel
Success through qualifications

Edexcel is one of the leading examining and awarding bodies in the UK and throughout the world. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers.

Through a network of UK and overseas offices, Edexcel's centres receive the support they need to help them deliver their education and training programmes to learners.

For further information please call our Customer Response Centre on 0870 240 9800, or visit our website at www.edexcel.org.uk.

June 2003

Publications Code UG014129

All the material in this publication is copyright
© London Qualifications Ltd 2003

CONTENTS

Notes on Marking Principles 2
Paper 5501 4
Paper 5502 11
Paper 5503 17
Paper 5504 24
Paper 5505 32
Paper 5506 40

NOTES ON MARKING PRINCIPLES

NOTES ON MARKING PRINCIPLES

1 Three types of mark are available

M marks - awarded for correct working seen or implied.
A marks - conditional accuracy marks which are awarded for accurate working following the award of M marks.
B marks - unconditional accuracy marks (independent of M).

2 Abbreviations

cao - correct answer only.
ft - follow through.
$\surd$ - Denotes a "follow through" answer.

SC - special case.
isw - ignore subsequent working.
oe - or equivalent (and appropriate).
NB: a candidate cannot benefit from both isw and ft.

3 If no working shown, then

correct answers normally score full marks
incorrect (even though nearly correct) answers score no marks.

4 Marking instructions

Misread loses A marks (and sometimes B marks) on that part but ft can be allowed on subsequent parts. M marks can still be earned. If in doubt contact your team leader.
If there is a wrong answer in the answer space DO CHECK the working in the body of the script.

- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.
- If there is a wrong answer in the answer space DO CHECK the working in the body of the script.
- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.

5 Style of marking

Answer correct: tick and write part mark in margin NEXT TO BRACKETED MARK.
Answer incorrect: cross, but show M, A or B marks if any earned in body of script and transfer the total of these to the margin next to the bracket mark.
Total for each double page at bottom right page (except for back if used), FINAL TOTAL IN RELEVANT BOX ON FRONT COVER.
Nought in margin for fully incorrect question or page AND FOR NO ATTEMPT.
Where no attempt has been made a line should be put in the answer space and zero in the margin next to the bracketed mark
CHOICE OF METHOD – No marks unless one answer is in answer space – then mark that.
CROSSED OUT WORK - if not replaced this should be marked (if legible).
There must always be a mark next to bracketed mark in the margin/

6 Follow Through Marks

Follow throughs are guided by two principles:

(a) Follow throughs which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous, do not award.

(b) Follow throughs which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

7 Probability

Probability answers must be given as fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least two decimal places (unless tenths).

Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.

8 Linear Equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

9 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

Paper 5501

No	Working	Answer	Mark	Notes
1 (a)		46	1	B1 cao
(b)		3.4	1	B1 oe
(c)		Arrow at 430	1	B1 allow ± half graduation
(d)		Arrow at 3.7	1	B1 allow ± half graduation Accept indications other than arrows as long as they are clear
2		1.60 2.05	2	B1) Condone B1) reversal
3 (a)	$\frac{18}{24}$ or $\frac{9}{12}$ or $\frac{6}{8}$	$\frac{3}{4}$	2	B2 for $\frac{3}{4}$ cao (B1 for $\frac{18}{24}$ or $\frac{9}{12}$ or $\frac{6}{8}$) SC B1 for $\frac{1}{4}$ only
(b)		16 squares shaded	1	B1 cao
4 (a)		line	1	B1 within overlay tolerance
(b)		midpoint	1	B1 within overlay tolerance ft from (a) ± 0.2cm
(c)		rectangle	1	B1 for rectangle 6 cm ± 0.2cm by 4 cm ± 0.2cm
5		kilograms, kg litre, *l* or cubic metres, m^3 inches, in	3	B1 B1 B1
6 (a)		parallel lines marked	1	B1
(b)		right angle marked	1	B1
(c)(i)		acute	1	B1
(ii)		reflex	1	B1

Paper 5501

No	Working	Answer	Mark	Notes
7 (i)		sphere	1	B1
(ii)		cylinder	1	B1 Accept circular prism
(iii)		pyramid	1	B1 Condone omission of "triangular" Accept tetrahedron
8 (a)(i)		40	2	B1 cao
(ii)		50		B1 cao
(b)		5 complete symbols	1	B1 cao
(c)		 and oe inc	1	B1
9 (i)		9, 37, 56, 59, 75	5	B1 cao
(ii)		0.067, 0.56, 0.6, 0.605, 0.65		B1 cao Ignore trailing zeros
(iii)		–10, –6, –4, 2, 5		B1 cao
(iv)		$\frac{2}{5}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$		B2 for all 4 correct (B1 for any 3 in correct order) SC B1 for all 4 in reverse order (applies to(iv) only)
10 (a)			1	B1
(b)		Plotting (4, 24)	1	B1 ft from their matchsticks
(c)		60	1	B1 cao
(d)		$m = 6n$	2	B2 for $m = 6n$ oe (B1 for $6n$ oe or m = multiple of n except $m = n$)
11 (i)		6, 12	4	B1 cao
(ii)		4, 16		B1 cao
(iii)		3, 4, 6 or 3, 4, 6, 12		B1 Condone omission of 12
(iv)		8, 27		B1 cao

Paper 5501

No	Working	Answer	Mark	Notes
12		2.43	4	B1 for 36 or 0.36 B1 for 96 or 0.96 B1 for 125 or 1.25 If none of first 3 B1s awarded then SC B1 for four 24s and five 25s seen OR 4 × 24 and 5 × 25 seen B1 for 2.43 cao
13 (a)(i)		Edinburgh and Plymouth	3	B1 for Edinburgh or −7 B1 for Plymouth or 5
(ii)		12		B1ft from (i) if one positive and one negative
(b)		Cardiff and Belfast London and Plymouth	2	B1 for Cardiff and Belfast OR −6 and −4 B1 for London and Plymouth OR 3 and 5
14		5 9 8	3	B1 cao B1 cao B1 cao
15 (a)			2	✓ / × / blank 2 / 0 / B2 1 / 0 / B1 1 / 1 / B1 2 / 1 / B1
(b)	$2\times2\times2$	8	2	M1 for $2\times2\times2$ A1 for 8 cao
16 (a)		30	1	B1 cao
(b)		3	1	B1 cao
(c)	$2 \times 29 = 58$ $5 \times 30 = 150$ $2 \times 31 = 62$ $1\times32 = 32$ $\frac{302}{10} = 30.2$	30.2	3	M1 for freq × no pins M1 (dep on 1st M1) for totalling and ÷ 10 A1 for 30.2 cao

Paper 5501

No	Working	Answer	Mark	Notes
17		7 5 5 13 33 52 23	3	B3 all correct (B2 for 4, 5 or 6 correct B1 for 2 or 3 correct)
18 (a)(i) (ii) (iii) (iv) (b)		$4c$ p^4 $8g$ $10pr$ OR $10rp$ $10y - 15$	4 1	B1 oe B1 cao B1 oe B1 B1 cao Accept $10y + - 15$
19		$\frac{2}{3}$	3	M1 for 3 rows (9 squares) shaded M1 for 2 columns (10 squares) shaded A1 for $\frac{2}{3}$
	$\frac{3}{5} = \frac{9}{15}$ $\frac{2}{3} = \frac{10}{15}$	$\frac{2}{3}$	3	M1 for $\frac{3}{5} = \frac{9}{15}$ M1 for $\frac{2}{3} = \frac{10}{15}$ A1 for $\frac{2}{3}$
	$\frac{3}{5} = 0.6$ $\frac{2}{3} = 0.66$ or 0.67 or better	$\frac{2}{3}$	3	M1 for $\frac{3}{5} = 0.6$) Accept M1 for $\frac{2}{3} = 0.66$ or 0.67 or better) percentages A1 for $\frac{2}{3}$

Paper 5501

No	Working	Answer	Mark	Notes
20 (a)	955 × 48 7640 38200 45840 OR 48 × 955 240 2400 43200 45840	458.40	3	M1 for complete correct method (condone one computational error) A2 for 458.40 cao (A1 for digits 4584 OR ft if M1 awarded)
(b)	14. 5 48 | 696. 0 48 216 192 24 0 24 0	14.50	3	M1 for 1 as first digit in answer and remainder 21 M1 (dep) 4 as second digit in answer A1 for 14.50 (Accept 14.5)
21 (a)		$12x$	1	B1 oe
(b)		$12x + 10y$	2	B2 oe ft from (a) (B1 $12x$ + multiple of y or $10y$ seen) SC B1 for $x = 12x + 10y$ OR $y = 12x + 10y$

Paper 5501

No	Working	Answer	Mark	Notes
22	$\frac{1}{3}+\frac{1}{4}=\frac{4}{12}+\frac{3}{12}=\frac{7}{12}$ $1-\frac{7}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	M1 for $\frac{4}{12}$ **and** $\frac{3}{12}$ oe A2 for $\frac{5}{12}$ oe (A1 for $\frac{7}{12}$) B1 for 1–"$\left(\frac{1}{3}+\frac{1}{4}\right)$" correctly evaluated
	$1-\frac{1}{3}=\frac{2}{3}$, $1-\frac{1}{4}=\frac{3}{4}$ $\frac{8}{12}-\frac{3}{12}=\frac{5}{12}$ or $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	B1 for $\frac{2}{3}$ or $\frac{3}{4}$ seen M1 for $\frac{8}{12}-\frac{3}{12}=\frac{5}{12}$ or $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}$ A1 for $\frac{5}{12}$ oe
		$\frac{5}{12}$	3	M1 for 0.25 and 0.33 or better A1 for 0.58 or better A1 for $0.41\dot{6}$ or recurring
23 (a) (b)(i) (ii)	 180 – (54 + 54)	54 72 Reason	1 3	B1 cao M1 for 180 – (54 + 54) A1 ft from (a) if $x < 90$ B1 for mentioning isosceles and equal or base angles or equal sides and equal or base angles

Paper 5501

No	Working	Answer	Mark	Notes
24 (a)		Bryani	2	M1 for 4×9 or $4 \times 3 \times 3$ or $4 \times x \times x$ or square x first or square 3 first A1 SC 4×3^2 with Bryani scores B2
(b)		64	1	B1 cao
25 (a)		 dotted line may be solid	3	B2 for rectangle base 3 squares and height 4 squares (B1 for rectangle with one correct dimension) B1 for horizontal line 1 cm from top) SC B2 for completely correct elevation on its side
(b)			2	B2 for perspective drawing showing slant face and cutout B1 for perspective drawing with either slant face cutout omitted
26 (a)	20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$	40	2	M1 for 20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$ A1 cao
(b)	$\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes	line from (45, 20) to (65, 0)	2	M1 for $\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen A1 for correct line SC If M0, B1 for line from (45, 20) to (t, 0) where $t > 45$ or B1 for a line of the correct gradient.

Paper 5502

No	Working	Answer	Mark	Notes
1 (a)		$\frac{7}{100}$	1	B1 cao accept 0.07
(b)		0.18	1	B1 cao
(c)	20 in 100 oe	40	2	M1 for sight of 20 in 100 or 20 × 2 A1 cao
2 (a)		6cm	2	B1 for 6 ± 0.2 or 60 ± 2 B1 indep for cm or mm consistent with 1st B1
(b)		At centre	1	B1 within overlay
(c)		Circle drawn	1	B1 all within overlay
3		See diagram	3	B3 all correct – see separate sheet (B2 for 3 correct B1 for 2 correct)
4 (a)		$\frac{1}{4}$ oe	1	B1 cao
(b)		0.75	1	B1 cao
(c)		75%	1	B1 cao
(d)(i)		9	2	B1 accept answer in range 9 - 9.2
(ii)		15 - 16		B1 accept answers in range15 - 16
5 (a)		9:30	1	B1 cao
(b)		2hrs 45 min	2	B2 for 2hr 45 min or 2 $\frac{3}{4}$ hr or 165 minutes B1 2:45 or 2.45 or 165 or 45min + 1hr + 1hr oe
(c)		17	1	B1 cao
6 (a)	96 × 4	3.84	2	M1 for 96 × 4 or digits 384 A1 cao
(b)	3 × 96 + 40 = 328	(0).56	2	M1 for 3 × 96 + 40 or digits 328 or digits 56 A1 cao accept 56p

Paper 5502

No	Working	Answer	Mark	Notes
7 (a)		54 000	1	B1 cao accept 54 thousand
(b)		50 000	1	B1 (accept ten thousand or 10 000) oe
8 (a)		14	1	B1 cao
(b)		6	1	B1 cao
(c)		Correct reflection	2	B2 fully correct (B1 correct reflection in a line parallel to the mirror line or condoning 1 block error in shape or position of shape)
9 (a)		Missing horiz label 1 (and 6) missing on vertical scale	2	B1 B1
(b)		Correct graph	2	B1 for bar up to 4 for yellow B1 for bar up to 2 for green
(c)		Blue	1	B1 cao
(d)	3 + 5 + 4 + 2	14	1	B1 ft from (b)
(e)		$\frac{3}{14}$	1	B1 ft on '14'
10	Barry (8) because you double Kath (7) because you add, 1,2,3		2	B1 oe B1 oe SC: B1 for correct rules only
11 (a)		$2n$	1	B1 for $2n$ or $n + n$ OR $2 \times n$ OR $n \times 2$ OR $n2$
(b)		$2n + 15$	1	B1 for "$2n$" + 15 oe
(c)		20q	1	B1 cao
12 (a)	1 + 3 + 5 + 8 + 5	22	2	M1 add frequencies A1 cao
(b)		No, is>no of cups of coffee in the table	1	B1 'average cannot be bigger than 6' oe OR 'Average must be less than 6 oe'
13 (a)		Trapezium	1	B1 cao ignore spelling
(b)		(2, 3)	1	B1 cao
(c)		Isosceles	1	B1 cao ignore spelling
(d)		Q correct	1	B1 cao

Paper 5502

No	Working	Answer	Mark	Notes
14 (a)		250 000	1	B1 cao
(b)	$\frac{28}{4}$	7	2	M1 for $\frac{28}{4}$ oe or "250000" × 28 A1 cao **SC** B1 for 7 000 000
15 (a)		10	1	B1 cao
(b)		5.5	1	B1 ±0.3 pounds
(c)	$\frac{110}{22}$	50	3	M1 for use of graph at 11 or $\frac{110}{22}$ A1 for 5 A1 cao **SC** B2 for 49.5 – 50.6

Paper 5502

No	Working	Answer	Mark	Notes
16 (a)	$269.30 - 56.80 = 212.50$ $\frac{212.50}{42.50}$	6	2	M1 for $\frac{269.30 - 56.80}{42.50}$ or 5 seen A1 cao
(b)	5% of £269.30 £269.30 – "£13.465" OR $\frac{95}{100} \times 269.30$	255.83 or 255.84	3	M1 for $(5 \div 100) \times 269.30$ M1 for $269.30 - $ "13.465" A1 cao OR M2 for $\frac{95}{100} \times 269.30$ A1 cao **Alternative Method:** M1 for $\frac{5}{100} \times 56.80$ (= 2.84) and $\frac{5}{100} \times 42.50$ (=2.12(5)) (OR 53.96 AND 40.38 (40.375) seen M1 for $56.80 -$ "2.84" (= 53.96) $42.50 -$ "2.12(5)" (= 40.375 or 40.38) "5" × "40.375" + "53.96" A1 cao
17	$4.1^2 \times 1.07 = 16.81 \times 1.07$	17.9867	2	M1 for ("4.1") followed by squaring, or sight of 16.81 A1 cao SC: *B1 for 18 or better with no working*
18 (a)		60	1	B1 cao
(b)	$360 - 60 - 90 - 90$	120	2	M1 for $360 -$ " 60 " $- 90 - 90$ or $180 -$ "60" A1 cao
(c)	6×2	12	2	M1 for 6×2 A1 cao for 12

Paper 5502

No	Working	Answer	Mark	Notes
19 (a)(i)	$240 \times 5 = 1200$	1250	3	B1 cao 1250
(ii)	$\frac{50}{'1250'}$	$\frac{1}{25}$		M1 cao $\frac{50}{'1250'}$ A1 for $\frac{1}{25}$ in its simplest form
(b)	$\frac{60}{100} \times 1000 = 600$	12:5	3	M1 for $\frac{60}{100} \times 1000$ oe A1 for 600 A1 cao
20 (a)		$x + 2$	1	B1 accept $2 + x$ but not $x = x + 2$
(b)	$x + 5 + x + 5 + x + 2 + x + 2$	$4x + 14$	2	M1 adding 4 sides, two of which are '$x + 2$' (all sides to be linear expressions in x) **SC** $x + 5 + x + 2 \times 2$ gets M1 A1 for correct simplified answer or $(20 - 14) \div 4$ oe gets M1
(c)	'$4x + 14$' = 20	1.5 oe	2	M1 for equation A1 cao
21	$\sum f = 90$	Angles drawn, labelled	3	M1 for 1 person = 4°or one angle correct in table or pie chart A1 any 2 correctly drawn angles in pie chart A1 fully correct chart labelled
22 (a)		$2p - q$	2	B1 cao for $2p$ B1 cao for $-q$ accept $(-q + 2p)$, $2p - 1q$ and $2p + -q$
(b)	$5x = 3 + 4$	1.4	2	M1 for either (+3 or sight of 7) or (÷ 5 or sight of 0.8 and 0.6) A1 cao accept $\frac{7}{5}$ or $1\frac{2}{5}$

Paper 5502

No	Working	Answer	Mark	Notes
23 (a)		$\frac{4\times5}{2}$	1	B1 cao
(b)	$1+2+3+4+5+6+7+8$	$\frac{8\times9}{2}$	1	B1 cao
(c)	$\frac{100\times101}{2}$	5050	1	B1 cao
24	0 | 5 7 8 8 1 | 0 0 0 0 2 5 5 5 6 2 | 0 0 0 4 5 3 | 3 5 Key 1 | 2 = 12 (min)	See working	3	B1 for stem 0, 1, 2, 3 or 0, 10, 20, 30 B1 for accurate unordered leaves condone 1 error or omission B1 for key and ordered leaves all correct
25	$3.2\times2.8=8.96$ $2\times4.5\times2.8=25.2$ $2\times4.5\times28.8=28.8$ $\frac{62.96}{2.5}\times2.99$	£75.30	5	M1 for area of any face found correctly M1 for 2 areas found correctly A1 for 62.96 or 54 M1 for $\frac{'62.96'}{2.5}\times2.99$ Al cao Alternate method for candidates who round up $\frac{"62.92"}{2.5}$ M1 for "26" × 2.99 A1 for £77.74 cao **SC**: *for top included B2 for 71.92 m^2 seen or* B3 for £86.02 seen **SC** B4 for £64.58 or £65.78 seen
26	$2.5\times10\,000$	25 000	2	M1 for $2.5\times100\times100$ A1 cao

Paper 5503

No	Working	Answer	Mark	Notes
1 (a)(i)		$8g$	2	B1 oe
(ii)		$10rp$		B1 for $10pr$ or $10\ rp$
(b)		$10y - 15$	1	B1 cao accept $10y$ - + 15
(c)	$6x + 8 - 12x + 15$	$-6x + 23$	2	M1 for 3 correct terms out of 4 A1 cao
2		$m = 6n$	2	B2 for $m = 6n$ oe accept $6 \times n$, n 6 (B1 for $6n$ alone, or $6n$ +1 oe OR m = multiple of n except $m = n$)
3 (i)		0.067, 0.56, 0.6, 0.605, 0.65	1	B1 cao Ignore trailing zeros
(ii)		$-10, -6, -4, 2, 5$	1	B1 cao
(iii)		$\frac{2}{5}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$	2	B2 all four correct (B1 any three in correct order) SC: B1 all 4 in reverse order
4		7 5 5 13 33 52 23	3	B3 all correct (B2 for 4, 5 or 6 correct entries) (B1 for 2, 3 correct entries)

Paper 5503

No	Working	Answer	Mark	Notes
5		$\frac{2}{3}$	3	M1 for 3 rows (9 squares) shaded M1 for 2 columns (10 squares) shaded A1
	OR $\frac{3}{5}=\frac{9}{15}$ $\frac{2}{3}=\frac{10}{15}$ Therefore $\frac{2}{3}>\frac{3}{5}$	$\frac{2}{3}$		M1 for $\frac{3}{5}=\frac{9}{15}$ M1 for $\frac{2}{3}=\frac{10}{15}$ A1
	OR $\frac{3}{5}=0.6$ or percent $\frac{2}{3}=0.66$ or 0.67 or better Therefore $\frac{2}{3}>\frac{3}{5}$	$\frac{2}{3}$		M1 for $\frac{3}{5}=0.6$ or percent M1 for $\frac{2}{3}=0.66$ or 0.67 or better A1
6	$2\times 29=58$ $5\times 30=150$ $2\times 31=62$ $1\times 32=32$ $\frac{302}{10}=30.2$	30.2	3	M1 for freq × no. pins (at least 3) M1 for totalling and for ÷ 10 (dep on 1st M1) A1 cao
7 (a)			2	B1 for 180° rotation (wrong centre) B1 cao
(b)			3	B1 for any enlargement sf other than 1 B1 for all sides halved B1 for position

Paper 5503

No	Working	Answer	Mark	Notes
8 (a)		$12x$	1	B1 oe
(b)		$12x + 10y$	2	B2 oe or ft from (a) (B1 for $12x$ + a multiple of y or $10y$ seen) **SC** B1 for $x = 12x + 10y$ or $y = 12x + 10y$
9	$\frac{1}{3}+\frac{1}{4}=\frac{4}{12}+\frac{3}{12}=\frac{7}{12}$ $1-\frac{7}{12}=\frac{5}{12}$ OR $1-\frac{1}{3}=\frac{2}{3}, 1-\frac{1}{4}=\frac{3}{4}$ $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}, \frac{8}{12}-\frac{3}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	M1 for $\frac{4}{12}$ and $\frac{3}{12}$ oe A2 for $\frac{5}{12}$ oe (A1 for getting $\frac{7}{12}$) (B1 for $1 - \frac{"1}{3} + \frac{1"}{4}$ correctly evaluated) OR B1 for $\frac{2}{3}$ or $\frac{3}{4}$ seen M1 for $\frac{3}{4}-\frac{1}{3}=\frac{9}{12}-\frac{4}{12}$ or $\frac{2}{3}-\frac{1}{4}=\frac{8}{12}-\frac{3}{12}$ A1 for $\frac{5}{12}$ oe OR M1 0.25 and 0.33 or better A1 for 0.58 or better A1 for 0.416 *recurring*
10 (a)		54	1	B1 cao
(b)(i)	180 – (54 +54)	72	3	M1 for 180 – (“54” + “54”) A1 for 72° ft from (a) if $x < 90°$
(ii)				B1 for mentioning isosceles and equal or base angles or equal sides and equal or base angles

Paper 5503

No	Working	Answer	Mark	Notes
11 (a)	Bryani was correct $4 \times 3^2 = 4 \times 9 = 36$	Bryani	2	M1 for 4×9 or $4 \times 3 \times 3$ or "square the three/x then multiply by four" A1 Bryani **SC** 4×3^2 with Bryani gets B2
(b)			1	B1 cao
12 (a)			3	B2 for rectangle height 4 squares, base 3 squares (B1 for rectangle with one correct dimension) B1for line 1 square from the top **SC** B2 for completely correct elevation on its side
(b)			2	B2 for perspective drawing showing slant face and cut out (B1 for perspective drawing with either slant face or cut out omitted or one aspect incorrect)
13 (a)	20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$	40	2	M1 for 20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$ A1 cao
(b)	$\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen	Line from (45, 20) to (65, 0)	2	M1 for $\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen A1 for correct line **SC** If M0, B1 for line from (45, 20) to (t, 0) where $t > 45$ or a line of the correct gradient
14 (i)		119.31	3	B1 cao
(ii)		119 310		B1 cao
(iii)		1.23		B1 cao

Paper 5503

No	Working	Answer	Mark	Notes
15	$\frac{10}{100}\times 12000$ 12 000 – 1200 = 10 800 $\frac{10800}{10}=1080$ 10 800 – 1080 = £9720	£9720	3	M1 for $\frac{10}{100}\times 12000$ or sight of 1200 or 2400 or 10 800 or 9600 M1 (dep) for $\frac{10}{100}\times(12\,000-\frac{10}{100}\times 12000)$ or sight of 1080 A1 cao Alternative mark scheme M2 for $12000\times(1-\frac{10}{100})^2$ (M1 for $12000\times(1-\frac{10}{100})$ A1 cao
16 (a)	$2p = 6$	$p = 3$	2	M1 for $7p - 5p = 8 - 2$ or $2p$ or 6 A1 cao
(b)	$7r - 5r = -20 - 2$	–11	2	M1 for $7r + 2 = 5r - 20$ or $\frac{7r}{5}+\frac{2}{5}=r-4$ or $7r - 5r = 20 - 2$ or $\frac{7r}{5}-r=-4-\frac{2}{5}$ A1 cao
17		$5n + 1$	2	B2 oe (B1 for $5n$ seen) NB: n = gets B1 max

Paper 5503

No	Working	Answer	Mark	Notes
18 (a)	–1, 0, 1		2	B2 for –1, 0, 1 (B1 for –1, 0 or 0,1 or –1,1 or –2, -1, 0, 1 only)
(b)	(–1, –1), (0, –1), (1, –1), (0, 0), (1, 0), (1, 1)		3	B3 for 6 points correct B2 for 3 points correct B1 for 1 point correct **NB** –B1 each additional point over six
19 (a)	Triangle with vertices at (0,0) (0,–2) and (3,0)		2	M1 for correct orientation A1 cao
(b)	Rotation, 180°, centre (0,1) Enlargement sf - 1 centre (0,1)		2	B2 for 180° 'rotation' centre (0, 1) B2 for Enlargement sf - 1 centre (0,1) (B1 for any two of the three parts) NB: B0 if additional transformation is included
20	Bisector of $\angle BAC$ Arc around A Region		3	B3 cao (B2 for either two correct boundaries, no shading/ wrong shading or one correct boundary, one incorrect boundary with valid shading) (B1 for either two incorrect boundaries but one drawn from A and one intersection, with valid shading or one correct boundary) Ignore shading outside the triangle
21		Length Volume Area	3	B1 for Length B1 for Volume B1 for Area
22 (a)	Unbiased question with choices		2	B1 for unbiased question B1 for at least 2 choices
(b)			2	Classification 1: A biased question Classification 2: A restricted sample of people Classification 3: Not specifying a range of foods Classification 4: Nothing to do with eating habits B2 reasons which satisfy 2 different classifications (B1 a reason which satisfies one classification)



Paper 5503

No	Working	Answer	Mark	Notes
23 (a)	$6 \times 10^2 \times 8 \times 10^4$ 48×10^6	4.8×10^7	3	M1 for $6 \times 10^a \times 8 \times 10^b$ oe, a and b integers including 0 A1 for 48×10^6 oe A1 cao
(b)	200 000 + 30 000	230000	2	B2 cao (B1 for sight of 200 000 or 30 000 or 2.3×10^5 or 23×10^4)
24 (i)		64	4	B1 cao
(ii)		3		B1 cao
(iii)	$\sqrt{16 \times 9} = \sqrt{144}$	12		B2 cao (B1 for sight of $\sqrt{2^4} \times \sqrt{9}$ or better, or 144 seen)
25 (i)	Tangent 90° to diameter /radius/ line from (through) centre	27°	4	B1 for 27° cao B1 for reason
(ii)	180 –(90+ "27") angle in semicircle (is 90°)/Alternate segments /angle at centre twice at circumference	63°		B1 ft for 90–"27" if not 63° B1 for reason
26 (a)(i)		152	2	B1 cao
(ii)		177		B1 cao
(b)			3	B1 for median marked at 167 B1 ft for postion of box with its ends at "152" and "177" B1 for position of whiskers with ends at 132 and 182 NB: For any points plotted between 141 and 149 give a tolerance of an extra ± 1 square
27	$x^2 + xy + xy + y^2$	$x^2 + 2xy + y^2$	2	M1 for at least 3 of the 4 terms correct A1 cao
		25	2	M1 for recognising 3.47 + 1.53 (= 5) A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
1 (a)	$4.1^2 \times 1.07 = 16.81 \times 1.07$	17.9867	2	M1 for (4.1) followed by squaring, or sight of 16.81 A1 cao SC: B1 for 18 or better with no working
(b)		$(1.6 + 3.8 \times 2.4) \times 4.2$	1	B1 cao Allow additional brackets if they give an expression with value 45.024
2 (a)	269.30 – 56.80 = 212.50	6	2	M1 for $\frac{269.30 - 56.80}{42.50}$ or 5 seen A1 cao
(b)	5% of £269.30 £269.30 – "£13.465" OR $\frac{95}{100} \times 269.30$	255.83 or 255.84	3	M1 for (5 ÷ 100) × 269.30 M1 (dep) for 269.30 – "13.465" A1 cao OR M2 for $\frac{95}{100} \times 269.30$ A1 cao **Alternative Method:** M1 for $\frac{5}{100} \times 56.80$ (= 2.84) and $\frac{5}{100} \times 42.50$ (=2.12(5)) (OR 53.96 AND 40.38 (40.375) seen M1 for 56.80 – "2.84" (= 53.96) 42.50 – "2.12(5)" (= 40.375 or 40.38) "5" × "40.375" + "53.96" A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
3 (a)		60	1	B1 cao
(b)	360 – 60 – 90 – 90	120	2	M1 for 360 – "60" – 90 – 90 or 180 – "60" A1 cao
(c)	6 × 2	12	2	M1 for 6 × 2 A1 cao 12
(d)		Correct drawing	2	B2 for triangle and construction lines (see overlay) (B1 for 1 line of length 4cm and correct arcs crossing OR for correct triangle with either no arcs or incorrect arcs) SC: B1 similar triangle drawn with construction lines
4 a(i)	240 × 5 = 1200	1250	3	B1 cao 1250
(ii)	$\frac{50}{1250}$	$\frac{1}{25}$		M1 $\frac{50}{"1250"}$ A1 oe in its simplest form
(b)	$\frac{60}{100} \times 1000 = 600$ 600: 250	12:5	3	M1 for $\frac{60}{100} \times 1000$ oe A1 for 600 A1 cao
5 (a)		$x + 2$	1	B1
(b)	$x + 5 + x + 5 + x + 2 + x + 2$	$4x + 14$	2	M1 adding 4 sides, two of which must be '$x + 2$' (all sides to be linear expressions in x) A1 for correct simplified answer
(c)	"$4x + 14$" = 20	1.5	2	M1 for equation "$4x + 14$" = 20 OR $\frac{20-14}{4}$ oe A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
6 (a)		$2p - q$	2	B1 cao for $2p$ B1 cao for $-q$ accept $-q + 2p$ and $2p - 1q$
(b)	$5x = 3 + 4$	1.4	2	M1 for either (+3 or sight of 7) or (÷ 5 or sight of 0.8 and 0.6) A1 cao accept $\frac{7}{5}$ or $1\frac{2}{5}$
7 (a)		$\frac{4\times5}{2}$	1	B1 cao
(b)	$1 + 2 + 3 + 4 + 5 + 6 + 7 + 8$	$\frac{8\times9}{2}$	1	B1 cao
(c)	$\frac{100\times101}{2}$	5050	1	B1 cao
(d)		$\frac{n(n+1)}{2}$	2	B2 cao (B1 for any quadratic in n)
8	$3.2 \times 2.8 = 8.96$ $2 \times 4.5 \times 2.8 = 25.2$ $2 \times 4.5 \times 3.2 = 28.8$ $\frac{62.96}{2.5} \times 2.99$	75.30	5	M1 for area of any face found correctly M1 for 2 areas seen A1 for 62.96 or 54 M1 for $\frac{'62.96'}{2.5} \times 2.99$ A1 cao Alternate method for candidates who round up $\frac{"62.96"}{2.5}$ M1 for "26" x 2.99 A1 for £77.74 cao SC: for top included B2 for 71.92 m^2 seen or B3 for £86.02 or £86.71 SC: B4 for £64.58 or £65.78 seen

Paper 5504

No	Working	Answer	Mark	Notes
9	2.5×10000	25000	2	M1 for 2.5×10000 or $2.5 \times 100 \times 100$ A1 cao
10 (a)	$\sum f = 90$ (88), 144, 32, 96	Angles drawn, labelled	3	M1 for 1 person = 4° or one angle correct in table or pie chart A1 any 2 angles correctly drawn in pie chart A1 fully correct chart labelled
(b)	$0.38 + 0.27 + 0.15$	0.20	2	M1 1 – sum A1 cao
11	0 | 5 7 8 8 1 | 0 0 0 0 2 5 5 5 6 2 | 0 0 0 4 5 3 | 3 5 Key 1 | 3 = 13 (min)	See working column	3	B1 for stem 0, 1, 2, 3 or 0, 10, 20, 30 B1 for accurate unordered leaves condone 1 error or omission B1 for key and ordered leaves all correct
12 (a)	$V = \pi \times 4^2 \times 10$	502 – 503	2	M1 for $\pi \times 4^2 \times 10$ A1 502 – 503
(b)	$P^2 = 10^2 + 8^2$ $P = \sqrt{164}$	$\sqrt{164} < 13$	3	M1 for sight of a correct right-angled triangle M1 for $10^2 + 8^2$ A1 for conclusion based on a correct calculation or 12.8 seen
13 (a)	2×30	$2 \times 2 \times 3 \times 5$	4	M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
	2×48	$2^5 \times 3$		M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
(b)		12	1	B1 cao
(c)	$2^5 \times 3 \times 5$	480	2	B2 cao B1 for $2^5 \times 3 \times 5$ or any correct common multiple

Paper 5504

No	Working	Answer	Mark	Notes
14 (a)		$150 < C \leq 200$	2	M1 use of cum freq to find the cost of the 20th or 20.5^{th} car OR $\frac{1}{2}\Sigma f$ or $\frac{1}{2}(\Sigma f + 1)$ A1 eg 150 to 200
(b)		No, because the 21st value is in the same interval	1	B1 20.5^{th} or 21st in same interval or an alternative correct explanation
(c)	80% = 5200 $\frac{5200}{80} \times 100$	6500	3	M1 for (100 – 20) % = 5200 M1 for $\frac{5200}{"80"} \times 100$ A1 cao
15 (a)	$x^2(x + 1) = 230$	AG	2	M1 for $x \times x \times (x+1)$ or $x \times x \times x + 1$ oe A1 cao from $x \times x \times (x+1)$
(b)	'5 – 150 5.1 – 158.7 5.2 – 167.6 5.3 – 177.0 5.4 – 186.6 5.5 – 196.6 5.6 – 207.0 5.7 – 217.7 5.8 – 228.8 5.9 –240.2 5.85 – 234.4	5.8	4	B 2 for trial between 5.8 and 5.9 inclusive (B1 for different trial between 5 and 6 inclusive) B1 for different trial between 5.8 and 5.85 (not including 5.8) B1 (dep on at least one previous B1) cao for 5.8, 5.81, 5.811

Paper 5504

No	Working	Answer	Mark	Notes
16	$\pi \times \left(\frac{15}{2}\right)^2 = 176.715$	88.4cm^2	3	M1 for $\pi \times \left(\frac{15}{2}\right)^2$ A1 88.3 – 88.4 B1(ind) for cm²
17 (a)	$5 = 0.5x + 1$	8	2	M1 for $5 = 0.5x + 1$ A1 cao
(b)		$y = \frac{1}{2}x + c$	1	B1 $y = \frac{1}{2}x + c$, c ≠ 1, oe
(c)		$x = 2y - 2$ OR $x = 2(y - 1)$	2	M1 for correctly multiplying both sides by 2 or correctly isolating $\frac{x}{2}$ A1 for $x = 2(y - 1)$, $x = \frac{y-1}{0.5}$, $x = \frac{y-1}{\frac{1}{2}}$ oe SC: B1 for $x = 2y - 1$
18	$4x - 6y = 22$ $15x + 6y = 54$ $19x = 76$	$x = 4,\ y = -1$	4	M1 for coefficients of x or y the same followed by correct operation , one arithmetical error A1 cao M1(dep on previous M mark) for sub for other variable A1 cao Trial and improvement –0 unless both x and y correct values found

Paper 5504

No	Working	Answer	Mark	Notes
19 (a)	$SF = \frac{10}{6}$ $\frac{10}{6} \times 4.8 = 8$	8	2	M1 for sight of $\frac{10}{6}$ or $\frac{6}{10}$ or 1.67 or better or $\frac{CD}{10} = \frac{4.8}{6}$ A1 cao
(b)	$\frac{10}{6} \times 4.5 - 4.5 = 3$	19.8	2	M1 for use of SF from (a) to find *BC* or *AC* and adding 4 sides A1 cao
20	$\frac{6 \times 10^{15}}{3.2 \times 10^{8}}$ 1.875×10^{7}	4.3×10^{3}	3	B3 for 4.3×10^{3} to 4.34×10^{3} (B2 for 1.875×10^{7} oe or 4300 to 4340 or final answer of 1.9×10^{7}) (B1 for sight of 6×10^{15} oe or 3.2×10^{8} oe)
21	$8.5 \times \tan 38 = 8.5 \times 0.7813$	6.64	3	M1 for correct use of trig, eg $\tan 38 = \frac{opp}{8.5}$ M1 for 8.5 × tan38 A1 6.64 – 6.641

Paper 5504

No	Working	Answer	Mark	Notes
22 (a)		No, as you would expect about 100. Yes, as it is possible to get 200 sixes with a fair dice	1	B1 for a consistent answer
(b)	$\frac{1}{6}, \frac{5}{6}$ + labels		3	B1 for $\frac{5}{6}$ on the red dice, *not six* branch B1 for a fully complete tree diagram with all branches labelled B1 for $\frac{1}{6}$, $\frac{5}{6}$ on all remaining branches as appropriate

Paper 5505

No	Working	Answer	Mark	Notes
1 (i) (ii) (iii)		119.31 119310 1.23	3	B1 cao B1 cao B1 cao
2	$\frac{10}{100}\times 12000 = 1200$ 12 000 – 1200 = 10 800 10 800 ÷ 10 =1080 10 800 – 1080 = £9720	9720	3	M1 for $\frac{10}{100}\times 12\,000$ or sight of 1200 or 2400 or 10 800 or 9600 M1 (dep) for $\frac{10}{100}\times(12\,000 - \frac{10}{100}\times 12\,000)$ or sight of 1080 A1 cao Alternative markscheme M2 for $12000\times\left(1-\frac{10}{100}\right)^2$ (M1 for $12000\times\left(1-\frac{10}{100}\right)$) A1 cao
3	$7r - 5r = -20 - 2$	–11	2	M1 for $7r + 2 = 5r - 20$ or $\frac{7r}{5} + \frac{2}{5} = r - 4$ or $7r - 5r = -20 - 2$ or $\frac{7r}{5} - r = -4 - \frac{2}{5}$ A1 cao

Paper 5505

No	Working	Answer	Mark	Notes
4 (a)		–1, 0, 1	2	B2 for –1, 0, 1 only (B1 for –1, 0 or 0,1 or –1, 1 or –2, -1, 0, 1 only)
(b)		(–1,–1)(0,–1) (1,–1) (0, 0) (1, 0) (1, 1)	3	B3 for 6 points correct (B2 for 3 points correct) (B1 for 1 point correct) *NB: –B1 for each additional point over six*
5		$5n + 1$	2	B2 oe (B1 for $5n$ seen) NB: n = gets B1 max
6 (a)	Triangle with vertices at (0,0) (0,–2) and (3,0)		2	M1 for correct orientation A1 cao
(b)	Rotation, 180°, centre (0,1) Enlargement sf –1 centre (0,1)		2	B2 for 180° 'rotation' centre (0, 1) or for Enlargement sf - 1 centre (0,1) (B1 for any two of the three parts) NB: B0 if additional transformation is included
7	Bisector of $\angle BAC$ Arc around A Region	See overlay	3	B3 cao (B2 for either two correct boundaries, no shading/ wrong shading or one correct boundary, one incorrect boundary with valid shading) (B1 for either two incorrect boundaries but one drawn from A and one intersection, with valid shading or one correct boundary) Ignore shading outside the triangle
8		Length Volume Area	3	B1 for Length B1 for Volume B1 for Area



Paper 5505

No	Working	Answer	Mark	Notes
9 (a)	Unbiased question with choices		2	B1 for unbiased question B1 for at least 2 choices
(b)	Leading question and a restricted sample		2	Classification 1: A biased question Classification 2: A restricted sample of people Classification 3: Not specifying a range of foods Classification 4: Nothing to do with eating habits B2 reasons which satisfy 2 different classifications (B1 a reason which satisfies one classification)
10 (a)	$6 \times 10^2 \times 8 \times 10^4$ $48 \times 10^6 = 4.8 \times 10^7$	4.8×10^7	3	M1 for $6 \times 10^a \times 8 \times 10^b$ oe, a and b integers including 0 A1 for 48×10^6 oe A1 cao
(b)	200 000 + 30 000 = 230 000	230 000	2	B2 cao (B1 for sight of 200 000 or 30 000 or 2.3×10^5 or 23×10^4)
11 (a)	$x^2 + xy + xy + y^2$	$x^2 + 2xy + y^2$	2	M1 for at least 3 of the 4 terms correct A1 cao
(b)		25	2	M1 for recognising 3.47 + 1.53 (= 5) A1 cao
12 (i)	Tangent 90° to diameter /radius/ line from (through) centre	27°	4	B1 for 27° cao B1 for reason
(ii)	180 –(90+ "27") angle in semicircle (is 90°)/Alternate segments /angle at centre twice at circumference	63°		B1 ft for 90–"27" if not 63° B1 for reason
13 (i)		p^9	1	B1 cao
(ii)		$6q^6$	2	B2 for $6q^6$ (B1 for sight of $\frac{6q^9}{q^3}$ or $3q \times 2q^5$ or $3q^4 \times 2q^2$ or $6 \times q \times q \times q \times q \times q \times q$ or final answer of the form kq^6, $k > 0$)

Paper 5505

No	Working	Answer	Mark	Notes
14 (a)(i)		152	2	B1 cao
(ii)		177		B1 cao
(b)			3	B1 for median marked at 167 B1 ft for postion of box with its ends at "152" and "177" B1 for position of whiskers with ends at 132 and 182 NB: For any points plotted between 141 and 149 give a tolerance of an extra ± 1 square
15	(arc =) $\frac{40}{360} \times 2\pi \times 9$ $= 2\pi$	$2\pi + 18$	4	M1 for $\frac{40}{360} \times$ M1 for $2\pi \times 9$ M1 (dep) for $\frac{40}{360} \times 2\pi \times 9$ oe A1 for $\frac{18 \times \pi}{9} + 18$ oe exact form
16 (i)		1	1	B1 cao
(ii)		$\frac{1}{16}$	1	B1 cao accept 0.0625
(iii)		64	1	B1 cao condone ± 64

Paper 5505

No	Working	Answer	Mark	Notes
17 (a)	$F \propto 1/x^2$ $F = k/x^2$ $4 = k / 3^2$ $F = 36/x^2$	$F = \frac{36}{x^2}$	3	M1 for $F = k/x^2$ seen or implied. ($k \neq 1$) M1 (dep) for subst. or sight of $k = 36$ A1 for $F = 36/x^2$
(b)		9	1	B1 ft for 9 (ft on $F = kx^n$, $n \neq 0$)
(c)	$64 = \frac{36}{x^2}$ $x^2 = \frac{36}{64}$ $x = \pm\frac{3}{4}$	$\frac{6}{8}$	2	M1 for $x^2 = \frac{"36"}{64}$ A1 for $\frac{6}{8}$ oe (condone $\pm$) *SC: Use of $F = kx^2$ max M1 M1 A0 B1 ft M0 A0* *SC: Use of* $F = \frac{k}{\sqrt{x}}$ *max M1 M1 A0 B0 M1* ($\sqrt{x} = \frac{4\sqrt{3}}{64}$) *A0*
18	$(5+\sqrt{3})(5-\sqrt{3}) = 5\times5 - 5\sqrt{3} + 5\sqrt{3} - \sqrt{3}\sqrt{3}$ $= 5\times5 - 3$ $\frac{22}{\sqrt{22}} = \frac{22\sqrt{22}}{22}$	$\sqrt{22}$	3	B1 for correct expansion 25 - $5\sqrt{3}$ + $5\sqrt{3}$ - $\sqrt{3}$ $\sqrt{3}$ with 1st three terms reducing to 25 **without** any errors seen B1 (indep) for $\sqrt{3}$ $\sqrt{3}$ = 3 B1 for $\sqrt{22}$ coming from $\frac{22}{\sqrt{22}}$ (S.C $\frac{(5+\sqrt{3})(5-\sqrt{3})\sqrt{22}}{22}$ gets B1)

Paper 5505

No	Working	Answer	Mark	Notes
19 (a)		60 40	2	B1 cao B1 cao
(b)		correct bars	2	B1 for $30 < x \leq 40$ with an area of 2½ squares B1 for $40 < x \leq 70$ with an area of 3 squares *SC:* $\frac{0}{4}$ *give M1 if clearly using area or frequency density*
20 (a)	$6x + 8 - 12x + 15$	$-6x + 23$	2	M1 for 3 of the 4 terms $6x$, $+8$, $-12x$, $+15$ correct A1 cao
(b)		$32x^5y^{15}$	2	B2 cao (B1 for two of 32, x^5, y^{15})
(c)	$\frac{(n+1)(n-1)}{n+1} \times \frac{2}{n-2}$ $\frac{2(n-1)}{n-2}$	$\frac{2(n-1)}{n-2}$	3	M1 for $k(n + 1)(n - 1)$ M1 dep for $\frac{(n+1)(n-1)}{(n+1)} = n - 1$ A1 for $\frac{2(n-1)}{n-2}$
21	Vertices at $(-3, -1\frac{1}{2}), (-4\frac{1}{2}, -1\frac{1}{2}), (-3, -4\frac{1}{2})$		3	B1 for all sides $\times 1\frac{1}{2}$ B1 for correct orientation with 2 vertices almost correct B1 cao

Paper 5505

No	Working	Answer	Mark	Notes
22	Total = 3 + 5 + 2 (=10) $\frac{3}{10}\times\frac{3}{10}\times\frac{5}{10}\left(=\frac{45}{1000}\right), \frac{3}{10}\times\frac{3}{10}\times\frac{2}{10}\left(=\frac{18}{1000}\right)$ $\frac{5}{10}\times\frac{5}{10}\times\frac{3}{10}\left(=\frac{75}{1000}\right), \frac{5}{10}\times\frac{5}{10}\times\frac{2}{10}\left(=\frac{50}{1000}\right)$ $\frac{2}{10}\times\frac{2}{10}\times\frac{3}{10}\left(=\frac{12}{1000}\right), \frac{2}{10}\times\frac{2}{10}\times\frac{5}{10}\left(=\frac{20}{1000}\right)$ $3\times\left(\frac{"45"}{1000}+\frac{"18"}{1000}+\frac{"75"}{1000}+\frac{"50"}{1000}+\frac{"12"}{1000}+\frac{"20"}{1000}\right)$ $\frac{660}{1000}$	$\frac{660}{1000}$ oe	5	M3 for all six expressions seen OR their combined equivalents (M2 for four expressions seen OR their combined equivalents) (M1 for two expressions seen OR their combined equivalents) M1 sum of 18 relevant products condone 1 slip A1 for $\frac{660}{1000}$ oe *SC: without replacement maximum M4 A0* SC: Just 2 beads: Answer either $\frac{38}{100}$ oe OR $\frac{28}{90}$ oe B1

Paper 5505

No	Working	Answer	Mark	Notes
23 (a)(i)		$6\mathbf{b} - 6\mathbf{a}$	2	B1 for $6\mathbf{b} - 6\mathbf{a}$ oe
(ii)		$6\mathbf{a}$		B1 for $6\mathbf{a}$ oe
(b)	$\overrightarrow{EX} = \overrightarrow{EB} + \overrightarrow{BX}$ $= 12\mathbf{b} + ½\ \overrightarrow{BC}$	$12\mathbf{b} - 3\mathbf{a}$	2	M1 for $\overrightarrow{EX} = \overrightarrow{EB} + \overrightarrow{BX}$ oe vector journey in a form ready for straightforward substitution A1 for $12\mathbf{b} - 3\mathbf{a}$ oe
(c)	$\overrightarrow{AY} = \frac{5}{3}\overrightarrow{AB}$ or $\overrightarrow{BY} = \frac{2}{3}\overrightarrow{AB}$ $\overrightarrow{EY} = 16\mathbf{b} - 4\mathbf{a}$ or $\overrightarrow{XY} = 4\mathbf{b} - \mathbf{a}$ $\overrightarrow{EY} = 4\overrightarrow{XY}$ or $\overrightarrow{EX} = 3\overrightarrow{XY}$ or $\overrightarrow{EY} = \frac{4}{3}\overrightarrow{EX}$	Printer Answer	3	B1 for either $\overrightarrow{AY} = \frac{5}{3}\overrightarrow{AB}$ or $\overrightarrow{BY} = \frac{2}{3}\overrightarrow{AB}$ oe B1 ft for either $\overrightarrow{EY} = 16\mathbf{b} - 4\mathbf{a}$ or $\overrightarrow{XY} = 4\mathbf{b} - \mathbf{a}$ ft only on parts (*a*) and (*b*) B1 for either $\overrightarrow{EY} = 4\overrightarrow{XY}$ or $\overrightarrow{EX} = 3\overrightarrow{XY}$ or $\overrightarrow{EY} = \frac{4}{3}\overrightarrow{EX}$ oe **plus** conclusion of *E*, *X*, *Y* on the same straight line
24 (a)(i)		$(5, -4)$	4	B1 cao
(ii)		$(2, -9)$		B1 cao
(iii)		$(2, 4)$		B1 cao
(iv)		$(1, -4)$		B1 cao
(b)		$(x-2)^2 - 4$	4	B4 for $(x-2)^2 - 4$ oe eg. $x^2 - 4x$ (B3 for $(x+2)^2 - 4$ or $(x-2)^2 + 4$) (B2 for $x^2 - 4$ or $(x-2)^2$ OR $x^2 + bx$, $b \neq 0$ OR $(x+2)^2 + 4$ OR $f(x-2) - 4$) (B1 for $x^2 + 4$ or $(x+2)^2$ or $ax^2 + bx$ or $x^2 + bx + c$ OR $x - 2 - 4$ or $x^2 - 2 - 4$, $a, b, c \neq 0$)

Paper 5506

No	Working	Answer	Mark	Notes
1 (a)	$V = \pi \times 4^2 \times 10$	502 – 503 cm^3	2	M1 for $\pi \times 4^2 \times 10$ A1 502 – 503
(b)	$P^2 = 10^2 + 8^2$ $P = \sqrt{164}$	$\sqrt{164} < 13$	3	M1 for sight of correct right angled triangle M1 for $10^2 + 8^2$ A1 for conclusion based on a correct calculation Or 12.8 seen
2 (a)(i)	2×30	$2 \times 2 \times 3 \times 5$	4	M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
(ii)	2×48	$2^5 \times 3$		M1 for systematic method, division, factor trees (at least one prime) A1 cao
(b)		12	1	B1 cao
(c)	$2^5 \times 3 \times 5$	480	2	B2 cao B1 for $2^5 \times 3 \times 5$ or any correct common multiple

Paper 5506

No	Working	Answer	Mark	Notes
3 (a)		$150 < C \leq 200$	2	M1 use of cum freq to find the cost of the 20th or 20.5^{th} car OR $\frac{1}{2}\Sigma f$ th or $\frac{1}{2}(\Sigma f + 1)$ th car. A1 eg 150 to 200, 150 – 200
(b)		No, because the 21st value is in the same interval	1	B1 for 20.5^{th} or 21st value in the same internal consistent with 'a' OR Refers to the median value being low in the interval (statement to be mathematically correct) See additional sheet
(c)	80% = 5200 $\frac{5200}{80} \times 100$	6500	3	M1 for (100 – 20)% = 5200 M1 for $\frac{5200}{"80"} \times 100$ A1 cao

Paper 5506

No	Working	Answer	Mark	Notes
4 (a)	$x^2(x+1) = 230$	AG	2	M1 for $x \times x \times (x+1)$ or $x \times x \times x + 1$ oe, $x^2(x+1)$, $x^2 \times x + 1$ A1 cao from $x \times x \times (x+1)$, no need to see 230
(b)	5 – 150 6 – 252 5.1 – 158.7 5.2 – 167.6 5.3 – 177.0 5.4 – 186.6 5.5 – 196.6 5.6 – 207.0 5.7 – 217.7 5.8 – 228.8 5.9 –240.2 5.85 – 234.4	5.8	4	B2 for trial between 5.8 and 5.9 inclusive evaluated (B1 for trial between 5 and 6 inclusive evaluated) B1 for different trial between 5.8 and 5.85 (not including 5.8) B1 dep on at least are previous B1 5.8, 5.81, 5.811
5	$\pi \times \left(\frac{15}{2}\right)^2 = 176.715$	88.4 cm^2	3	M1 for $\pi \times \left(\frac{15}{2}\right)^2$ seen A1 88.3 – 88.4 B1 for cm² (independent)

Paper 5506

No	Working	Answer	Mark	Notes
6 (a)	$5 = 0.5x + 1$	8	2	M1 for $5 = 0.5x + 1$ A1 cao
(b)		$y = \frac{1}{2}x + c$	1	B1for $y = \frac{1}{2}x + c$, $c \neq 1$, oe
(c)		$x = 2y - 2$ OR $x = 2(y - 1)$	2	M1for correctly multiplying both sides by 2 or correctly isolating $\frac{x}{2}$ A1 for $x = 2(y - 1)$, $x = \frac{y-1}{0.5}$, $\frac{y-1}{\frac{1}{2}}$ oe SC B1 for x= 2y -1
7	$4x - 6y = 22$ $15x + 6y = 54$ $19x = 76$	$x = 4,\ y = -1$	4	M1 for coefficients of x or y the same followed by correct operation, allow one arithmetical error A1 cao M1 (dep) for correct sub for other variable A1 cao Trial and improvement 0 marks unless both correct values of x and y found
8 (a)	SF = $\frac{10}{6}$ $\frac{10}{6} \times 4.8 = 8$	8	2	M1 for sight of $\frac{10}{6}$ or $\frac{6}{10}$ or 1.67 or better or $\frac{CD}{10} = \frac{4.8}{6}$ A1 cao
(b)	$\frac{10}{6} \times 4.5 - 4.5 = 3$	19.8	2	M1 for use of SF from "a" to find AC or BC or $\frac{BC}{4.5} = \frac{4}{6}$ and adding 4 sides A1 cao

Paper 5506

No	Working	Answer	Mark	Notes
9	$\frac{6\times10^{15}}{3.2\times10^{8}}$ 1.875×10^{7}	4.3×10^{3}	3	B3 for 4.3×10^{3} to 4.34×10^{3} (B2 for 1.875×10^{7} oe or 4300 to 4340, final answer of 1.9×10^{7} B1 for sight of 6×10^{15} oe or 3.2×10^{8} oe)
10	$8.5\times\tan38$ $=8.5\times0.7813$ $\frac{8.5}{\sin(90-38)}=\frac{AB}{\sin38}$ $AB=\frac{8.5\times\sin38}{\sin(90-38)}$ $=\frac{5.2331}{0.788}=6.64$	6.64	3	M1 for correct use of trig, eg $\tan 38=\frac{opp}{8.5}$ M1 for $8.5\times\tan38$ A1 6.64 – 6.641 OR M1 for correct substitution into the sine rule M1 (dep) for correct rearrangement for AB= A1 6.64 – 6.641
11 (a)		No, as you would expect about 100. Yes, as it is possible to get 200 sixes with a fair dice	1	B1 for a consistent answer See additional sheet

Paper 5506

No	Working	Answer	Mark	Notes
(b)	$\frac{1}{6}, \frac{5}{6}$ + labels		3	B1 for $\frac{5}{6}$ on the red dice, *not six* branch B1 for a fully complete tree diagram with all branches labelled B1 for $\frac{1}{6}$ and $\frac{5}{6}$ on all remaining branches as appropriate
(c)(i)	$\left(\frac{1}{6}\right)^2$	$\frac{1}{36}$	2	M1 $\left(\frac{1}{6}\right)^2$ or $\frac{1}{6}\times\frac{1}{6}$ only or 0.28 A1 $\frac{1}{36}$ or 0.03 or better
(ii)	$1-\left(\frac{5}{6}\right)^2$ OR $\frac{1}{6}\times\frac{5}{6}+\frac{5}{6}\times\frac{1}{6}+\frac{1}{6}\times\frac{1}{6}$	$\frac{11}{36}$	3	M2 for $1-\left(\frac{5}{6}\right)^2$ or $1-\frac{5}{6}\times\frac{5}{6}$ A1 cao OR M1 for $\frac{1}{6}\times\frac{5}{6}$ oe M1 for 2 or 3 only of $\frac{1}{6}\times\frac{5}{6}, \frac{5}{6}\times\frac{1}{6}$, "a" A1 for $\frac{11}{36}$ or 0.31 or better

Paper 5506

No	Working	Answer	Mark	Notes
12 (a)	$\pi \times 30 \times \frac{7.5^2}{3} - \pi \times 10 \times \frac{2.5^2}{3} = 1767 - 65$	1700	3	M1 for either $\pi \times 30 \times \frac{7.5^2}{3}$ or $\pi \times 10 \times \frac{2.5^2}{3}$ M1 (dep) for difference A1 1700 – 1702 **SC** B1 Using d instead of r, 6800 – 6808
(b)	$\frac{S}{2\pi d} = \sqrt{h^2 + d^2}$ $\left(\frac{S}{2\pi d}\right)^2 = h^2 + d^2$	$h = \sqrt{\frac{S^2 - 4\pi^2 d}{4\pi^2 d^2}}$	3	M1 for correctly isolating $\sqrt{h^2 + d^2}$ or $h^2 + d^2$ or $h + d$ or kh^2 or kh M1(indep) squaring both sides A1 $h = \sqrt{\frac{S^2 - 4\pi^2 d^4}{4\pi^2 d^2}}$, $h = \frac{\sqrt{S^2 - 4\pi^2 d^4}}{2\pi d}$ $h = \sqrt{\left(\frac{S}{2\pi d}\right)^2 - d^2}$
(c)	$\left(\frac{30}{20}\right)^2 \times 450$ or $450 \div \left(\frac{20}{30}\right)^2$	1012.5	2	M1 for sight of correct SF^2 including 4:9 A1 1010 to 1013

Paper 5506

No	Working	Answer	Mark	Notes
13 (a)	$\frac{2x(x+20)}{2} = 400$	As given	2	M1 $\frac{2x(x+20)}{2}$ or $\frac{2x \times x + 20}{2}$ or $2x(x + 20) = 800$ A1 cao following correct working, no need for = 400 *SC B1* $2x \times x + \frac{1}{2} \times 2x(10 - \frac{x}{2}) \times 2$
(b)	$\frac{-20 \pm \sqrt{20^2 - 4 \times 1 \times (-400)}}{2}$ $= \frac{-20 \pm 44.721}{2}$	12.361	3	M1 for correct sub, up to signs, in the quad formula A1 for 44.7 or $\sqrt{2000}$ A1 for 12.3606 – 12.361, ignore negative solution T.I B3 for 12.361 OR Completing the square M1 for $(x+10)^2$ seen A1 for $-10 \pm \sqrt{500}$ A1 for 12.3606 – 12.361 ignore negative solution

Paper 5506

No	Working	Answer	Mark	Notes
14 (a)	$0.5\times 8\times 15\times \sin 70^0$	56.4	2	M1 for correct sub into area formula A1 56.38 – 56.4
(b)	$AB^2 = 8^2 + 15^2 - 2\times 8\times 15\times \cos 70^0 = 206.9$ EITHER $0.5\times AB\times CX$ ='56.38' OR $\frac{\sin B}{8} = \frac{\sin 70}{\sqrt{'206.9'}}$ $B = 31.5$ 15 sin '31.5'	7.84	4	M1 for correct sub into cos rule A1 for 206.9 - 207 or 14.38 – 14.4 EITHER M1 for use of area rule to find CX A1 7.83 – 7.84 OR M1 for correct use of sine rule to find sin B or sin A and then sight of 15sin B *or* 8 sin A A1 7.83 – 7.84

Paper 5506

No	Working	Answer	Mark	Notes
15 (a)	$4a^2 - 4a + 1 - (4b^2 - 4b + 1) =$ $4(a^2 - b^2) - 4(a - b)$ $4(a - b)(a + b - 1)$ OR $((2a - 1) - (2b - 1))((2a - 1) + (2b - 1))$ $(2a - 2b)(2a + 2b - 2)$	AG	3	Expansion Method M1 for a correct expansion of any one of the three terms M1(dep) on an attempt to expand all 3 terms and show LHS = RHS A1 fully correct algebra RHS exp is $4(a^2 + ab - a - ba - b^2 + b)$ OR Factorisation Method M1 for attempt to use difference of 2 squares on LHS M1 for one bracket correctly simplified A1 fully correct
(b)	Any 2 odd square numbers have the above form If a and b are both even or odd then $a - b$ is even, so $4(a - b)$ is a multiple of 8 If one of a,b is odd, then $a + b - 1$ is even, so $4(a + b - 1)$ is a multiple of 8		3	B1 'any 2 square nos have the above form' (may be implied by sight of $(2a - 1)^2 - (2b - 1)^2$ in part (b)) B1 first reason B1 second reason SC B1 for $(2r + 1)^2 - (2r - 1)^2$ B1 for 8r
16 (a)	$g_L = \frac{2 \times 4.495}{1.35^2 \times \sin 30.5}$ $g_u = \frac{2 \times 4.505}{1.25^2 \times \sin 29.5}$	9.719 11.710	4	B2 for any 4 of 4.505, 1.25, 29.5, 4.495, 1.35, 30.5 seen (B1 for any two or three seen) B1 for 11.710 – 11.7103 B1 cao 9.719 – 9.71904
(b)	Round, until lower and upper bounds agree	10	1	B1 for 10 + reason " they agree to this level of accuracy"

Paper 5506

No	Working	Answer	Mark	Notes
17 (a)(i)		xy	3	B1 cao
(ii)		y^2		B1 for y^2 or $y \times y$
(iii)		$\frac{x}{2}$		B1 for $\frac{x}{2}$ or $0.5x$ or $2^{-1}x$
(b)	Divide to get $2y = 1$	$q = -1$	2	M1 for $2y = 1$ or $\frac{x}{2} = 32$ or $p + q = 5$ or $1 + p + 2q = 5$
		$p = 6$		A1 cao
18 (a)	$x^2 - 2mx + m^2 - k$	$k = m^2$	2	M1 for correct exp of $(x - m)^2$ or correct completion of the square eg $\left(x - \frac{2m}{2}\right)^2 - \left(\frac{2m}{2}\right)^2$
				A1 cao
				SC B1 for $k = -m^2$
(b)(i)	Min value is $-m^2$	$-m^2$	3	M1 for recognition that min value occurs when $(x - m)^2 = 0$ (either (b)(i) or (b)(ii) correct implies this M1)
(ii)	$x = m$	m		A1 ft on 'k', " $-k$" gets M1 A0
				A1 cao
19	$0.06 \times 0.05 = 0.003$	No	2	M1 for 0.06×0.05
				A1 correct conclusion based on 0.003 or 0.06 x 0.05 stated as $\neq 0.0011$
				OR M1 for statement that for the two events to be independent P (BL and CL) = P(BL) × P(CL)

Paper 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
20		50 50 4	3	B1 50 or $\frac{100}{2}$ B1 for 50 or "a" B1 4 or $\frac{360}{90}$ oe

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4LN

Telephone 01623 467467
Fax 01623 450481

Order Code UG014129 June 2003

For more information on Edexcel qualifications please contact our
Customer Response Centre on 0870 240 9800
or email: enquiries@edexcel.org.uk
or visit our website: www.edexcel.org.uk

London Qualifications Limited. Registered in England and Wales no.4496750
Registered Office: Stewart House, 32 Russell Square, London WC1B 5DN



edexcel

GCSE
Edexcel GCSE
Mathematics A 1387

July 2004

advancing learning, changing lives

Mark Scheme

Edexcel GCSE
Mathematics A 1387

London Qualifications is one of the leading examining and awarding bodies in the UK and throughout the world. It incorporates all the qualifications previously awarded under the Edexcel and BTEC brand. We provide a wide range of qualifications including general (academic), vocational, occupational and specific programmes for employers.

Through a network of UK and overseas offices, our centres receive the support they need to help them deliver their education and training programmes to learners.

For further information please call Customer Services on 0870 240 9800, or visit our website at www.edexcel.org.uk

July 2004

Publications Code UG015616

All the material in this publication is copyright
© London Qualifications Ltd 2004

CONTENTS

Notes on Marking Principles....2
Paper 5514....4
Paper 5515....8
Paper 5516.... 11
Paper 5517.... 15
Paper 5518.... 19
Paper 5519.... 23

NOTES ON MARKING PRINCIPLES

NOTES ON MARKING PRINCIPLES

1 Three types of mark are available

M marks - awarded for correct working seen or implied.
A marks - conditional accuracy marks which are awarded for accurate working following the award of M marks.
B marks - unconditional accuracy marks (independent of M).

2 Abbreviations

cao - correct answer only.
ft - follow through.
$\surd$ - Denotes a "follow through" answer.

SC - special case.
isw - ignore subsequent working.
oe - or equivalent (and appropriate).
NB: a candidate cannot benefit from both isw and ft.

3 If no working shown, then

correct answers normally score full marks
incorrect (even though nearly correct) answers score no marks.

4 Marking instructions

Misread loses A marks (and sometimes B marks) on that part but ft can be allowed on subsequent parts. M marks can still be earned. If in doubt contact your team leader.
If there is a wrong answer in the answer space DO CHECK the working in the body of the script.

- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.
- If there is a wrong answer in the answer space DO CHECK the working in the body of the script.
- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.

5 Style of marking

Answer correct: tick and write part mark in margin NEXT TO BRACKETED MARK.
Answer incorrect: cross, but show M, A or B marks if any earned in body of script and transfer the total of these to the margin next to the bracket mark.
Total for each double page at bottom right page (except for back if used), FINAL TOTAL IN RELEVANT BOX ON FRONT COVER.
Nought in margin for fully incorrect question or page AND FOR NO ATTEMPT.
Where no attempt has been made a line should be put in the answer space and zero in the margin next to the bracketed mark
CHOICE OF METHOD – No marks unless one answer is in answer space – then mark that.
CROSSED OUT WORK - if not replaced this should be marked (if legible).
There must always be a mark next to bracketed mark in the margin/

6 Follow Through Marks

Follow throughs are guided by two principles:

(a) Follow throughs which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous, do not award.
(b) Follow throughs which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

7 Probability

Probability answers must be given as fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least two decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.

6 Linear Equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

8 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

PAPER 5501					
No		**Working**	**Answer**	**Mark**	**Notes**
1			K: 1020 L: 8.06	2	B1 for 1020 or 1,020 B1 for 8.06 Accept £8.06p and £8,06
2	(a)		28, 33	2	B1, B1 (B1 ft for "28" + 5 if both numbers >25)
	(b)			1	B1 for add 5, +5, for going up in 5's the difference is 5 oe
	(c)			1	B1 for they end in 3 and 8, it ends in 7; or refers to 383 and 388 are in sequence
3	(a)(i)		$\frac{1}{2}$	2	B2 for ½ accept half (B1 for an equivalent unsimplified fraction eg 4/8 or 50% or 0.5)
	(ii)		2 rectangles shaded	1	B1 for correct shading (any 2 rectangles)
	(b)(i)		40	4	B1 for 40 cao
	(ii)		150 000		B1 for 150 000 cao (accept 150,000 not 150.000)
	(iii)		6.55		B1 for 6.55 cao not $6.5^{½}$
	(iv)		$\frac{3}{8}$		B1 for $\frac{3}{8}$ oe accept 0.375
	(c)		Cross 3cm from *A*	1	B1 mark a cross 3 cm (±2 mm) from *A*
4	(a)(i)		metres	2	B1 for metres (m)
	(ii)		grams		B1 for grams (g)
	(b)		miles	1	B1 for miles
5	(a)		(3, 2)	1	B1 for (3, 2)
	(b)(i)		*Q* at (0, 3)	1	B1 for *Q* plotted correctly on *y*-axis at (0, 3) ±2mm
	(ii)		*R* at (−2, −3)	1	B1 for *R* plotted correctly at (−2, −3) ±2mm
6	(a)(i)		30	2	B1 for 30
	(ii)		25		B1 for 25
	(b)(i)		4 shapes	2	B1 for drawing 4 shapes
	(ii)		1½ shapes		B1 for drawing 1½ shapes

PAPER 5501					
	No	Working	Answer	Mark	Notes
7	(a)		30	1	B1 for 30
	(b)	$20 \times 3 + 5$	65	2	M1 for $20 \times 3 + 5$ oe A1 for 65
8	(a)		Draws perp.	1	B1 for correctly drawing perp must touch line or cut line *AB* ± 2mm
	(b)		Sketches a cylinder	1	B1 for sketching cylinder
9	(a)	1974 6580 8554	855.4	3	M1 for complete method with relative place value correct, condone 1 error in multiplication A2 cao (A1 for digits 8554 seen or A1 for "855.4" dependent on 1 arithmetic error)
	(b)	990 ÷ 69 = 14.3…. or 14 rem 24	14	4	Method 1 - Everything excluding long division M2 for a valid method with no errors …need to see 966 or 1035 (M1 for a valid method, including estimation, that reaches an answer between 901 and 1099 inclusive. Ignore errors.) A2 for 14 with a fully correct method (A1 (dep on 1st M1) for an answer between 14 and 15 inclusive. Ignore errors. Cannot have used estimation.) Note: Estimation can only score a maximum of M1 unless accompanied by another method or 966 or 1035 see (award M2) Method 2 – long division method M2 for 990 ÷ 69 = integer answer between 12 and 19 inclusive and rem 30 seen (M1 for 990 ÷ 69 with 1 in tens column.) A2 for 14 with fully correct method (A1 (dep on 1st M1) for an answer between 14 and 15 inclusive.)

PAPER 5501					
	No	Working	Answer	Mark	Notes
10	(a)(i)		7	2	B1 for 7
	(ii)		−10		B1 for −10
	(b)(i)		6	2	B1 for 6 (accept −6)
	(ii)		8		B1 for 8 (accept −8)
	(c)		−7	1	B1 for −7 cao
11	(a)		B and D	2	B1, B1 (–1 each extra)
	(b)(i)		A	2	B1 for A
	(ii)		3		B1 for 3
12	(a)	800 − 144	656	2	M1 for at least 1 digit correct and in correct position needs to be 3 digit number A1 for 656
	(b)	144 is less than 200 so Trudy is wrong		2	B1 for 200 B1ft for 'correct' explanation based on cand's "200"
	(c)	$\frac{45\times800}{100}$	360	2	M1 for 45 × 800 ÷ 100 oe A1 for 360
	(d)	$\frac{176}{800}\times100$	22	2	M1 for $\frac{176}{800}\times100$ oe A1 for 22
13	(a)(i)		25	4	B1 for 25
	(ii)		28		B1 for 28
	(iii)		5 and 20		B1 for 5 and 20
	(iv)		26 and 33		B1 for 26 and 33
	(b)	$2^3 = 8$ or $2^3 = 2 \times 2 \times 2$ (which is not 6)		1	B1 for valid 'explanation'
14			10 m^2	2	B1 for 10 B1 indep for m^2.

PAPER 5501					
No		**Working**	**Answer**	**Mark**	**Notes**
15	(a)	$\frac{11}{12}-\frac{10}{12}$	$\frac{1}{12}$	2	M1 for correctly writing both fractions to a common denominator A1 for $\frac{1}{12}$ oe
	(b)	$\frac{70\times400}{200}$	140	2	B2 for 140 (accept 136) (B1 for sight of any two of 70, 400 or 200)
16	(a)		$2y$	1	B1 for $2y$ or $2\times y$, $y2$, $y\times2$
	(b)		$3p^2$.	1	B1 for $3p^2$ or $3\times p^2$ or $p^2\times3$ or $p^2 3$
	(c)		$x(x-3)$	2	B2 for $x(x-3)$ (B1 for x (x…….)) $\frac{25}{60}$ wrongly cancelled gets B1 ISW
17	(a)		2 23 9 34 15 2 9 26 17 25 18 60	3	B3 for all correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
	(b)		$\frac{25}{60}$	1	B1 for $\frac{25}{60}$ or $\frac{5}{12}$ oe $\frac{25}{60}$ wrongly cancelled gets B1 ISW

PAPER 5501					
	No	**Working**	**Answer**	**Mark**	**Notes**
18	(a)(i)		60	2	B1 for 60
	(ii)				B1 for all **angles equal** so equilateral triangle oe
	(b)(i)		130	3	B1 for 130
	(ii)				B1 for isosceles triangle oe or 2 angles equal accept $\angle Q = \angle R$ B1 for angles on a straight **line** add up to **180°**oe (180° could be in working)
	(c)		64	1	B1 for 64
19	(a)		1	1	B1 for 1
	(b)		3	1	B1 for 3
	(c)	$9\times1+3\times2+5\times3+3\times4$ (= 42) "42" ÷ 20	2.1	3	M1 for 9×1, 3×2, 5×3, 3×4 or for 42 seen M1 (dep) for "42" ÷ 20 A1 for 2.1 or $2\frac{1}{10}$ or $2\frac{2}{20}$
20	(a)		09 05	1	B1 for 09 05 oe
	(b)		7	1	B1 for 7
	(c)		10	1	B1 for 10
	(d)	7km in 20 mins	21	3	B1 for 20 (minutes) oe or $\times3$ seen M1 for $\frac{"7"}{"20"}$ A1 cao [SC: "7" × 3 seen gets B1 M1]

PAPER 5501				
No	**Working**	**Answer**	**Mark**	**Notes**
21	Vertices of new triangle at (2, −2) (2, 6) and (6, −2)	Correct triangle drawn	3	B3 cao (B2 for either correct triangle in wrong translated position or for 2 vertices correct) (B1 a right angled triangle with horizontal length 4 or vertical length 8 in the same orientation as the shaded triangle) SC B2 for s + 3 totally correct
22 (a) (b) (c)	 8560 ÷ (10 × 10)	8 Pentagon 85.6	1 1 2	B1 for 8 B1 for pentagon M1 for 8560 ÷ (10 × 10) oe A1 for 85.6
23	$2x + x + 100 + 47 = 360$ $2x + x = 360 - 100 - 47$ $x = 71$ Largest angle = $2x$ =	142	4	M1 for $2x + x + 100 + 47 = 360$ or 360 – 147 or 213 seen M1 dep for correctly separating x-terms and non x terms or "360 – 147" ÷ 3 A1 for $x = 71$provided M2 awarded A1 ft for 142

PAPER 5502					
	No	**Working**	**Answer**	**Mark**	**Notes**
1	(a)		Diagram	1	B1 cao
	(b)		22, 26	1	B1 cao
	(c)		46	1	B1 cao
2	(a)	£5.95 + £1.62 + 25p + 2 × 48p = £8.78	1.22	3	M1 for 3 of £5.95, £1.62, 25p, 48p seen with intention to add or 170 seen A1 for £8.78 A1 ft from " 8.78"
	(b)	160 ÷ 12 = 13.(333…)	14	2	M1 for 160 ÷ 12, or 13 or better or 12 × 13 or 12 × 14 A1 14 cao
	(c)	"14" × £12.20 = £170.8**0**	170.80	2	M1 for "14" × 12.20 A1 for 170.8**0** or 158.6**0** if 13 in (b) NB: 170.8 or 158.6 gets M1 A0
3	(a)(i)		1459	1	B1 cao
	(ii)		9541	1	B1 cao
	(b)		9 + 5 = 14	1	B1 cao
	(c)		0	1	B1 cao
4	(a)		1123	1	B1 cao
	(b)		1125	1	B1 cao
	(c)		43	1	B1 cao
	(d)	67 – "43"	24	2	M1 for 67 – "43" A1 ft from "43"
	(e)(i)		80	2	B1 cao
	(ii)		56 – 58		B1 answer in range 56 to 58 inc
	(f)		Completes graph	2	B2 for (Apr , 70) and (May , 60 < p < 65) plotted and joined (B1 for one point plotted)

PAPER 5502					
	No	Working	Answer	Mark	Notes
5	(a)(i)		4	1	B1 cao
	(ii)		10	1	B1 cao
	(b)		28	2	B2 for 28 (B1 for 29 or 14×2)
6	(a)		$\frac{3}{4}$	1	B1 accept 0.75, 75%
	(b)	$\frac{3}{4} \times 28 = 21$	15.54	3	M1 for $\frac{3}{4} \times 28$ or 21 seen M1 for "21" $\times$ 74 or 28×74 or 7×74 A1 cao
	(c)(i)		44 – 46	2	B1 44 – 46 inc
	(ii)		5.2 – 5.4		B1 5.2 – 5.4 inc
7	(a)		Correct shape	1	B1
	(b)		Correct shape	1	B1
8	(a)		Hexagon	1	B1
	(b)		Right	1	B1 cao
	(c)		Drawing	2	B2 for 7 additional hexagons with at least 2 points at which 3 hexagons meet (B1 for one point at which 3 hexagons meet)
9	(a)		$\frac{3}{4}$	2	M1 $\frac{80-20}{80}$ or $\frac{60}{80}$ or 0.75 (oe) A1 cao Do not accept equivalents
	(b)		15	1	B1 cao
	(c)		Iron and Cook set	1	B1 for both Accept mixer and fryer
	(d)		Microwave	1	B1 cao
	(e)		Bar chart	2	B1 one column (mixer): 70, 90 B1 second column (fryer): 70, 85 [SC: B1 columns correct but reversed]

PAPER 5502					
No		**Working**	**Answer**	**Mark**	**Notes**
10	(a)		Acute	1	B1
	(b)		Reflex	1	B1
	(c)		reason	1	B1 reason eg 120 + 230 = 350 ≠ 360
11	(a)		$\frac{1}{2}$	1	B1 for $\frac{1}{2}$ oe
	(b)		reason	1	B1 for reason e.g could get 30 heads
12	(a)	7.5×4	30	2	M1 for 7.5×4 or $7\frac{1}{2} \times 4$ A1 cao
	(b)	$\sqrt{(42.25)}$	6.5	2	B2 for 6.5 (B1 for 42.25)
13	(a)		$6x$	1	B1 accept $6 \times x$, $x6$ oe
	(b)		$x - 4$	1	B1 cao
	(c)		$12(x - 4)$	1	B1 for $12(x - 4)$ or $12x - 48$ or $12 \times x - 48$ oe
	(d)		$18x - 48$	2	M1 for "$6x$" + "$12(x-4)$" or "$6x$" + "$12x - 48$" oe A1 ft $18x - 48$, $2(9x - 24)$, $3(6x - 16)$, $6(3x - 8)$
14	(a)		90	2	B2 for 90 ± 2 (B1 for 9 ± 0.2)
	(b)		317	1	B1 for 317 ± 4
15	(a)	Accurate drawing of triangle		2	B1 cao for 38° (±2°) B1 cao (indep) for BC drawn 7.3 cm (±2mm) and completing the triangle.
	(b)	Measure angle A	63°	1	B1 for 63° (±2°) or ft their diagram (±2°)

PAPER 5502					
	No	Working	Answer	Mark	Notes
16	(a)	0 × 1 = 0 1 × 1 = 1 2 × 4 = 8 3 × 8 = 24 4 × 8 = 32 5 × 7 = 35	100	3	M1 col 1 × col 2 (at least 3 shown) M1 (dep) sum of totals A1 cao SC: M1 M1 A0 for 101
	(b)	Either 35.50 ÷ 1.42 = 25; 26.99 – 25 = 1.99 Cheaper in the USA Or 26.99 × 1.42 = 38.33; 38.33 – 35.50 = 2.83 Cheaper in the USA		3	M1 35.50 ÷ 1.42 A1 25 seen B1 ft (dep on M1) £1.99 with conclusion (must have units) **OR** M1 26.99 × 1.42 A1 38.32 or 38.33… seen B1 ft (dep on M1) $2.83 or $2.82 with conclusion (must have units) must be to 2dp
17	(a)		-1, (1), (3), 5, 7, 9	2	B2 cao (B1 for 2 values)
	(b)		Graph	2	B1 ft for plotting points ±1/2 square B1 cao for line between $x = -2$ and $x = 3$
	(c)(i)		0.4	2	B1 for 0.4 or ft from single straight line with positive gradient
	(ii)		1.2		B1 for 1.2 or ft from single straight line with positive gradient

PAPER 5502					
	No	Working	Answer	Mark	Notes
18	(a)		Plots	1	B1 cao
	(b)		description	1	B1 dynamic relationship or "positive" (correlation)
	(c)		line of best fit	1	Line within overlay region, and to the extent of.
	(d)(i)	280 g →	reading	2	B1 ft from single straight line of positive gradient (±1/2 square)
	(ii)	120 pages →	reading		B1 ft from single straight line of positive gradient (±1/2 square)
19			200 150 225 150 10	3	B3 cao (B2 for three correct, or B1 for one correct)
20	(a)			2	B1 B1 for correct sketch – ignore additional internal lines B1 B0 for rectangle or right-angled triangle or correct shape without line NB 3-D sketch gets B0 B0
	(b)			2	B1 B1 for correct plan – ignore internal lines – accept a rotated plan, not reflected B1 B0 for a single rectangle drawn NB 3-D sketch gets B0 B0
21	(a)	163.25 – 35.50 = 127.75 127.75 ÷ 18.25 = 7	8	3	M1 163.25 – 35.50 (or sight of 127.75) M1 (dep) "127.75" ÷ 18.25 A1 cao SC: M2 for 7 days
	(b)	1.175 × £64 or $\frac{17.5}{100}$ × 64 or £11.20 seen	75.20	2	M1 1.175 × 64, 0.175 × 64 oe or 11.20 or 75.2 seen or 6.40, 3.20 and 1.60 seen A1 cao

PAPER 5502					
	No	Working	Answer	Mark	Notes
22	(a)		6	1	B1 cao
	(b)		$t^2 - 2t$	1	B1 oe
	(c)		$3(y - 4)$	1	B1 Accept $3 \times (y - 4)$ or $3(y - 4$
23	(a)		Reason	1	B1 Makes some mention of bias either directly or making reference to an insufficient or biased range of responses
	(b)		Reason	1	B1 (a) an insufficient range of responses (b) No mention of money (c) No time frame in the question (d) Misunderstanding of "A lot" and "Not much"

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
1			10.	1	B1 for 10
2	(a)(i)		$3e + 2f$	2	B1 for $3e + 2f$
	(ii)		$3p^2$		B1 for $3p^2$
	(b)	$5 \times -3 + 1$	-14	2	M1 for $5 \times -3 + 1$ A1 for -14
3		1974 $\frac{6580}{8554}$	855.4	3	M1 for complete correct method with relative place value correct, condone 1 error in multiplication. A2 cao (A1 for digits 8554 seen or A1 ft for "855.4" dependent on one arithmetic error only)
4	(a)		2 23 9 34 15 2 9 26 17 25 18 60	3	B3 all correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
	(b)		$\frac{25}{60}$	1	B1 for $\frac{25}{60}$ or $\frac{5}{12}$ oe
5	(a)	$\frac{45}{100} \times 800$	360	2	M1 for $\frac{45}{100} \times 800$ oe A1 for 360
	(b)	$\frac{176}{800} \times 100$	22	2	M1 for $\frac{176}{800} \times 100$ oe A1 for 22

PAPER 5503					
	No	Working	Answer	Mark	Notes
6	(a)	$\frac{11}{12}-\frac{10}{12}$	$\frac{1}{12}$	2	M1 for correctly writing both fractions to a common denominator A1 for $\frac{1}{12}$ oe
	(b)	$\frac{70\times400}{200}$	140	2	B2 for 140 (accept 136) (B1 for sight of any two of 70, 400 or 200)
7	(a)(i)		60	2	B1 for 60
	(ii)				B1 for all angles equal so equilateral triangle oe
	(b)(i)		130	3	B1 for 130
	(ii)				B1 for isosceles triangle oe B1 for angles on a straight line add up to 180°oe
	(c)		64	1	B1 for 64
8		$9\times1+3\times2+5\times3+3\times4$ (=42) "42" ÷ 20	2.1	3	M1 for 9×1, 3×2, 5×3, 3×4 or for 42 seen M1 (dep) "42" ÷20 A1 for 2.1 or $2\frac{1}{10}$ or $2\frac{2}{20}$
9	(a)		09 05	1	B1 for 09 05 oe
	(b)		7	1	B1 for 7
	(c)		10	1	B1 for 10
	(d)	7 km in 20 minutes	21	3	B1 for 20 (minutes) oe or $\times3$ seen M1 for $\frac{"7"}{"20"}$ A1 cao SC: "7" $\times3$ gets B1 M1

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
10		Vertices of new triangle at (2, −2) (2, 6) and (6, −2)	Correct triangle drawn	3	B3 cao (B2 for either correct triangle in wrong translated position or for 2 vertices correct) (B1 for a right-angled triangle with horizontal length 4 or vertical length 8 in the same orientation as shaded triangle) SC B2 for scale factor 3, totally correct
11		$2^2 + 3 =$	7 which is not even	2	B2 (B1 for correctly evaluating $n^2 + 3$ with a prime number value for n.)
12	(a)	360 ÷ 5	72	2	M1 for 360 ÷ 5 oe A1 for 72
	(b)	8560 ÷ (10 × 10)	85.6	2	M1 for 8560 ÷ (10 × 10) oe A1 for 85.6
	(c)(i)	Least length = 100.5	100.5	2	B1 for 100.5
	(ii)	Greatest length = 101.5	101.5		B1 for 101.5 or 101.499 or better
13		$2x + x + 100 + 47 = 360$ $2x + x = 360 - 100 - 47$ $x = 71$ Largest angle = $2x$ =	142	4	M1 for $2x + x + 100 + 47 = 360$ or 360 – 147 or 213 seen M1 (dep) for correctly separating x-terms and non x terms or $\frac{"360-147"}{3}$ A1 for $x = 71$ A1 ft (provided M2 awarded) for "142"
14	(a)(i)		2.21	2	B1 for 2.21
	(ii)		0.013		B1 for 0.013
	(b)	LCM = 3 × 13 × 17 = 3 × 221	663	2	M1 for 3 × 13 × 17 oe A1 for 663

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
15			Tick boxes 1,3 & 6	3	B1 for $\frac{\pi abc}{2d}$; B1 for $2a^2$; B1 for $2\left(c^2+d^2\right)$ (−B1 for each additional expression ticked (>3) to a minimum of 0)
16		200×0.2	40	2	M1 for 200×0.2 or $\frac{40}{200}$ seen A1 for 40
17	(a)	eg $2 \mid \underline{108}$ $2 \mid \underline{54}$ $3 \mid \underline{27}$ $3 \mid \underline{9}$ 3	$2^2 \times 3^3$	3	M2 for full systematic method of at least 4 divisions by prime numbers oe factor trees; condone 1 calculation error (M1 for 108 written as a correct product(s) with only one non-prime or equivalent division or a full process with 2 calculation errors.) A1 for $2^2 \times 3^3$ (accept $2 \times 2 \times 3 \times 3 \times 3$)
	(b)		12	1	B1 for 12
18		Perpendicular from P to intersecting arcs (within tramlines); perpendicular at least 2cm long		2	M1 relevant pair of arcs crossing within tramlines A1 SC M1 AO for a full construction of a perpendicular to AB not passing through P.
19		15×10	150 cm^3.	3	M1 for 15×10 A1 for 150 B1 for cm^3.

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
20			$y = 2x + 6$	2	B2 for $y = 2x + 6$ (B1 for $y = 2x + k$, $k \neq 1$ or for $y = mx + 6$, m $\neq 0$ or for $2x + 6$)
21		$6\frac{2}{5} = \frac{32}{5}$ Area of triangle = $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ (=2) Length of a side of sq. = $\sqrt{18 \times "2"}$ (=6) Perimeter of square = 4 × 6	24	5	B1 for $6\frac{2}{5} = \frac{32}{5}$ oe or $3\frac{1}{5} = \frac{16}{5}$ or $\frac{30}{8} + \frac{2}{8}$ oe (or implied by area of triangle=2) M1 for $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ oe M1 for area of square = 18 × product of two lengths A1 for $\sqrt{18 \times "2"}$ A1 for 24
22	(a)		$x(x-3)$	2	B2 for $x(x-3)$ (B1 for x (…….))
	(b)		k^3.	1	B1 for k^3.
	(c)(i)	$4x + 20 + 3x - 21$	$7x - 1$	4	M1 for **three** of 4 terms $4x + 20 + 3x - 21$ (or better) A1 for $7x - 1$
	(ii)	$x^2 + 3yx + 2xy + 6y^2$	$x^2 + 5xy + 6y^2$		M1 for **three** of 4 terms $x^2 + 3yx + 2xy + 6y^2$ A1 for $x^2 + 5xy + 6y^2$
	(d)		$(p+q)(p+q+5)$	1	B1 for $(p+q)(p+q+5)$

PAPER 5503					
	No	Working	Answer	Mark	Notes
23	(a)		32	1	B1 for 32 (accept 31.5 to 33.5 inclusive)
	(b)			3	B1 for ends of whiskers at 9 and 57, (with a box) B1 for ends of box at 16 and 45 (± 0.5) B1 for median marked at 32 or a complete box and whisker diagram drawn with a median inside the box
	(c)	Median(B)>Median(G); on average boys take longer IQR(B)>IQR(G); times for boys have a greater spread		2	B1 eg for comparison of medians B1 eg for comparison of (interquartile) ranges
24	(a)	$6y = 15 - 5x$	$y = \frac{15-5x}{6}$	2	M1 for either $6y = 15 - 5x$ or -6 $y = 5x - 15$ or for $\frac{5x}{6} + y = \frac{15}{6}$ or a correct ft on sign error to $y=$ A1 for $y = \frac{15-5x}{6}$ oe
	(b)	$6k + 5(-21) = 15$	20	2	M1 for substitution of $x = -21$ (or $x = 21$) into given equation or candidate's answer to (a) A1 for $k = 20$
	(c)(i)		Region R indicated	3	B2 correct region shaded (accept unshaded if R clear) (B1 shaded or R region satisfies 3 of the 4 given inequalities with same boundaries)
	(ii)		(1,1)		B1 for (1,1)

PAPER 5503					
	No	Working	Answer	Mark	Notes
25	(a)		60	1	B1 for 60 B1 for *BDC* = 25
	(b)	eg Angle *BDC* = 25 *ADB* = 60 − 25	35	2	[Award the mark for equivalent approaches] B1 ft for (a) − 25
	(c)	Ben is correct; angle *DAB* = 65 + 25 = 90 and since angle in a semi-circle is 90°, *BD* must be a diameter		1	B1 for full valid justification

PAPER 5504					
	No	Working	Answer	Mark	Notes
1	(a)	Accurate drawing of triangle		2	B1 cao for 38º (±2º) B1 cao (indep) for BC drawn 7.3 cm (±2mm) and completing the triangle.
	(b)	Measure angle A	63º	1	B1 for 63º (±2º) or ft their diagram (±2º)
2	(a)	0 × 1 = 0 1 × 1 = 1 2 × 4 = 8 3 × 8 = 24 4 × 8 = 32 5 × 7 = 35	100	3	M1 col 1 × col 2 (at least 3 shown) could be implied by answers. M1 (dep) sum of totals A1 cao SC: M1 M1 A0 for 101
	(b)	Either $35.50 ÷ 1.42 = £25; £26.99 - £25 = £1.99 Cheaper in the USA Or £26.99 × 1.42= $38.33; $38.33 - $35.50 = $2.83 Cheaper in the USA		3	M1 35.50 ÷ 1.42 A1 25 seen B1 ft (dep on M1) £1.99 with conclusion; units needed OR: M1 26.99 × 1.42 A1 38.33 or 38.32…seen B1 ft (dep on M1) $2.83 or $2.82 with conclusion; units needed
3	(a)		-1, (1), (3), 5, 7, 9	2	B2 cao (B1 for 2 values)
	(b)		Graph	2	B1 ft for plotting points ±1/2 square B1 cao for line between $x = -2$ and $x = 3$
	(c)(i)		0.4	2	B1 0.4 or ft single straight line with positive gradient
	(ii)		1.2		B1 1.2 or ft single straight line with positive gradient

PAPER 5504					
	No	Working	Answer	Mark	Notes
4	(a)			2	B1 Rectangle drawn B1 Triangle attached Ignore additional internal lines; 3D sketch gets B0
	(b)			2	B1 single Rectangle drawn B1 Attached smaller rectangle drawn Accept rotated plan, Ignore internal lines down; Nets get B0
5	(a)	£163.25 - £35.50 = £127.75 £127.75 ÷ £18.25 = 7	8	3	M1 163.25 – £35.50 (or sight of £127.75) M1 (dep) "127.75" ÷ 18.25 A1 cao SC: M2 for 7 days
	(b)	1.175 × £64 or $\frac{17.5}{100}$ × 64 or £11.20 seen	75.20	2	M1 1.175 × 64.00 0.175 × 64 oe or 11.20 or 75.2 seen OR 6.40, 3.20, and 1.60 seen A1 cao
	(c)	54 × £2.38 =	128.52	2	M1 54 × £2.38 A1 cao
6		Tessellation	Drawing	2	B2 seven additional hexagons, with at least 2 points at which 3 hexagons meet (B1 one point at which 3 hexagons meet).
7			200 150 225 150 10	3	B3 cao (B2 for three correct, or B1 for one correct)
8	(a)(i)	Bearing measured	70	2	B1 70 ± 4
	(ii)	Bearing measured	317		B1 317 ± 4
	(b)	Locus (circle) drawn & shaded		2	B1 circle ±2 mm centre Manchester B1 shading with accurate or approximate circle within tolerance

PAPER 5504					
	No	Working	Answer	Mark	Notes
9	(a)		Plots	1	B1 cao
	(b)		Description	1	B1 dynamic relationship or "positive" (correlation)
	(c)		Line of best fit	1	Line within overlay region, and to the extent of.
	(d)(i)	280 g →	Reading	2	B1 ft from single straight line of positive gradient (±1/2 square) B1 ft from single straight line of positive gradient (±1/2 square)
	(ii)	120 pages →	Reading		
10	(a)	$\frac{1}{6}, \frac{3}{8}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$		2	B2 for all correct (B1 for 1 error or all correct but wrong order, or use of a common denominator decimals).
	(b)	3/5, 65%, 2/3, 0.72, 3/4		2	B2 for all correct (B1 for 1 error or all correct but wrong order or conversions to decimals oe)
11	(a)		182, 178, 180, 184	2	M1 mean of any three consecutive months, eg (147 + 161 + 238) ÷ 3 oe A1 cao
	(b)	Sale price = 80% Fun Friday price = 70% of 80% = 56% (oe)		2	B1 B1 for a fully correct explanation involving a worked example (oe) B1 a partially complete explanation

PAPER 5504					
	No	Working	Answer	Mark	Notes
12	(a)		Reason	1	B1 makes a mention of bias, either directly, or making reference to an insufficient or biased range of responses.
	(b)(i)		Reason	1	B1 make some mention of any one of (a) an insufficient range of responses (b) no mention of money (c) no time frame in the question (d) misunderstanding of "a lot" or "not much"
	(ii)		Question	2	B2 B1 for each of the following upto B2 (a) an improved question eg time frame made clear (b) response boxes (imperfect) (c) response boxes no errors OR For suggesting a generally improved question (a) a question clearly in the context of changes to the canteen (b) at least 3 boxes showing a full range of responses
13	(a)	$20y - 18y = 16 - 9$ oe $2y = 7$	$3\frac{1}{2}$ oe	3	M1 $20y - 18y = 16 - 9$ oe M1 $2y = 7$ A1 cao
	(b)	$40 - x = 3(4 + x)$ $40 - x = 12 + 3x$ $40 - 12 = x + 3x$ $4x = 28$	7	3	M1 multiplying through by 3: $3 \times \frac{40 - x}{3} = 3 \times 4 + 3 \times x$ A1 $40 - 12 = x + 3x$ A1 cao
14	(a)		$12(x\text{-}4)$	1	B1 for $12(x - 4)$ or $12x - 48$ or $12 \times x - 48$ oe $x = 12(x - 4)$ gets B0
	(b)		$18x\text{-}48$	2	M1 $6x +$ "$12(x - 4)$" or $6x +$ "$12x - 48$" A1 ft a linear expression $18x - 48$, $2(9x - 24)$, $3(6x - 16)$, $6(3x - 8)$

PAPER 5504					
No		**Working**	**Answer**	**Mark**	**Notes**
15		x $x^3 - 2x$ 4.1 60.7(21) 4.2 65.6(88) 4.3 70.9(07) Accept answer to 1 dp 4.22 66.7(114) or more 4.23 67.2(269) 4.24 67.7(45) 4.25 68.2(656)	4.2	4	B2 for trial $4.1 \leq x \leq 4.3$ evaluated (B1 for trial $4 < x < 5$ evaluated) B1 for different trial $4.225 \leq x \leq 4.25$ evaluated B1 (dep on at least one previous B1) for 4.2 cao
16	(a)		1.0×10^{-9}	1	B1 accept 1×10^{-9} or just 10^{-9}
	(b)	$1 \div 5 \times 10^{-9}$	2×10^{8}	2	M1 for $1 \div$ ("5×10^{-9}") or digit 2 with zeros only seen Condone omission of bracket for M1. A1 cao
17	(a)	$\frac{6.27 \times 4.52}{4.81 + 9.63} = \frac{28.3404}{14.44} = 1.962631579$	1.9626…	2	B2 for 1.9626… (B1 for 28.34 or 14.44)
	(b)		1.96	1	B1 ft from (a) as rounded to 1dp or 2dp. Do not accept 2, 2.00, but accept 2.0
18			$d = 4n + 6$	2	B2 $d = 4n + 6$ oe (B1 $d = 4n + k$, k an integer or 0, $4n + 6$, $n = 4n + 6$)
19		Vol = $\pi \times 3.8^2 \times 2.5 = \pi \times 14.44 \times 2.5$ = 45.36… × 2.5 = 113.411 Mass = "113" × 1.5 = 170.1165	170	4	M1 for $\pi \times r^2 \times 2.5$ where r = is 3.8 or 7.6 A1 if $r = 3.8$ M1 for "113" × 1.5 A1 for 169.5 – 170.3 cao

PAPER 5504					
	No	Working	Answer	Mark	Notes
20	(a)	$10^2 + 6^2$ or 136 $\sqrt{(100+36)}$ or $\sqrt{136} = 11.66\ldots$	11.7	3	M1 $10^2 + 6^2$ or 136 seen M1 (dep) $\sqrt{100+36}$ or $\sqrt{136}$ A1 11.66 – 11.7
	(b)	$\cos x = \frac{8}{10}$ or 0.8 $x = \cos^{-1} 0.8 = 36.869^\circ$	36.9	3	M1 for $\cos = \frac{8}{10}$, cos = 0.8 (oe) M1 (dep) for $\cos^{-1}$ (oe) A1 for 36.86 – 36.9
21		$18x - 6y = 99$ $\quad 12x - 4y = 66$ $8x + 6y = 18$ $\quad 12x + 9y = 27$ $26x = 117$ $\quad -13y = 39$	$x = 4\frac{1}{2}$ $y = -3$	4	M1 correct process to eliminate either x or y (condone one error) A1 cao for non – eliminated one. M1 (dep on 1st M1) for correct substitution of their found value. A1 cao (need both)
22		$\frac{133}{72} = 1.8472, \frac{160}{82} = 1.9512$ OR $\frac{72}{133} = 0.54135, \frac{82}{160} = 0.5125$ OR $\frac{160}{133} = 1.203...., \frac{82}{72} = 1.1388....$ OR $\frac{133}{160} = 0.83125...., \frac{72}{82} = 0.878$	1.84..≠ 1.95.. 1.20..≠ 1.13..	3	M1 for $\frac{133}{72}$ (= 1.8472…) oe Accept 1.8, 1.85 M1 for $\frac{160}{82}$ (=1.9512…) oe consistent pairing Accept 2.0, 1.9 **OR** M1 for $\frac{160}{133}$ (= 1.203…) oe M1 for $\frac{82}{72}$ (=1.1388) oe A1 for enough decimal places to show that the ratios are not equal; since the scale factors are different the shapes cannot be similar. NB Do Not need conclusion

PAPER 5504					
	No	Working	Answer	Mark	Notes
23	(a)		0.4, 0.6 0.4, 0.6, 0.4	2	B1 for LHS: (0.6), 0.4 B1 for RHS: 0.6, 0.4, 0.6, 0.4
	(b)	(30 × 42) – (25 × 42.8) = 1260 – 1070 = 190 190 ÷ 5 =	38	3	M1 for (30 × 42) – (25 × 42.8) or 1260 – 1070 or 190 seen M1 (dep) for "190" ÷ 5 A1 cao
24	(a)	£12000 × 0.25 = £3000; £12000 – £3000 = £9000 £9000 × 0.25 = £2250; £9000 – £2250 = £6750 £6750 × 0.25 = £1687.50; £6750 – £1687.50 =	£5062.50	3	M1 for 12000 × 0.75 (=9000) oe or £3000 or £23437.50 seen M1 (dep) for at least two further depreciation calculations (complete steps) A1 cao **OR** M2 for $12000 \times (0.75)^3$ or 5062.50 seen (M1 for $12000 \times (0.75)^n$, $n = 2$ or 4)
	(b)	0.8 × 0.8 × 0.8 × 0.8 (oe)	0.4096	2	M1 0.8^4 (oe) A1 cao

PAPER 5505					
	No	Working	Answer	Mark	Notes
1	(a)(i) (ii) (b)	 LCM = 3 × 13 × 17 = 3 × 221	2.21 0.013 663	2 2	B1 for 2.21 B1 for 0.013 M1 for 3 × 13 × 17 oe A1 for 663
2			Tick boxes 1,3 & 6	3	B1 for $\frac{\pi abc}{2d}$; B1 for $2a^2$; B1 for $2(c^2 + d^2)$ (−B1 for each additional expression ticked (>3) to a minimum of 0)
3	(a) (b)	200 × 0.2 0.2 + 0.4	40 0.6	2 2	M1 for 200 × 0.2 or $\frac{40}{200}$ seen A1 for 40 M1 for 0.2 + 0.4 A1 for 0.6
4	(a) (b)	eg 2 | 108 2 | 54 3 | 27 3 | 9 3 12	$2^2 \times 3^3$ 12	3 1	M2 for full systematic method of at least 4 divisions by prime numbers oe factor trees; condone 1 calculation error (M1 for 108 written as a correct product with only one non-prime or equivalent division or a full process with 2 calculation errors.) A1 for $2^2 \times 3^3$ (accept 2 × 2 × 3 × 3 × 3) B1 for 12
5		Perpendicular from P to intersecting arcs (within tramlines); perpendicular at least 2 cm long		2	M1 relevant pair of arcs crossing within tramlines A1 SC M1A0 for full construction of a line perpendicular to AB not through P
6		15 × 10	150 cm^3.	3	M1 for 15 × 10 A1 for 150 B1 for cm^3

PAPER 5505					
	No	Working	Answer	Mark	Notes
7	(a)		k^3.	1	B1 for k^3.
	(b)(i)	$4x + 20 + 3x - 21$	$7x - 1$	4	M1 for **three** of 4 terms $4x + 20 + 3x - 21$ (or better) A1 for $7x - 1$
	(ii)	$x^2 + 3yx + 2xy + 6y^2$	$x^2 + 5xy + 6y^2$		M1 for **three** of 4 terms $x^2 + 3yx + 2xy + 6y^2$ A1 for $x^2 + 5xy + 6y^2$
	(c)		$(p+q)(p+q+5)$	1	B1 for $(p+q)(p+q+5)$
	(d)		m^8	1	B1 for m^8.
	(e)		$6r^3t^6$	2	B2 for $6r^3t^6$ (B1 for $.....r^3t^6$ or for $6....t^6$)
8	(i)	Least length = 100.5	100.5	2	B1 for 100.5
	(ii)	Greatest length = 101.5	101.5		B1 for 101.5; ACCEPT 101.499 or better
9		$6\frac{2}{5} = \frac{32}{5}$ Area of triangle = $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ (= 2) Length of a side of sq. = $\sqrt{18 \times "2"}$ (=6) Perimeter of square = 4 × 6	24	5	B1 for $6\frac{2}{5} = \frac{32}{5}$ oe or $3\frac{1}{5} = \frac{16}{5}$ oe or $\frac{30}{8} + \frac{2}{8}$ oe (or implied by area of triangle=2) M1 for $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ oe M1 for (area of square) = 18 × product of two lengths A1 = $\sqrt{18 \times "2"}$ A1 for 24

PAPER 5505					
	No	Working	Answer	Mark	Notes
10	(a)	$6y = 15 - 5x$	$y = \frac{15-5x}{6}$	2	M1 for either $6y = 15 - 5x$ or for $\frac{5x}{6} + y = \frac{15}{6}$ or $-6y = 5x - 15$ or a correct ft on sign error to $y =$ A1 for $y = \frac{15-5x}{6}$ oe
	(b)	$6k + 5(-21) = 15$	20	2	M1 for subst. of $x = -21$ (or $x = 21$) into given eq^n or answer to (a) A1 for $k = 20$
	(c)(i)		Region R indicated	3	B2 correct region shaded (accept unshaded if R clear) (B1 shaded (R) region satisfies 3 of the 4 given inequalities with same boundaries)
	(ii)		(1,1)		B1 for (1,1)
11	(a)		$y = 2x + 6$	2	B2 for $y = 2x + 6$ (B1 for $y = 2x + k$, $k \neq 1$ or for $y = mx + 6$, $m \neq 0$ or for $2x+6$)
	(b)	Grad of $AB = 2$; Grad of $BC = \frac{-1}{"2"}$	$y = -\frac{1}{2}x + 6$	2	M1 for Grad of $BC = \frac{-1}{"2"}, -\frac{1}{2}$ or grad of $BC = -\frac{1}{\text{grad of AB}}$ A1 ft for $y = -\frac{1}{2}x + 6$ oe ft on wrong coeff. of x in (a)
	(c)	Eg A rectangle is always a cyclic quadrilateral because the opposite angles of a rectangle always add up to 180° (90+90)		1	B1 for valid explanation. (eg lines from the pt of int. of diagonals of rect to all 4 vertices are equal(radii))
12		Vertices of new triangle at $(-1, -4)$ $(-4, 2)$ and $(2, 2)$	Correct triangle drawn	3	B3 cao (B2 for 3 correct vertices no triangle or triangle with 2 correct vertices (B1 for triangle with two of six co-ordinates correct from using P as centre or any isosceles triangle with base 6 and height 6)

PAPER 5505					
	No	Working	Answer	Mark	Notes
13	(a)		32	1	B1 for 32 (accept 31.5 to 33.5 inclusive)
	(b)			3	B1 for ends of whiskers at 9 and 57 (with a box) B1 for ends of box at 16 and 45/46 ($\pm$ 0.5) B1for median marked at "32"or complete box and whisker diagram drawn with a median inside the box
	(c)	Median(B)>Median(G); on average boys take longer IQR(B)>IQR(G); times for boys have a greater spread		2	B1 eg for comparison of medians (ft on diagrams) B1 eg for comparison of (interquartile) ranges (ft on diagram)
14		Reading top to bottom frequencies are 20; 18; 45; 52		2	B2 all correct (B1 for one frequency correct)
15	(a)	$1600 = p\,q^0$.; $400 = pq^2$ $q^2 = 0.25$	$p = 1600$ $q = 0.5$	3	M1 for either $400 = pq^2$ or $1600 = pq^0$ B1 for $p = 1600$ A1 for $q = 0.5$
	(b)	$V = pq^{-2}$	6400	2	M1 for recognition that t = –2 A1 for 6 400

PAPER 5505					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	(I) $AB = AC$ (triangle ABC is isosceles) (II) PB = PC tangents (from a point to a circle are) equal (III) AP = AP (common side) so the 2 triangles are congruent ,SSS.		3	B3 for I, II, III with congruency reason (B2 for any two of I, II or III) (B1 for any one of the I, II or III)
	(b)	$BPC = 20°$ PBC (or PCB) = 90-1/2 "20" (= 80°) $BAC = PBC$ = "80"	50°	4	B4 for 50° (B3 for $BAC = 80°$) (B2 for $PBC = 80°$ or $PCB = 80°$) (B1 for $APC = 10°$ or $BPC = 20°$ or a middle angle = 90°) SC if clear numerical slip seen eg "PBC = 180 – 90 – 10 = 70" then goes on to get correct ft angle $ABC = 55$ deduct 1 from total so this cand would get B4–1 = B3
17	(a)	$\overrightarrow{OP} = \overrightarrow{OA} + \overrightarrow{AP}$ $= \overrightarrow{OA} + \frac{2}{3}(6\mathbf{c} - 6\mathbf{a})$ $= 6\mathbf{a} + 4\mathbf{c} - 4\mathbf{a}$	$2\mathbf{a} + 4\mathbf{c}$	3	M1 for $\overrightarrow{OP} = \overrightarrow{OA} + \overrightarrow{AP}$ or any correct vector journey involving $\overrightarrow{OP}$ M1 for $\overrightarrow{AP} = \frac{2}{3}(6\mathbf{c} - 6\mathbf{a})$ oe or $\overrightarrow{CP} = \frac{1}{3}(-6\mathbf{c} + 6\mathbf{a})$ oe or reverse vectors A1 for $2\mathbf{a} + 4\mathbf{c}$ oe (accept unsimplified)
	(b)	Eg $\overrightarrow{OM} = \overrightarrow{OC} + \overrightarrow{CM} = 6\mathbf{c} + 3\mathbf{a}$ $\overrightarrow{OM} = 1.5\overrightarrow{OP}$	$\overrightarrow{OM} = 1.5\overrightarrow{OP}$ so OPM is a straight line	2	B1 for $\overrightarrow{OM} = 6\mathbf{c} + \frac{1}{2}(6\mathbf{a})$ or $\overrightarrow{PM} = 2\mathbf{c} + \mathbf{a}$ unsimplified or reverse vectors B1 for a fully correct proof.

PAPER 5505					
	No	Working	Answer	Mark	Notes
18	(a)		4	1	B1 for 4 condone $\pm$ 4
	(b)		2	1	B1 for 2 condone ± 2
	(c)	$\sqrt{160} = 4\sqrt{10}$; $\left[\frac{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)-\sqrt{2}\times\sqrt{5}}{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)}\right]\times 100$ $\left[\frac{6\sqrt{10}-\sqrt{10}}{6\sqrt{10}}\right]\times 100$	$\frac{500}{6}$	4	B1 for **either** $\sqrt{160} = 4\sqrt{10}$ or $\sqrt{8} = 2\sqrt{2}$ **or** $\sqrt{20} = 2\sqrt{5}$ M1 for $\left[\frac{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)-\sqrt{2}\times\sqrt{5}}{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)}\right]$ oe $(\times 100)$ B1 for either $6\sqrt{10} - \sqrt{10}$ or $6\sqrt{10}$ A1 for $\frac{500}{6}$ (accept 83.3 if no obvious earlier error)

PAPER 5505					
	No	Working	Answer	Mark	Notes
19	(a)(i)		$(2x-7)(x-14)$	3	M1 x^2 term and constant term (± 98) obtained or $2x(x-14) - 7(x-14)$ or $x(2x-7) - 14(2x-7)$ A1 for $(2x-7)(x-14)$
	(ii)		$x = \frac{7}{2}$; $x = 14$		B1ft ft (i) provided of form $(2x\pm a)(x\pm b)$
	(b)(i)		$\frac{7}{n+7}$	3	B1 for $\frac{7}{n+7}$ oe
	(ii)	$\frac{7}{n+7} = \frac{2}{5} \Rightarrow 2(n+7) = 5 \times 7$ $2n = 21$	$n=10.5$ is not possible since n has to be an integer		M1 for $2(n+7) = 5\times 7$ or $n+7=5\times 3.5$ (can be implied) ft (b)(i) fractional in terms of n and < 1 A1 ft for $n=10.5$ not possible (since n not integer) oe
	(c)	$2\times\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right) = \frac{4}{9}$ $14n\times 9 = 4(n+7)^2$ $14n\times 9 = 4(n^2+14n+49)$ $4n^2+56n+196-126n = 0$	$2n^2 - 35n + 98 = 0$	5	M1 for $\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right)$ seen M1 for $2\times\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right)$ oe $(=\frac{4}{9})$ M1(dep on 1st M) elimination of fractions within an equation B1 3 terms correct in expansion of $(n+7)^2 = n^2 + 7n + 7n + 49$ A1 full valid completion to printed answer

PAPER 5505					
	No	Working	Answer	Mark	Notes
	(d)	$\frac{7}{n+7}\times\frac{7}{n+7}=\frac{7}{21}\times\frac{7}{21}=$	$\frac{1}{9}$	2	M1 for $\frac{7}{n+7}\times\frac{7}{n+7}$ or better or ft [answer (b)(i)]^2 or $1-\frac{4}{9}-(\frac{n}{n+7})^2$ A1 for $\frac{1}{9}$ oe cao
20	(a)(i)		$y=1+\sin x$	2	B1 for $y=1+\sin x$
	(ii)		$y=2\sin x$		B1 for $y=2\sin x$ SC both (i) f(x) + 1, (ii) 2f(x) B1
	(b)	Stretch parallel to y-axis scale factor 3 Stretch parallel to x-axis scale factor $\frac{1}{2}$		3	M1 for 'stretch' A1 for Stretch parallel to y-axis scale factor 3 oe A1 for Stretch parallel to x-axis scale factor $\frac{1}{2}$ oe SC if M0 award BI for "sf 3 vertically" **and** "sf $\frac{1}{2}$ horizon."

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
1		Question	2	B1 for each of the following upto B2 (a) an improved question eg time frame made clear (b) response boxes (imperfect) (c) response boxes no errors OR For suggesting a generally improved question (a) a question clearly in the context of changes to the canteen (b) at least 3 boxes showing a full range of responses
2	Locus (circle) drawn & shaded		2	B1 circle centre Manchester ±2mm B1 shading with accurate or approximate circle within tolerance
3 (a)		182, 178, 180, 184	2	M1 mean of any three consecutive months, eg (147 + 161 + 238) ÷ 3 oe A1 cao
(b)	Sale price = 80% Fun Friday price = 70% of 80% = 56% (oe)		2	B1 B1 for a fully correct explanation involving a worked example (oe) B1 a partially complete explanation
4	x $x^3 - 2x$ 4.1 60.7(21) 4.2 65.6(88) 4.3 70.9(07) 4.22 66.7(114) 4.23 67.2(269) 4.24 67.7(45) 4.25 68.2(656)	4.2	4	B2 for trial $4.1 \leq x \leq 4.3$ evaluated (B1 for trial $4 < x < 5$ evaluated) B1 for different trial $4.225 \leq x \leq 4.25$ evaluated B1 (dep on at least one previous B1) for 4.2 cao

PAPER 5506					
	No	Working	Answer	Mark	Notes
5	(a)		1.0×10^{-9}	1	B1 accept 1×10^{-9} or just 10^{-9}
	(b)	$1 \div (5 \times 10^{-9})$	2×10^{8}	2	M1 for $1 \div$ ("5×10^{-9}") or digit 2 with zeros only seen Condone omission of bracket for M1. A1 cao
6	(a)	$\frac{6.27 \times 4.52}{4.81 + 9.63} = \frac{28.3404}{14.44} = 1.962631579$	1.9626…	2	B2 for 1.9626… (B1 for 28.34… or 14.44)
	(b)		1.96	1	B1 ft from (a) as rounded to 1dp or 2dp. Do not accept 2, 2.00, but accept 2.0
7			$d = 4n + 6$	2	B2 $d = 4n + 6$ oe (B1 $d = 4n + k$, k an integer $\neq 6$, $4n + 6$, $n = 4n + 6$)
8		Vol = $\pi \times 3.8^2 \times 2.5 = \pi \times 14.44 \times 2.5$ $= 45.36\ldots \times 2.5 = 113.411$ Mass = "113" × 1.5 = 170.1165	170	4	M1 for $\pi \times r^2 \times 2.5$ where r = is 3.8 or 7.6 A1 if $r = 3.8$ M1 for "113" × 1.5 A1 for 169.5 – 170.3 cao

PAPER 5506					
	No	Working	Answer	Mark	Notes
9	(a)	$10^2 + 6^2$ or 136 $\sqrt{(100 + 36)}$ or $\sqrt{136} = 11.66\ldots$	11.7	3	M1 for $10^2 + 6^2$ or 136 seen M1 (dep) $\sqrt{100+36}$ or $\sqrt{136}$ A1 11.66 – 11.7
	(b)	Cos x = 8/10 or 0.8 $x = \cos^{-1} 0.8 = 36.869^o$	36.9	3	M1 for cos = $\frac{8}{10}$, cos = 0.8(oe) M1 (dep) for $\cos^{-1}$ (oe) A1 for 36.86 – 36.9 M1 Use of sine rule and x found M1 for $x = 90 - \sin^{-1}$("0.8") A1 for 36.86 – 36.9
10		$18x - 6y = 99$ $12x - 4y = 66$ $8x + 6y = 18$ $12x + 9y = 27$ $26x = 117$ $-13y = 39$	$x = 4\frac{1}{2}$ $y = -3$	4	M1 correct process to eliminate either x or y (condone one error) A1 cao for non – eliminated one. M1 (dep on 1st M1) for correct substitution of their found value. A1 cao (need both)

PAPER 5506					
	No	Working	Answer	Mark	Notes
11		$\frac{133}{72} = 1.8472\,,\ \frac{160}{82} = 1.9512$ OR $\frac{72}{133} = 0.54135, \frac{82}{160} = 0.5125$ OR $\frac{160}{133} = 1.203...., \frac{82}{72} = 1.1388....$ OR $\frac{133}{160} = 0.83125...., \frac{72}{82} = 0.878$	1.84..≠ 1.95.. 1.20..≠ 1.13..	3	M1 for $\frac{133}{72}$ (= 1.8472…) oe Accept 1.8, 1.85 M1 for $\frac{160}{82}$ (=1.9512…) oe consistent pairing Accept 2.0, 1.9 **OR** M1 for $\frac{160}{133}$ (= 1.203…) oe M1 for $\frac{82}{72}$ (=1.1388) oe A1 for enough decimal places to show that the ratios are not equal; since the scale factors are different the shapes cannot be similar. NB Do Not need conclusion
12	(a)	£12000 × 0.25 = £3000; £12000 – £3000 = £9000 £9000 × 0.25 = £2250; £9000 – £2250 = £6750 £6750 × 0.25 = £1687.50; £6750 – £1687.50 =	£5062.50	3	M1 for 12000 × 0.75 (=9000) oe or £3000 or £23437.50 seen M1 (dep) for at least two further depreciation calculations (complete steps) A1 cao **OR** M2 for 12000 × $(0.75)^3$ or 5062.50 seen (M1 for 12000 × $(0.75)^n$, $n = 2$ or 4)
	(b)	0.8 × 0.8 × 0.8 × 0.8 (oe)	0.4096	2	M1 0.8^4 (oe) A1 cao

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
13	$r^2 = \frac{3\times10}{\pi h} = \frac{3\times10}{\pi 1.5} = \frac{3\times10}{4.712..} = 6.36, 6.37$ $r = \sqrt{6.366\ldots}$	2.52-2.54	3	M1 for correct rearrangement to give $r^2 = \frac{3V}{\pi h}$ or $30 \div 4.712..$ or $6.36 - 6.37$ *Allow 0.3, 0.33 for* $\frac{1}{3}$ M1 (dep) for $\sqrt{}$ A1 cao 2.52 – 2.54
14 (a)		0.4 0.6,0.4, 0.6,0.4	2	B1 for LHS: (0.6), 0.4 B1 for RHS: 0.6, 0.4, 0.6, 0.4
(b)	0.6×0.6	0.36	2	M1 $0.6 \times$ "0.6" [0 < "0.6" < 1] A1 cao
(c)	$(30 \times 42) - (25 \times 42.8) = (1260 - 1070 = 190$ $190 \div 5 =$	38	3	M1 for $(30 \times 42) - (25 \times 42.8)$ or $1260 - 1070$ or 190 seen M1(dep) for "190" ÷ 5 A1 cao 38

PAPER 5506					
	No	Working	Answer	Mark	Notes
15	(a)	$S = \frac{k}{f^2};\ 125 = \frac{k}{8^2};\ k = 8000$	$S = \frac{8000}{f^2}$	3	M1 for $S = \frac{k}{f^2}$ M1 for $125 = \frac{k}{8^2}$ A1 cao These marks can be awarded if the full formula appears in part (b), rather than in part (a). [SC: $S = \frac{125}{64} f^2$ M1 M0 A0, $S = 1.95(3125) f^2$ M1 M0 A0 $S = \frac{1000}{f}$ M1 M0 A0]
	(b)		500	1	B1 cao

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
16	$0.5 \times 3.2 \times 8.4 \times \text{Sin } B = 10$ $\sin B = 0.74404\ldots$ 48.077 $AC^2 = 3.2^2 + 8.4^2 - 2 \times 3.2 \times 8.4 \times \cos B$ $AC^2 = 44.8815\ldots..$ $AC = 6.69\ (936\ldots)$ Perimeter = 18.3 Use the altitude AD, $\frac{h \times 8.4}{2} = 10 \Rightarrow h = (2.381)$ $BD = \sqrt{3.2^2 - h^2} = 2.139$ $DC = 6.261$ $AC = \sqrt{2.38^2 + '6.261'^2} = 6.69(936)$ Perimeter = 18.3	18.3	6	M1 for $0.5 \times 3.2 \times 8.4 \times \sin B$ (= 10) A1 for sin B = 0.74(404…) or B = 47.7 – 48.1 M1 for $3.2^2 + 8.4^2 - 2 \times 3.2 \times 8.4 \times \cos$ "48.077" M1(dep) for AC^2 = "44.8(815)"….. with correct order of evaluation A1 AC = 6.69 – 6.7 A1 18.29 – 18.3 **for** $\frac{h \times 8.4}{2} = 10 \Rightarrow h = (2.381)$ M1 for $BD^2 = 3.2^2 - "2.381"^2$ A1 BD = 2.1 – 2.2 M1 (dep) $AC^2 = "2.381"^2 + "6.261"^2$ A1 AC = 6.69 – 6.7 A1 18.29 – 18.3

PAPER 5506					
	No	Working	Answer	Mark	Notes
17	(a)	$(x + 8)^2 = x^2 + (x + 5)^2$ $x^2 + 16x + 64 = 2x^2 + 10x + 25$		4	B1 for angle $OTA = 90°$ (implied by use of Pythagoras with OA as hypotenuse) M1 $(x + 8)^2 = x^2 + (x + 5)^2$ oe M1 for correct squaring of x+8 or x+5 A1 for completion following correct working
	(b)	$(+6 + \sqrt{(6^2 - - 4\times39)})/2$ $= (6 \pm \sqrt{(36 + 156)})/2$ $= (6 \pm \sqrt{192})/2 = (6 + 13.856)/2$	9.93	3	M1 for substitution into quadratic formula, allow sign errors in b and c M1 for $x = (6 \pm \sqrt{192})/2$ [+ alone will do] A1 for 9.92 – 9.93
					M1 for $(x-3)^2-9-39$ M1 for $x = 3 \pm \sqrt{48}$ [+ alone will do it] A1 for 9.92 – 9.93 T&I= 9.93 gets M1,M0,A0
18		$EB = 60 \times \tan 30°$ $BD = \sqrt{(60^2 + 60^2)}$ $\tan BDE = 34.64 \div 84.85$	22.2°	4	M1 for $EB = 60\times\tan30$ M1 for $BD = \sqrt{(60^2 + 60^2)}$ M1 for $\tan BDE =$ "34.64" ÷ "84.85" A1 22.17 – 22.21
		$EB = 60 \times\tan 30°$ (= 34.64) $ED^2 = 60^2 + (\frac{60}{\cos 30})^2$ $ED = \sqrt{8400} = (91.65)$ $\text{Angle} = \sin^{-1}\left(\frac{EB}{\sqrt{8400}}\right) = 22.2$			M1 for $EB = 60 \times\tan 30°$ oe M1 for fully correct method for ED M1 for $\sin BDE = \left(\frac{'34.84'}{'\sqrt{8400}'}\right)$(oe) A1 22.17 – 22.21

PAPER 5506					
	No	Working	Answer	Mark	Notes
19	(a)	$x^2 + 6^2 = 25$ $x^2 = -11$		2	M1 substitutes y=6 to get x^2+36 = 25 A1 deduces x^2=25-36<0; impossible, (so line does not intersect curve)
	(b)	$y^2 = (2x - 2)^2$ $x^2 + (2x - 2)^2 = 25$ $x^2 + 4x^2 - 8x + 4 = 25$ $5x^2 - 8x + 4 - 25 = 0$ $5x^2 - 8x - 21 = 0$ $(5x + 7)(x - 3) = 0$ or $x = \frac{-(-8) \pm \sqrt{(-8)^2 - 4 \times 5 \times (-21)}}{10} = \frac{8 \pm \sqrt{484}}{10}$ So $x = 3$, or $x = -1.4$ Subs into either equation gives: $y = 4$, or $y = -4.8$	$x = 3$ $y = 4$ $x = -1.4$ $y = -4.8$	6	M1 $y^2=(2x-2)^2$ seen or implied A1 $x^2 + 4x^2 - 8x + 4 = 25$ (oe expanded form) M1 correct attempt to solve 3 term quadratic equation A1 $x = 3$, $x = -1.4$ M1 (dep on previous Ms) Sub one value of x into either equation gives: A1 $y = 4$, $y = -4.8$ NB: incorrectly matched pairs loses the final A1.

PAPER 5506					
	No	Working	Answer	Mark	Notes
20	(a)	400.005 ÷ 59.95 = 6.672310 6.672310 ÷ 1000 × 3600 = 24.02032 399.995 ÷ 60.05 = 6.661032 6.661032 ÷ 1000 × 3600 = 23.97972	24.020 23.980	5	B1 for 400.005 or 59.95 seen oe M1 for "400.005" ÷ "59.95" where "400.005" ∈ [400.005,400.5] and "59.95" ∈ [59.5,59.95] oe B1 for 399.995 or 60.05 seen oe M1 for "399.995" ÷ "60.05" where "399.995" ∈ [399.5,399.95] and "60.05" ∈ [60.05,60.5] oe A1 23.979-23.980 and 24.020-24.0204
	(b)	24.0 because to 1dp the answers are the same		1	B1cao for 24.0 with reason
	(c)	177 × 50/477 = 18.553 → 19 → 18 111 × 50/477 = 11.635 → 12 86 × 50/477 = 9.0147 → 9 82 × 50/477 = 8.595 → 9 21 × 50/477 = 2.201 → 2	18 12 9 9 2	3	M1 for $\frac{50}{"477"} \times 177$ or 111 or 86 or 82 or 21 A1 for all integers or better answers, at least 3 correct A1 cao
21	(a)	$40 - x = 3(4 + x)$ $40 - x = 12 + 3x$ $40 - 12 = x + 3x$ $4x = 28$	7	3	M1 multiplying through by 3: $3 \times \frac{40 - x}{3} = 3 \times 4 + 3 \times x$ A1 $40 - 12 = x + 3x$ A1 cao
	(b)	$\frac{2x(2x - 3)}{(2x - 3)(2x + 3)} = \frac{2x}{2x + 3}$	$\frac{2x}{2x + 3}$	3	B1 for $(2x-3)(2x+3)$ B1 for $2x(2x-3)$ or $(2x + 0)(2x + 3)$ B1 cao

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
22	Distance from x axis is y. Distance from (0, 2) is $\sqrt{(x^2+(y-2)^2)}$ $y^2 = x^2 + (y-2)^2$ $y^2 = x^2 + y^2 - 4y + 4$ $0 = x^2 - 4y + 4$ $4y = x^2 + 4$ and finish		4	B1 for $(x-0)^2 + (y-2)^2$ or $\sqrt{((x-0)^2+(y-2)^2)}$ oe seen B1 for $y = \sqrt{(x-0)^2+(y-2)^2}$ or $y^2 = (x-0)^2 + (y-2)^2$ oe B1 $(y-2)^2 = y^2 - 4y + 4$ seen B1 for $4y = x^2 + 4$ and finish

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone: 01623 467467
Fax: 01623 450481
Email: publications@linneydirect.com

Order Code UG015616 July 2004

For more information on Edexcel and BTEC qualifications please contact
Customer Services on 0870 240 9800
or http://enquiries.edexcel.org.uk
or visit our website: www.edexcel.org.uk

London Qualifications Limited, trading as Edexcel. Registered in England and Wales No. 4496750
Registered Office: Stewart House, 32 Russell Square, London WC1B 5DN



GCSE

Edexcel GCSE

Mathematics A 1387

Summer 2005
Mark scheme

Edexcel GCSE
Mathematics A 1387

Edexcel is one of the leading examining and awarding bodies in the UK and throughout the world. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers.

Through a network of UK and overseas offices, Edexcel's centres receive the support they need to help them deliver their education and training programmes to learners.

For further information please call our Customer Services on 0870 240 9800, or visit our website at www.edexcel.org.uk.

Summer 2005

Publications Code UG016720

All the material in this publication is copyright
© Edexcel Ltd 2005

CONTENTS

Notes on Marking Principles 1

Paper 5521/01 3

Paper 5521/02 12

Paper 5523/03 18

Paper 5523/04 27

Paper 5525/05 37

Paper 5525/06 45

NOTES ON MARKING PRINCIPLES

1 Types of mark

- M marks: method marks
- A marks: accuracy marks
- B marks: unconditional accuracy marks (independent of M marks)

2 Abbreviations

cao – correct answer only
ft – follow through
isw – ignore subsequent working
SC: special case
oe – or equivalent (and appropriate)
dep – dependent
indep - independent

3 No working

If no working is shown then correct answers normally score full marks
If no working is shown then incorrect (even though nearly correct) answers score no marks.

4 With working

If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks. Discuss each of these situations with your Team Leader.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.
If there is no answer on the answer line then check the working for an obvious answer.

5 Follow through marks

Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

6 **Ignoring subsequent work**
It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: eg. incorrect cancelling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect eg algebra.
Transcription errors occur when candidates present a correct answer in working, and write it incorrectly on the answer line; mark the correct answer.

7 **Probability**
Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

8 **Linear equations**
Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

9 **Parts of questions**
Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)		17252	1	B1 cao
	(b)		5400	1	B1 cao
	(c)		thousands, 1000, 4000	1	B1
2	(a)		grams, g	3	B1 oe spelling
			centimetres, cm		B1 oe spelling
			millilitres, m*l*, cm^3		B1 oe spelling
	(b)		5	1	B1 cao
3	(a)		106, 102	1	B1 cao ignore extras
	(b)		eg take away 4	1	B1 could be indicated on the diagram
	(c)		46	1	B1 cao

Paper 5521/01

No	Working	Answer	Mark	Notes
4	286 × 43 = 11440 + 12298 = 12298 43 × 286 = 258 + 3440 + 8600 = 12298 286 × 40 = 1140 286 × 3 = 858 1140+858=12298 x | 40 | 3 200 | 8000 | 600 | 8600 80 | 3200 | 240 | 3440 6 | 240 | 18 | 258 12298 2 8 6 1 | 0 8 | 3 2 | 2 4 | 4 2 | 0 6 | 2 4 | 1 8 | 3 2 9 8	12298	3	M2 for complete correct method (condone one computational error) (M1 for complete correct method with two computational errors) A1 cao OR B2 inside of grid completed (condone missing zeros and one error) (B1 2 or 3 errors) B1 cao
5 (a)		18, 69	1	B1
(b)(i)		18 or 36	1	B1
(ii)		16 or 36	1	B1
(c)		factor	1	B1
(d)(i)		18	3	B1 cao
(ii)		11 or 88		B1
(iii)		69		B1 cao

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
6	(a)		April & May	1	B1 for both
	(b)		Daffodil	1	B1
	(c)		Feb	1	B1
	(d)		Crocus	1	B1
	(e)(i)		$\frac{1}{5}$	2	B1 for $\frac{1}{5}$ oe
	(ii)		× from 56 mm to 64 mm from 0		B1 A single mark on the line, between 56 mm and 64 mm measured from end 0
7	(a)	$\frac{40}{100}$	$\frac{2}{5}$	2	B2 for $\frac{2}{5}$ B1 for $\frac{40}{100}$ or $\frac{4}{10}$ or $\frac{20}{50}$ or $\frac{8}{20}$
	(b)		0.98	1	B1 cao
	(c)		7 500 000	1	B1 cao
	(d)		25	1	B1 cao
	(e)		60	1	B1 cao

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
8	(a)(i)		(0, 2)	2	B1 cao
	(ii)		(4, 1)		B1 cao
	(b)		$(2, 1\frac{1}{2})$ marked	1	B1 Allow 2mm tolerance from $(2, 1\frac{1}{2})$
9	(a)		2.40	1	B1 cao could be indicated on the diagram
	(b)	1.60 + 0.40	2.00	2	M1 for appropriate sum or product in £ or p or 200 seen eg 1.60 + 0.40, 160 + 40, 0.80 + 0.80 + 0.40, 80 + 80 + 40, 0.08×25, 0.80×2.5, 200 A1 cao
	(c)	$1\div0.8$ or $2.50\div2$	1.25	2	M1 for $1.00\div0.8$ or $2.50\div2$ or 125 or appropriate combination eg $1+\frac{1}{2}\times0.50$ A1 cao
10	(a)		hexagon	1	B1 Condone spelling error
	(b)		Sum of angles at a point is 360°	2	B1 for 360 seen B1 for "point", "complete turn" or "a circle" or similar unless accompanied by an incorrect angle SC If neither B1 scored, award B1 for a clear indication that the size of an angle, other than *x*, is 90° or a right angle (may be on diagram)
	(c)	$30\times4+8\times2$	136	2	M1 $30\times4+8\times2$ or attempt to sum 5 or 6 lengths A1 cao

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
11	(a)		13, 67, 76, 103, 130	5	B1 cao
	(b)		$-7, -3, -1, 0, 5$		B1 cao
	(c)		0.07, 0.072,0.7, 0.702, 0.72		B1 cao
	(d)		0.6, $\frac{2}{3}$, 70%, $\frac{3}{4}$		B2 (B1 for any 3 in correct order)
12	(a)		16 30	1	B1 Accept 4 30 pm Do not accept 4 30
	(b)(i)	$33.56 \div 4$ oe	8.39	3	M1 for $33.56 \div 4$ oe eg $3356 \div 4$, division by 2 twice A1 cao
	(ii)		9		B1 ft from "8.39" unless whole number of pounds
13	(a)		6 cm^2	3	B2 for 6 cao for numerical answer (B1 for $5.5 < \text{Area} \leq 7$) then B1 (indep) for cm^2 with or without numerical answer
	(b)	See diagram	Correct shape	2	B2 (B1 for any 2 sides correct or a correct enlargement scale factor $\neq 1$ or 2)

Paper 5521/01				
No	**Working**	**Answer**	**Mark**	**Notes**
14 (a)	$(4+3)\times10$	70	2	M1 for (4 + 3) × 10 A1 cao
(b)	$120\div10-3$	9	2	M1 for $\frac{120}{10}$ or 12 seen eg $12\times10=120$ A1 cao
(c)		$C=10(n+3)$	3	B3 for $C=10(n+3)$ oe such as $C=(n+3)\times10$ (B2 for correct RHS or $C=n+3\times10$, $C=10n+3$ oe B1 for C = some other linear expression in n or for $n+3\times10$, $10n+3$ etc) Note: $C = n$ scores no marks
15		11 13 16 8 21	2	B2 all correct (B1 for 2 correct)

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)		$2p + 4q$	2	B2 for $2p + 4q$ (accept $2 \times p$ etc) (B1 for $2p$ or $4q$)
	(b)		$2y^2$	1	B1 accept $2 \times y^2$ oe inc $2 \times y \times y$
	(c)		$3c + 4d$	2	B2 for $3c + 4d$ (accept $3 \times c$ etc) (B1 for $3c$ or $4d$)
	(d)		$8pq$	1	B1 accept in any order but must not include $\times$ sign
17	(a)(i)		60	2	B1 cao
	(ii)		eg top triangle is equilateral		B1 for reason
	(b)		150	2	M1 for $\frac{180-"60"}{2} + 90$ A1 ft from (a)(i) if $x < 90$ SC B1 for "60" + 90 if $x < 90$
18			40	2	M1 for 60×2 or 120 or $60 \div 3$ or 20 or $\frac{120}{180}$ A1 cao
19			correct drawing	2	B2 Condone hidden detail shown with solid lines and missing lines on front face (B1 for a correct sketch with other incorrect sketch(es) or for prism with correct cross section >1 cube wide or for attempt to draw prism with correct cross section or prism with correct plan and side elevation)

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
20		$\frac{600}{3\times10}$ or $\frac{640}{3.2\times10}$	$20\text{-}21\frac{1}{3}$	2	M1 for rounding at least two of the numbers to 1 sf or for sight of 640, 3.2 or 640, 32 or 600, 32 or 30 seen A1 for $20\text{-}21\frac{1}{3}$ Note: 20.3125 scores M0 A0
21	(a)		Points plotted	1	B1 $\pm$ 1 full (2 mm) square
	(b)		positive	1	B1 cao
	(c)		Line of best fit	1	B1 Must pass through (42.5, 1.45), (42.5, 1.55) AND (67.5, 1.75), (67.5, 1.85)
	(d)		~ 1.65	1	B1 ft from single line segment with positive gradient $\pm$ 1 full (2 mm) square
22	(a)	eg $50\times\frac{2000}{500}$	200	2	M1 for $\frac{2000}{500}$ or 4 seen A1 cao
	(b)	eg $400\times\frac{750}{500}$	600	2	M1 for $\frac{750}{500}$ or 1.5 seen or 400 + 200 A1 cao

Paper 5521/01					
No		Working	Answer	Mark	Notes
23	(a)	$4\times3-2\times1$ $12-2$	10	3	M1 for 3×4 (=12) or 1×2 or attempt to divide diagram up into rectangles M1 "12"– "2" or sum of areas of rectangles A1 cao
	(b)(i)	$\frac{10}{100}\times680$ or $680\div10$ 680 + 68	748	5	M1 $\frac{10}{100}\times680$ or 680÷10 or 68 seen M1 (dep) 680 + "68" or M2 for 680×1.10 A1 cao
	(ii)	"748"÷50 or 14.96	15		M1 For "748"÷50 or 14.96 Accept "748" rounded up or down to next 50 followed by $\div50$ A1 ft from (b)(i) rounded up SC B1 for 680 (seen) leading to 14

Paper 5521/02					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	Plain llll lll 8 Chicken lll 3 Bovril llll 5 S & Vin llll 4		3	M1 for attempt to tally A1 for 1 frequency correct or all tallies correct A1 for all frequencies correct (accept for /20)
	(b)		4	1	B1 ft
	(c)		Plain or 8	1	B1 ft
2	(a)(i)		11	2	B1 cao
	(ii)		16		B1 cao
	(b)	See diagram	Correct lines	2	B2 cao for both lines correct (B1 for one line correct)
	(c)		12	2	B2 cao (B1 for 11 or 13)
3	(a)		580	1	B1 for 580 (± 2) could be written on line
	(b)		7.2	1	B1 for 7.2 ± 0.02 could be written on line
	(c)		Arrow at 48	1	B1 allow ± half graduation
	(d)		Arrow at 6.7	1	B1 allow ± half graduation
4	(i)		Cylinder	2	B1 ignore spelling
	(ii)		Cuboid		B1 ignore spelling
5	(a)	£10 – (£2.15 + £2.30)	5.55	4	M1 £2.15 + £2.30 A1 for 4.45 M1 £10 – "4.45" A1 cao
	(b)	£60 ÷ £2.80 = 21.42857	21	2	M1 for £60 ÷ 2.80 or sight of digits 214… A1 for 21
	(c)	$120 \times 25 \div 100$	30	2	M1 ¼ of £120 (oe) A1 cao SC B2 for £90

Paper 5521/02					
No		**Working**	**Answer**	**Mark**	**Notes**
6	(a)(i)		143^0	2	B1 for 143 ($\pm 2^0$)
	(ii)		Obtuse		B1 for obtuse (ignore spelling)
	(b)	See diagram	Accurate drawing	1	B1 for accurate drawing ± 2mm
7	(a)(i)		5	2	B1 cao
	(ii)		23		B1 cao
	(b)	$\times 2 - 1$		1	B1 for explaining a suitable method
	(c)	See their diagram		1	B1 for a correct diagram
	(d)		14, 17	2	B2 cao for both (B1 for one only ft from their 14)
8	(a)		90	1	B1 accept –90
	(b)		540	1	B1 accept –540
	(c)		Jupiter	1	B1 accept –150
	(d)		- 230	1	B1 cao

Paper 5521/02					
No		Working	Answer	Mark	Notes
9	(a)	2658 – 2430 = 228 "228" × 32	72.96	4	M1 2658 – 2430 A1 228 M1 "228" × 32 or "228" × 0.32 or digits 7296 seen A1 cao **Or** M1 for 2430 × 32 (or digits 77760 seen) or 2658 × 32 (or digits 85056 seen) A1 if 1 correct M1 for "85056" – "77760" or 7296 seen A1 cao
	(b)	$\frac{2}{5} \times 145 = 58$ 145 – "58"	87	3	M1 $\frac{2}{5} \times 145$ (or M1 $\frac{3}{5}$ seen) A1 58 (or M1 $\frac{3}{5} \times 145$) A1 for 87 ft
	(c)(i) (ii)		80 125	2	B1 for 80 (± 1) B1 125 (± 3)

Paper 5521/02				
No	**Working**	**Answer**	**Mark**	**Notes**
10 (a)		1.5 – 2.0	1	B1 for height between 1.5m – 2.0m inclusive
(b)	Height of man × "2.5"	3 – 6	3	B3 for height between 3m – 6m inclusive (B2 for multiplying (a) by a number between 2 and 3 inclusive) (B1 for multiplying (a) by a number)
11	61 – 19 = 42 42 ÷ 3 = 14	14	2	M1 for – 19 or 42 seen A1 cao
12 (a)		5	1	B1
(b)	4+5+5+5+4+3+2+1+4+5 = 38 mean = 38 ÷ 10 = 3.8	3.8	2	M1 for attempt to add and ÷ 10 or 3.7 or 3.9 seen A1 for 3.8 SC B1 for 33.5 seen
13 (a)		$3x$	1	B1 cao Accept $3 \times x$, $x3$, $x \times 3$, $x + x + x$
(b)		x - 9	1	B1 for x – 9 cao
14 (a)	14.44 – 8.660254038	5.77974(…)	2	M1 for 14.44 seen or 8.66(…) or 5.7 or 5.8 or better rounded or truncated
(b)		6	1	A1 cao B1 ft
15	15 ÷ 24	62.5	2	M1 for 15 ÷ 24 or 1500 ÷ 24 or sight of digits 625 A1 cao
16	2.10 × 450	945	2	M1 for digits 210 × 450 or sight of digits 945 A1 cao
17	See diagram	$2(y + y)$ $2y + 2y$	2	B1 for $2(y + y)$ B1 for $2y + 2y$ (Deduct B1 for each additional tick (>2) to min 0)
18	360° ÷ 18 (=20) Sector angles: G= 60; S= 80; B=220; Correct sectors labelled correctly Use angle measurer	Angles drawn, labelled	4	B4 for fully correct and labelled pie chart (B3 for all angles correct or for a labelled pie chart with 2 correct angles) (B2 for labelled pie chart with 1 correct angle drawn) (B1 for 360° ÷ 18 or 20 seen or implied)

Paper 5521/02					
No		Working	Answer	Mark	Notes
19	(a)		Correct plane	2	B2 for a correct plane defined by showing at least 2 lines. (B1 for a line of symmetry on one face)
	(b)		Correct net	2	B2 cao (B1 for 2 equilateral triangles joined appropriately to at least one rectangle or for 1 equilateral triangle joined appropriately to one of 3 rectangles)
	(c)		Correct drawing	2	B1 for two extra sides of length 6cm (± 2mm) B1 for construction arcs 6cm from each of the ends of the given line.
20	(a)		15	1	B1 for 15 (± 1)
	(b)		15	1	B1 for 15 (± 0.4)
	(c)			2	B1 horiz. line from (2, 20) to (3, 20) B1 line from (3, 20) to (5,0) or horizontal translation of it SC B1 for any journey ending at (5,0)
21	(a)	$x+4+x+x+4+x$	$4x+8$	2	M1 for attempting to add x, $x + 4$, x, $x + 4$ may be implied by $4x + a$ ($a > 0$) A1 for $4x + 8$ or $4(x + 2)$
	(b)	$4x + 8 = 54$ $4x = 46$ $x = 11.5$ Length = "11.5" + 4	15.5	3	M1 for "$4x + 8$" = 54 A1 cao for 11.5 seen B1 ft for "11.5" + 4
22		0.4 + 0.15 1 – "0.55"	0.45	2	M1 for 1 – sum A1 for 0.45 o.e. SC B1 for 0.81
23	(a)		3:1	1	B1 cao
	(b)	$\pi \times 2.45$	7.7	2	M1 for $\pi \times 2.45$ (accept π as 3.1 or better) A1 for 7.59 to 7.70

Paper 5521/02					
No		**Working**	**Answer**	**Mark**	**Notes**
24		7×10000	70 000	2	M1 for 7 X 10 000 or 7 X 100 X 100 A1 cao
25		5.40 ÷ 3 × 7	12.60	3	M1 for 5.40 ÷ 3 or sight of 1.8 M1 dep for "1.80" × 7 A1 for 12.6 or equivalent
26		7.60 x $\frac{17.5}{100}$ = 1.33 7.60 + 1.33 = 8.93 1650 x "8.93"	£14 734.50	4	M1 for 7.60 x $\frac{17.5}{100}$ or 1.33 seen or 7.60 x 1.175 (oe) (Award M1 for 10%, 5% and 2½% correctly calculated) A1 for 8.93 or 893 M1 for 1650 x "8.93" or digits 147345 seen A1 cao Accept 14734.5 **Alternative** M1 for 1650 × 7.6(0) or 12540 seen M1 for "12540" × $\frac{17.5}{100}$ or 2194.5 seen or "12540"× 1.175 (oe) (Award M1 for 10%, 5% and 2½% correctly calculated) M1 for "12540" + "2194.5" (dep on both previous method marks) or digits 147345 seen A1 cao accept 14 734.5

Paper 5523/03				
No	**Working**	**Answer**	**Mark**	**Notes**
1		Correct shape	2	B2 B1 for any 2 sides correct, or a correct enlargement scale factor ≠1 or 2.
2 (a)		11 13 16 8 21	2	B2 all correct (B1 for 2 correct) sign
(b)		$\frac{31}{80}$	1	B1 oe
3 (a)		$2p+3q$	2	B2 for $2p+3q$ (accept $2\times p$ etc) (B1 for $2p$ or $3q$ or $2p3q$)
(b)		$2y^2$	1	B1 accept $2\times y^2$ or $2\times y\times y$
(c)		$3c+4d$	2	B2 for $3c+4d$ (accept $3\times c$ etc) (B1 for $3c$ or $4d$ or $3c4d$)
(d)		$8pq$	1	B1 accept in any order but must not include ×
4 (a)(i)		60	2	B1 cao
(ii)		eg top triangle is equilateral		B1 for reason
(b)		150	2	M1 $\frac{(180-"60")}{2}+90$ A1 ft from (a)(i) if $x < 90°$ SC:B1 for answer from "60" + 90 if $x < 90°$

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
5	(a)	$4\times3-2\times1$ $12-2$	10	3	M1 for 3×4 (=12) or 1×2 or attempt to divide diagram up into rectangles M1 "12" – "2" A1 cao
	(b)(i)	$\frac{10}{100}\times680$ or $680\div10$ 680 + 68	748	5	M1 $\frac{10}{100}\times680$ or $680\div10$ or 68 seen M1 (dep) 680 +"68" (or M2 for 680×1.10) A1 cao
	(ii)	"748" ÷ 50 or 14.96	15		M1 for "748" $\div50$ or 14.96; accept "748" rounded up or down to next 50 followed by $\div50$ A1 ft from (b)(i) rounded up SC B1 for 680 (seen) leading to 14
6	(a)	$2\times5+5\times-3=10-15=$	-5	2	M1 substitute e.g 2×5 and 5×-3 or 10 and -15 A1 cao
	(b)	5×4^2 - 7 5×16 - 7	73	3	M1 substitution e.g 5×4^2 -7; do not accept 54^2-7 M1 $5\times16-7$ or $5\times4\times4$-7 or 80 – 7 (NB 4^2 as 4×4) A1 cao

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
7		679 × 28 = 5432 + 13580 = 19012 or 28 × 679 = 252 + 1960 + 16800 = 19012 or  	190.12	3	M1 for an attempt to multiply the units and tens, or correct partitioning M1 complete correct method (condone one arithmetic error) A1 for 190.12 cao OR M1 for putting the numbers in a grid M1 for multiplying out and addition (condone one error) A1 answer shown with point OR M1 for correct partitioning M1 679×20 and 679×8 calculated oe (condone one error) A1 cao
8	(a)		Points plotted	1	B1 ±1 full (2mm) square
	(b)		positive	1	B1 cao
	(c)		Line of best fit	1	B1 must pass through (42.5, 1.45), (42.5, 1.55) AND (67.5, 1.75), (67.5, 1.85)
	(d)		approx 1.65	1	B1 ft from single line segment with positive gradient ± 1 full (2mm) square

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
9	(a)	eg $50 \times \frac{2000}{500}$	200	2	M1 $2000 \div 500$ or 4 seen A1 cao
	(b)	eg $400 \times \frac{750}{500}$	600	2	M1 $750 \div 500$ or 1.5 seen or 400 + 200 A1 cao
10			$C = 10(n+3)$	3	B3 for $C = 10(n+3)$ oe such as $C = (n+3) \times 10$ (B2 for correct RHS or $C = n + 3 \times 10$, $C = 10n + 3$ etc B1 for C = some other linear expression in n or $n + 3 \times 10$, $10n + 3$ etc) NB: C=n scores no marks
11	(a)		$p(p+6)$	2	B2 for $p(p+6)$ or $p \times (p+6)$ (B1 for $p(ap+b)$ where a,b are numbers or $p+6$ seen on it's own, or part of an expression)
	(b)	$x^2 - 4x + 7x - 28$	$x^2 + 3x - 28$	2	M1 for 4 terms correct ignoring signs (e.g $x^2, 4x, 7x, 28$) or 3 terms with correct signs (e.g $x^2, -4x, 7x, -28$) A1 cao
12			correct drawing	2	B2. Condone hidden detail shown with solid lines, or missing lines on front face. (B1 for : one sketch correct with other sketches incorrect cross-section correct with depth > 1 cube, correct plan and side elevation)

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
13		$\frac{600}{3\times10}$ or $\frac{640}{3.2\times10}$	20 to 21 $\frac{1}{3}$	2	M1 For rounding at least two of the numbers to 1 sf, or for sight of 640, 3.2 or 640, 32 or 600, 32 or 30 seen A1 for 20 to 21 $\frac{1}{3}$ NB: 20.3125 scores M0 A0
14	(a)		correct reflection	2	B2 (B1 reflection in line other than x=3)
	(b)		reflection in $y = x$	2	B2 cao Accept the word "reflected" (B1 any statement including the word "reflection")
15	(a)(i)		5^6	1	B1 accept 15125, 5^{4+2}
	(ii)		5^3	1	B1 accept 125, 5^{9-6}
	(b)	$x + y = 10$ and $x - y = 4$	$x = 7$ $y = 3$	3	M1 for either $x + y = 10$ or $x - y = 4$ A2 for both values correct [(A1 for one value correct) If M0, award B3 for both values correct or B2 for one value correct, otherwise B0] SC B2 for $x = 3$ and $y = 7$

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	$5-3x=2x+2$ $5-2=2x+3x$	$\frac{3}{5}$	3	B1 for $2x+2$ seen OR $2.5-1.5x=x+1$ M1 for correct rearrangement of 4 terms A1 for $\frac{3}{5}$ oe
	(b)		$-3,-2,-1,0,1,2$	2	B2 (B1 for 5 correct and not more than one incorrect integers)
17			question + response boxes oe	2	1st aspect: One question with time period (eg each night); ignore other questions. 2nd aspect: Response list (at least two), not overlapping.* 3rd aspect: Some mention of units (eg hours) in either question or responses Award B2 for all three aspects, or B1 for just two aspects. * 0-1, 2-3, 4-5 is OK, but 0-1, 1-2, 2-3 is not OK.

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
18	(a)	$\frac{2}{3}\times\frac{3}{4}=\frac{6}{12}$	$\frac{1}{2}$	2	M1 for $\frac{6}{12}$ or $\frac{3}{6}$ or $\frac{2\times3}{3\times4}$ A1 accept 0.5
	(b)	$1+2+\frac{8}{12}+\frac{9}{12}$	$4\frac{5}{12}$	3	M1 for attempt to convert to fractions with common denominator e.g two fractions, denominator of 12 A1 correct conversion : $\frac{8}{12}$ and $\frac{9}{12}$, or $\frac{20}{12}$ and $\frac{33}{12}$ seen (oe) A1 cao for $4\frac{5}{12}$ OR attempts to convert to decimals: must use at least 2dp M1 0.66+0.75 (or 1.66+2.75) or 0.67+0.75 etc A1 4.41, 4.417, 4.416 A1 4.416 (*recurring*)
19		$2\times\frac{1}{2}\times6\times8$ or 48 $8\times9+6\times9+10\times9$ or 72 +54 + 90	264 cm^2	4	M1 attempt to find the area of one face; $\frac{1}{2}\times6\times8$ or (8×9) or (6×9) or (10×9) or 72 or 54 or 90 or 24 M1 all five faces with an intention to add A1 cao numerical answer of 264 B1 (indep) cm^2 with or without numerical answer

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
20			$\frac{\pi ab^3}{3d}$ $3(c+d)^3$ $3\pi bc^2$	3	B3 (B1 for each one correct) Nb –B1 for each of the 4th,5th,6th tick
21	(a)	$x+0.3+0.2+x=1$	0.25	2	M1 for $x+0.3+0.2+x=1$ oe, or $0.5\div 2$ A1 oe
	(b)	0.3×200	60	2	M1 0.3×200 A1 cao Accept 60 out of 200 (in words) SC B1 for $\frac{60}{200}$
22	(a)		$(-12)-4$ -2 $(0)8$	3	B3 for all correct [(B1 for each one correct)
	(b)		points plotted accurately points joined with smooth curve	2	B1 ± 1 full (2mm) square ft table if at least B1 awarded (all 5 points plotted) B1 ft for any smooth curve if previous B1 gained NB: curve must pass within 1 full square of the points
23			$\frac{1}{4}$ on LH branch $\frac{2}{3}$ & $\frac{1}{3}$ & $\frac{2}{3}$ on RH branches	2	B1 B1
24			m=3 n=5	2	B1 for 3 B1 for 5 (B2 for $2^3\times 5$ or $2\times 2\times 2\times 5$) SC: award B1 only if m=5, n=3 or for 8×5 seen

Paper 5523/03					
No		Working	Answer	Mark	Notes
25		$\frac{5--1}{-1-2} = -2$	$y = -2x + 5$	4	M1 for clear attempt to find gradient eg fraction with -1,5 in numerator, 2,-1 in denominator A1 for -2 B2 ft for $y =$"-2"$x + 5$ oe (eg $y = \frac{-6}{3}x + 5$) (B1 for $y = mx + 5$ or , $-2x+5$ or $y =$"-2"$x + c$)
26	(a)(i)		150	2	B1 accept 150 or 210
	(ii)				B1 for angle at the centre is twice the angle at the circumference
	(b)		30	3	B1 identifies angle between radius and tangent as $90°$ (may be in working or on diagram) M1 $360° - 90 - 90 -$"150" A1 ft from (a)(i) excluding a negative answer OR B1 for 90 M1 for $2 \times (180 - 90 -$"$\frac{150}{2}$"$)$ A1 ft from (a)(i) excluding a negative answer OR B3 for $180 -$(a)
		$360 - 90 - 90 -$"150"			

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	14.44 – 8.660254038	5.77974(….)	2	M1 for 14.44 seen or 8.66(……) seen or 5.7 or 5.8 or better, rounded or truncated A1 cao
	(b)		6	1	B1 ft
2		15 ÷ 24	62.5	2	M1 for 15 ÷ 24 or 1500 ÷ 24 or sight of digits 625 A1 cao
3	(a)	2.10 × 450	945	2	M1 for digits 210 × 450 or sight of digits 945 A1 cao
	(b)	63÷2.10	30	2	M1 for 63 ÷ digits 210 A1 cao
4		See diagram	$2(y + y)$ $2y + 2y$	2	B1 for $2(y + y)$ B1 for $2y + 2y$ (Deduct B1 for each additional tick (>2) to min 0)
5		$360^o \div 18$ (=20) Sector angles: G= 60; S= 80; B=220; Correct sectors labelled correctly Use angle measurer	Angles drawn, labelled	4	B4 for fully correct and labelled pie chart (B3 for all angles correct or for a labelled pie chart with two angles correct) (B2 for labelled pie chart with one correct angle drawn) (B1 for $360 \div 18$ or 20 seen or implied)
6	(a)		Correct plane	2	B2 for a correct plane defined by showing at least 2 lines. (B1 for a line of symmetry on one face)
	(b)		Correct net	2	B2 cao (B1 for 2 equilateral triangles joined appropriately to at least one rectangle or for 1 equilateral triangle joined appropriately to one of the three rectangles)
	(c)		Correct drawing	2	B1 for two extra sides of length 6 cm (± 2mm) B1 for construction arcs 6cm from each of the ends of the given line
7		61 – 19 = 42 42 ÷ 3 = 14	14	2	M1 for –19 or 42 seen or $3x + 19$ A1 cao

Paper 5523/04					
No		Working	Answer	Mark	Notes
8	(a) (b) (c)		15 15	1 1 2	B1 cao for $15(\pm 1)$ B1 cao for $15(\pm 0.4)$ B1 horiz. line from (2,20) to (3,20) B1 line from (3,20) to (5,0) or horiz. translation of it SC: B1 for any journey ending at (5,0)
9	(a)	$x+4+x+x+4+x$	$4x+8$	2	M1 for attempting to add $x+4, x, x+4, x$ may be implied by $4x+a$, $a>0$ A1 for $4x+8$ or $4(x+2)$
	(b)	$4x + 8 = 54$ $4x = 46$ $x = 11.5$ Length = "11.5" + 4	15.5	3	M1 for "$4x + 8$" = 54 A1 cao for 11.5 seen B1 ft for "11.5"+ 4
10		0.4 + 0.15 1 – 0.55	0.45	2	M1 for 1 – sum A1 for 0.45 oe SC: B1 for 0.81
11	(a) (b)	 $\pi \times 2.45$	3:1 7.7	1 2	B1 cao M1 for $\pi \times 2.45$ (accept π as 3.1 or better) A1 for 7.59 to 7.70
12		7×10000	70000	2	M1 for 7×10000 or $7 \times 100 \times 100$ A1 cao
13		5.40 ÷ 3 × 7	12.60	3	M1 for 5.40 ÷ 3 or sight of 1.8 M1 (dep) for "1.80" × 7 A1 for 12.6 or equivalent

Paper 5523/04				
No	**Working**	**Answer**	**Mark**	**Notes**
14	$7.60 \times \frac{17.5}{100} = 1.33$ 7.60 + 1.33 = 8.93 1650 × "8.93"	£14734.50	4	M1 for $7.60 \times \frac{17.5}{100}$ or 1.33 seen or 7.60 ×1.175 (oe) (Award M1 for 10%, 5% and 2½% correctly calculated) A1 for 8.93 or 893 M1 for 1650 × "8.93" or digits 147345 seen A1 cao Accept 14734.5 OR M1 for 1650×7.6 or 12540 seen M1 for "12540" $\times \frac{17.5}{100}$ or 2194.5 seen or "12540" ×1.175 (oe) (Award M1 for 10%, 5%, and 2½% correctly calculated) M1 for "12540" + "2194.5" (dep on both previous M marks) or digits 147345 seen A1 cao accept 14734.5

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
15		$285 \times 1000/(60 \times 60) = 79.1\dot{6}$		3	M2 for $285 \times 1000 \div 60 \div 60$ or $80 \times 60 \times 60 \div 1000$ or for a correct method to obtain two comparable values e.g $80 \times 60 \times 60$ and 285×1000 (M1 for $285 \div 60 \div 60$ or 0.079(….) seen or $80 \times 60 \times 60$ or 288000 seen or for 285×1000 or 285000 seen or $80 \div 1000$ or 0.08 seen) A1 for 288 or 79.(….) or for two correctly calculated comparable values e.g 288000 and 285000
16	(a)	$4x + 12 = 6$ $4x = -6$	-1.5	3	B1 for $4x + 12$ or $x + 3 = \frac{6}{4}$ M1 for a correct re-arrangement of their 3 terms to isolate $4x$ or x A1 for -1.5 oe
	(b)	$v - u = 5t$	$\frac{v-u}{5}$	2	M1 for isolating $\pm 5t$ or $\pm t$ or for dividing through by 5 A1 oe

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
17		3→15 4→48 3.1→17.3(91) 3.2→19.9(68) 3.3→22.7(37) 3.4→25.7(04) 3.5→28.8(75) 3.4→25.7(04) 3.3→22.7(37) 3.35→24.1(95375)	3.3	4	B2 for trial between 3.3 and 3.4 inclusive (B1 for trial between 3 and 4 inclusive) B1 for different trial between 3.3 and 3.4 exclusive B1 (dep on at least one previous B1) for 3.3 NB trials should be evaluated to at least 1 dp truncated or rounded
18	(a)	36 ÷ (7+3+2) "3" × 7	21	3	M1 for 36 ÷ (7+3+2) M1 (dep) for "3" × 7 or 3 or 2 A1 cao
	(b)	$51.5 \times \frac{8.5}{100} = 4.3775$ 51.5 – 4.3775 = 47.1225	47 or 47.1 or 47.12	4	M1 for $51.5 \times \frac{8.5}{100}$ or 4.37(75) seen M1 (dep) for 51.5 – "4.37(75)" A1 for 47 or better B1 (indep) for rounding their answer correctly to the nearest whole number or 1 or 2 d.p OR M1 for $51.5 \times \frac{100-8.5}{100}$ M1 for $51.5 \times$"0.915" or 0.515 × "91.5" A1 for 47 or better B1 (indep) for rounding their answer correct to the nearest whole number or 1 or 2 d.p

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
19	(a)		Angle in a semicircle	1	B1 oe
	(b)	$12^2 + 16^2 = 400$ $\sqrt{400} = 20$	20	3	M1 for $12^2 + 16^2$ M1 for $\sqrt{144+256}$ A1 cao
	(c)	$\pi \times 10^2$	314	3	M1 for $\pi \times \left(\frac{"20"}{2}\right)^2$ M1 (indep) for correct order of evaluation of $\pi \times r^2$ for any r A1 for 314 – 315 inclusive

Paper 5523/04					
No		Working	Answer	Mark	Notes
20	(a)	$(1 \times 10)+(3 \times 15)+(5 \times 30)+(7 \times 35)+$ $(9 \times 25)+(11 \times 5) = 730$ "730" $\div$ 120 = 6.08333	6.08	4	M1 for use of *fx* with *x* consistent within intervals (including end points) M1 (dep) for use of midpoints M1 (dep on 1st M1) for use of $\frac{\sum fx}{\sum f}$ A1 6.08 to 6.085
	(b)		(10),25,55,90,115, 120	1	B1 for all correct
	(c)		graph	2	B1 ft for 5 or 6 points plotted correctly $\pm$ 1 full (2mm) square at the end of interval dep on sensible table (condone 1 addition error) B1(dep) for points joined by curve or line segments provided no gradient is negative – ignore any part of graph outside range of their points. (SC: B1 if 5 or 6 points plotted not at end but consistent within each interval and joined)

Paper 5523/04				
No	**Working**	**Answer**	**Mark**	**Notes**
(d)		72–74	2	M1 (ft dep on graph being cf) for reading from graph at 7 A1 ft ±1 full (2 mm) square Or B2 for $72-74$
21 (a) (b) (c) (d)		a^7 $15x^3y^4$ $x-1$ $(x+3)(x-3)$	1 2 1 1	B1 accept a^{4+3} B2 cao (B1 for two of 15, x^3, y^4 in a product) B1 cao B1 cao
22	80% = 220 $220 \div 80 \times 100$	275	3	M1 for recognising that 80% is equivalent to 220 M1 for $220 \div 80 \times 100$ oe A1 cao

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
23			$x = 3$ $y = 0.5$	3	M1 for coefficients of x or y the same followed by correct operation, condone one arithmetical error M1 (dep) for substituting found value in one equation A1 cao SC: B1 for one correct answer only if M's not awarded
24			1.4×10^{10}	2	B2 for 1.4×10^{10} or 1.44×10^{10} (B1 for 14.4×10^{9} or 14400,000,000 or 14000,000,000 or 14×10^{9})
25	(a)	$\tan x = \frac{1.9}{3.2}$ $x = \tan^{-1}\left(\frac{1.9}{3.2}\right) = 30.7$	30.7	3	M1 for $\tan x = \frac{1.9}{3.2}$ or $\tan \frac{1.9}{3.2}$ M1 for $\tan^{-1}\left(\frac{1.9}{3.2}\right)$ A1 for 30.6 – 30.7
	(b)	90 + "30.7"	121	1	B1 (indep) ft for 90 + "30.7" rounded to 3 or 4 s.f

Paper 5523/04				
No	**Working**	**Answer**	**Mark**	**Notes**
26	SF$=\frac{12}{9}$ $\frac{12}{9}\times 6=8$	2	2	M1 for $\frac{12}{9}$ or $\frac{9}{12}$ or 1.33… seen or 0.75 seen or 8 seen or $\frac{6}{9}$ or $\frac{9}{6}$ or 0.66… or 1.5 or $\frac{1}{3}$ or 3 oe seen A1 cao

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	$x^2-4x+7x-28$	$x^2+3x-28$	2	M1 for 4 terms correct ignoring signs (e.g $x^2,4x,7x,28$) or 3 terms with correct signs (e.g $x^2,-4x,7x,-28$) A1 cao
	(b)		y^4+2y^2	2	B2 cao B1 for y^4 or $2y^2$
	(c)		$p(p+6)$	2	B2 for $p(p+6)$ or $p\times(p+6)$ (B1 for $p(ap+b)$ where a,b are numbers or $p+6$ seen on it's own, or part of an expression)
	(d)		$3x(2x-3y)$	2	B2 (B1 for $3(2x^2-3xy)$ or $x(6x-9y)$ or $3x(...)$)
2			question + response boxes oe	2	1st aspect: One question with time period (eg each night); ignore other questions. 2nd aspect: Response list (at least two), not overlapping.* 3rd aspect: Some mention of units (eg hours) in either question or responses Award B2 for all three aspects, or B1 for just two aspects. * 0-1, 2-3, 4-5 is OK, but 0-1, 1-2, 2-3 is not OK.
3	(b)		reflection in $y=x$	2	B2 cao accept the word "reflected" (B1 any statement including the word "reflection")
4	(a)	$5-3x=2x+2$ $5-2=2x+3x$	$\frac{3}{5}$	3	B1 for $2x+2$ seen OR $2.5-1.5x=x+1$ M1 for correct rearrangement of 4 terms A1 for $\frac{3}{5}$ oe
	(b)		$-3,-2,-1,0,1,2$	2	B2 (B1 for 5 correct and not more than one incorrect integers)

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
5	(a)	$\frac{2}{3}\times\frac{3}{4}=\frac{6}{12}$	$\frac{1}{2}$	2	M1 for $\frac{6}{12}$ or $\frac{3}{6}$ or $\frac{2\times3}{3\times4}$ A1 accept 0.5
	(b)	$1+2+\frac{8}{12}+\frac{9}{12}$	$4\frac{5}{12}$	2	M1 for attempt to convert to fractions with common denominator e.g two fractions, denominator of 12 A1 correct conversion : $\frac{8}{12}$ and $\frac{9}{12}$, or $\frac{20}{12}$ and $\frac{33}{12}$ seen (oe) A1 cao for $4\frac{5}{12}$ OR attempts to convert to decimals: must use at least 2dp M1 0.66+0.75 (or 1.66+2.75) or 0.67+0.75 etc A1 4.41, 4.417, 4.416 or 0.41, 0.417, 0.416 or 0.42, 4.42 A1 4.416 (*recurring*)
6	(a)(i)		5^6	1	B1 accept 15625, 5^{4+2}
	(ii)		5^3	1	B1 accept 125, 5^{9-6}
	(b)	$x+y=10$ and $x-y=4$	$x = 7$ $y = 3$	3	M1 for either $x + y = 10$ or $x-y=4$ A2 for both values correct [(A1 for one value correct) If M0, award B3 for both values correct or B2 for one value correct, otherwise B0] SC B2 for $x = 3$ or $y = 7$

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
7		$2\times\frac{1}{2}\times6\times8$ or 48 $8\times9+6\times9+10\times9$ or 72 +54 + 90	264 cm^2	4	M1 attempt to find the area of one face; $\frac{1}{2}\times6\times8$ or (8×9) or (6×9) or (10×9) or 72 or 54 or 90 or 24 or 48 M1 all five faces with an intention to add A1 cao numerical answer of 264 B1 (indep) cm^2 with or without numerical answer
8			$\frac{\pi ab^3}{3d}$ $3(c+d)^3$ $3\pi bc^2$	3	B3 (B1 for each one correct) Nb –B1 for each of the 4th,5th,6th tick
9	(a)	$x+0.3+0.2+x=1$	0.25	2	M1 for $x+0.3+0.2+x=1$ oe, or 0.5 ÷ 2 A1 oe
	(b)	0.3×200	60	2	M1 0.3×200 A1 cao Accept 60 out of 200 (in words) SC B1 for $\frac{60}{200}$
10	(a)		$(-12)-4\quad-2\quad(0)8$	3	B3 for all correct [(B1 for each one correct)
	(b)		5 points plotted accurately points joined with smooth curve	2	B1 ±1 full (2mm) square ft table if at least B1 awarded (all 5 points plotted) B1 ft for any smooth curve if previous B1 gained NB: curve must pass within 1 full square of the points
11			m=3 n=5	2	B1 for 3 B1 for 5 (B2 for $2^3\times5$ or $2\times2\times2\times5$) SC: award B1 only if m=3, n=3, for 8×5 seen

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
12		$\frac{5--1}{-1-2} = -2$	$y = -2x + 5$	4	M1 for clear attempt to find gradient eg fraction with -1,5 in numerator, 2,-1 in denominator A1 for -2 cao B2 ft for $y =$"-2"$x + 5$ oe (eg $y = \frac{-6}{3}x + 5$) (B1 for $y = mx + 5$ or , $-2x+5$ or $y =$"-2"$x + c$)
13	(a)		$\frac{1}{4}$ on LH branch $\frac{2}{3}$ & $\frac{1}{3}$ & $\frac{2}{3}$ on RH branches	2	B1 cao B1
	(b)	$\frac{3}{4} \times \frac{2}{3} + \frac{1}{4} \times \frac{1}{3} = \frac{6}{12} + \frac{1}{12}$	$\frac{7}{12}$	3	M1 for $\frac{3}{4} \times \frac{2}{3}$ or $\frac{1}{4} \times \frac{1}{3}$ from their tree diagram M1 for sum of two products A1 for $\frac{7}{12}$ oe
	(c)	$n = 21 \times 4$ or $\frac{1}{6} : \frac{1}{4}$ oe $\frac{1}{6} \times 84$ or $21 \times \frac{2}{3}$	14	3	M1 for either $\frac{1}{3} \times \frac{3}{4} \left(= \frac{1}{4}\right)$ or $\frac{2}{3} \times \frac{1}{4} \left(= \frac{1}{6}\right)$ from their tree diagram M1 for 21×4 (=84) or $\frac{21}{3} \times 2$ A1 for 14 cao SC: B2 for 63 seen in fraction or ratio

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
14	(a)(i)		150	2	B1 accept 150 or 210
	(ii)				B1 for angle at the centre is twice the angle at the circumference
	(b)		30	3	B1 identifies angle between radius and tangent as $90°$ (may be in working or on diagram)
		$360 - 90 - 90 - "150"$ or $180 - "150"$			M1 $360° - 90 - 90 - "150°"$ A1 ft from (a)(i) excluding a negative answer Or B1 for 90 M1 for $2 \times (180 - 90 - "\frac{150}{2}")$ A1 ft from (a)(i) excluding a negative answer Or B3 for $180 - (a)$ SC: 180 – "210" can get B1 for $90°$ and/or B1 for "cyclic quadrilateral"
15	(a)		0.2727…	1	B1 for 2.27 recurring or 0.2727…. oe or 0.273
	(b)	eg $x = 0.3939…$ so $100x = 39.3939…$ $99x = 39$ so $x = \frac{39}{99} = \frac{13}{33}$		3	M1 for $100x = 39.39…$ M1 dep for subtraction of both sides A1 for $\frac{13}{33}$ from correct proof **Alternative method** M1 for $13.000 \div 33$ M1 for remainders 31 and 13 A1 for 0.39 recurring SC:B1 for $\frac{39}{99}$

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	$d = kt^2$ $80 = k \times 4^2$	$d = 5t^2$	3	M1 for $d = kt^2$ or $d \propto t^2$ M1 sub d=80 and t=4 into their equation A1 for $d = 5t^2$ oe (cao)
	(b)		245	1	B1 ft from (a) using "k"
	(c)	$45 = 5t^2$	3	2	M1 ft from (a) for substituting d=45 into their equation A1 for 3 cao (condone inclusion of -3)
17	(a)(i) (ii)		(0, 9) (8, 25)	3	B1 cao B1 for $x = 8$ cao B1 for $y = 25$ cao SC: B1 for (25, 8)
	(b)	LHS = $\left(\frac{100-(x^2-16x+64)}{4}\right)$ = $\left(\frac{36+16x-x^2}{4}\right)$ RHS = $\left(\frac{36-2x+18x-x^2}{4}\right)$ = LHS		3	M1 for expansion of either set of brackets with at least 3 of 4 terms correct M1 for common denominator of 4 or multiplying through by 4 or reducing each numerator to a single term A1 for fully correct solution **Alternative method** M1 for $(5-\frac{(x-8)}{2})(5+\frac{(x-8)}{2})$ M1 for $(\frac{2\times5-(x-8)}{2})(\frac{2\times5+(x-8)}{2})$ A1 for $\frac{(18-x)(x+2)}{4}$

Paper 5525/05					
No		Working	Answer	Mark	Notes
18	(a)	$\frac{810\pi}{90\pi}$ or 9 $\sqrt{9}$ or 3	12	3	M1 for $\frac{810\pi}{90\pi}$ or 9 or $\frac{1}{9}$ or 1:9 oe M1 for $\sqrt{\frac{810\pi}{90\pi}}$ or $\sqrt{9}$ or 3 or $\frac{1}{3}$ or $\sqrt{9}:\sqrt{1}$ oe A1 cao
	(b)	3^3 or 27 or 2700	2700π	2	SC:B1 for answer of 36 M1 for "3"^{3} or 27 or $\left(\sqrt{9}\right)^3 : (\sqrt{81})^3$ oe or 9^3 or 2700– A1 cao
19	(a)(i)		1	1	B1 cao
	(ii)		8	1	B1 cao
	(iii)	$64^{-\frac{2}{3}} = \frac{1}{64^{\frac{2}{3}}}$ or $64^{-\frac{2}{3}} = (4^2)^{-1}$	$\frac{1}{16}$	2	M1 for knowing negative power is a reciprocal or power of $\frac{1}{3}$ root is a cube root A1 cao for $\frac{1}{16}$
	(b)	$\sqrt{27} = \sqrt{9\times3}$ or $\sqrt{27} = 3\sqrt{3}$ or $\sqrt{27} = 3^{3/2}$	$\frac{5}{2}$ oe	2	M1 for $\sqrt{27} = \sqrt{9\times3}$ or $\sqrt{27} = 3^{3/2}$ A1 for $\frac{5}{2}$ oe (cao) **Alternative method** M1 for $9\times27 = 3^{2n}$ A1 for $\frac{5}{2}$ oe (cao)

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
20	(a)(i) (ii) (b)(i) (ii)		(90, 1) (180, 0) (45, 0) (90, -3)	2 2 	B1 cao could be indicated on diagram B1 cao could be indicated on diagram B1 cao could be indicated on diagram B1 cao could be indicated on diagram
21		$\frac{1}{3}\pi x^2 h = \frac{4}{3}\pi(2x)^3$ $x^2 h = 4\times 8x^3$	$32x$	3	M1 for substitution in correct formulae M1 (dep.) for correct unsimplified expression eg $h = \frac{\frac{4}{3}\pi(2x)^3}{\frac{1}{3}\pi x^2}$ oe or $h = 8x$ oe A1 for $32x$ cao
22	(a)	$\left(\overline{OM} =\right)\ \boldsymbol{a} + 2\boldsymbol{b}$ $\left(\overline{ON} =\right) 3\boldsymbol{a}$ or $\frac{6}{2}\boldsymbol{a}$ $\left(\overline{MN} =\right)\ -\boldsymbol{a} - 2\boldsymbol{b} + 3\boldsymbol{a}$	$2\boldsymbol{a} - 2\boldsymbol{b}$	2	B2 (B1 for either $\overline{OM}$ or $\overline{ON}$ or $-\boldsymbol{a} - 2\boldsymbol{b} + 3\boldsymbol{a}$ SC: B1 for $2\boldsymbol{b} - 2\boldsymbol{a}$
	(b)	$\left(\overline{OX} =\right)\ 2\boldsymbol{a} + \boldsymbol{b}$ $\left(\overline{OY} =\right) \boldsymbol{b} + 4\boldsymbol{a}$ (½ $\overline{QR}$ =) $2\mathbf{a} - \boldsymbol{b}$ or (½ $\overline{RQ}$ =) $\boldsymbol{b} - 2\boldsymbol{a}$	$\overline{XY} = 2\boldsymbol{a}$ (hence parallel)	2	B1 for either $\overline{OX}$ or $\overline{OY}$ or (½ $\overline{QR}$) B1 for $\overline{XY} = 2\boldsymbol{a}$ or $\overline{YX} = -2\boldsymbol{a}$

Paper 5525/06					
No		Working	Answer	Mark	Notes
1	(a)	$v - u = 5t$	$\frac{v-u}{5}$	2	M1 for isolating $\pm 5t$ or $\pm t$ or for dividing through by 5 A1 oe
	(b)	$x - 3 = 5x - 25$ $22 = 4x$	$5\frac{1}{2}$	3	M1 for $x - 3 = 5(x-5)$ or $\frac{x}{5} - \frac{3}{5} = x - 5$ M1 for isolating terms in x correctly from $ax + b = cx + d$ A1 cao accept $5\frac{1}{2}$, $\frac{11}{2}$, 5.5
2	(a)	$36 \div (7+3+2)$ "3" $\times 7$	21	3	M1 for $36 \div (7+3+2)$ M1 (dep) for "3" $\times 7$ or 3 or 2 A1 cao
	(b)	$51.5 \times \frac{8.5}{100} = 4.3775$ $51.5 - 4.3775 = 47.1225$	47 or 47.1 or 47.12	4	M1 for $51.5 \times \frac{8.5}{100}$ or 4.37(75) seen M1 (dep) for 51.5 – "4.37(75)" A1 for 47 or better B1 (indep) for rounding their answer correctly to the nearest whole number or 1 or 2 d.p OR M1 for $51.5 \times \frac{100 - 8.5}{100}$ M1 for $51.5 \times$"0.915" or 0.515 ×"91.5" A1 for 47 or better B1 (indep) for rounding their answer correct to the nearest whole number or 1 or 2 d.p

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
3		3→15 4→48 3.1→17.3(91) 3.2→19.9(68) 3.3→22.7(37) 3.4→25.7(04) 3.5→28.8(75) 3.4→25.7(04) 3.3→22.7(37) 3.35→24.1(95375)	3.3	4	B2 for trial between 3.3 and 3.4 inclusive (B1 for trial between 3 and 4 inclusive) B1 for different trial between 3.3 and 3.4 exclusive B1 (dep on at least one previous B1) for 3.3 NB trials should be evaluated to at least 1 dp truncated or rounded
4	(a)		Angle in a semicircle	1	B1 oe
	(b)	$12^2 + 16^2 = 400$ $\sqrt{400} = 20$	20	3	M1 for $12^2 + 16^2$ M1 for $\sqrt{144+256}$ A1 cao
	(c)	$\pi \times 10^2$	314	3	M1 for $\pi \times \left(\frac{"20"}{2}\right)^2$ M1 (indep) for correct order of evaluation of $\pi \times r^2$ for any r A1 for 314 – 315 inclusive

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
5	(a)	$(1 \times 10)+(3 \times 15)+(5 \times 30)+(7 \times 35)+$ $(9 \times 25)+(11 \times 5) = 730$ "730" ÷ 120 = 6.08333	6.08	4	M1 for use of *fx* with *x* consistent within intervals (including end points) M1 (dep) for use of midpoints M1 (dep on 1st M1) for use of $\frac{\sum fx}{\sum f}$ A1 6.08 to 6.085
	(b)		(10),25,55,90, 115,120	1	B1 for all correct
	(c)		graph	2	B1 ft for 5 or 6 points plotted correctly ± 1 full (2mm) square at the end of interval dep on sensible table (condone 1 addition error) B1(dep) for points joined by curve or line segments provided no gradient is negative – ignore any part of graph outside range of their points. (SC: B1 if 5 or 6 points plotted not at end but consistent within each interval and joined)
	(d)		72 – 74	2	M1 (ft dep on graph being cf) for reading from graph at 7 A1 ft ±1 full (2 mm) square Or B2 for $72 - 74$

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
6	(a)		a^7	1	B1 accept a^{4+3}
	(b)		$15x^3y^4$	2	B2 cao (B1 for two of 15, x^3, y^4 in a product)
	(c)		$x-1$	1	B1 cao
	(d)		$(a + 3b)(a - 3b)$	2	B2 for $(a + 3b)(a - 3b)$ (B1 for $(a \pm 3b)(a \pm 3b)$
7		80% = 220 $220 \div 80 \times 100$	275	3	M1 for recognising that 80% is equivalent to 220 M1 for $220 \div 80 \times 100$ oe A1 cao
8			$x = 3$ $y = 0.5$	3	M1 for coefficients of x or y the same followed by correct operation, condone one arithmetical error M1 (dep) for substituting found value in one equation A1 cao SC: B1 for one correct answer only if Ms not awarded
9			1.4×10^{10}	2	B2 for 1.4×10^{10} or 1.44×10^{10} (B1 for 14.4×10^9 or 14400,000,000 or 14000,000,000 or 14×10^9)

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
10	(a)	$\tan x = \frac{1.9}{3.2}$ $x = \tan^{-1}\left(\frac{1.9}{3.2}\right) = 30.7$	30.7	3	M1 for $\tan x = \frac{1.9}{3.2}$ or $\tan \frac{1.9}{3.2}$ M1 for $\tan^{-1}\left(\frac{1.9}{3.2}\right)$ A1 for 30.6 – 30.7
	(b)	90 + "30.7"	121	1	B1 (indep) ft for 90 + "30.7" rounded to 3 or 4 s.f
11	(a)	$SF = \frac{12}{9}$ $\frac{12}{9} \times 6 = 8$	2	2	M1 for $\frac{12}{9}$ or $\frac{9}{12}$ or 1.33… seen or 0.75 seen or 8 seen or $\frac{6}{9}$ or $\frac{9}{6}$ or 0.66… or 1.5 or $\frac{1}{3}$ or 3 oe seen A1 cao
	(b)	$SF = \frac{9}{12}, \frac{9}{12} \times 7 = 5.25$	5.25	2	M1 for $\frac{BE}{7} = \frac{9}{12}$ oe A1 cao

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
12	(a)	$84 = 6.7\pi + 2 \times 6.7 + 2a$ $2a + 13.4 = 62.95\ldots$ or $2a + 34.44 = 84$	24.8	3	M1 for substituting correctly, π may be left M1 for correct rearrangement as far as $\pm 2a$ A1 for $24.7 - 24.8$
	(b)	$P = \pi r + 2r + 2a$ $P - 2a = \pi r + 2r$ $P - 2a = (\pi + 2)r$	$\frac{P-2a}{\pi+2}$	3	M1 subtracting $2a$ from each side M1 for factorising to get $(\pi+2)r$ A1 for $\frac{P-2a}{\pi+2}$ oe S.C $\frac{p-2a}{5.14}$ oe is M1 M1 A0
13		Area $\Delta ABC = \frac{1}{2} \times 14 \times 8 \times \sin 106$ (= 53.8)	53.8	3	M1 for $\frac{1}{2} \times 14 \times 8 \times \sin 106$ M1 (dep) for $56 \times 0.961(26..)$ or $107.6\ldots$ A1 $53.8 - 53.9$ SC 107.6 is B2
14	(a)		4.5	1	B1 cao
	(b)	$500 \times 1.045^{20} = 1205.857\ldots\ldots$	1205.86	2	M1 for 500×1.045^{20} A1 for $1205.85 - 1206$ (SC:B1 for $705.85 - 706$ no working)

Paper 5525/06				
No	**Working**	**Answer**	**Mark**	**Notes**
15 (a)	$6x^2 + 11x - 10 + 6x - 4 = 25$ $6x^2 + 17x - 39 = 0$		3	M1 for an expression for the area involving either $(3x-2)(2x+5)+2(3x-2)$ or $3x(3x-2)+(3x-2)(7-x)$ or $3x(2x+5)-2(7-x)$ or $(3x-2)^2 + 2(3x-2) + (3x-2)(7-x)$ where in each case at least one of 2 or 3 product terms must be correct M1 (indep) for one correct expansion involving x^2 A1 for simplification to final answer

Paper 5525/06					
No		Working	Answer	Mark	Notes
15	(b)(i)	$x = \frac{-17 \pm \sqrt{17^2 - 4\times 6\times(-39)}}{2\times 6}$ $= \frac{-17 \pm \sqrt{289+936}}{12}$ $x = +\frac{18}{12}$ or -4.33	1.5, $-\frac{13}{3}$	4	M1 for $x = \frac{-17 \pm \sqrt{17^2 - 4\times 6\times(-39)}}{2\times 6}$ up to signs in b & c M1 for $x = \frac{-17 \pm \sqrt{1225}}{12}$ A1 $x = 1.5$ or -4.33, or better OR M2 for $(3x+13)(2x-3)$ (M1 for $(3x \pm a)(2x \pm b)$ with ab = ±39 A1 x = 1.5 or – 4.33, or better
		$x^2 + \frac{17}{6}x - \frac{39}{6} = 0$ $\left(x+\frac{17}{12}\right)^2 - \left(\frac{17}{12}\right)^2 - \frac{39}{6} = 0$ $\left(x+\frac{17}{12}\right)^2 = \left(\frac{17}{12}\right)^2 + \frac{39}{6}$			OR M1 for $\left(x+\frac{17}{12}\right)^2$ *seen* M1 $\left(x+\frac{17}{12}\right)^2 = \left(\frac{17}{12}\right)^2 + \frac{39}{6}$ A1 x = 1.5 or – 4.33, or better SC:M1 for answer "1.5" with no working or T & I
	(ii)		8		B1 cao length = 8

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	P(win) = $\frac{2}{5}\times\frac{3}{5}+\frac{2}{5}\times\frac{1}{5}(=\frac{8}{25})$	$\frac{8}{25}$	3	M1 for $\frac{2}{5}\times\frac{3}{5}$ or $\frac{2}{5}\times\frac{1}{5}$ or for clearly identifying in P(R) $\times$P(R) + P(B) $\times$ P(B) M1 for P(win) = " $\frac{2}{5}$ " $\times$ " $\frac{3}{5}$ " + " $\frac{2}{5}$ " $\times$ " $\frac{1}{5}$ " A1 for $\frac{8}{25}$, oe
	(b)	$\frac{8}{25}$ $\times$ 100 (=32) 100 $\times$ 20 – "32" $\times$ 50	£4	2	M1 for (" $\frac{8}{25}$ " $\times$100)$\times$50 or $\times$ 0.5 A1 cao

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
17		Lower bound of 1200 is 1150 Upper bound of 60 is 65 $1150 \div 65$	17	4	B1 for 1150 or 1250 seen B1 for 65 or 55 seen M1 (Lower bound of load) ÷ (Upper bound of weight) Where 1150 ≤ LB load < 1200 and 60 < UB Weight ≤ 65 A1 for 17 requires fully correct working OR B1 for 1150 or 1250 seen B1 for 65 or 55 seen M1 (upper bound of load) ÷(lower bound of weight) Where 1200 ‹ UB load ≤ 1250 and 55 ≤ LB weight < 60 A1 for 22 requires fully correct working OR M2 $1200 \div 55$ A1 21.8 A1 21 requires fully correct working OR M2 $1200 \div 65$ A1 18.4(6) A1 18 requires fully correct working
18	(a)	$3^4 x^4 y^8$	$81x^4y^8$	2	B2 for $81x^4y^8$ (B1 for 2 of 81, x^4, y^8)
	(b)	$\frac{x(x-3)}{(x-5)(x-3)}$	$\frac{x}{x-5}$	3	B1 for $x(x-3)$ B1 for $(x-5)(x-3)$ B1 cao

Paper 5525/06

No	Working	Answer	Mark	Notes
19 (a)	$6^2 - 2^2 = 32$	5.66	2	M1 for $6^2 - 2^2$ (= 32) A1 5.65 – 5.66
(b)	V  $DVA = 2 \times \sin^{-1}(\frac{2}{6})$ OR $\cos DVA = \frac{6^2 + 6^2 - 16}{2 \times 6 \times 6}$ $= \frac{56}{72}$ $DVA = \cos^{-1}\left(\frac{56}{72}\right) = 38.94$	38.9	3	M1 $\sin x = \frac{2}{6}$ oe M1 for $DVA = 2 \times \sin^{-1}(\frac{2}{6})$ A1 38.9 – 38.95 OR M1 for $(\cos DVA =) \frac{6^2 + 6^2 - 4^2}{2 \times 6 \times 6}$ M1 for $DVA = \cos^{-1}\left(\frac{56}{72}\right)$ A1 38.9 – 38.95

Paper 5525/06				
No	**Working**	**Answer**	**Mark**	**Notes**
19 (c)	$AC^2 = 2^2 + 2^2 - 2 \times 2 \times 2 \times \cos 120^o$ $AC = \sqrt{12}$ **OR** $AN = 2 \times \sin 60 = \sqrt{3}$ **OR** $VN = \sqrt{"32"+1} = \sqrt{33}$ $\cos AVC = \frac{6^2+6^2-12}{2\times 6\times 6}$ $\cos AVC = \frac{60}{72}$ **OR** $AVC = 2 \times \sin^{-1}\frac{\sqrt{3}}{6}$, using AN **OR** $AVC = 2\times\cos^{-1}\frac{\sqrt{33}}{6}$, using VN	33.6	4	M1 for any valid method for AC or AN or VN where N is the midpoint of AC A1 for $AC^2 = 12$ or $AC = \sqrt{12}$ (= 3.46…) or $AN = \sqrt{3}$ (=1.73…)or $VN = \sqrt{33}$ (=5.74…) M1 (indep) for correct method to find angle AVC A1 33.55 – 33.6

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
20	(a)	Graph translated 1 unit to the right passing through the points (-1,0), (1,2) and (2,0)		2	M1 for translation of $\begin{pmatrix}1\\0\end{pmatrix}$ or $\begin{pmatrix}-1\\0\end{pmatrix}$ A1 for right through the 3 points, $\pm\frac{1}{4}$ sq
	(b)	Graph stretched 2 units parallel to y-axis; passing through the points (-2,0), (0,4) and (1,0)		2	M1 for graph stretched parallel to the y-axis by scale factor 2 A1 through all 3 points; $\pm\frac{1}{4}$ sq not on grid at $x = 2$

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone 01623 467467
Fax 01623 450481

Email publications@linneydirect.com

Order Code UG016720 Summer 2005

For more information on Edexcel qualifications, please visit www.edexcel.org.uk/qualifications
Alternatively, you can contact Customer Services at www.edexcel.org.uk/ask or on 0870 240 9800

Edexcel Limited. Registered in England and Wales no.4496750
Registered Office: One90 High Holborn, London, WC1V 7BH

PMT

edexcel

Mark Scheme (Results)

March 2013

GCSE Mathematics (2MB01) Higher
5MB3H (Calculator) Paper 01

PMT

Edexcel and BTEC Qualifications

Edexcel and BTEC qualifications come from Pearson, the world's leading learning company. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers. For further information visit our qualifications websites at www.edexcel.com or www.btec.co.uk for our BTEC qualifications.
Alternatively, you can get in touch with us using the details on our contact us page at www.edexcel.com/contactus.

If you have any subject specific questions about this specification that require the help of a subject specialist, you can speak directly to the subject team at Pearson.
Their contact details can be found on this link: www.edexcel.com/teachingservices.

You can also use our online Ask the Expert service at www.edexcel.com/ask. You will need an Edexcel username and password to access this service.

Pearson: helping people progress, everywhere
Our aim is to help everyone progress in their lives through education. We believe in every kind of learning, for all kinds of people, wherever they are in the world. We've been involved in education for over 150 years, and by working across 70 countries, in 100 languages, we have built an international reputation for our commitment to high standards and raising achievement through innovation in education. Find out more about how we can help you and your students at: www.pearson.com/uk

March 2013
Publications Code UG035055
All the material in this publication is copyright
© Pearson Education Ltd 2013

NOTES ON MARKING PRINCIPLES

1 All candidates must receive the same treatment. Examiners must mark the first candidate in exactly the same way as they mark the last.

2 Mark schemes should be applied positively. Candidates must be rewarded for what they have shown they can do rather than penalised for omissions.

3 All the marks on the mark scheme are designed to be awarded. Examiners should always award full marks if deserved, i.e if the answer matches the mark scheme. Examiners should also be prepared to award zero marks if the candidate's response is not worthy of credit according to the mark scheme.

4 Where some judgement is required, mark schemes will provide the principles by which marks will be awarded and exemplification may be limited.

5 Crossed out work should be marked UNLESS the candidate has replaced it with an alternative response.

6 Mark schemes will indicate within the table where, and which strands of QWC, are being assessed. The strands are as follows:

i) *ensure that text is legible and that spelling, punctuation and grammar are accurate so that meaning is clear*
Comprehension and meaning is clear by using correct notation and labeling conventions.

ii) *select and use a form and style of writing appropriate to purpose and to complex subject matter*
Reasoning, explanation or argument is correct and appropriately structured to convey mathematical reasoning.

iii) *organise information clearly and coherently, using specialist vocabulary when appropriate*.
The mathematical methods and processes used are coherently and clearly organised and the appropriate mathematical vocabulary used.

7 With working

If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
If there is no answer on the answer line then check the working for an obvious answer.
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks. Discuss each of these situations with your Team Leader.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.

8 Follow through marks

Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

9 Ignoring subsequent work

It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: e.g. incorrect canceling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect e.g. algebra.
Transcription errors occur when candidates present a correct answer in working, and write it incorrectly on the answer line; mark the correct answer.

10 Probability

Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

11 Linear equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

12 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

13 Range of answers

Unless otherwise stated, when an answer is given as a range (e.g 3.5 – 4.2) then this is inclusive of the end points (e.g 3.5, 4.2) and includes all numbers within the range (e.g 4, 4.1)

Guidance on the use of codes within this mark scheme
M1 – method mark A1 – accuracy mark B1 – Working mark C1 – communication mark QWC – quality of written communication oe – or equivalent cao – correct answer only ft – follow through sc – special case dep – dependent (on a previous mark or conclusion) indep – independent isw – ignore subsequent working

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
*1			small and correct answers	3	M1 for 4.2 ÷ 1.75 (=2.4(0)) **or** 8.68 ÷ 3.5 (=2.48) M1 for 4.2 ÷ 1.75 (=2.4(0)) **and** 8.68 ÷ 3.5 (=2.48) C1 (dep on at least M1) for small and (£)2.4(0) and (£)2.48 **OR** M1 for 1.75 ÷ 4.2 (=0.41(6)) **or** 3.5 ÷ 8.68 (=0.40(3)) M1 for 1.75 ÷ 4.2 (=0.41(6)) **and** 3.5 ÷ 8.68 (=0.40(3)) C1 (dep on at least M1) for small and 0.41(6)(kg) and 0.40(3)(kg) **OR** M1 for 4.2 ÷ 1.75 (=2.4(0)) **or** 8.68 ÷ 3.5 (=2.48) M1 for (4.2 ÷ 1.75) × 3.5 (=8.4(0)) or (8.68 ÷ 3.5) × 1.75 (=4.34) C1 (dep on at least M1) for small and (£)8.4(0) or for small and (£)4.34 **OR** M1 for 1.75 ÷ 4.2 (=0.41(6)) or 3.5 ÷ 8.68 (=0.40(3)) M1 for (1.75 ÷ 4.2) × 8.68 (=3.61(6)) or (3.5 ÷ 8.68) × 4.2 (=1.69(3)) C1 (dep on at least M1) for small and 3.61(6)(kg) or 1.69(3)(kg) **OR** M2 for 8.68 ÷ 2 (=4.34) or 4.20 × 2 (=8.40) C1 (dep on at least M1) for small and (£)4.34 or (£8.40) **OR** Any other method considered equivalent. Figures may be truncated or rounded as long as their method is clear.

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
2		$7 \times 8^2 + 320 = 448 + 320$ 768p = 7.68	£7.68	3	M1 for 7×8^2 or 448 seen A1 for 768 B1 for correct monetary answer written correctly eg £7.68 or 768p
3			correct shaded region	2	B1 for arc of circle, centre oak tree, radius 4cm(±2mm) B1 for shaded region where the tree can be planted, bounded by sides of garden and arc of circle centre oak tree
4	(a)		−3, −2, −1,0,1	2	B2 for all 5 values and no others (B1 for 4 correct values and no others or -4,-3,-2,-1,0,1 or -3,-2,-1,0,1,2
	(b)		$-2 \leq x < 4$	2	B2 for $-2 \leq x < 4$ (B1 for $-2 \leq x$ or $x < 4$ or $-2 < x \leq 4$) [Note: accept the use of any letter other than x throughout and ignore any attempt to list integer values]
5			25.1-25.2	2	M1 for $2 \times 3.142 \times 4$ or 8π oe A1 for 25.1 – 25. 2
6	(a)		5, −4, −3	2	B2 for 5, −4 and −3 (B1 for 5 or −4 or −3)
	(b)		correct curve	2	B2 for fully correct curve (B1 ft for at least 5 points plotted correctly)

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
7			enlargement, scale factor 2, centre (6, −5)	3	B1 for enlargement B1 for (scale) factor 2 or ×2 or sf 2 B1 for (6, −5) NB: award 0 marks for an explanation that includes reference to more than one transformation.
*8		Cost of wages, rent and other expenses last year 92 000+10 800+7000=109 800 Cost of wages, rent and other expenses this year $1.075\times92\,000 + \frac{7}{9} \times 10$ 800 + 7000÷2 = 98 900+8400+3500 = 110 800 Costs are more this year, so she cannot increase the amount she spends on goods	no, with working and reason	4	M1 for an attempt to calculate using 7.5% and 92000 (eg 7.5% of 92000 or increase of 7.5%) eg 92000 + 6900 or 98900 M1 for an attempt to find a fractional amount of 10800 (eg $\frac{7}{9}$ × 10800 or 8400 or $\frac{2}{9}$ × 10800 or 2400) M1 for complete method of increasing 92000 by 7.5%, finding $\frac{7}{9}$ of 10800, and halving 7000, with at least all of these three added together. C1 for statement eg "no" with both 110800 & 109800 seen, OR "no" with "1000 more" OR "no" and compares 181800 with 182800, oe.
9	(a)	$\sqrt{30} = 5.4772255\ldots$ $2.5^2 = 6.25$ 5.4772255...÷ 6.25 =	0.876	2	M1 for $\sqrt{30} \div 6.25$ or $5.4(7\ldots) \div 2.5^2$ A1 for any answer in the range 0.876 to 0.877
	(b)	4.5 × 1000 × 1000	4 500 000	2	M1 for complete method equivalent to 4.5 × 1000 × 1000 A1 for 4 500 000 oe

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
10		3 → 21 4 → 56 3.1 → 23.5(9) 3.2 → 26.3(6) 3.3 → 29.3(3) 3.4 → 32.5(0) 3.5 → 35.8(7) 3.6 → 39.4(5) 3.7 → 43.2(5) 3.8 → 47.2(7) 3.9 → 51.(5) 3.35 → 30.8(9)	3.3	4	B2 for a trial between 3.3 and 3.4 inclusive (B1 for a trial between 3 and 4 inclusive) B1 for a different trial between 3.3 and 3.4 exclusive B1 (dep on at least one previous B1) for 3.3 NB trials should be evaluated to at least 1dp truncated or rounded
11			45	3	M1 for 60000 × 0.75 or ÷1000 or digits 45 or the numbers 60 or 0.00075) M1 for the complete method 60 000 × 0.75 ÷ 1000 oe A1 cao
12	(a)		−7	2	M1 for an attempt to get *x*s on one side or number terms on one side A1 cao
	(b)		8.5	2	M1 for an attempt to divide each side by 4 or an attempt to expand the bracket eg $4 \times x - 4 \times 5$ A1 for 8.5 oe

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
*13		2500×0.04×2 =£200 2500×$(1.039)^2$ = £2698.80 £2698.80 – £2500 = £198.80 Scheme A gives £1.20 more	statement	4	M1 for a correct method to find 4% of 2500 or 3.9% of 2500 A1 for a correctly calculated amount 2700 or 2698.8(0) or 200 or 198.8(0); or percentage rate calculated over the 2 years for comparison: 3.93% or 3.976% oe M1 for a correct compound interest method using 3.9% and 2500 over 2 years C1 for statement of scheme A, with two correct comparable figures.
14		$3x - 2y = 7$ $7x + 2y = 13$ $10x = 20$ $x = 2$ $3\times2 - 2y = 7$ $-2y = 1$ $y = -0.5$	2, −0.5	3	M1 for a correct process to eliminate either x or y (allow one arithmetic error) M1 (dep) for correct substitution of their found variable or an otherwise correct method to eliminate the other variable A1 for 2 and −0.5 oe
15	(a)		3.7×10^{-3}	1	B1 cao
	(b)		49 000	1	B1 cao
	(c)	500 ÷ 250 000 [= 0.002] OR $(5 \times 10^2) \div (2.5 \times 10^5)$ [= $(5\div2.5)\times10^{2-5}$] OR $\frac{500}{250} \times \frac{1}{10^3}$ [= 2×10^{-3}] OR $\frac{500\div100}{250000\div100} = \frac{5}{2500}$ [= 0.002]	2×10^{-3}	2	M1 for an attempt to divide using two numbers that are in consistent form eg following an attempt to convert to ordinary numbers, or standard form numbers. A1 for 2×10^{-3}

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
16			12.7	3	M1 for 3.142 × 5 × 5 oe or 3.142 × 5 × 5 × '*h*' (=78.5 – 78.55) M1 for 1000 ÷ (3.142 × 5 × 5) A1 for 12.7 – 12.8 NB: multiples of π acceptable for M marks
17		$4x - 3 = 2x + 2y$ $2x - 3 = 2y$ $2x = 2y + 3$ $x = y + 1.5$	$x = y + 1.5$	3	M1 for attempt to expand brackets eg $2\times x+2\times y$ or divide through by 2 (each term). M1 for attempt to get x on one side of equation. A1 for $(x =) y + 1.5$, $\frac{2y + 3}{2}$, oe
18			(11, 21)	3	M1 for 5 – 2 or 9 – 3 OR 3 or 6 as long as these are not related to the 3 from *A* or multiple 3 or 9,18 M1 for 2 + 3 × "3" and 3 + 3 × "6" OR for 5 + 2 × "3" and 9 + 2 × "6" OR for 2 + 3 × "3" (=11) and (y=) 2 × '11' – 1 A1 cao SC: B1 if no method shown and answer shows x coordinate as 11 or y coordinate as 21.

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
19			4.6	5	M1 for $AC = \sqrt{(3^2+4^2)}$ (=5) or $DA = \sqrt{(5^2+2^2)}$ M1 for tan BAC = 0.75 oe or (BAC=) 36.8(6) or 36.9 M1 for tan DAC = 0.4 oe or (DAC=) 21.8(0) M1 for $\sqrt{'5'^2+2^2}$ × sin("36.8(6)"+"21.8(0)") or 5.385 × sin 58.7 A1 for 4.59 – 4.61 OR M1 for $AC = \sqrt{3^2+4^2}(=5)$ or $DP = \sqrt{(29 - AP^2)}$ M1 for cos BAC = 0.8 oe or (BAC=) 36.8(6) oe M1 for angle CDP = angle BAC M1 for (DP=) 3 + 2×cos CDP or (AP=) 4 – 2×sin CDP A1 for 4.59 – 4.61
20			0.5, −3	3	M1 for $(2x \pm 1)(x \pm 3)$ M1 for $(2x - 1)(x + 3)$ A1 cao OR M1 for $\frac{-5 \pm \sqrt{5^2 - 4 \times 2 \times -3}}{2 \times 2}$ allow sub. of $c = \pm 3$ M1 for $\frac{-5 \pm \sqrt{49}}{4}$ A1 cao NB: any other method put in review.

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
21		$1180.5 \div \frac{4}{3}\pi(6.15)^3$	1.21	4	M1 for 1180 ± 0.5 or 6.2 ± 0.05 M1 for 'max. mass' ÷ 'min. volume' where "min volume" is defined as any expression involving 6.15 M1 for $1180.5 \div \frac{4}{3}\pi(6.15)^3$ A1 for 1.21 – 1.22
22			proof	3	B1 for *AD* = *AB* and *AE* = *AG* B1 for angle *EAB* = angle *DAG* (= 90 + angle *DAE*) B1 (dep on previous B marks) for 2 sides and included angle (SAS) oe
23	(a)		$3\boldsymbol{a} + \boldsymbol{b}$	1	B1 oe
	(b)		$3\mathbf{c}$	4	M1 for writing *QB* as a combination of vectors eg $\frac{1}{2}$ ('3**a** + **b**') + **b** or 3**a** + 2**b** – $\frac{1}{2}$ ('3**a** + **b**') or 2**a** + 2**b** − **c** oe M1 for equating **a** + **b** = 2**c** or writing *PQ* in terms of vectors **a** and **b** eg −**a** + $\frac{1}{2}$ ('3**a** + **b**') or 2**a** + **b** – $\frac{1}{2}$ ('3**a** + **b**') A1 for (*PQ*=) $\frac{1}{2}$**a** + $\frac{1}{2}$**b or** (*QB*=) $\frac{3}{2}$**a** + $\frac{3}{2}$**b** or (*QB*=) 2**c**−**a** + **a** + **c** A1 cao NB: accept equivalent expressions throughout

PMT

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone 01623 467467
Fax 01623 450481
Email publication.orders@edexcel.com
Order Code UG035055 March 2013

For more information on Edexcel qualifications, please visit our website
www.edexcel.com

Pearson Education Limited. Registered company number 872828
with its registered office at Edinburgh Gate, Harlow, Essex CM20 2JE

Ofqual
Llywodraeth Cynulliad Cymru
Welsh Assembly Government
Rewarding Learning

PMT

edexcel

Mark Scheme (Results)

Summer 2013

GCSE Mathematics (Linear) 1MA0
Higher (Calculator) Paper 2H

PMT

Edexcel and BTEC Qualifications

Edexcel and BTEC qualifications come from Pearson, the world's leading learning company. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers. For further information visit our qualifications websites at www.edexcel.com or www.btec.co.uk for our BTEC qualifications.
Alternatively, you can get in touch with us using the details on our contact us page at www.edexcel.com/contactus.

If you have any subject specific questions about this specification that require the help of a subject specialist, you can speak directly to the subject team at Pearson.
Their contact details can be found on this link: www.edexcel.com/teachingservices.

You can also use our online Ask the Expert service at www.edexcel.com/ask. You will need an Edexcel username and password to access this service.

Pearson: helping people progress, everywhere
Our aim is to help everyone progress in their lives through education. We believe in every kind of learning, for all kinds of people, wherever they are in the world. We've been involved in education for over 150 years, and by working across 70 countries, in 100 languages, we have built an international reputation for our commitment to high standards and raising achievement through innovation in education. Find out more about how we can help you and your students at: www.pearson.com/uk

Summer 2013
Publications Code UG037224
All the material in this publication is copyright
© Pearson Education Ltd 2013

PMT

NOTES ON MARKING PRINCIPLES

1 All candidates must receive the same treatment. Examiners must mark the first candidate in exactly the same way as they mark the last.

2 Mark schemes should be applied positively. Candidates must be rewarded for what they have shown they can do rather than penalised for omissions.

3 All the marks on the mark scheme are designed to be awarded. Examiners should always award full marks if deserved, i.e if the answer matches the mark scheme. Examiners should also be prepared to award zero marks if the candidate's response is not worthy of credit according to the mark scheme.

4 Where some judgement is required, mark schemes will provide the principles by which marks will be awarded and exemplification may be limited.

5 Crossed out work should be marked UNLESS the candidate has replaced it with an alternative response.

6 Mark schemes will indicate within the table where, and which strands of QWC, are being assessed. The strands are as follows:

i) *ensure that text is legible and that spelling, punctuation and grammar are accurate so that meaning is clear*
Comprehension and meaning is clear by using correct notation and labeling conventions.

ii*) select and use a form and style of writing appropriate to purpose and to complex subject matter*
Reasoning, explanation or argument is correct and appropriately structured to convey mathematical reasoning.

iii) *organise information clearly and coherently, using specialist vocabulary when appropriate*.
The mathematical methods and processes used are coherently and clearly organised and the appropriate mathematical vocabulary used.

7 With working

If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
If there is no answer on the answer line then check the working for an obvious answer.
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks. Discuss each of these situations with your Team Leader.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.

8 Follow through marks

Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

9 Ignoring subsequent work

It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: e.g. incorrect canceling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect e.g. algebra.
Transcription errors occur when candidates present a correct answer in working, and write it incorrectly on the answer line; mark the correct answer.

10 Probability

Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

11 Linear equations
Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

12 Parts of questions
Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

13 Range of answers
Unless otherwise stated, when an answer is given as a range (e.g 3.5 – 4.2) then this is inclusive of the end points (e.g 3.5, 4.2) and includes all numbers within the range (e.g 4, 4.1)

Guidance on the use of codes within this mark scheme
M1 – method mark A1 – accuracy mark B1 – Working mark C1 – communication mark QWC – quality of written communication oe – or equivalent cao – correct answer only ft – follow through sc – special case dep – dependent (on a previous mark or conclusion) indep – independent isw – ignore subsequent working

PMT

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
1			40.5	3	M1 for 1.5×6 or 1.5 ×1.5 M1 for adding area of 5 or 6 faces provided at least 3 are the correct area A1 cao NB: anything that leads to a volume calculation 0 marks.
*2			Not enough mincemeat since 600<700 OR Only able to make 38 mince pies since insufficient mincemeat	4	M1 for 45 ÷ 18 (= 2.5) M1 for 2.5 used as factor or divisor A1 for ingredients as 562.5 and 875 and 250 and 700 and 2.5 (accept 2 or 3) OR for availables as 400, 400, 200 240, 2.4 (accept 2 or 3) C1 ft (dep on at least M1) for identifying and stating which ingredient is insufficient for the recipe (with some supportive evidence) OR M1 for a correct method to determine the number of pies one ingredient could produce M1 for a correct method to determine the number of pies **all** ingredient could produce A1 for 80 and 51 and 90 and 38 and 108 C1 ft (dep on at least M1) for identifying and stating which ingredient is insufficient for the recipe. (with some supportive evidence)

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
3	(a)		Points plotted at (1,8200) and (3.5,5000)	1	B1 for points accurately plotted ±1/2 square tolerance
	(b)		'the older the car the lower the value' 'the greater the value the newer the car'	1	B1 for an acceptable relationship eg. 'the older the car the lower the value' (accept 'negative correlation' but not just 'negative')
	(c)		5200 to 6600	2	M1 for a single line segment with negative gradient that could be used as a line of best fit or a vertical line from 2.5 or a point at (2.5,*y*) where *y* is from 5200 to 6600 A1 for given answer in the range 5200 − 6600
4			126	3	M1 for 1 – 0.05 – 0.32 (= 0.63) M1 for '0.63' × 200 A1 cao OR M1 for 0.05 × 200 (= 10) or 0.32 × 200 (= 64) or 0.37 × 200 (=74) M1 for 200 – '10' – '64' A1 cao OR M1 for 100 – 5 – 32 (= 63) M1 for $\frac{"63"}{100}\times 200$ A1 cao SC: B2 for $\frac{126}{200}$ as the answer.

PMT

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
5	(a)		Response boxes overlap and are not exhaustive	2	B2 for **TWO** aspects from: No time frame given Non-exhaustive responses Response boxes over-lapping (B1 for ONE correct aspect)
	(b)		How many magazines do you buy each month? 0-4 5-8 over 8	2	B1 for a question with a time frame B1 for at least 3 correctly labelled response boxes (non-overlapping, need not be exhaustive) **or** for a set of response boxes that are exhaustive (could be overlapping) [Do not allow inequalities in response boxes]
	(c)		One reason	1	B1 for ONE reason Eg. All the same age, may all be males, may all like same types of magazines, sample too small, biased
6			4.8	4	M1 for 60 × 60 (=3600) M1 for 15000÷ 20 (=750) or 20÷15000 (=0.00133..) or "3600"÷15000 (=0.24) or 15000÷"3600" (=4.16..) M1 for "3600" ÷ (15000÷20) or "3600"×20÷15000 oe A1 cao

PMT

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
7			28% or $\frac{14}{50}$	4	M1 for 100 30 (= 70) or $1 - \frac{3}{10}$ $(= \frac{7}{10})$ M1 for "70" ÷ (3 + 2) (= 14) or $"\frac{7}{10}" \div (3+2)$ $(= \frac{7}{50})$ M1 for "14" × 2 or $\frac{7}{50} \times 2$ A1 for 28% or $\frac{14}{50}$ oe **OR** M1 for a correct method to find (100-30)% of any actual sum of money M1 for "350" ÷ (3 + 2) (= 70) M1 for "70" × 2 A1 for 28% or $\frac{14}{50}$ oe **OR** M1 for starting with two numbers in ratio 3:2, eg 21 and 14 M1 for equating sum of their numbers to 100 – 30 (=70%), eg '21' + '14' (=35) M1 for scaling sum of their numbers to 100%, eg '35'÷70×100 (=50) A1 for 28% or $\frac{14}{50}$ oe SC: award B3 for oe answers expressed in an incorrect form eg $\frac{2.8}{10}$

PMT

PAPER: 1MA0_2H					
Question		Working	Answer	Mark	Notes
8			10752	4	M1 for splitting the pentagon (or show the recognition of the "absent" triangle) and using a correct method to find the area of one shape M1 for a complete and correct method to find the total area M1 (dep on at least one prev M1) for multiplying their total area by 2.56 (where total area is a calculation involving at least two areas) A1 cao
9			55	4	M1 for a correct method to find a different angle using 35° M1 for setting up a complete process to calculate angle *x* A1 cao B1 states one of the following reasons relating to their chosen method: Alternate angles are equal; Corresponding angles are equal; Allied angles / Co-interior angles add up to 180; the exterior angle of a triangle is equal to the sum of the interior opposite angles.

<table>
<tr><th colspan="5">PAPER: 1MA0_2H</th></tr>
<tr><th colspan="2">Question</th><th>Working</th><th>Answer</th><th>Mark</th><th>Notes</th></tr>
<tr><td>10</td><td></td><td><table>
<tr><th>x</th><th>$x^3 + 2x$</th></tr>
<tr><td>4</td><td>72</td></tr>
<tr><td>4.1</td><td>77.(121)</td></tr>
<tr><td>4.2</td><td>82.(488)</td></tr>
<tr><td>4.3</td><td>88.(107)</td></tr>
<tr><td>4.4</td><td>93.(984)</td></tr>
<tr><td>4.5</td><td>100.(125)</td></tr>
<tr><td>4.6</td><td>106.(536)</td></tr>
<tr><td>4.7</td><td>113.(223)</td></tr>
<tr><td>4.8</td><td>120.(192)</td></tr>
<tr><td>4.9</td><td>127.(449)</td></tr>
<tr><td>5</td><td>135</td></tr>
<tr><td></td><td></td></tr>
<tr><td>4.65</td><td>109.8(44625)</td></tr>
<tr><td>4.66</td><td>110.5(14696)</td></tr>
<tr><td>4.67</td><td>111.1(87563)</td></tr>
<tr><td>4.68</td><td>111.8(63232)</td></tr>
<tr><td>4.69</td><td>112.5(41709)</td></tr>
</table></td><td>4.7</td><td>4</td><td>B2 for a trial $4.6 \leq x \leq 4.7$ evaluated correctly
(B1 for a trial evaluated correctly for $4 \leq x \leq 5$)
B1 for a different trial evaluated correctly for $4.65 \leq x < 4.7$
B1 (dep on at least one previous B1) for 4.7

[Note: Trials should be evaluated to at least accuracy shown in table, truncated or rounded]

No working scores 0 marks</td></tr>
<tr><td>11</td><td></td><td></td><td>3.52</td><td>3</td><td>M1 for $1.35^2 + 3.25^2$
M1 (dep) for $\sqrt{(1.35^2 + 3.25^2)}$ $(= \sqrt{12.385})$
A1 for answer in the range 3.51 to 3.52</td></tr>
</table>

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
12	(a)	$3x - 6 = x + 7$ $2x = 13$	6.5	3	M1 for $3\times x - 3\times 2$ ($=3x - 6$) or $\frac{x}{3} + \frac{7}{3}$ seen M1 for correct method to isolate the terms in x or the number terms on opposite sides of an equation A1 for 6.5 oe
	(b)	$2 - y = 1 \times 5$	-3	2	M1 for intention to multiply both sides by 5 (to give $2 - y = 1 \times 5$) A1 cao
13	(a)		(3, 3.5) oe	2	M1 for a correct method to find the value of either the x coordinate or the y coordinate of the midpoint **or** $x = 3$ **or** $y = 3.5$ A1 cao
	(b)		-1.8 oe	2	M1 for correct method to find the gradient OR (+)1.8 A1 for -1.8 oe

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
*14			The Friendly Bank	4	M1 for a correct method to find interest for the first year for either bank **OR** correct method to find the value of investment after one year for either bank **OR** use of the multiplier 1.04 or 1.05 M1 for a correct full method to find the value of the investment (or the value of the total interest) at the end of 2 years in either bank A1 for 2100.8(0) and 2110.5(0) (accept 100.8(0) and 110.5(0)) C1 (dep on M1) ft for a correct comparison of *their* total amounts, identifying the bank from their calculations **OR** M1 for either 1.04 × 1.01 or 1.05 × 1.005 M1 for 1.04 × 1.01 and 1.05 × 1.005 A1 for 1.0504 and 1.05525 C1 (dep on M1) ft for a correct comparison of *their* total multiplying factors identifying the bank from their calculations

PMT

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
15	(a)		-2 -1 0 1 2 3 4 **8** 3 0 **-1** **0** 3 **8**	2	B2 for 8, -1, 0, 8 (B1 for at least two of 8, -1, 0, 8)
	(b)		Correct curve	2	M1 (ft) for at least 5 points plotted correctly A1 for a fully correct curve
	(c)	$x^2 - 2x - 3 = 0$ OR $(x - 3)(x + 1) = 0$	3 and −1	2	M1 for the straight line $y = 3$ drawn to intersect the "graph" from (a) A1 for both solutions **OR** M1 for identifying $y = 3$ from the table A1 for both solutions **OR** M1 for $(x \pm 3)(x \pm 1)$ A1 for both solutions

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
*16		Angle *POT* = 180 – 90 – 32 = 58 (angle between radius and tangent = 90° and sum of angles in a triangle = 180°) Angle *OST* =angle *OTS* = 58÷2 (ext angle of a triangle equal to sum of int opp angles and base angles of an isos triangle are equal) or (angle at centre = 2x angle at circumference) OR Angle *SOT* = 90 + 32 = 122 (ext angle of a triangle equal to sum of int opp angles) (180 – 122) ÷ 2 (base angles of an isos triangle are equal)	29	5	B1 for angle OTP = 90°, quoted or shown on the diagram M1 for a method that leads to 180 – (90 + 32) or 58 shown at *TOP* M1 for completing the method leading to "58"÷2 or 29 shown at *TSP* A1 cao C1 for "angle between radius and tangent = 90°" **and** one other correct reason given from theory used NB: C0 if inappropriate rules listed OR B1 for angle OTP = 90°, quoted or shown on the diagram M1 for a method that leads to 122 shown at *SOT* M1 for (180 – "122") ÷ 2 or 29 shown at *TSP* A1 cao C1 for "angle between radius and tangent = 90°" **and** one other correct reason given from theory used NB: C0 if inappropriate rules listed

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
17	(a)		Box plot overlay	2	M1 for a box drawn with at least 2 correct points from LQ, Med and UQ A1 for a fully correct box plot
	(b)		Comparison of a measure of spread plus a comparison of medians (in context)	2	B1 for a correct comparison of a measure of spread (using either range or iqr) B1 for a correct comparison of medians For the award of both marks at least one of the comparisons made must be in the context of the question.
18		$3p^2 = y + 4$ $p^2 = \frac{y+4}{3}$	$p = \sqrt{\frac{y+4}{3}}$	3	M1 for clear intention to add 4 to both sides or divide all terms by 3(with at least 3 terms) M1 for clear intention to find the square root from p^2 = (expression in y) A1 for $p = \sqrt{\frac{y+4}{3}}$ oe (accept ± a correct root)
19	(a)		$3(2 + 3x)$	1	B1 for $3(2 + 3x)$
	(b)		$(y + 4)(y – 4)$	1	B1 for $(y + 4)(y – 4)$
	(c)		$(2p − 5)(p + 2)$	2	M1 for $(2p \pm 5)(p \pm 2)$ A1 for $(2p − 5)(p + 2)$

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
20		cos y = 2.25 ÷ 6 y = cos^{-1} (2.25 ÷ 6) OR 6cos 75 = 1.55…	The ladder is not safe because y is not near to 75	3	M1 for cos y = 2.25 ÷ 6 oe M1 for cos^{-1} (2.25 ÷ 6) C1 for sight of 67-68 and a statement eg this angle is NOT (near to) 75° and so the ladder is not steep enough and so not safe. OR M1 for cos 75 = x ÷ 6 M1 for 6cos 75 C1 for sight of 1.55(29…) and a statement eg that 2.25 NOT (near to) 1.55 and so the ladder is not steep enough and so not safe.
21			48 or 49	2	M1 for $\frac{460}{460+320+165}\times 100$ (=48.67 ….) or $\frac{460}{9.5}$ or $\frac{460}{9.45}$ A1 for 48 or 49
22			1.33	3	M1 for $3.4 = \frac{k}{5^2}$ oe or 3.4×5^2 (=85) M1 for '3.4×5^2' ÷ 8^2 A1 for answer in range 1.32 to 1.33 or $\frac{85}{64}$
23		d: UB = 54.5 (or 54.499), LB = 53.5 C: UB = 170.5 (or 170.499), LB = 169.5 170.5 ÷ 53.5 169.5 ÷ 54.5	3.19 3.11..	4	B1 for any one correct bound quoted M1 for 170.5 ÷ 53.5 or 169.5 ÷ 54.5 A1 for UB = answer in range 3.18 to 3.19 from correct working A1 for LB = 3.11.. from correct working

PMT

PAPER: 1MA0_2H					
Question		**Working**	**Answer**	**Mark**	**Notes**
24	(a)		18.2	2	M1 for ½ × 6 × 7 × sin60 A1 for answer in range 18.1 to 18.2
	(b)		6.56	3	M1 for $6^2 + 7^2 - 2 \times 6 \times 7 \times \cos 60$ M1 for correct order of operation eg 36 + 49 – 42 (=43) A1 for answer in range 6.55 to 6.56
25			$x = 2.87$, $y = -0.87$ and $x = -0.87$, $y = 2.87$	6	M1 for $x^2 + (2 - x)^2 = 9$ M1 for $4 - 4x + x^2$ A1 for $2x^2 - 4x - 5 = 0$ oe 3 term simplified quadratic M1 for a correct method to solve their quadratic Eg $x = \frac{4 \pm \sqrt{(16 - 4 \times 2 \times -5)}}{4}$ A1 for $x = 2.87$, $y = -0.87$ or better A1 for $x = -0.87$, $y = 2.87$ or better Award marks for equivalent algebraic expressions. Apply the same scheme as above for y first.

PMT

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5°
Measurements of length: ±5 mm

PAPER: 1MA0_2H			
Question		**Modification**	**Notes**
1		Model as well as diagram provided	Standard mark scheme
3	(a)	*y*-axis 2 cm for 1000. *x*-axis 2 cm for ½ Table: 8200 changed to 8000	Points plotted at (1,8000) and (3.5,5000
8		Braille diagram labelled A B E D C	Standard mark scheme
12	(a)	MLP only: *x* changed to *y*.	Standard mark scheme
13		Crosses at A and B changed to a filled-in circle. Braille: AB is joined with a line.	Standard mark scheme

PMT

PAPER: 1MA0_2H			
Question		**Modification**	**Notes**
15		Table: wording added "There are four spaces to fill." *x*-axis 2 cm for ½. *y*-axis 2 cm for 1. Labelling remains same as on standard paper.	Standard mark scheme
17		Both box plots put on one page and labelled 'Girls' and 'Boys' Girls: LQ changed to 15, UQ changed to 40 Boys: figures changed to 5 20 35 40 50 2 cm grids.	Standard mark scheme
20		'horizontal ground' and 'vertical wall' labelled.	Standard mark scheme
24		Braille: Information about measurements given	Standard mark scheme

PMT

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone 01623 467467
Fax 01623 450481
Email publication.orders@edexcel.com

Order Code UG037224 Summer 2013

For more information on Edexcel qualifications, please visit our website
www.edexcel.com

Pearson Education Limited. Registered company number 872828
with its registered office at Edinburgh Gate, Harlow, Essex CM20 2JE

Ofqual
Llywodraeth Cynulliad Cymru
Welsh Assembly Government
Rewarding Learning

Question 17

Many of the students who used the given statement, $x^2 : (3x + 5) = 1 : 2$, to form a correct equation were able to give fully correct solutions. Marks were sometimes lost through factorising $2x^2 – 3x – 5 = 0$ incorrectly. Some students gained only the first mark because they could not write their equation (which was often $2x^2 = 3x + 5$) in a suitable form ready for solution. Many students scored no marks at although some of these students had attempted to form an equation. Common incorrect equations were $x^2 = 2(3x + 5)$ and $x^2 + 3x + 5 = 3$ and some students used $x^2 = 1$ and $3x + 5 = 2$. Many students, though, simply substituted different values of x into the given statement. This approach sometimes resulted in an answer of $x = –1$ but gained no marks because two values of x are needed.

Question 18

Students usually scored well on part (a) of this question requiring the expansion of a product of three linear expressions to give a fully simplified cubic expression. Errors were usually restricted to incorrect terms rather than a flawed strategy although some students omitted terms from their expansion. It was usual for students to earn two or three of the available marks. Less able students lacked a clear strategy and sometimes tried the multiply all three brackets together at once.

Part (b) of the question proved to be more challenging than part (a) and it was relatively rare for examiners to award full marks. Credit awarded to students was often restricted to the mark gained for taking the square root of each side of the inequality or, in the case of students who started by expanding the left hand side, for getting a quadratic equation or inequality with all the terms on one side. Very few students used the expected method of taking the square root of both sides, taking into account both square roots of $\frac{9}{25}$. Students who expanded $(1 - x)^2$ were more likely to gain two or three marks for their responses but only about a third of all students earned one or more marks. The best answers demonstrated a very good understanding of the topic together with the good practice of including a graph sketch with the rest of their working.

Question 14

Very few students were able to derive a correct quadratic equation from which a complete solution could be found. A common mistake was in finding the area of the triangle, $(x – 2)(x + 4)$ and $(x – 2) + (x + 4)$ were often seen, many times without brackets shown. One mark was available in a special case for a correct product expanded and equated to 27.5.

Many students after seeing a right-angled triangle, often started their solutions by attempting to use Pythagoras' theorem. When a trial and improvement method was employed, credit could only given if the final answer was correct.

Those students who realised that the area of the rectangle of sides $(x – 2)$ and $(x + 4)$ was 55 were often successful in getting the correct answer.

Question 6

There were a good number of totally correct responses to this question. However, in part (a) some students attempted to solve the equations algebraically usually without success.

Part (b) was not answered well and a significant number of students did not attempt the question. Students who included correct solutions in an incorrect format, such as (0.6, 0) and (3.4, 0) or $0.6 < x < 3.4$ were given one mark on the basis that they had clearly used the intercepts of the x axis. One mark was also available to students who marked the two intercepts of the x axis on the diagram but not to those students who also marked extra intercepts, for example at (0, 2).

Question 8

Students who rearranged the given equation to get $x^2 – 5x – 24 = 0$ often went on to give a fully correct answer. Some, however, lost marks because they were unable to factorise correctly or they factorised correctly but then wrote $(x – 8)(x + 3)$ as the final answer. A surprising number of students did not realise that a sensible first step would be to rearrange the equation and attempted to factorise straight away. Those who gave a factorisation of the form $(x \pm 8)(x \pm 3)$ gained the second method mark.

Question 16

Many students gave a concise, clear and accurate algebraic argument to score full marks for their answers to this question. Lower attaining students often made errors in the

manipulation of the equations involved. It was common for examiners to award 3 marks for students completing the algebra correctly but not the fourth communication mark because the student had not made a statement to conclude their findings.

Question 19

Relatively few students could demonstrate the necessary skills of algebraic manipulation to solve the equation and give the answer in the required form. Many students were able to correctly write the two fractions with a common denominator and gain the first mark but a significant number were then unable to carry the algebraic solution any further. Those that did reduce the equation to a 3 term quadratic often made errors when rearranging and did not get the second mark. Substitution into the quadratic equation formula was generally done well but some students attempted to use completing the square and this was done less well due to not dealing with the coefficient of 2 correctly. Some students who did not get a correct quadratic equation were still able to gain the third mark for dealing correctly with their 3 term quadratic equation. The final step to write $\frac{10 \pm \sqrt{60}}{4}$ in the required form proved difficult with $\frac{5 \pm \sqrt{30}}{2}$ a common incorrect answer.

Question 22

This question was accessible to and discriminated well between the most high attaining students sitting this paper. These students often gave a complete and fully correct solution and scored full marks. They usually used the approach of eliminating y to get an equation in x. This was more straightforward to deal with than the corresponding equation in y. The most common errors made by students included expanding $(2x - 5)^2$ incorrectly, often as $4x^2 + 25$, and making errors when re-arranging their quadratic equation to get all terms on one side of the equation. Some students who did get the correct quadratic equation to solve, made errors when trying to factorise and so restricted themselves to the award of 2 marks.

Summary

Based on their performance on this paper, students are offered the following advice:

- make sure you put negative numbers in brackets when substituting them into algebraic expressions or when using a calculator.
- check all your working for careless errors and to make sure you have not miscopied numbers or algebraic expressions either given in the question or in a previous line of your working.
- practise the addition and subtraction of algebraic fractions.
- check your working when expanding brackets and collecting terms, especially when finding the product of three linear expressions or when removing brackets after a subtraction of one expression from another.
- ensure you have a good understanding of how to use multipliers in problems concerning reverse percentages.
- practise drawing histograms and using them to solve problems.

Question 19

Some students correctly wrote the two fractions with a common denominator and gained the first mark but many were then unable to carry the algebraic solution any further. Those that did reduce the equation to a 3-term quadratic sometimes made errors when rearranging and did not get the second mark. Substitution into the quadratic equation formula was generally done well. Some students who did not get a correct quadratic equation were still able to gain the third mark for dealing correctly with their 3-term quadratic equation. The first of the two accuracy marks was awarded for two correct values of x, e.g. $\frac{-4 \pm \sqrt{32}}{8}$. Some students gave this as the final answer and others made errors when attempting to write it in the required form. Only a few students could demonstrate the necessary skills of algebraic manipulation to solve the equation and give the answer in the required form.

Question 19

Again, a high proportion of learners trying to use the formula would suggest that the additional information provided was well used. Those using the formula had very mixed results. It was evident that many candidates were not confident in their substitution, and missing signs, short root notation and short fraction notation led not only to incorrect answers but often to the withholding of marks.

Those who attempted factorisation typically struggled, probably down to the coefficient of x^2 being 6. All that said, a significant proportion of candidates scored 2 or 3 marks, for either one or two correct values given. Again, it is important that candidates remember when rounding values such as 23 one decimal place is not enough, and as such an answer given of 0.6 (without first seeing 2/3 or $0.\dot{6}$) did not get credit.

Question 17

This question also discriminated well between students targeting the higher grades. In part (a) of the question, most students working at this level were able to make an attempt to complete the square. They were often successful and where they did not give a fully correct response, they were often able to get as far as including $(x - 4)^2$ as part of their answer. $(x - 8)^2$ was an error commonly seen by examiners. An encouraging number of students were able to use their completed square form to write down the coordinates of the turning point on the graph. However, confusion over signs prevented some students from its accurate identification from their completed square form.
In part (b), examiners were surprised that only a minority of students realised that they should use the quadratic formula. The question requested that students give their solutions correct to 3 significant figures and this provided a hint that the equation could not be factorised. Many students did attempt to factorise the quadratic or manipulate the equation in some other way. Despite being given the quadratic formula on the formula sheet, some students used an incorrect version in their working, for example $-b \pm \frac{\sqrt{b^2 - 4ac}}{2a}$. Some other students replaced the "±" in the formula with "+" and so only found one of the two solutions. There were a good number of fully correct solutions, with most students giving their solutions correct to 3 significant figures. A few students lost a mark as they gave one solution as 0.45 rather than 0.449
The identification of the mistake in Alex's working for part (c) of the question was usually clearly expressed in one way or another.