Chhetri Academy

chhetriacademy.com

GCSE MATHS

Algebra

Edexcel 1MA1 | Subtopic collection Topic 21

Inequalities

Higher tier

Answers and examiner comments

49	2003-2025	Higher
question groups	available papers	tier

Using this booklet

1. Answer numbers match the companion question booklet.
2. Follow the original question number on marking tables.
3. Examiner comments are included where available.

Name _____ **Date** _____

Some entries use full source marking material in an appendix. Any unavailable mark schemes are identified beside the relevant answer.

Original question 4

The full source mark scheme begins on page 85. Use the original paper code, tier and question number shown above.

Original question 8

No matching mark scheme was available in the supplied archive for this question.

Original question 14

No matching mark scheme was available in the supplied archive for this question.

Original question 10

The full source mark scheme begins on page 139. Use the original paper code, tier and question number shown above.

Original question 7

No matching mark scheme was available in the supplied archive for this question.

Original question 9

The full source mark scheme begins on page 190. Use the original paper code, tier and question number shown above.

Question		Working	Answer	Mark	Notes
20	(a)	$\frac{90}{600}$	$\frac{3}{20}$	2	M1 $\frac{90}{600}$ A1 $\frac{3}{20}$ cao [SC: B1 for 0.15 or 15% if M0 scored]
	(b)	$\frac{180}{600}\times 100$ **OR** $\frac{180}{600}=\frac{30}{100}$	30	2	M1 $\frac{180}{600}\times 100$ A1 cao **OR** M1 $\frac{180}{600}=\frac{30}{100}$ or attempt to cancel to 100 A1 cao
	(c)	$600-(90+180)$ = 330 blue or green 330÷3	110	2	M1 [“$600-(90+180)$”]÷3 A1 cao [SC: B1 for an answer of 140 or 170 if M0 scored]

1380/1F

22			$2c + 4r$	2	B2 for 2*c* +4*r* oe [B1 for 2*c* or 4*r* oe seen] Ignore any Left Hand Side = $2c + 4r$ {Note: ignore units or use of 'p'}

15	(a)		–1,0,1,2	2	B2 cao (–1 each error or omission)
	(b)	$5y \geq 10$	5 $y \geq 2$	2	M1 for $5y \geq 10$, condone use of = sign or > A1 for $y \geq 2$ oe as final answer [SC: B1 for 2 or $\frac{10}{5}$ seen if M0 as an answer]

1380 3H

1380/3H

10	(a)		$-2, -1, 0, 1, 2$	2	B2 for $-2, -1, 0, 1, 2$ (B1 for one extra or one missing)
	(b)	$2x < 30$	$x < 15$	2	M1 for $2x < 30$ or $\frac{x}{3} < 5$ or $x = 15$ or $x > 15$ A1 cao

15	(a)			2	B2 for an open circle at –3 with either an arrow to the right or a line segment from –3 to at least 5, ±2 mm (B1 for an open circle at –3 with either an arrow to the left or an incorrect line segment OR a closed circle or no circle at –3 with either an arrow to the right or a line segment from –3 to at least 5 ±2 mm)
	(b)	$7y \leq 8 - 36$ $7y \leq -28$	$y \leq -4$	2	M1 for a correct process to isolate $7y$ in an inequality or $y = -4$ or $y < -4$ A1 cao

1380_4H

Question		Working	Answer	Mark	Notes
12	(a)		−2, −1, 0, 1, 2, 3, 4	2	B2 for all 7 correct values; ignore repeats, any order (-1 for each omission or additional value)
	(b)	$4x > 10$	$x > 2.5$	2	M1 for $4x > 11 - 1$ or clear attempt to subtract 1 from both sides **or** clear attempt to divide all 3 terms by 4 or $4x > 10$ **or** $4x = 10$ **or** $4x < 10$ etc A1 $x > 2.5$ oe [SC: B1 for 2.5 oe seen if M0 scored]

21		$4n^2 + 12n + 3^2 - (4n^2 - 12n + 3^2)$ $= 4n^2 + 12n + 9 - 4n^2 + 12n - 9$ $= 24n$ $=8 \times 3n$	Proof	3	M1 for 3 out of 4 terms correct in expansion of either $(2n + 3)^2$ or $(2n - 3)^2$ **or** $((2n + 3) - (2n - 3))((2n + 3) + (2n - 3))$ A1 for $24n$ from correct expansion of both brackets A1 (dep on A1) for $24n$ is a multiple of 8 or $24n = 8 \times 3n$ or $24n \div 8 = 3n$

1MA0_2H

Question		Working	Answer	Mark	Notes
14	(a)	listing –1,0,1,2,3 or –1,0,1,2,3,4	–1,0,1,2,3	2	M1 listing –1,0,1,2,3 or –1,0,1,2,3,4 A1 for –1,0,1,2,3 (ignore any algebra with the answer)
	(b)		Region identified	4	M1 for any two of the lines $y=1$, $y=2x-2$, $y=6-x$ M1 for any two of the lines $y=1$, $y=2x-2$, $y=6-x$ with at least one showing shading (in or out) M1 for any two of the lines $y=1$, $y=2x-2$, $y=6-x$ with at least two showing consistent and correct shading (in or out) A1 lines drawn, and correct region identified by either shading in, or shading out; the letter R is not required. Accept without shading only with the correct region indicated by R. NB: accept lines that are solid or dotted/dashed etc. or lines defined by unambiguous shading.

Question		Working	Answer	Mark	Notes
8	(a)		–1, 0, 1, 2, 3	2	B2 for all 5 correct values; ignore repeats, any order (B1 for 4 correct (and no incorrect values) eg. 0, 1, 2, 3 **or** one additional value, eg –1, 0, 1, 2, 3, 4)
	(b)		$-4 < x \leq 3$	2	B2 for $-4 < x \leq 3$ **or** > -4 **and** ≤ 3 (B1 for $-4 < x$ **or** $x > -4$ **or** $x \leq 3$ **or** $3 \geq x$ **or** > -4 **or** ≤ 3 **or** $-4 \leq x < 3$) NB : Accept the use of any letter
	(c)	$3y - 2 > 5$ $3y > 7$	$y > \frac{7}{3}$	2	M1 for clear intention to add 2 to both sides (of inequality or equation) or clear intention to divide all three terms by 3 **or** $3y > 7$ **or** $3y < 7$ **or** $3y = 7$ A1 $y > \frac{7}{3}$ **or** $y > 2\frac{1}{3}$ **or** $y > 2.\dot{3}$ NB. final answer **must** be an inequality (SC B1 for $\frac{7}{3}$ oe seen if M0 scored)

Question		Working	Answer	Mark	Notes
1		$3x > 11$ $x > \frac{11}{3}$ or 3.66.. OR $(16 - 5) \div 3$ $\frac{11}{3}$ or 3.66..	4	3	M1 $3x >$ 11 or $3x >$ 16 – 5 or $3x$ + 5 – 5 $>$ 16 – 5 A1 $\frac{11}{3}$ or 3.6(66..) or 3.7 (Accept = or ≥ in place of >) B1 ft OR M1 $(16 - 5) \div 3$ A1 $\frac{11}{3}$ or 3.6(66..) or 3.7 B1 ft

Question		Working	Answer	Mark	Notes
12	(a)		−2, −1, 0, 1,	2	B2 for all 4 correct values; ignore repeats, any order (B1 for 3 correct (and no incorrect values) eg. −2, −1, 0 **or** one additional value eg. −3, −2, −1, 0, 1)
	(b)		$p>6$	2	M1 for clear intention to add 7 to both sides **or** $3p > 11 + 7$ **or** clear intention to divide all 3 terms by 3 as a first step **or** $3p > 18$ **or** $3p = 18$ **or** $3p < 18$ **or** $\frac{18}{3}$ A1 for $p > 6$ as final answer NB: (p =) 6 on the answer line scores M1 A0

Original question 4

The full source mark scheme begins on page 242. Use the original paper code, tier and question number shown above.

Question		Working	Answer	Mark	Notes
14	(a)	Line joins an empty circle at -2 to a solid circle at 3	diagram	2	B2 cao (B1 for line from -2 to 3)
	(b)	$2x \geq 7$	$x \geq 3.5$	2	M1 for correct method to isolate variable and number terms (condone use of =, >, ≤, or <) or (x =) 3.5 A1 for $x \geq 3.5$ oe as final answer
*Q15 QWC			No + explanation	3	M1 for $500 \times 9 \times 10^{-3}$ oe A1 for 4.5 C1 (dep M1) for correct decision based on comparison of their paper height with 4 **OR** M1 for $4 \div 500$ oe A1 for 0.008 C1 (dep M1) for correct decision based on comparison of their paper thickness with 0.009 **OR** M1 for $4 \div (9 \times 10^{-3})$ oe A1 for 444(.4...) C1 (dep M1) for correct decision based on comparison of their number of sheets of paper with 500

12		Region identified	4	B1 for $x + y = 6$ or $x = –1$ or $y = 2$ drawn B1 for $x + y = 6$ and $x = –1$ and $y = 2$ drawn M1 for consistent shading (in or out) for any two of the lines $x + y = 6$, $x = –1$, $y = 2$ A1 lines drawn, and correct region identified by either shading in, or shading out; the letter R is not required, but necessary if no shading. Note: Lines may be solid or dotted/dashed etc

PAPER: 5MB3H_01

12		Region identified	4	B1 for $x + y = 6$ or $x = –1$ or $y = 2$ drawn B1 for $x + y = 6$ and $x = –1$ and $y = 2$ drawn M1 for consistent shading (in or out) for any two of the lines $x + y = 6$, $x = –1$, $y = 2$ A1 lines drawn, and correct region identified by either shading in, or shading out; the letter R is not required, but necessary if no shading. Note: Lines may be solid or dotted/dashed etc

PAPER: 5MB3H_01

PAPER: 1MA0_2H

Question		Working	Answer	Mark	Notes
21	(a)	$y^2 - 2y - 5y + 10$	$y^2 - 7y + 10$	2	M1 for all 4 terms correct (condone incorrect signs) or 3 out of 4 terms correct with correct signs A1 cao
	*(b)	$(4n^2 + 2n + 2n + 1)$ $- (2n + 1)$ $= 4n^2 + 4n + 1 - 2n - 1$ $= 4n^2 + 2n$ $= 2n(2n + 1)$	Proof	3	M1 for 3 out of 4 terms correct in the expansion of $(2n + 1)^2$ or $(2n + 1)\{(2n+1) - 1\}$ A1 for $4n^2 + 2n$ or equivalent expression in factorised form C1 for convincing statement using $2n(2n + 1)$ or $2(2n^2 + n)$ or $4n^2 + 2n$ to prove the result
*22			Yes	3	M1 for $1 - 0.6$ (=0.4) M1 for ("0.4")^3 oe C1 (dep on M1) for 0.064 oe leading to a correct deduction OR M1 for $1-\Pr(3H, 0T) - \Pr(2H, 1T) - \Pr(1H, 2T)$ oe M1 for $1-(0.6)^3-3(0.6)^2(0.4)-3(0.6)(0.4)^2$ C1 (dep on M1) for 0.064 oe leading to a correct deduction

12	(a)		$e > \frac{9}{4}$	2	M1 for correct process to isolate terms in e from other terms A1 for $e > \frac{9}{4}$ oe
	(b)		shaded region	2	M1 for $x + y = 1$ drawn or for a region shaded above their line with negative gradient A1 for region shaded above line

PAPER: 1MA0_1H

Question		Working	Answer	Mark	Notes
5	(a)		$y > 0.5$	2	M1 for clear intention to subtract 5 from both sides of inequality or equation **or** divide all terms of the inequality or equation by 6 **or** $6y > 3$ **or** 0.5 oe seen A1 for $y > 0.5$ oe as final answer
	(b)		$-3 < x \leq 4$	2	B2 for $-3 < x \leq 4$ oe (B1 for one correct inequality, eg $-3 < x$ **or** $x > -3$ **or** $x \leq 4$ **or** $4 \geq x$ **or** $-3 \leq x < 4$) NB Accept the use of any letter
*6		554 ×27 3878 11080 14958 1 0 1 0 0 8 3 5 3 5 2 8 1 4 9 5 8	Yes with correct working	4	M1 for a complete method with relative place value correct. Condone 1 multiplication error, addition not necessary. M1 (dep) for addition of all the appropriate elements of the calculation. A1 for £149.58 or 42p (spare) C1 ft (dep on M1) for correct decision for their total cost **OR** M1 for a complete grid with not more than 1 multiplication error, addition not necessary M1 (dep) for addition of all the appropriate elements of the calculation A1 for £149.58 or 42p (spare) C1 ft (dep on M1) for correct decision for their total cost **PTO**

		<table><tr><th>500</th><th>50</th><th>4</th><th>×</th></tr><tr><td>10 000</td><td>1000</td><td>80</td><td>20</td></tr><tr><td>3500</td><td>350</td><td>28</td><td>7</td></tr></table> 10000 1000 3500 350 80 28 14958			**OR** M1 for sight of a complete partitioning method, condone 1 multiplication error, addition not necessary. M1 (dep) for addition of all the appropriate elements of the calculation. A1 for £149.58 or 42p (spare) C1 ft (dep on M1) for correct decision for their total cost **OR** M1 for 150.0... ÷ 27 at least 5 seen and 15 carried or $\frac{50}{9}$ M1 (dep) for full correct process to divide 150 by 27 or $5\frac{5}{9}$ A1 for £5.55 or £5.56 or £5.55... C1 ft (dep on M1) for correct decision for their plant cost **OR** M1 for 150.0…÷ 5.54 at least 2 seen and 392 carried M1 (dep) for full correct process to divide 150 by 5.54 A1 for 27 (.07…) C1 ft (dep on M1) for correct decision for their number of plants

PAPER: 1MA0_1H

Question		Working	Answer	Mark	Notes
18			Region identified	4	M1 for the graph of $x + y = 7$ or $y = 2x$ drawn M1 for the graphs of $x + y = 7$, $y = 2x$ and $y = 3$ drawn M1 for any correct shading (in or out), satisfying at least two correct inequalities where the shading must extend from the appropriate lines. A1 for correct region identified by either shading in, or shading out; the letter R is not required. Accept without shading only with the correct region indicated by R. NB accept lines that are solid or dotted/dashed etc or lines defined by unambiguous shading

PAPER: 1MA0_2H

Question		Working	Answer	Mark	Notes
20			Shown	3	M1 for correct expansion of $(n+3)^2$ or $(n-3)^2$ eg $(n+3)^2 = n^2+6n+9$ or $(n-3)^2 = n^2-6n+9$ M1 for correct expansion of complete expression, eg $(n^2+6n+9) - (n^2-6n+9)$ A1 for $12n$ and conclusion OR M1 for $[n+3+n-3][n+3-(n-3)]$ M1 for $2n \times 6$ A1 for conclusion

Question	Working	Answer	Mark	Notes
3 (a)		1.75	2	M1 for intention to multiply brackets or for intention to divide all terms by 4 as the first step A1 for 1.75 oe
(b)		p > 7.5	2	M1 for correct method to isolate *p* or intention to divide all terms by 2 as the first step (condone the use of '=' in method) A1 for *p* > 7.5 oe
(c)		3, -5	3	M2 for $(x - 3)(x + 5)$ (M1 for $(x \pm 3)(x \pm 5)$) A1 cao 3 and –5 OR M1 for $\frac{-2 \pm \sqrt{2^2 - 4 \times 1 \times -15}}{2 \times 1}$ M1 for $\frac{-2 \pm \sqrt{64}}{2}$ A1 for 3 and – 5 cao

5MB3H/01 June 2015				
Question	**Working**	**Answer**	**Mark**	**Notes**
*4		275g (£7.95) pack with reason	4	M1 for one of 439 ÷ 150 (= 2.92), 639 ÷ 200 (= 3.19), 795 ÷ 275 (= 2.89) OR one of 150 ÷ 439 (= 0.341), 200 ÷ 639 (= 0.31), 275 ÷ 795 (= 0.345) OR any other calculation that could lead to a comparative figure M1 for calculations that could lead to comparative figures for 2 jars M1 for calculations that could lead to comparative figures for 3 jars eg all 3 from the above lists C1 for correct comparative figures for all 3 jars leading to a correctly stated comparison: 275g best value

13	(a)		5 and 6	2	M1 for evidence that (x =) 4, 5, 6 or evidence that (y =) 5,6,7, 8 A1 cao
	(b)		Region identified	4	M1 for two of the lines $y = -1$,$y = 3x - 1$ and $y = 4 - x$ drawn M1 for three of the lines $y = -1$, $y = 3x - 1$ and $y = 4 - x$ drawn M1 any correct shading(in or out) satisfying at least two of the inequalities where the shading must extend from the appropriate line A1 Fully correct region shown by either shading in, shading out or the use of R Accept lines that are solid or dashed

11	(a)		$x > -4$	1	B1 cao
	(b)		$y \leq 3$	2	M1 for intention to isolate y or for $y = 3$ or $y < 3$ A1 cao
	(c)		$-1,0,1$	2	M1 for listing $-3, -2, -1,0,1$ or $-1, 0,1,2,3$ or for $-2 < ? < 2$ A1 for $-1,0,1$

Original question 12

The full source mark scheme begins on page 257. Use the original paper code, tier and question number shown above.

10	(a)		Diagram	2	B2 for fully correct solution with all three aspects with no ambiguity Aspect 1: circle at 3 Aspect 2: circle not shaded Aspect 3: arrow pointing left indicating extension beyond −4 or line extending beyond −4 (B1 for any two aspects)
	(b)		$x \geq 5$	2	M1 for intention to add 7 to both sides (of inequality or equation) or to divide all 3 terms by 4 as a first step, or (x =) 5 A1 for $x \geq 5$ oe

5	(a)		Inequality drawn	2	B2 for all three features of −2, O and right arrow (B1 for two of these features)
	(b)		2	3	M1 for isolating the y terms A1 for $3y < 8$ or $3y = 8$ or better B1 ft

7		$4.755 \leq n < 4.765$	B2 [B1	for $4.755 \leq n < 4.765$ for 4.755 or 4.765 or 4.764̇9]

13		$y \geq -2, y \geq x$ and $y \leq 0.5x + 1$	M1 M1 M1 A1	$y = -2$ indicated; accept any inequality for "=" $y = x$ oe indicated; accept any inequality for "=" $y = 0.5x + 1$ oe indicated; accept any inequality for "=" $y \geq -2, y \geq x$ and $y \leq 0.5x + 1$

23		$x > 2$	P1 M1 M1 M1 A1	for process to derive algebraic expressions for area of both rectangle and triangle eg $(x - 1)(3x - 2)$ and $(2x \times x) \div 2$ (condone missing brackets) for method to rearrange inequality to $2x^2-5x+2> 0$ oe providing in the form $ax^2 + bx + c >0$ for a correct method to solve $2x^2-5x+2>0$ for establishing critical values 2 and $\frac{1}{2}$ $x > 2$

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5°
Measurements of length: ±5 mm

PAPER: 1MA1_1H			
Question		**Modification**	**Mark scheme notes**
3		Diagram enlarged. Angles moved outside the angle arcs and the angle arcs made smaller. Arrow heads made longer and more obvious. Wording added 'AD is parallel to BC. AB is parallel to EC.'	Standard mark scheme
4		Diagram enlarged. Cross changed to a solid dot. Shading changed to dotty shading.	Standard mark scheme
5		Frequency column has been extended to allow for working.	Standard mark scheme
6		Diagram enlarged. Wording added 'All marked angles are right angles'. MLP only: *x* changed to *e*, *y* changed to *f*. Braille only: will label the corners of the rectangle A to D and will give information about the rectangle.	Standard mark scheme with *x* replaced by *e*, and *y* replaced by *f*.
7		Diagram enlarged. Crosses changed to solid dots.	Standard mark scheme

PAPER: 1MA1_1H			
Question		**Modification**	**Mark scheme notes**
12		Numbers on the table changed: least height changed from 154 to 155, lower quartile changed from 161 to 160 and interquartile range changed from 7 to 10.	
12	(a)	Diagram enlarged and labelled 'Diagram (i)'. Diagram (ii) put below Diagram (i) on the same page in the diagram book. Axis label moved to the left of the horizontal axis.	M1 for method to find UQ (168) or highest value (174), may be implied by correct values plotted M1 for showing a box and at least 3 correctly plotted values from 155, 160, 165, 170, 175 A1 fully correct box plot
	(b)	Diagram enlarged and labelled 'Diagram (ii)'. Axis label moved to the left of the horizontal axis. Points on the box plot changed to: 145, 155, 160, 165 and 170.	Med IQR Range Y7 160 10 25 Y11 165 10 20 otherwise standard mark scheme using these figures
14		MLP only: x has been changed to e and y has been changed to f.	Standard mark scheme with x replaced by e, and y replaced by f.

PAPER: 1MA1_1H			
Question		**Modification**	**Mark scheme notes**
18		Question reversed. Wording added 'It shows Shape P and Shape Q given on a grid.' Question changed to 'Describe fully the transformation that maps Shape P onto Shape Q.' Three answer lines provided. Shape Q drawn on the grid. Shape P and Shape Q labelled. Shape P has been moved down a square so that the new coordinates of Shape P are (2,2) (4,2)(2,6). New coordinates of Shape Q are (-1,-1)(-2,-1)(-1,-3). X axis has been reduced so it goes from -6 to 8; Y axis has been reduced so it goes from -4 to 8. 	B1 for centre of enlargement (0,0) B1 for sf given as $-\frac{1}{2}$

PAPER: 1MA1_1H			
Question		**Modification**	**Mark scheme notes**
19		Diagram enlarged.	Standard mark scheme
20		Table has been turned to vertical format	Standard mark scheme
22		Diagram enlarged. Wording changed to 'It shows two triangles CDA and BEA that are similar.' Wording added 'CB equals x cm, BA = 8 cm, AE = 12 cm and ED = 3 cm.'	Standard mark scheme
23		Diagrams enlarged. Braille only: will add information about the diagram.	Standard mark scheme

Question	Working	Answer	Mark	Notes
14		Region R shaded	M1	for two of the lines $y = 1$, $x + y = 5$, $y = 2x$ correctly drawn
			M1	for three lines correctly drawn
			A1	for fully correct region indicated with all lines correct

Question	Answer	Mark	Mark scheme	Additional guidance
20	2, 3, 4	M1	for method to solve $3n + 2 \leq 14$ eg $n \leq (14 - 2) \div 3$ oe	This could be shown within an equation rather than an inequality at this stage
		M1	for complete method to rearrange $\frac{6n}{n^2 + 5} > 1$ to the form $an^2 + bn + c$ (< 0)	For the 2rd and 3rd M marks condone no '< 0' and condone use of incorrect inequality signs or '='
		M1	for method to begin to solve $n^2 - 6n + 5$ (< 0) eg $(n \pm 5)(n \pm 1)$ (< 0)	Accept $\frac{--6 \pm \sqrt{(-6)^2 - 4 \times 1 \times 5}}{2 \times 1}$ (condone one sign error)
		M1	(dep on previous M2) for $n > 1$ and $n \leq 4$ **or** $1 < n < 5$	Must come from correct working Could be shown on a number line
		A1	(dep M4) cao	
			Alternative method	
		M1	for method to solve $3n + 2 \leq 14$ eg $n \leq (14 - 2) \div 3$ oe **OR** for $3 \times 4 + 2 = 14$	This could be shown within an equation rather than an inequality at this stage
		M3	for trials with 1, 2, 3 and 4 in the quadratic inequality, correctly evaluated	The values from the trials may be given as improper fractions eg $\frac{24}{21}, \frac{18}{14}, \frac{12}{9}, \frac{6}{6}$
		(M2	for trials with three of 1, 2, 3 and 4, correctly evaluated)	
		(M1	for trials with two of 1, 2, 3 and 4, correctly evaluated)	
		A1	(dep M4) cao	

Q18



Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5º
Measurements of length: ±5 mm

Paper: 1MA1/1H			
Question		**Modification**	**Mark scheme notes**
5	(a)	Model and a diagram provided. Diagram enlarged. Dashed lines made longer and thicker. Dotted lines made more obvious. Question reversed: Four different options of the front view of the pyramid have been provided. The pyramid has been put on page one for question 23(a) and the four shapes labelled A to D have been put on page two for question 23(a). Question changed to 'Look at the model or at the diagrams for Question 23(a) in the Diagram Book. They are shown on two pages in the Diagram Book. Page one shows a solid square-based pyramid, VABCD. The base of the pyramid is a square of side 6 cm. The height of the pyramid is 4 cm. M is the midpoint of BC and VM = 5 cm. Page two for Question 23 shows four shapes, labelled A, B, C and D. Each square represents a one centimetre square. Which shape shows the accurate front elevation of the pyramid from the direction of the arrow?' [See below for diagram]	Award 1 mark for an answer of D Award 2 marks for an answer of C NB: Accept any other unambiguous indication of the answer such the diagram indicated by circling etc.

Paper: 1MA1/1H			
Question		**Modification**	**Mark scheme notes**
5			See above for question 5 mark scheme.

Paper: 1MA1/1H			
Question		**Modification**	**Mark scheme notes**
6		Diagram enlarged. Crosses changed to solid dots. Wording changed to 'It shows a pattern made from four identical squares.'	Standard mark scheme
7		Question reversed. Diagram enlarged. Shading changed to dotty shading. Shapes R and S also drawn on the grid. Shapes labelled, shape R, shape S and shape T. Axis extended to go from minus 8 to 5. One unlabelled shape is provided. Wording added 'A cut out shape is available if you wish to use it.' New question wording 'Look at the diagram for Question 7 in the Diagram Book. It shows shape T, shape R and shape S on a grid. A cut out shape is available if you wish to use it. (a) Describe the single transformation that maps shape T to shape R. [1 mark] (b) Describe the single transformation that maps shape T to shape S. [1 mark].	(a) B1 for "a reflection in the line $x = -1$" (b) B1 for "rotation 180° about (−1, −2)" or "enlargement sf −1 centre (−1, −2)" Note: award either 0, 1 or 2 for Q7; do not award separate marks for (a) and (b) on MLP scripts.
10		Values in the table changed: Least height changed from 133 cm to 135 cm. Upper quartile changed from 157 cm to 160 cm. Median changed from 151 cm to 150 cm.	
10	(a)	Diagram enlarged. Wording added 'It shows a grid.' The axis label to the left of the horiz.axis.	Standard mark scheme
10	(b)	Question wording changed to, 'Work out an estimate for the number of these girls with a height between 135 cm and 160 cm'.	Standard mark scheme

Paper: 1MA1/1H			
Question		**Modification**	**Mark scheme notes**
11		Diagram enlarged. Dot at O made bigger. Dashed line added from OB and an angle arc has been marked labelled x^o.	Standard mark scheme
15	(a)	Braille only: *a* changed to *q* and *b* changed to *r*.	Standard mark scheme with *a* changed to *q* and *b* changed to *r* for Braille.
15	(b)	*x* changed to *y* – MLP only.	Standard mark scheme with *x* changed to *y* – MLP only.
18		Diagram enlarged. Wording changed to 'It shows'.	Standard mark scheme, but apply normal tolerance for MLP papers in taking readings.

Paper: 1MA1/3H

Question	Answer	Mark	Mark scheme	Additional guidance
1 (a)	n^8	B1	cao	
(b)	cd^3	M1	for partial simplification, eg c or d^3	May be seen as simplification in original fraction
		A1	for cd^3	Accept c^1d^3
(c)	$x > \frac{14}{5}$	M1	for $5x > 14$ or $5x = 14$ or critical value, $\frac{14}{5}$ oe	Must see carried out correctly, ie at least $5x > 7 \times 2$ not just intention seen. Allow other signs for this mark.
		A1	$x > \frac{14}{5}$ or $x > 2\frac{4}{5}$ or $x > 2.8$	

13	(a)	region identified	M1	for 2 of lines $x = 2$, $y = x + 3$, $2x + 3y = 6$ correctly drawn	Accept use of full or broken lines for all marks
			M1	for all 3 lines $x = 2$, $y = x + 3$, $2x + 3y = 6$ correctly drawn	
			M1	for region which satisfies at least 2 of the inequalities $x \leq 2$, $y \leq x + 3$, $2x + 3y \geq 6$	Award for clear intention, shading not needed.
			A1	for correct region identified	Award for clear intention, shading not needed.
	(b)	no supported with reason	B1	for no and reason, eg (2, 4) does satisfy $x + y \leq 6$ or (2, 4) lies on the boundary of the region satisfying the equality sign.	

Paper: 1MA1/3H				
Question	**Answer**	**Mark**	**Mark scheme**	**Additional guidance**

Question	Answer	Mark	Mark scheme	Additional guidance
17	Region shaded	M1	for two of the lines $2y + 4 = x$, $x = 3$, $y = 6 - 3x$ correctly drawn	Accept full or broken lines for all marks
		M1	for all three correct lines correctly drawn	
		A1	for a fully correct region indicated with all lines correct	Award for clear intention, shading not needed Diagram at end of mark scheme

Paper: 1MA1/2H

Question	Answer	Mark	Mark scheme	Additional guidance
1 (a)	$x > -1$	B1	cao	
(b)	Diagram drawn	C2	for a fully correct diagram, eg  	
		(C1	for drawing a line from −3 to 4 **or** (indep) for an open circle at 4 **or** (indep) for a closed circle at −3)	Condone arrow heads or line ending to denote the 'end' of the line

22	$x < -7, x > 8$	M1	for method to solve $x^2 - 49 > 0$ eg $(x + 7)(x - 7)$ **or** 7 **and** −7	accept use of = or incorrect inequality symbol for both the M marks
		A1	for $x < -7$ **and** $x > 7$	This may be implied by a suitable diagram
		M1	for method to solve $5x^2 - 31x - 72 > 0$ eg $(5x \pm 9)(x \pm 8)$ **or** $\frac{--31 \pm \sqrt{(-31)^2 - 4 \times 5 \times (-72)}}{2 \times 5}$ **or** 8 **and** −1.8 oe	
		A1	for $x < -1.8$ **and** $x > 8$	This may be implied by a suitable diagram
		A1	cao	

QUESTION 7 – Additional information NOT Exhaustive

Cost per litre in £: 27 × 0.85 (=22.95) "22.95" ÷ 18 (=1.275) 8 × 4.5 (=36) No **and** 40.8 ÷ "36" = 1.133.. (cost per litre in £ in Wales) compared to 1.275 (cost per litre in £ in Spain).	**Cost per litre in euros:** 27 ÷ 18 (=1.5) 8 × 4.5 (=36) 40.8 ÷ 0.85 (= 48) No **and** "48" ÷ "36" = 1.333.. (cost per litre in euros in Wales) compared to 1.5 (cost per litre in euros in Spain).
Cost per gallon in £: 40.8 ÷ 8 (=5.1) 27 × 0.85 (=22.95) 18 ÷ 4.5 (= 4) No **and** "22.95" ÷ "4" = 5.7375 (cost per gallon in £ in Spain) compared to 5.1(0) (cost per gallon in £ in Wales).	**Cost per gallon in euros:** 40.8 ÷ 0.85 (=48) "48" ÷ 8 (= 6) 18 ÷ 4.5 (=4) No **and** 27 ÷ "4" = 6.75 (cost per gallon in euros in Spain) compared to 6 (cost per gallon in euros in Wales). **Note:** "2" comes from 8 ÷ "4" or "36" ÷ 18
Cost of 8 gallons in £: 18 ÷ 4.5 (= 4) 27 × 0.85 (=22.95) "22.95" × "2" (=45.90) No **and** 45.90 (total cost in £ in Spain) compared to 40.80 (total cost in £ in Wales given).	**Cost of 8 gallons in euros:** 18 ÷ 4.5 (=4) 40.8 ÷ 0.85 (=48) 27 × "2" (= 54) No **and** 54 (cost for 8 gallons in euros in Spain) compared to 48 (cost of 8 gallons in euros in Wales).
Cost of 18 litres in £: 8 × 4.5 (= 36) 40.8 ÷ "2" (= 20.4) 27 × 0.85 (= 22.95) No **and** 22.95 (cost for 18 litres in £ in Spain) compared to 20.40 (cost of 18 litres in £ in Wales). **OR** 18 ÷ 4.5 (= 4) 27 × 0.85 (= 22.95) 40.8 ÷ "2" (= 20.4) No **and** 22.95 (cost for 18 litres in £ in Spain) compared to 20.40 (cost of 18 litres in £ in Wales).	**Cost of 18 litres in euros:** 18 ÷ 4.5 (=4) 40.8 ÷ 0.85 (=48) "48" ÷ "2" (= 24) No **and** 24 (cost for 18 litres in euros in Wales) compared to 27 (cost of 18 litres in euros in Spain given). **OR** 8 × 4.5 (= 36) 40.8 ÷ "2" (= 20.4) "20.4" ÷ 0.85 (= 24) No **and** 24 (cost for 18 litres in euros in Wales) compared to 27 (cost of 18 litres in euros in Spain given).

Modifications to the mark scheme for Modified Large Print (MLP) papers: 1MA1 2H

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme. Notes apply to both MLP papers and Braille papers unless otherwise stated.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5°
Measurements of length: ±5 mm

PAPER: 1MA1_2H			
Question		**Modification**	**Mark scheme notes**
1	(b)	The letter *x* changed to *y*.	Standard mark scheme but note change of letter.
2		Wording added 'Look at the diagram for Question 2 in the Diagram Booklet. It shows shape S and shape T on a grid. A cut out shape may be available if you wish to use it.' Cut out shape provided. Diagram enlarged. Shading changed. The axes labels moved to the top of the vertical axis and to the right of the horizontal axis. Open headed arrows. The shapes labelled as 'shape T' and 'shape S'.	Standard mark scheme
9		The frame removed from the formula.	Standard mark scheme
10	(a)	Wording added 'Look at the diagram for Question 10(a) in the Diagram Booklet. It is a box plot which shows…'. The values changed so that they can be on grid lines. The least value changed to 50; lower quartile changed to 150; greatest value changed to 450. Diagram enlarged. Small squares removed. The horizontal axis label moved to the left of the horizontal axis. The grid cut at 500. The wording '…lies between 160 000 and 350 000' removed and replaced by '…lies between 150 000 and 350 000'.	Standard mark scheme but explanation should reference the adjusted figures. 160 now 150 350 still 350 IQR now 200 (000)
10	(c)	Wording added 'The table below shows…'. Wording added 'Look at the diagram for Question 10(b) in the Diagram Booklet.' The wording 'On the grid below,' removed and replaced by 'On the grid in the Diagram Booklet,'. The values changed so that they can be plotted on grid lines. The least value changed to 50; LQ changed to 100; median changed to 150; UQ changed to 250. Diagram enlarged. Small squares removed. The horizontal axis label moved to the left of the horizontal axis. The grid cut at 500.	Standard mark scheme but explanation should reference the adjusted figures. Median Range IQR Online 190 400 200 Shop 150 300 150

PAPER: 1MA1_2H			
Question		**Modification**	**Mark scheme notes**
13		The question reversed and the candidate asked to describe the transformation instead of drawing. The shape drawn on the grid at the points (4, 8), (6, 4), (10, 4) and (12, 8) and labelled 'shape B'. The original shape labelled 'shape A'. Wording added 'Look at the diagram for Question 13 in the Diagram Booklet. It shows shape A and shape B on a grid. Shape A has been mapped onto shape B. Describe fully the single transformation that maps shape A onto shape B'. The grid cut at $x = -7$ and $x = 13$. The grid cut at $y = -6$ and $y = 9$. Diagram enlarged. Open headed arrows. Shading changed. The axes labels moved to the top of the vertical axis and to the right of the horizontal axis. 3 answer lines provided.	B2 for a complete answer containing all three aspects: enlargement, (scale factor) −2, (centre of enlargement) origin or (0,0) (B1for a partial answer containing two of the three aspects listed above). Award no marks if more than one transformation is given.
16		Wording added 'Look at the diagram for Question 16 in the Diagram Booklet. It shows an incomplete Venn diagram.' In part (a) wording added 'Complete the Venn diagram in the Diagram Booklet for this information.' Diagram enlarged. The circles relabelled as 'type A', 'type B' and 'type C'. Braille: In the Venn diagram, add (i), (ii), (iii), (iv), (v), (vi), (vii) & (viii) in the blank spaces. Also add "Ans: (i) __ (ii) __ (iii) __ (iv) __ (v) __ (vi) __ (vii) __ (viii) __"	Standard mark scheme

PAPER: 1MA1_2H			
Question		**Modification**	**Mark scheme notes**
17		Wording added 'Look at Diagram 1, Diagram 2 and the formulas for Question 17 in the Diagram Booklet. You may be provided with a model for the question and additional formula models.' The wording '…to make the solid T shown below' removed and replaced by '…to make the solid T as shown by Diagram 1 and the model'. Model provided. Formula models provided. Diagram 2 to show a 2D diagram of solid T. Diagrams enlarged. Open headed arrows. The dashed lines made longer and thicker. The frame removed from the formulas. Wording added 'You may be provided with a model.' below the formulas. Wording added 'Diagram 2 is a simplified 2D diagram of solid T. 'The total vertical height…' Braille: Add the sentence "Separate models are provided to accompany these formulae."	Standard mark scheme
18		Wording added 'Look at the diagram for Question 18 in the Diagram Booklet. It shows triangles PQR and QRS which have a common side QR.' Wording added: 'PQ = 11 cm PR = 9.4 cm angle QPR = 27° angle QRS = 88° angle RSQ =41°'. Diagram enlarged. The angles moved outside of the angle arcs and the angle arcs made smaller.	Standard mark scheme
20		Wording added 'Look at the diagram for Question 20 in the Diagram Booklet.' Wording added: 'Angle BOD = 132° Angle CED = 16°' Diagram enlarged. The angles moved outside of the angle arcs and the angle arcs made smaller.	Standard mark scheme

PAPER: 1MA1_2H			
Question		**Modification**	**Mark scheme notes**
21	(a)	Wording added 'Look at the diagram for Question 21(a) in the Diagram Booklet. It shows the graph of $y = f(x)$ on a grid.' Wording removed 'The graph of $y = f(x)$ is shown on the grid below.' Diagram enlarged. The axes labels moved to the top of the vertical axis and to the right of the horizontal axis. Wording added 'On the grid in the Diagram Booklet,'.	Standard mark scheme
21	(b)	Wording added 'Look at the diagram for Question 21(b) in the Diagram Booklet. It shows a sketch…'. Diagram enlarged. The axes labels moved to the top of the vertical axis and to the right of the horizontal axis. The dashed lines made longer and thicker. The wording 'shown on the graph above' removed and replaced by 'shown on the graph in the Diagram Booklet'.	Standard mark scheme

16	$y \geq 3x + 6$	M1	for $y = 6$ indicated **or** $x = -3$ indicated	Accept any inequality in place of "=" for all method marks
	$x \geq -3$	M1	for $y = 3x + 6$ oe indicated	Equations/inequalities may be seen on the diagram
	$y \geq -\frac{x}{2} + 1$	M1	for $y = -\frac{x}{2} + 1$ oe indicated	
	$y \leq 6$	A1	for $y \geq 3x + 6$ oe, $x \geq -3$, $y \geq -\frac{x}{2} + 1$ oe and $y \leq 6$	

Paper: 1MA1/2H

11	5, 6, 7	M1 A1	for identification of possible values of x (4,5,6,7) or of y (5,6,7,8,9) cao	Could be shown on a number line or using a Venn diagram This mark can be awarded for an answer of 4, 5, 6, 7 Answers may be given in any order.

Question	Answer	Mark	Mark scheme	Additional guidance
24	$-2.5 < x < \frac{4}{3}$	M1	for method to find the critical values of $4x^2 - 25 < 0$ eg $(2x + 5)(2x - 5)$ or critical values -2.5 and 2.5 oe	accept use of = or incorrect inequality symbol for 1st and 3rd M marks
		M1	(dep on M1) for $x > -2.5$ **and** $x < 2.5$ or $x > a$ **and** $x < b$ where a and b are their critical values and $a < b$	This may be implied by a suitable diagram
		M1	for method to find the critical values of $12 - 5x - 3x^2 > 0$ or $3x^2 + 5x - 12 < 0$ eg $(4 - 3x)(x + 3)$ or $(3x - 4)(x + 3)$ $\frac{--5 \pm \sqrt{(-5)^2 - 4\times(-3)\times 12}}{2\times(-3)}$ or $\frac{-5 \pm \sqrt{5^2 - 4\times 3\times(-12)}}{2\times 3}$ $3\left[\left(x + \frac{5}{6}\right)^2 - \left(\frac{5}{6}\right)^2\right] - 12 = 0$ oe or critical values -3 and $\frac{4}{3}$ oe	
		M1	(dep on previous M1) for $x > -3$ **and** $x < \frac{4}{3}$ or $x > c$ **and** $x < d$ where c and d are their critical values and $c < d$	This may be implied by a suitable diagram
		A1	for $-2.5 < x < \frac{4}{3}$ oe eg $x < \frac{4}{3}$, $x > -2.5$	A correct answer with no supportive working gets 0 marks

Modifications to the mark scheme for Modified Large Print (MLP) papers: 1MA1 1H

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme. Notes apply to both MLP papers and Braille papers unless otherwise stated.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5º
Measurements of length: ±5 mm

PAPER: 1MA1_1H			
Question		**Modification**	**Mark scheme notes**
4		Table enlarged and left aligned. Black outline and tracking lines added. Values changed in the table: 8 changed to 5; 24 changed to 25; 13 changed to 15; 11 changed to 10; 4 changed to 5 Wording 'Draw' removed and replaced with 'Look at the diagram for Question 4 in the Diagram Booklet. It shows a blank grid. On the grid, draw'. Wording 'this' removed and replaced with 'the'. Axes labels moved to the top of the vertical axis and to the left of the horizontal axis. Right axis labelled. Grid enlarged and small squares removed. Grid lines made black. Open headed arrows.	Standard mark scheme but note the change in points to be plotted.
5		Wording added 'Look at the diagram for Question 5 in the Diagram Booklet. It shows an incomplete Venn diagram.' Wording added 'in the Diagram Booklet'. Diagram enlarged. Labels changed to 'set A' and 'set B'. For Braille add "Ans: (i) __ (ii) __ (iii) __ (iv) __"	Standard mark scheme
6		Wording added 'Look at the diagram for Question 6 in the Diagram Booklet. It shows a scatter graph with'. Wording removed 'The scatter graph shows'. Axes labels moved to the top of the vertical axis and to the left of the horizontal axis. Right axis labelled. Grid enlarged and small squares removed. Grid lines made black. Open headed arrows. Crosses changed to dots.	
6	(b)	Wording added 'in the Diagram Booklet'. Value changed from 5.8 kg to 6.0 kg.	B2 for an answer in the range 2.5 to 4.5 (B1 for a suitable line of best fit drawn **or** for a point on the grid at (x, 6) where x lies between 2.5 and 4.5 **or** a horizontal line drawn from 6 across to (x, 6) where x is in the range 2.5 to 4.5)

8		Wording added 'Look at the diagram for Question 8 in the Diagram Booklet. You may be provided with a model. They are NOT accurate. They show'. Wording removed 'The diagram shows'. Diagram enlarged. A floor added to the diagram, labelled 'Floor' to match the model provided. Label '40 cm' changed to 'height 40 cm'. Dashed lines made longer and thicker. Formula moved to top left of the diagram and frame removed. Model provided.	Standard mark scheme
9		Wording added 'Look at the diagram for Question 9 in the Diagram Booklet. It shows two intersecting straight lines on a grid.' Equations moved outside the grid. Grid enlarged. Grid lines made black. Open headed arrows. Graph lines made thicker. Axes labels moved to the top of the vertical axis and to the right of the horizontal axis.	Standard mark scheme
10		Wording added 'Look at the diagram for Question 10 in the Diagram Booklet. It shows a pentagon ABCDE'. Diagram enlarged. Angles moved outside angle arcs and angle arcs made smaller. Wording added 'Angle EAB = 120°; Angle BCD = 110°; Angle CDE = 135°'	Standard mark scheme
12		Wording added 'Look at the diagram for Question 12 in the Diagram Booklet. It shows a probability tree diagram'. Diagram enlarged	Standard mark scheme
16		Wording added 'Look at the diagram for Question 16 in the Diagram Booklet. You may be provided with two models. Model 1 is a sphere. Model 2 is made from two hemispheres showing the radius r. They are NOT accurate. The diagram shows a sphere.' Wording removed 'Here is a sphere'. Diagram enlarged. Dashed lines made longer and thicker. Radius label moved to the left. Open headed arrows. Formula moved to the top left of the diagram and frame removed.	Standard mark scheme
17		Change 'x' to 'y'. Change 'y' to 'x'.	Standard mark scheme but note the change in letters.
21		Wording added 'Look at the diagram for Question 21 in the Diagram Booklet.' Diagram enlarged. Angles moved outside angle arcs and angle arcs made smaller. Centre dot enlarged. Wording added 'Angle ABO = 51°; Angle BOD = 64°'	Standard mark scheme

22		Wording added 'Look at the diagram for Question 22 in the Diagram Booklet. You may be provided with a model. They are NOT accurate. They show a cuboid ABCDEFGH.' Wording removed 'ABCDEFGH is a cuboid'. Diagram enlarged. Dashed lines made longer and thicker. Dimensions added to the diagram. For Braille: Wedge added at FCA, marked **y**. Sentence changed to "Work out the size of the angle y, between FC and the plane ABCD."	Standard mark scheme

Question	Answer	Mark	Mark scheme	Additional guidance
4 (a)	4	B1	cao	
(b)	correct diagram	C2	for a fully correct diagram, eg 	
		(C1	for drawing a line from –4 to 1 **or** (indep) for an open circle at 1 **or** (indep) for an closed circle at –4)	Condone arrow heads or line ending to denote the 'end' of the line
(c)	$g < 25$	M1	for a correct first step, eg adding 4 to both sides, eg $\frac{2}{5}g < 6 + 4$ **or** multiplying throughout by 5, eg $2g - 4 \times 5 < 6 \times 5$ **or** dividing throughout by 2, eg $\frac{1}{5}g - 4 \div 2 < 6 \div 2$	Allow use of any inequality or as an equation for both method marks $\frac{2}{5}g < 10$ $2g - 20 < 30$ $\frac{g}{5} - 2 < 3$
		M1	for a correct second step, eg $2g <$ "10" $\times 5$ or $\frac{1}{5}g <$ "10" $\div 2$ **or** $2g <$ "30" + "20" or $g -$ "20" $\div 2 <$ "30" $\div 2$ **or** $\frac{g}{5} <$ "3" + "2" or $g -$ "2" $\times 5 <$ "3" $\times 5$ **or** showing 25 oe as the critical value	$2g < 50$ $\frac{g}{5} < 5$ $g - 10 < 15$ Can be written as $g = 25$
		A1	for $g < 25$ oe	

Paper: 1MA1/2H

4 (a)	Explanations	C2	for two different correct explanations **Acceptable examples** She should have a solid/full/shaded/coloured circle at 4 It does not show that x could be equal to 4 She should have marked/drawn a (clear/empty) circle at −3 The line should be drawn to –3 Jenna started from –2 not –3 **Not acceptable examples** Both circles should be black One circle should be filled in (needs to say which circle) She shouldn't have to reach number 4 Jenna has made no mistakes	Any incorrect statement as part of a correct response can be ignored unless it contradicts the statement,
		(C1	for one correct mistake described)	

Paper: 1MA1/3H				
Question	**Answer**	**Mark**	**Mark scheme**	**Additional guidance**
(b)	4	M1	for a correct first step, eg for adding 7 to both sides $5y - 7 + 7 < 16 + 7$ or for dividing throughout by 5 eg $\frac{5y}{5} - \frac{7}{5} < \frac{16}{5}$ **or** for showing 4.6 (oe) as the critical value **or** for $5 \times 4 - 7$ with 13 seen as answer	Allow use of any inequality or as an equation for the first mark Award 1 mark for 4.6 oe, eg $y = \frac{23}{5}$ or $y < 4.6$
		A1	for 4 or $y = 4$ with no incorrect working	An answer of 4 from incorrect working can score 1 mark at most.

13	Correct region **R**	M1 M1 C1	for at least two correct boundaries, eg $y = -3$ or $x = 2$ or $y = 2x + 1$ or $3x + 2y = 6$ for the remaining two correct boundaries **or** a third correct boundary with shading correct with the inequalities for at least two correct boundaries for a correct region (**R**) clearly identified	

Paper: 1MA1/2H

Question	Answer	Mark	Mark scheme	Additional guidance
15 (a)	Region shown	B4	for a fully correct region identified	See diagram at end of mark scheme Can exclude $y = 3x - 2$ for B4
		(B3	for drawing three correct lines)	Condone solid lines for all marks Region can be identified by shading in or shading out
		(B2	for drawing two correct lines, must include at least one of $x + y = 5$ or $y = 3x - 2$)	Lines need to be long enough to enclose the region
		(B1	for drawing $x = 2$ **and** $y = 1$ correctly **OR** for drawing $x + y = 5$ correctly **OR** for drawing $y = 3x - 2$ correctly)	
(b)	$y < 3x - 2$	B1	(dep on B1 in (a)) for $y < 3x - 2$ or ft their diagram if 1 line is redundant	Condone use of '=' or '$\leqslant$' and $3x - 2$

Paper: 1MA1/2H

GCSE

Mark Scheme

Mathematics A (1387)

June 2003

Edexcel
Success through qualifications

Edexcel is one of the leading examining and awarding bodies in the UK and throughout the world. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers.

Through a network of UK and overseas offices, Edexcel's centres receive the support they need to help them deliver their education and training programmes to learners.

For further information please call our Customer Response Centre on 0870 240 9800, or visit our website at www.edexcel.org.uk.

June 2003

Publications Code UG014129

All the material in this publication is copyright
© London Qualifications Ltd 2003

CONTENTS

Notes on Marking Principles 2
Paper 5501 4
Paper 5502 11
Paper 5503 17
Paper 5504 24
Paper 5505 32
Paper 5506 40

NOTES ON MARKING PRINCIPLES

NOTES ON MARKING PRINCIPLES

1 Three types of mark are available

M marks - awarded for correct working seen or implied.
A marks - conditional accuracy marks which are awarded for accurate working following the award of M marks.
B marks - unconditional accuracy marks (independent of M).

2 Abbreviations

cao - correct answer only.
ft - follow through.
√ - Denotes a "follow through" answer.

SC - special case.
isw - ignore subsequent working.
oe - or equivalent (and appropriate).
NB: a candidate cannot benefit from both isw and ft.

3 If no working shown, then

correct answers normally score full marks
incorrect (even though nearly correct) answers score no marks.

4 Marking instructions

Misread loses A marks (and sometimes B marks) on that part but ft can be allowed on subsequent parts. M marks can still be earned. If in doubt contact your team leader.
If there is a wrong answer in the answer space DO CHECK the working in the body of the script.

- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.
- If there is a wrong answer in the answer space DO CHECK the working in the body of the script.
- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.

5 Style of marking

Answer correct: tick and write part mark in margin NEXT TO BRACKETED MARK.
Answer incorrect: cross, but show M, A or B marks if any earned in body of script and transfer the total of these to the margin next to the bracket mark.
Total for each double page at bottom right page (except for back if used), FINAL TOTAL IN RELEVANT BOX ON FRONT COVER.
Nought in margin for fully incorrect question or page AND FOR NO ATTEMPT.
Where no attempt has been made a line should be put in the answer space and zero in the margin next to the bracketed mark
CHOICE OF METHOD – No marks unless one answer is in answer space – then mark that.
CROSSED OUT WORK - if not replaced this should be marked (if legible).
There must always be a mark next to bracketed mark in the margin/

6 Follow Through Marks

Follow throughs are guided by two principles:

(a) Follow throughs which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous, do not award.
(b) Follow throughs which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

7 Probability

Probability answers must be given as fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least two decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.

8 Linear Equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

9 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

Paper 5501

No	Working	Answer	Mark	Notes
1 (a)		46	1	B1 cao
(b)		3.4	1	B1 oe
(c)		Arrow at 430	1	B1 allow ± half graduation
(d)		Arrow at 3.7	1	B1 allow ± half graduation Accept indications other than arrows as long as they are clear
2		1.60 2.05	2	B1) Condone B1) reversal
3 (a)	$\frac{18}{24}$ or $\frac{9}{12}$ or $\frac{6}{8}$	$\frac{3}{4}$	2	B2 for $\frac{3}{4}$ cao (B1 for $\frac{18}{24}$ or $\frac{9}{12}$ or $\frac{6}{8}$) SC B1 for $\frac{1}{4}$ only
(b)		16 squares shaded	1	B1 cao
4 (a)		line	1	B1 within overlay tolerance
(b)		midpoint	1	B1 within overlay tolerance ft from (a) ± 0.2cm
(c)		rectangle	1	B1 for rectangle 6 cm ± 0.2cm by 4 cm ± 0.2cm
5		kilograms, kg litre, *l* or cubic metres, m^3 inches, in	3	B1 B1 B1
6 (a)		parallel lines marked	1	B1
(b)		right angle marked	1	B1
(c)(i)		acute	1	B1
(ii)		reflex	1	B1

Paper 5501

No	Working	Answer	Mark	Notes
7 (i)		sphere	1	B1
(ii)		cylinder	1	B1 Accept circular prism
(iii)		pyramid	1	B1 Condone omission of "triangular" Accept tetrahedron
8 (a)(i)		40	2	B1 cao
(ii)		50		B1 cao
(b)		5 complete symbols	1	B1 cao
(c)		 and oe inc	1	B1
9 (i)		9, 37, 56, 59, 75	5	B1 cao
(ii)		0.067, 0.56, 0.6, 0.605, 0.65		B1 cao Ignore trailing zeros
(iii)		–10, –6, –4, 2, 5		B1 cao
(iv)		$\frac{2}{5}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$		B2 for all 4 correct (B1 for any 3 in correct order) SC B1 for all 4 in reverse order (applies to(iv) only)
10 (a)			1	B1
(b)		Plotting (4, 24)	1	B1 ft from their matchsticks
(c)		60	1	B1 cao
(d)		$m = 6n$	2	B2 for $m = 6n$ oe (B1 for $6n$ oe or m = multiple of n except $m = n$)
11 (i)		6, 12	4	B1 cao
(ii)		4, 16		B1 cao
(iii)		3, 4, 6 or 3, 4, 6, 12		B1 Condone omission of 12
(iv)		8, 27		B1 cao

Paper 5501

No	Working	Answer	Mark	Notes
12		2.43	4	B1 for 36 or 0.36 B1 for 96 or 0.96 B1 for 125 or 1.25 If none of first 3 B1s awarded then SC B1 for four 24s and five 25s seen OR 4 × 24 and 5 × 25 seen B1 for 2.43 cao
13 (a)(i)		Edinburgh and Plymouth	3	B1 for Edinburgh or −7 B1 for Plymouth or 5
(ii)		12		B1ft from (i) if one positive and one negative
(b)		Cardiff and Belfast London and Plymouth	2	B1 for Cardiff and Belfast OR −6 and −4 B1 for London and Plymouth OR 3 and 5
14		5 9 8	3	B1 cao B1 cao B1 cao
15 (a)			2	✓ / × / 2 / 0 / B2 1 / 0 / B1 1 / 1 / B1 2 / 1 / B1
(b)	$2\times2\times2$	8	2	M1 for $2\times2\times2$ A1 for 8 cao
16 (a)		30	1	B1 cao
(b)		3	1	B1 cao
(c)	$2 \times 29 = 58$ $5 \times 30 = 150$ $2 \times 31 = 62$ $1\times32 = 32$ $\frac{302}{10} = 30.2$	30.2	3	M1 for freq × no pins M1 (dep on 1st M1) for totalling and ÷ 10 A1 for 30.2 cao

Paper 5501

No	Working	Answer	Mark	Notes
17		7 5 5 13 33 52 23	3	B3 all correct (B2 for 4, 5 or 6 correct B1 for 2 or 3 correct)
18 (a)(i) (ii) (iii) (iv) (b)		$4c$ p^4 $8g$ $10pr$ OR $10rp$ $10y - 15$	4 1	B1 oe B1 cao B1 oe B1 B1 cao Accept $10y + - 15$
19		$\frac{2}{3}$	3	M1 for 3 rows (9 squares) shaded M1 for 2 columns (10 squares) shaded A1 for $\frac{2}{3}$
	$\frac{3}{5} = \frac{9}{15}$ $\frac{2}{3} = \frac{10}{15}$	$\frac{2}{3}$	3	M1 for $\frac{3}{5} = \frac{9}{15}$ M1 for $\frac{2}{3} = \frac{10}{15}$ A1 for $\frac{2}{3}$
	$\frac{3}{5} = 0.6$ $\frac{2}{3} = 0.66$ or 0.67 or better	$\frac{2}{3}$	3	M1 for $\frac{3}{5} = 0.6$) Accept M1 for $\frac{2}{3} = 0.66$ or 0.67 or better) percentages A1 for $\frac{2}{3}$

Paper 5501

No	Working	Answer	Mark	Notes
20 (a)	955 × 48 7640 38200 45840 OR 48 × 955 240 2400 43200 45840	458.40	3	M1 for complete correct method (condone one computational error) A2 for 458.40 cao (A1 for digits 4584 OR ft if M1 awarded)
(b)	14. 5 48 | 696. 0 48 216 192 24 0 24 0	14.50	3	M1 for 1 as first digit in answer and remainder 21 M1 (dep) 4 as second digit in answer A1 for 14.50 (Accept 14.5)
21 (a)		$12x$	1	B1 oe
(b)		$12x + 10y$	2	B2 oe ft from (a) (B1 $12x$ + multiple of y or $10y$ seen) SC B1 for $x = 12x + 10y$ OR $y = 12x + 10y$

Paper 5501

No	Working	Answer	Mark	Notes
22	$\frac{1}{3}+\frac{1}{4}=\frac{4}{12}+\frac{3}{12}=\frac{7}{12}$ $1-\frac{7}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	M1 for $\frac{4}{12}$ **and** $\frac{3}{12}$ oe A2 for $\frac{5}{12}$ oe (A1 for $\frac{7}{12}$) B1 for 1–"$\left(\frac{1}{3}+\frac{1}{4}\right)$" correctly evaluated
	$1-\frac{1}{3}=\frac{2}{3}$, $1-\frac{1}{4}=\frac{3}{4}$ $\frac{8}{12}-\frac{3}{12}=\frac{5}{12}$ or $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	B1 for $\frac{2}{3}$ or $\frac{3}{4}$ seen M1 for $\frac{8}{12}-\frac{3}{12}=\frac{5}{12}$ or $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}$ A1 for $\frac{5}{12}$ oe
		$\frac{5}{12}$	3	M1 for 0.25 and 0.33 or better A1 for 0.58 or better A1 for $0.41\dot{6}$ or recurring
23 (a) (b)(i) (ii)	 180 – (54 + 54)	54 72 Reason	1 3	B1 cao M1 for 180 – (54 + 54) A1 ft from (a) if $x < 90$ B1 for mentioning isosceles and equal or base angles or equal sides and equal or base angles

Paper 5501

No	Working	Answer	Mark	Notes
24 (a)		Bryani	2	M1 for 4×9 or $4 \times 3 \times 3$ or $4 \times x \times x$ or square x first or square 3 first A1 SC 4×3^2 with Bryani scores B2
(b)		64	1	B1 cao
25 (a)		 dotted line may be solid	3	B2 for rectangle base 3 squares and height 4 squares (B1 for rectangle with one correct dimension) B1 for horizontal line 1 cm from top) SC B2 for completely correct elevation on its side
(b)			2	B2 for perspective drawing showing slant face and cutout B1 for perspective drawing with either slant face cutout omitted
26 (a)	20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$	40	2	M1 for 20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$ A1 cao
(b)	$\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes	line from (45, 20) to (65, 0)	2	M1 for $\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen A1 for correct line SC If M0, B1 for line from (45, 20) to (t, 0) where $t > 45$ or B1 for a line of the correct gradient.

Paper 5502

No	Working	Answer	Mark	Notes
1 (a)		$\frac{7}{100}$	1	B1 cao accept 0.07
(b)		0.18	1	B1 cao
(c)	20 in 100 oe	40	2	M1 for sight of 20 in 100 or 20 × 2 A1 cao
2 (a)		6cm	2	B1 for 6 ± 0.2 or 60 ± 2 B1 indep for cm or mm consistent with 1st B1
(b)		At centre	1	B1 within overlay
(c)		Circle drawn	1	B1 all within overlay
3		See diagram	3	B3 all correct – see separate sheet (B2 for 3 correct B1 for 2 correct)
4 (a)		$\frac{1}{4}$ oe	1	B1 cao
(b)		0.75	1	B1 cao
(c)		75%	1	B1 cao
(d)(i)		9	2	B1 accept answer in range 9 - 9.2
(ii)		15 - 16		B1 accept answers in range15 - 16
5 (a)		9:30	1	B1 cao
(b)		2hrs 45 min	2	B2 for 2hr 45 min or 2 $\frac{3}{4}$ hr or 165 minutes B1 2:45 or 2.45 or 165 or 45min + 1hr + 1hr oe
(c)		17	1	B1 cao
6 (a)	96 × 4	3.84	2	M1 for 96 × 4 or digits 384 A1 cao
(b)	3 × 96 + 40 = 328	(0).56	2	M1 for 3 × 96 + 40 or digits 328 or digits 56 A1 cao accept 56p

Paper 5502

No	Working	Answer	Mark	Notes
7 (a)		54 000	1	B1 cao accept 54 thousand
(b)		50 000	1	B1 (accept ten thousand or 10 000) oe
8 (a)		14	1	B1 cao
(b)		6	1	B1 cao
(c)		Correct reflection	2	B2 fully correct (B1 correct reflection in a line parallel to the mirror line or condoning 1 block error in shape or position of shape)
9 (a)		Missing horiz label 1 (and 6) missing on vertical scale	2	B1 B1
(b)		Correct graph	2	B1 for bar up to 4 for yellow B1 for bar up to 2 for green
(c)		Blue	1	B1 cao
(d)	3 + 5 + 4 + 2	14	1	B1 ft from (b)
(e)		$\frac{3}{14}$	1	B1 ft on '14'
10	Barry (8) because you double Kath (7) because you add, 1,2,3		2	B1 oe B1 oe SC: B1 for correct rules only
11 (a)		$2n$	1	B1 for $2n$ or $n + n$ OR $2 \times n$ OR $n \times 2$ OR $n2$
(b)		$2n + 15$	1	B1 for "$2n$" + 15 oe
(c)		20q	1	B1 cao
12 (a)	1 + 3 + 5 + 8 + 5	22	2	M1 add frequencies A1 cao
(b)		No, is>no of cups of coffee in the table	1	B1 'average cannot be bigger than 6' oe OR 'Average must be less than 6 oe'
13 (a)		Trapezium	1	B1 cao ignore spelling
(b)		(2, 3)	1	B1 cao
(c)		Isosceles	1	B1 cao ignore spelling
(d)		Q correct	1	B1 cao

Paper 5502

No	Working	Answer	Mark	Notes
14 (a)		250 000	1	B1 cao
(b)	$\frac{28}{4}$	7	2	M1 for $\frac{28}{4}$ oe or "250000" × 28 A1 cao **SC** B1 for 7 000 000
15 (a)		10	1	B1 cao
(b)		5.5	1	B1 ±0.3 pounds
(c)	$\frac{110}{22}$	50	3	M1 for use of graph at 11 or $\frac{110}{22}$ A1 for 5 A1 cao **SC** B2 for 49.5 – 50.6

Paper 5502

No	Working	Answer	Mark	Notes
16 (a)	$269.30 - 56.80 = 212.50$ $\frac{212.50}{42.50}$	6	2	M1 for $\frac{269.30 - 56.80}{42.50}$ or 5 seen A1 cao
(b)	5% of £269.30 £269.30 – "£13.465" OR $\frac{95}{100} \times 269.30$	255.83 or 255.84	3	M1 for $(5 \div 100) \times 269.30$ M1 for $269.30 - $ "13.465" A1 cao OR M2 for $\frac{95}{100} \times 269.30$ A1 cao **Alternative Method:** M1 for $\frac{5}{100} \times 56.80$ $(= 2.84)$ and $\frac{5}{100} \times 42.50$ (=2.12(5)) (OR 53.96 AND 40.38 (40.375) seen M1 for $56.80 -$ "2.84" (= 53.96) $42.50 -$ "2.12(5)" (= 40.375 or 40.38) "5" × "40.375" + "53.96" A1 cao
17	$4.1^2 \times 1.07 = 16.81 \times 1.07$	17.9867	2	M1 for ("4.1") followed by squaring, or sight of 16.81 A1 cao SC: *B1 for 18 or better with no working*
18 (a)		60	1	B1 cao
(b)	$360 - 60 - 90 - 90$	120	2	M1 for $360 -$ " 60 " $- 90 - 90$ or $180 -$ "60" A1 cao
(c)	6×2	12	2	M1 for 6×2 A1 cao for 12

Paper 5502

No	Working	Answer	Mark	Notes
19 (a)(i)	$240 \times 5 = 1200$	1250	3	B1 cao 1250
(ii)	$\frac{50}{'1250'}$	$\frac{1}{25}$		M1 cao $\frac{50}{'1250'}$ A1 for $\frac{1}{25}$ in its simplest form
(b)	$\frac{60}{100} \times 1000 = 600$	12:5	3	M1 for $\frac{60}{100} \times 1000$ oe A1 for 600 A1 cao
20 (a)		$x + 2$	1	B1 accept $2 + x$ but not $x = x + 2$
(b)	$x + 5 + x + 5 + x + 2 + x + 2$	$4x + 14$	2	M1 adding 4 sides, two of which are '$x + 2$' (all sides to be linear expressions in x) **SC** $x + 5 + x + 2 \times 2$ gets M1 A1 for correct simplified answer or $(20 - 14) \div 4$ oe gets M1
(c)	'$4x + 14$' = 20	1.5 oe	2	M1 for equation A1 cao
21	$\sum f = 90$	Angles drawn, labelled	3	M1 for 1 person = 4°or one angle correct in table or pie chart A1 any 2 correctly drawn angles in pie chart A1 fully correct chart labelled
22 (a)		$2p - q$	2	B1 cao for $2p$ B1 cao for $-q$ accept $(-q + 2p)$, $2p - 1q$ and $2p + -q$
(b)	$5x = 3 + 4$	1.4	2	M1 for either (+3 or sight of 7) or (÷ 5 or sight of 0.8 and 0.6) A1 cao accept $\frac{7}{5}$ or $1\frac{2}{5}$

Paper 5502

No	Working	Answer	Mark	Notes
23 (a)		$\frac{4\times5}{2}$	1	B1 cao
(b)	$1+2+3+4+5+6+7+8$	$\frac{8\times9}{2}$	1	B1 cao
(c)	$\frac{100\times101}{2}$	5050	1	B1 cao
24	0 | 5 7 8 8 1 | 0 0 0 0 2 5 5 5 6 2 | 0 0 0 4 5 3 | 3 5 Key 1 | 2 = 12 (min)	See working	3	B1 for stem 0, 1, 2, 3 or 0, 10, 20, 30 B1 for accurate unordered leaves condone 1 error or omission B1 for key and ordered leaves all correct
25	$3.2\times2.8=8.96$ $2\times4.5\times2.8=25.2$ $2\times4.5\times28.8=28.8$ $\frac{62.96}{2.5}\times2.99$	£75.30	5	M1 for area of any face found correctly M1 for 2 areas found correctly A1 for 62.96 or 54 M1 for $\frac{'62.96'}{2.5}\times2.99$ Al cao Alternate method for candidates who round up $\frac{"62.92"}{2.5}$ M1 for "26" × 2.99 A1 for £77.74 cao **SC**: *for top included B2 for 71.92 m^2 seen or* B3 for £86.02 seen **SC** B4 for £64.58 or £65.78 seen
26	$2.5\times10\,000$	25 000	2	M1 for $2.5\times100\times100$ A1 cao

Paper 5503

No	Working	Answer	Mark	Notes
1 (a)(i)		$8g$	2	B1 oe
(ii)		$10rp$		B1 for $10pr$ or $10\ rp$
(b)		$10y - 15$	1	B1 cao accept $10y$ - + 15
(c)	$6x + 8 - 12x + 15$	$-6x + 23$	2	M1 for 3 correct terms out of 4 A1 cao
2		$m = 6n$	2	B2 for $m = 6n$ oe accept $6 \times n$, n 6 (B1 for $6n$ alone, or $6n$ +1 oe OR m = multiple of n except $m = n$)
3 (i)		0.067, 0.56, 0.6, 0.605, 0.65	1	B1 cao Ignore trailing zeros
(ii)		$-10, -6, -4, 2, 5$	1	B1 cao
(iii)		$\frac{2}{5}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$	2	B2 all four correct (B1 any three in correct order) SC: B1 all 4 in reverse order
4		7 5 5 13 33 52 23	3	B3 all correct (B2 for 4, 5 or 6 correct entries) (B1 for 2, 3 correct entries)

Paper 5503

No	Working	Answer	Mark	Notes
5		$\frac{2}{3}$	3	M1 for 3 rows (9 squares) shaded M1 for 2 columns (10 squares) shaded A1
	OR $\frac{3}{5}=\frac{9}{15}$ $\frac{2}{3}=\frac{10}{15}$ Therefore $\frac{2}{3}>\frac{3}{5}$	$\frac{2}{3}$		M1 for $\frac{3}{5}=\frac{9}{15}$ M1 for $\frac{2}{3}=\frac{10}{15}$ A1
	OR $\frac{3}{5}=0.6$ or percent $\frac{2}{3}=0.66$ or 0.67 or better Therefore $\frac{2}{3}>\frac{3}{5}$	$\frac{2}{3}$		M1 for $\frac{3}{5}=0.6$ or percent M1 for $\frac{2}{3}=0.66$ or 0.67 or better A1
6	$2\times 29=58$ $5\times 30=150$ $2\times 31=62$ $1\times 32=32$ $\frac{302}{10}=30.2$	30.2	3	M1 for freq × no. pins (at least 3) M1 for totalling and for ÷ 10 (dep on 1st M1) A1 cao
7 (a)			2	B1 for 180° rotation (wrong centre) B1 cao
(b)			3	B1 for any enlargement sf other than 1 B1 for all sides halved B1 for position

Paper 5503

No	Working	Answer	Mark	Notes
8 (a)		$12x$	1	B1 oe
(b)		$12x + 10y$	2	B2 oe or ft from (a) (B1 for $12x$ + a multiple of y or $10y$ seen) **SC** B1 for $x = 12x + 10y$ or $y = 12x + 10y$
9	$\frac{1}{3}+\frac{1}{4}=\frac{4}{12}+\frac{3}{12}=\frac{7}{12}$ $1-\frac{7}{12}=\frac{5}{12}$ OR $1-\frac{1}{3}=\frac{2}{3}, 1-\frac{1}{4}=\frac{3}{4}$ $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}, \frac{8}{12}-\frac{3}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	M1 for $\frac{4}{12}$ and $\frac{3}{12}$ oe A2 for $\frac{5}{12}$ oe (A1 for getting $\frac{7}{12}$) (B1 for $1 - \frac{"1"}{3} + \frac{1"}{4}$ correctly evaluated) OR B1 for $\frac{2}{3}$ or $\frac{3}{4}$ seen M1 for $\frac{3}{4}-\frac{1}{3}=\frac{9}{12}-\frac{4}{12}$ or $\frac{2}{3}-\frac{1}{4}=\frac{8}{12}-\frac{3}{12}$ A1 for $\frac{5}{12}$ oe OR M1 0.25 and 0.33 or better A1 for 0.58 or better A1 for 0.416 *recurring*
10 (a)		54	1	B1 cao
(b)(i)	180 – (54 +54)	72	3	M1 for 180 – (“54” + “54”) A1 for 72° ft from (a) if $x < 90°$
(ii)				B1 for mentioning isosceles and equal or base angles or equal sides and equal or base angles

Paper 5503

No	Working	Answer	Mark	Notes
11 (a)	Bryani was correct $4 \times 3^2 = 4 \times 9 = 36$	Bryani	2	M1 for 4×9 or $4 \times 3 \times 3$ or "square the three/x then multiply by four" A1 Bryani **SC** 4×3^2 with Bryani gets B2
(b)			1	B1 cao
12 (a)			3	B2 for rectangle height 4 squares, base 3 squares (B1 for rectangle with one correct dimension) B1for line 1 square from the top **SC** B2 for completely correct elevation on its side
(b)			2	B2 for perspective drawing showing slant face and cut out (B1 for perspective drawing with either slant face or cut out omitted or one aspect incorrect)
13 (a)	20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$	40	2	M1 for 20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$ A1 cao
(b)	$\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen	Line from (45, 20) to (65, 0)	2	M1 for $\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen A1 for correct line **SC** If M0, B1 for line from (45, 20) to (t, 0) where $t > 45$ or a line of the correct gradient
14 (i)		119.31	3	B1 cao
(ii)		119 310		B1 cao
(iii)		1.23		B1 cao

Paper 5503

No	Working	Answer	Mark	Notes
15	$\frac{10}{100}\times 12000$ 12 000 – 1200 = 10 800 $\frac{10800}{10}=1080$ 10 800 – 1080 = £9720	£9720	3	M1 for $\frac{10}{100}\times 12000$ or sight of 1200 or 2400 or 10 800 or 9600 M1 (dep) for $\frac{10}{100}\times(12\,000-\frac{10}{100}\times 12000)$ or sight of 1080 A1 cao Alternative mark scheme M2 for $12000\times(1-\frac{10}{100})^2$ (M1 for $12000\times(1-\frac{10}{100})$ A1 cao
16 (a)	$2p = 6$	$p = 3$	2	M1 for $7p - 5p = 8 - 2$ or $2p$ or 6 A1 cao
(b)	$7r - 5r = -20 - 2$	-11	2	M1 for $7r + 2 = 5r - 20$ or $\frac{7r}{5} + \frac{2}{5} = r - 4$ or $7r - 5r = 20 - 2$ or $\frac{7r}{5} - r = -4 - \frac{2}{5}$ A1 cao
17		$5n + 1$	2	B2 oe (B1 for $5n$ seen) NB: n = gets B1 max

Paper 5503

No	Working	Answer	Mark	Notes
18 (a)	–1, 0, 1		2	B2 for –1, 0, 1 (B1 for –1, 0 or 0,1 or –1,1 or –2, -1, 0, 1 only)
(b)	(–1, –1), (0, –1), (1, –1), (0, 0), (1, 0), (1, 1)		3	B3 for 6 points correct B2 for 3 points correct B1 for 1 point correct **NB** –B1 each additional point over six
19 (a)	Triangle with vertices at (0,0) (0,–2) and (3,0)		2	M1 for correct orientation A1 cao
(b)	Rotation, 180°, centre (0,1) Enlargement sf - 1 centre (0,1)		2	B2 for 180° 'rotation' centre (0, 1) B2 for Enlargement sf - 1 centre (0,1) (B1 for any two of the three parts) NB: B0 if additional transformation is included
20	Bisector of $\angle BAC$ Arc around A Region		3	B3 cao (B2 for either two correct boundaries, no shading/ wrong shading or one correct boundary, one incorrect boundary with valid shading) (B1 for either two incorrect boundaries but one drawn from A and one intersection, with valid shading or one correct boundary) Ignore shading outside the triangle
21		Length Volume Area	3	B1 for Length B1 for Volume B1 for Area
22 (a)	Unbiased question with choices		2	B1 for unbiased question B1 for at least 2 choices
(b)			2	Classification 1: A biased question Classification 2: A restricted sample of people Classification 3: Not specifying a range of foods Classification 4: Nothing to do with eating habits B2 reasons which satisfy 2 different classifications (B1 a reason which satisfies one classification)



Paper 5503

No	Working	Answer	Mark	Notes
23 (a)	$6 \times 10^2 \times 8 \times 10^4$ 48×10^6	4.8×10^7	3	M1 for $6 \times 10^a \times 8 \times 10^b$ oe, a and b integers including 0 A1 for 48×10^6 oe A1 cao
(b)	200 000 + 30 000	230000	2	B2 cao (B1 for sight of 200 000 or 30 000 or 2.3×10^5 or 23×10^4)
24 (i)		64	4	B1 cao
(ii)		3		B1 cao
(iii)	$\sqrt{16 \times 9} = \sqrt{144}$	12		B2 cao (B1 for sight of $\sqrt{2^4} \times \sqrt{9}$ or better, or 144 seen)
25 (i)	Tangent 90° to diameter /radius/ line from (through) centre	27°	4	B1 for 27° cao B1 for reason
(ii)	180 –(90+ "27") angle in semicircle (is 90°)/Alternate segments /angle at centre twice at circumference	63°		B1 ft for 90–"27" if not 63° B1 for reason
26 (a)(i)		152	2	B1 cao
(ii)		177		B1 cao
(b)			3	B1 for median marked at 167 B1 ft for postion of box with its ends at "152" and "177" B1 for position of whiskers with ends at 132 and 182 NB: For any points plotted between 141 and 149 give a tolerance of an extra ± 1 square
27	$x^2 + xy + xy + y^2$	$x^2 + 2xy + y^2$	2	M1 for at least 3 of the 4 terms correct A1 cao
		25	2	M1 for recognising 3.47 + 1.53 (= 5) A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
1 (a)	$4.1^2 \times 1.07 = 16.81 \times 1.07$	17.9867	2	M1 for (4.1) followed by squaring, or sight of 16.81 A1 cao SC: B1 for 18 or better with no working
(b)		$(1.6 + 3.8 \times 2.4) \times 4.2$	1	B1 cao Allow additional brackets if they give an expression with value 45.024
2 (a)	269.30 – 56.80 = 212.50	6	2	M1 for $\frac{269.30 - 56.80}{42.50}$ or 5 seen A1 cao
(b)	5% of £269.30 £269.30 – "£13.465" OR $\frac{95}{100} \times 269.30$	255.83 or 255.84	3	M1 for $(5 \div 100) \times 269.30$ M1 (dep) for 269.30 – "13.465" A1 cao OR M2 for $\frac{95}{100} \times 269.30$ A1 cao **Alternative Method:** M1 for $\frac{5}{100} \times 56.80$ (= 2.84) and $\frac{5}{100} \times 42.50$ (=2.12(5)) (OR 53.96 AND 40.38 (40.375) seen M1 for 56.80 – "2.84" (= 53.96) 42.50 – "2.12(5)" (= 40.375 or 40.38) "5" × "40.375" + "53.96" A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
3 (a)		60	1	B1 cao
(b)	360 – 60 – 90 – 90	120	2	M1 for 360 – "60" – 90 – 90 or 180 – "60" A1 cao
(c)	6 × 2	12	2	M1 for 6 × 2 A1 cao 12
(d)		Correct drawing	2	B2 for triangle and construction lines (see overlay) (B1 for 1 line of length 4cm and correct arcs crossing OR for correct triangle with either no arcs or incorrect arcs) SC: B1 similar triangle drawn with construction lines
4 a(i)	240 × 5 = 1200	1250	3	B1 cao 1250
(ii)	$\frac{50}{1250}$	$\frac{1}{25}$		M1 $\frac{50}{"1250"}$ A1 oe in its simplest form
(b)	$\frac{60}{100} \times 1000 = 600$ 600: 250	12:5	3	M1 for $\frac{60}{100} \times 1000$ oe A1 for 600 A1 cao
5 (a)		$x + 2$	1	B1
(b)	$x + 5 + x + 5 + x + 2 + x + 2$	$4x + 14$	2	M1 adding 4 sides, two of which must be '$x + 2$' (all sides to be linear expressions in x) A1 for correct simplified answer
(c)	"$4x + 14$" = 20	1.5	2	M1 for equation "$4x + 14$" = 20 OR $\frac{20-14}{4}$ oe A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
6 (a)		$2p - q$	2	B1 cao for $2p$ B1 cao for $-q$ accept $-q + 2p$ and $2p - 1q$
(b)	$5x = 3 + 4$	1.4	2	M1 for either (+3 or sight of 7) or (÷ 5 or sight of 0.8 and 0.6) A1 cao accept $\frac{7}{5}$ or $1\frac{2}{5}$
7 (a)		$\frac{4\times5}{2}$	1	B1 cao
(b)	$1 + 2 + 3 + 4 + 5 + 6 + 7 + 8$	$\frac{8\times9}{2}$	1	B1 cao
(c)	$\frac{100\times101}{2}$	5050	1	B1 cao
(d)		$\frac{n(n+1)}{2}$	2	B2 cao (B1 for any quadratic in n)
8	$3.2 \times 2.8 = 8.96$ $2 \times 4.5 \times 2.8 = 25.2$ $2 \times 4.5 \times 3.2 = 28.8$ $\frac{62.96}{2.5} \times 2.99$	75.30	5	M1 for area of any face found correctly M1 for 2 areas seen A1 for 62.96 or 54 M1 for $\frac{'62.96'}{2.5} \times 2.99$ A1 cao Alternate method for candidates who round up $\frac{"62.96"}{2.5}$ M1 for "26" x 2.99 A1 for £77.74 cao SC: for top included B2 for 71.92 m^2 seen or B3 for £86.02 or £86.71 SC: B4 for £64.58 or £65.78 seen

Paper 5504

No	Working	Answer	Mark	Notes
9	2.5×10000	25000	2	M1 for 2.5×10000 or $2.5 \times 100 \times 100$ A1 cao
10 (a)	$\sum f = 90$ (88), 144, 32, 96	Angles drawn, labelled	3	M1 for 1 person = 4° or one angle correct in table or pie chart A1 any 2 angles correctly drawn in pie chart A1 fully correct chart labelled
(b)	$0.38 + 0.27 + 0.15$	0.20	2	M1 1 – sum A1 cao
11	0 | 5 7 8 8 1 | 0 0 0 0 2 5 5 5 6 2 | 0 0 0 4 5 3 | 3 5 Key 1 | 3 = 13 (min)	See working column	3	B1 for stem 0, 1, 2, 3 or 0, 10, 20, 30 B1 for accurate unordered leaves condone 1 error or omission B1 for key and ordered leaves all correct
12 (a)	$V = \pi \times 4^2 \times 10$	502 – 503	2	M1 for $\pi \times 4^2 \times 10$ A1 502 – 503
(b)	$P^2 = 10^2 + 8^2$ $P = \sqrt{164}$	$\sqrt{164} < 13$	3	M1 for sight of a correct right-angled triangle M1 for $10^2 + 8^2$ A1 for conclusion based on a correct calculation or 12.8 seen
13 (a)	2×30	$2 \times 2 \times 3 \times 5$	4	M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
	2×48	$2^5 \times 3$		M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
(b)		12	1	B1 cao
(c)	$2^5 \times 3 \times 5$	480	2	B2 cao B1 for $2^5 \times 3 \times 5$ or any correct common multiple

Paper 5504

No	Working	Answer	Mark	Notes
14 (a)		$150 < C \leq 200$	2	M1 use of cum freq to find the cost of the 20th or 20.5^{th} car OR $\frac{1}{2}\Sigma f$ or $\frac{1}{2}(\Sigma f + 1)$ A1 eg 150 to 200
(b)		No, because the 21st value is in the same interval	1	B1 20.5^{th} or 21st in same interval or an alternative correct explanation
(c)	80% = 5200 $\frac{5200}{80} \times 100$	6500	3	M1 for (100 – 20) % = 5200 M1 for $\frac{5200}{"80"} \times 100$ A1 cao
15 (a)	$x^2(x + 1) = 230$	AG	2	M1 for $x \times x \times (x+1)$ or $x \times x \times x + 1$ oe A1 cao from $x \times x \times (x+1)$
(b)	'5 – 150 5.1 – 158.7 5.2 – 167.6 5.3 – 177.0 5.4 – 186.6 5.5 – 196.6 5.6 – 207.0 5.7 – 217.7 5.8 – 228.8 5.9 –240.2 5.85 – 234.4	5.8	4	B 2 for trial between 5.8 and 5.9 inclusive (B1 for different trial between 5 and 6 inclusive) B1 for different trial between 5.8 and 5.85 (not including 5.8) B1 (dep on at least one previous B1) cao for 5.8, 5.81, 5.811

Paper 5504

No	Working	Answer	Mark	Notes
16	$\pi \times \left(\frac{15}{2}\right)^2 = 176.715$	88.4cm^2	3	M1 for $\pi \times \left(\frac{15}{2}\right)^2$ A1 88.3 – 88.4 B1(ind) for cm²
17 (a)	$5 = 0.5x + 1$	8	2	M1 for $5 = 0.5x + 1$ A1 cao
(b)		$y = \frac{1}{2}x + c$	1	B1 $y = \frac{1}{2}x + c$, c ≠ 1, oe
(c)		$x = 2y - 2$ OR $x = 2(y - 1)$	2	M1 for correctly multiplying both sides by 2 or correctly isolating $\frac{x}{2}$ A1 for $x = 2(y - 1)$, $x = \frac{y-1}{0.5}$, $x = \frac{y-1}{\frac{1}{2}}$ oe SC: B1 for $x = 2y - 1$
18	$4x - 6y = 22$ $15x + 6y = 54$ $19x = 76$	$x = 4,\ y = -1$	4	M1 for coefficients of x or y the same followed by correct operation , one arithmetical error A1 cao M1(dep on previous M mark) for sub for other variable A1 cao Trial and improvement –0 unless both x and y correct values found

Paper 5504

No	Working	Answer	Mark	Notes
19 (a)	$SF = \frac{10}{6}$ $\frac{10}{6} \times 4.8 = 8$	8	2	M1 for sight of $\frac{10}{6}$ or $\frac{6}{10}$ or 1.67 or better or $\frac{CD}{10} = \frac{4.8}{6}$ A1 cao
(b)	$\frac{10}{6} \times 4.5 - 4.5 = 3$	19.8	2	M1 for use of SF from (a) to find *BC* or *AC* and adding 4 sides A1 cao
20	$\frac{6 \times 10^{15}}{3.2 \times 10^{8}}$ 1.875×10^{7}	4.3×10^{3}	3	B3 for 4.3×10^{3} to 4.34×10^{3} (B2 for 1.875×10^{7} oe or 4300 to 4340 or final answer of 1.9×10^{7}) (B1 for sight of 6×10^{15} oe or 3.2×10^{8} oe)
21	$8.5 \times \tan 38 = 8.5 \times 0.7813$	6.64	3	M1 for correct use of trig, eg $\tan 38 = \frac{opp}{8.5}$ M1 for 8.5 × tan38 A1 6.64 – 6.641

Paper 5504

No	Working	Answer	Mark	Notes
22 (a)		No, as you would expect about 100. Yes, as it is possible to get 200 sixes with a fair dice	1	B1 for a consistent answer
(b)	$\frac{1}{6}, \frac{5}{6}$ + labels		3	B1 for $\frac{5}{6}$ on the red dice, *not six* branch B1 for a fully complete tree diagram with all branches labelled B1 for $\frac{1}{6}$, $\frac{5}{6}$ on all remaining branches as appropriate

Paper 5505

No	Working	Answer	Mark	Notes
1 (i) (ii) (iii)		119.31 119310 1.23	3	B1 cao B1 cao B1 cao
2	$\frac{10}{100}\times 12000 = 1200$ 12 000 – 1200 = 10 800 10 800 ÷ 10 =1080 10 800 – 1080 = £9720	9720	3	M1 for $\frac{10}{100}\times 12\,000$ or sight of 1200 or 2400 or 10 800 or 9600 M1 (dep) for $\frac{10}{100}\times(12\,000 - \frac{10}{100}\times 12\,000)$ or sight of 1080 A1 cao Alternative markscheme M2 for $12000\times\left(1-\frac{10}{100}\right)^2$ (M1 for $12000\times\left(1-\frac{10}{100}\right)$) A1 cao
3	$7r - 5r = -20 - 2$	–11	2	M1 for $7r + 2 = 5r - 20$ or $\frac{7r}{5} + \frac{2}{5} = r - 4$ or $7r - 5r = -20 - 2$ or $\frac{7r}{5} - r = -4 - \frac{2}{5}$ A1 cao

Paper 5505

No	Working	Answer	Mark	Notes
4 (a)		–1, 0, 1	2	B2 for –1, 0, 1 only (B1 for –1, 0 or 0,1 or –1, 1 or –2, -1, 0, 1 only)
(b)		(–1,–1)(0,–1) (1,–1) (0, 0) (1, 0) (1, 1)	3	B3 for 6 points correct (B2 for 3 points correct) (B1 for 1 point correct) *NB: –B1 for each additional point over six*
5		$5n + 1$	2	B2 oe (B1 for $5n$ seen) NB: n = gets B1 max
6 (a)	Triangle with vertices at (0,0) (0,–2) and (3,0)		2	M1 for correct orientation A1 cao
(b)	Rotation, 180°, centre (0,1) Enlargement sf –1 centre (0,1)		2	B2 for 180° 'rotation' centre (0, 1) or for Enlargement sf - 1 centre (0,1) (B1 for any two of the three parts) NB: B0 if additional transformation is included
7	Bisector of $\angle BAC$ Arc around A Region	See overlay	3	B3 cao (B2 for either two correct boundaries, no shading/ wrong shading or one correct boundary, one incorrect boundary with valid shading) (B1 for either two incorrect boundaries but one drawn from A and one intersection, with valid shading or one correct boundary) Ignore shading outside the triangle
8		Length Volume Area	3	B1 for Length B1 for Volume B1 for Area



Paper 5505

No		Working	Answer	Mark	Notes
9	(a)	Unbiased question with choices		2	B1 for unbiased question B1 for at least 2 choices
	(b)	Leading question and a restricted sample		2	Classification 1: A biased question Classification 2: A restricted sample of people Classification 3: Not specifying a range of foods Classification 4: Nothing to do with eating habits B2 reasons which satisfy 2 different classifications (B1 a reason which satisfies one classification)
10	(a)	$6 \times 10^2 \times 8 \times 10^4$ $48 \times 10^6 = 4.8 \times 10^7$	4.8×10^7	3	M1 for $6 \times 10^a \times 8 \times 10^b$ oe, a and b integers including 0 A1 for 48×10^6 oe A1 cao
	(b)	200 000 + 30 000 = 230 000	230 000	2	B2 cao (B1 for sight of 200 000 or 30 000 or 2.3×10^5 or 23×10^4)
11	(a)	$x^2 + xy + xy + y^2$	$x^2 + 2xy + y^2$	2	M1 for at least 3 of the 4 terms correct A1 cao
	(b)		25	2	M1 for recognising 3.47 + 1.53 (= 5) A1 cao
12	(i)	Tangent 90° to diameter /radius/ line from (through) centre	27°	4	B1 for 27° cao B1 for reason
	(ii)	180 –(90+ "27") angle in semicircle (is 90°)/Alternate segments /angle at centre twice at circumference	63°		B1 ft for 90–"27" if not 63° B1 for reason
13	(i)		p^9	1	B1 cao
	(ii)		$6q^6$	2	B2 for $6q^6$ (B1 for sight of $\frac{6q^9}{q^3}$ or $3q \times 2q^5$ or $3q^4 \times 2q^2$ or $6 \times q \times q \times q \times q \times q \times q$ or final answer of the form kq^6, $k > 0$)

Paper 5505

No	Working	Answer	Mark	Notes
14 (a)(i)		152	2	B1 cao
(ii)		177		B1 cao
(b)			3	B1 for median marked at 167 B1 ft for postion of box with its ends at "152" and "177" B1 for position of whiskers with ends at 132 and 182 NB: For any points plotted between 141 and 149 give a tolerance of an extra ± 1 square
15	(arc =) $\frac{40}{360} \times 2\pi \times 9$ $= 2\pi$	$2\pi + 18$	4	M1 for $\frac{40}{360} \times$ M1 for $2\pi \times 9$ M1 (dep) for $\frac{40}{360} \times 2\pi \times 9$ oe A1 for $\frac{18 \times \pi}{9} + 18$ oe exact form
16 (i)		1	1	B1 cao
(ii)		$\frac{1}{16}$	1	B1 cao accept 0.0625
(iii)		64	1	B1 cao condone ± 64

Paper 5505

No	Working	Answer	Mark	Notes
17 (a)	$F \propto 1/x^2$ $F = k/x^2$ $4 = k / 3^2$ $F = 36/x^2$	$F = \frac{36}{x^2}$	3	M1 for $F = k/x^2$ seen or implied. ($k \neq 1$) M1 (dep) for subst. or sight of $k = 36$ A1 for $F = 36/x^2$
(b)		9	1	B1 ft for 9 (ft on $F = kx^n$, $n \neq 0$)
(c)	$64 = \frac{36}{x^2}$ $x^2 = \frac{36}{64}$ $x = \pm\frac{3}{4}$	$\frac{6}{8}$	2	M1 for $x^2 = \frac{"36"}{64}$ A1 for $\frac{6}{8}$ oe (condone $\pm$) *SC: Use of $F = kx^2$ max M1 M1 A0 B1 ft M0 A0* *SC: Use of* $F = \frac{k}{\sqrt{x}}$ *max M1 M1 A0 B0 M1* ($\sqrt{x} = \frac{4\sqrt{3}}{64}$) *A0*
18	$(5+\sqrt{3})(5-\sqrt{3}) = 5\times5 - 5\sqrt{3} + 5\sqrt{3} - \sqrt{3}\sqrt{3}$ $= 5\times5 - 3$ $\frac{22}{\sqrt{22}} = \frac{22\sqrt{22}}{22}$	$\sqrt{22}$	3	B1 for correct expansion 25 - $5\sqrt{3}$ + $5\sqrt{3}$ - $\sqrt{3}$ $\sqrt{3}$ with 1st three terms reducing to 25 **without** any errors seen B1 (indep) for $\sqrt{3}$ $\sqrt{3}$ = 3 B1 for $\sqrt{22}$ coming from $\frac{22}{\sqrt{22}}$ (S.C $\frac{(5+\sqrt{3})(5-\sqrt{3})\sqrt{22}}{22}$ gets B1)

Paper 5505

No	Working	Answer	Mark	Notes
19 (a)		60 40	2	B1 cao B1 cao
(b)		correct bars	2	B1 for $30 < x \leq 40$ with an area of 2½ squares B1 for $40 < x \leq 70$ with an area of 3 squares *SC:* $\frac{0}{4}$ *give M1 if clearly using area or frequency density*
20 (a)	$6x + 8 - 12x + 15$	$-6x + 23$	2	M1 for 3 of the 4 terms $6x$, $+8$, $-12x$, $+15$ correct A1 cao
(b)		$32x^5y^{15}$	2	B2 cao (B1 for two of 32, x^5, y^{15})
(c)	$\frac{(n+1)(n-1)}{n+1} \times \frac{2}{n-2}$ $\frac{2(n-1)}{n-2}$	$\frac{2(n-1)}{n-2}$	3	M1 for $k(n + 1)(n - 1)$ M1 dep for $\frac{(n+1)(n-1)}{(n+1)} = n - 1$ A1 for $\frac{2(n-1)}{n-2}$
21	Vertices at $(-3, -1\frac{1}{2}), (-4\frac{1}{2}, -1\frac{1}{2}), (-3, -4\frac{1}{2})$		3	B1 for all sides $\times 1\frac{1}{2}$ B1 for correct orientation with 2 vertices almost correct B1 cao

Paper 5505

No	Working	Answer	Mark	Notes
22	Total = 3 + 5 + 2 (=10) $\frac{3}{10}\times\frac{3}{10}\times\frac{5}{10}\left(=\frac{45}{1000}\right), \frac{3}{10}\times\frac{3}{10}\times\frac{2}{10}\left(=\frac{18}{1000}\right)$ $\frac{5}{10}\times\frac{5}{10}\times\frac{3}{10}\left(=\frac{75}{1000}\right), \frac{5}{10}\times\frac{5}{10}\times\frac{2}{10}\left(=\frac{50}{1000}\right)$ $\frac{2}{10}\times\frac{2}{10}\times\frac{3}{10}\left(=\frac{12}{1000}\right), \frac{2}{10}\times\frac{2}{10}\times\frac{5}{10}\left(=\frac{20}{1000}\right)$ $3\times\left(\frac{"45"}{1000}+\frac{"18"}{1000}+\frac{"75"}{1000}+\frac{"50"}{1000}+\frac{"12"}{1000}+\frac{"20"}{1000}\right)$ $\frac{660}{1000}$	$\frac{660}{1000}$ oe	5	M3 for all six expressions seen OR their combined equivalents (M2 for four expressions seen OR their combined equivalents) (M1 for two expressions seen OR their combined equivalents) M1 sum of 18 relevant products condone 1 slip A1 for $\frac{660}{1000}$ oe *SC: without replacement maximum M4 A0* SC: Just 2 beads: Answer either $\frac{38}{100}$ oe OR $\frac{28}{90}$ oe B1

Paper 5505

No	Working	Answer	Mark	Notes
23 (a)(i)		$6\mathbf{b} - 6\mathbf{a}$	2	B1 for $6\mathbf{b} - 6\mathbf{a}$ oe
(ii)		$6\mathbf{a}$		B1 for $6\mathbf{a}$ oe
(b)	$\overrightarrow{EX} = \overrightarrow{EB} + \overrightarrow{BX}$ $= 12\mathbf{b} + \frac{1}{2}\overrightarrow{BC}$	$12\mathbf{b} - 3\mathbf{a}$	2	M1 for $\overrightarrow{EX} = \overrightarrow{EB} + \overrightarrow{BX}$ oe vector journey in a form ready for straightforward substitution A1 for $12\mathbf{b} - 3\mathbf{a}$ oe
(c)	$\overrightarrow{AY} = \frac{5}{3}\overrightarrow{AB}$ or $\overrightarrow{BY} = \frac{2}{3}\overrightarrow{AB}$ $\overrightarrow{EY} = 16\mathbf{b} - 4\mathbf{a}$ or $\overrightarrow{XY} = 4\mathbf{b} - \mathbf{a}$ $\overrightarrow{EY} = 4\overrightarrow{XY}$ or $\overrightarrow{EX} = 3\overrightarrow{XY}$ or $\overrightarrow{EY} = \frac{4}{3}\overrightarrow{EX}$	Printer Answer	3	B1 for either $\overrightarrow{AY} = \frac{5}{3}\overrightarrow{AB}$ or $\overrightarrow{BY} = \frac{2}{3}\overrightarrow{AB}$ oe B1 ft for either $\overrightarrow{EY} = 16\mathbf{b} - 4\mathbf{a}$ or $\overrightarrow{XY} = 4\mathbf{b} - \mathbf{a}$ ft only on parts (*a*) and (*b*) B1 for either $\overrightarrow{EY} = 4\overrightarrow{XY}$ or $\overrightarrow{EX} = 3\overrightarrow{XY}$ or $\overrightarrow{EY} = \frac{4}{3}\overrightarrow{EX}$ oe **plus** conclusion of *E*, *X*, *Y* on the same straight line
24 (a)(i)		$(5, -4)$	4	B1 cao
(ii)		$(2, -9)$		B1 cao
(iii)		$(2, 4)$		B1 cao
(iv)		$(1, -4)$		B1 cao
(b)		$(x-2)^2 - 4$	4	B4 for $(x-2)^2 - 4$ oe eg. $x^2 - 4x$ (B3 for $(x+2)^2 - 4$ or $(x-2)^2 + 4$) (B2 for $x^2 - 4$ or $(x-2)^2$ OR $x^2 + bx$, $b \neq 0$ OR $(x+2)^2 + 4$ OR $f(x-2) - 4$) (B1 for $x^2 + 4$ or $(x+2)^2$ or $ax^2 + bx$ or $x^2 + bx + c$ OR $x - 2 - 4$ or $x^2 - 2 - 4$, $a, b, c \neq 0$)

Paper 5506

No	Working	Answer	Mark	Notes
1 (a)	$V = \pi \times 4^2 \times 10$	502 – 503 cm^3	2	M1 for $\pi \times 4^2 \times 10$ A1 502 – 503
(b)	$P^2 = 10^2 + 8^2$ $P = \sqrt{164}$	$\sqrt{164} < 13$	3	M1 for sight of correct right angled triangle M1 for $10^2 + 8^2$ A1 for conclusion based on a correct calculation Or 12.8 seen
2 (a)(i)	2×30	$2 \times 2 \times 3 \times 5$	4	M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
(ii)	2×48	$2^5 \times 3$		M1 for systematic method, division, factor trees (at least one prime) A1 cao
(b)		12	1	B1 cao
(c)	$2^5 \times 3 \times 5$	480	2	B2 cao B1 for $2^5 \times 3 \times 5$ or any correct common multiple

Paper 5506

No	Working	Answer	Mark	Notes
3 (a)		$150 < C \leq 200$	2	M1 use of cum freq to find the cost of the 20th or 20.5^{th} car OR $\frac{1}{2}\Sigma f$ th or $\frac{1}{2}(\Sigma f + 1)$ th car. A1 eg 150 to 200, 150 – 200
(b)		No, because the 21st value is in the same interval	1	B1 for 20.5^{th} or 21st value in the same internal consistent with 'a' OR Refers to the median value being low in the interval (statement to be mathematically correct) See additional sheet
(c)	80% = 5200 $\frac{5200}{80} \times 100$	6500	3	M1 for (100 – 20)% = 5200 M1 for $\frac{5200}{"80"} \times 100$ A1 cao

Paper 5506

No	Working	Answer	Mark	Notes
4 (a)	$x^2(x+1) = 230$	AG	2	M1 for $x \times x \times (x+1)$ or $x \times x \times x + 1$ oe, $x^2(x+1)$, $x^2 \times x + 1$ A1 cao from $x \times x \times (x+1)$, no need to see 230
(b)	5 – 150 6 – 252 5.1 – 158.7 5.2 – 167.6 5.3 – 177.0 5.4 – 186.6 5.5 – 196.6 5.6 – 207.0 5.7 – 217.7 5.8 – 228.8 5.9 –240.2 5.85 – 234.4	5.8	4	B2 for trial between 5.8 and 5.9 inclusive evaluated (B1 for trial between 5 and 6 inclusive evaluated) B1 for different trial between 5.8 and 5.85 (not including 5.8) B1 dep on at least are previous B1 5.8, 5.81, 5.811
5	$\pi \times \left(\frac{15}{2}\right)^2 = 176.715$	88.4 cm^2	3	M1 for $\pi \times \left(\frac{15}{2}\right)^2$ seen A1 88.3 – 88.4 B1 for cm² (independent)

Paper 5506

No	Working	Answer	Mark	Notes
6 (a)	$5 = 0.5x + 1$	8	2	M1 for $5 = 0.5x + 1$ A1 cao
(b)		$y = \frac{1}{2}x + c$	1	B1for $y = \frac{1}{2}x + c$, $c \neq 1$, oe
(c)		$x = 2y - 2$ OR $x = 2(y - 1)$	2	M1for correctly multiplying both sides by 2 or correctly isolating $\frac{x}{2}$ A1 for $x = 2(y - 1)$, $x = \frac{y-1}{0.5}$, $\frac{y-1}{\frac{1}{2}}$ oe SC B1 for x= 2y -1
7	$4x - 6y = 22$ $15x + 6y = 54$ $19x = 76$	$x = 4$, $y = -1$	4	M1 for coefficients of x or y the same followed by correct operation, allow one arithmetical error A1 cao M1 (dep) for correct sub for other variable A1 cao Trial and improvement 0 marks unless both correct values of x and y found
8 (a)	SF = $\frac{10}{6}$ $\frac{10}{6} \times 4.8 = 8$	8	2	M1 for sight of $\frac{10}{6}$ or $\frac{6}{10}$ or 1.67 or better or $\frac{CD}{10} = \frac{4.8}{6}$ A1 cao
(b)	$\frac{10}{6} \times 4.5 - 4.5 = 3$	19.8	2	M1 for use of SF from "a" to find AC or BC or $\frac{BC}{4.5} = \frac{4}{6}$ and adding 4 sides A1 cao

Paper 5506

No	Working	Answer	Mark	Notes
9	$\frac{6\times10^{15}}{3.2\times10^{8}}$ 1.875×10^{7}	4.3×10^{3}	3	B3 for 4.3×10^{3} to 4.34×10^{3} (B2 for 1.875×10^{7} oe or 4300 to 4340, final answer of 1.9×10^{7} B1 for sight of 6×10^{15} oe or 3.2×10^{8} oe)
10	$8.5\times\tan38$ $=8.5\times0.7813$ $\frac{8.5}{\sin(90-38)}=\frac{AB}{\sin38}$ $AB=\frac{8.5\times\sin38}{\sin(90-38)}$ $=\frac{5.2331}{0.788}=6.64$	6.64	3	M1 for correct use of trig, eg $\tan 38=\frac{opp}{8.5}$ M1 for $8.5\times\tan38$ A1 6.64 – 6.641 OR M1 for correct substitution into the sine rule M1 (dep) for correct rearrangement for AB= A1 6.64 – 6.641
11 (a)		No, as you would expect about 100. Yes, as it is possible to get 200 sixes with a fair dice	1	B1 for a consistent answer See additional sheet

Paper 5506

No	Working	Answer	Mark	Notes
(b)	$\frac{1}{6}, \frac{5}{6}$ + labels		3	B1 for $\frac{5}{6}$ on the red dice, *not six* branch B1 for a fully complete tree diagram with all branches labelled B1 for $\frac{1}{6}$ and $\frac{5}{6}$ on all remaining branches as appropriate
(c)(i)	$\left(\frac{1}{6}\right)^2$	$\frac{1}{36}$	2	M1 $\left(\frac{1}{6}\right)^2$ or $\frac{1}{6}\times\frac{1}{6}$ only or 0.28 A1 $\frac{1}{36}$ or 0.03 or better
(ii)	$1-\left(\frac{5}{6}\right)^2$ OR $\frac{1}{6}\times\frac{5}{6}+\frac{5}{6}\times\frac{1}{6}+\frac{1}{6}\times\frac{1}{6}$	$\frac{11}{36}$	3	M2 for $1-\left(\frac{5}{6}\right)^2$ or $1-\frac{5}{6}\times\frac{5}{6}$ A1 cao OR M1 for $\frac{1}{6}\times\frac{5}{6}$ oe M1 for 2 or 3 only of $\frac{1}{6}\times\frac{5}{6}, \frac{5}{6}\times\frac{1}{6}$, "a" A1 for $\frac{11}{36}$ or 0.31 or better

Paper 5506

No	Working	Answer	Mark	Notes
12 (a)	$\pi \times 30 \times \frac{7.5^2}{3} - \pi \times 10 \times \frac{2.5^2}{3} = 1767 - 65$	1700	3	M1 for either $\pi \times 30 \times \frac{7.5^2}{3}$ or $\pi \times 10 \times \frac{2.5^2}{3}$ M1 (dep) for difference A1 1700 – 1702 **SC** B1 Using d instead of r, 6800 – 6808
(b)	$\frac{S}{2\pi d} = \sqrt{h^2 + d^2}$ $\left(\frac{S}{2\pi d}\right)^2 = h^2 + d^2$	$h = \sqrt{\frac{S^2 - 4\pi^2 d}{4\pi^2 d^2}}$	3	M1 for correctly isolating $\sqrt{h^2 + d^2}$ or $h^2 + d^2$ or $h + d$ or kh^2 or kh M1(indep) squaring both sides A1 $h = \sqrt{\frac{S^2 - 4\pi^2 d^4}{4\pi^2 d^2}}$, $h = \frac{\sqrt{S^2 - 4\pi^2 d^4}}{2\pi d}$ $h = \sqrt{\left(\frac{S}{2\pi d}\right)^2 - d^2}$
(c)	$\left(\frac{30}{20}\right)^2 \times 450$ or $450 \div \left(\frac{20}{30}\right)^2$	1012.5	2	M1 for sight of correct SF^2 including 4:9 A1 1010 to 1013

Paper 5506

No	Working	Answer	Mark	Notes
13 (a)	$\frac{2x(x+20)}{2} = 400$	As given	2	M1 $\frac{2x(x+20)}{2}$ or $\frac{2x \times x + 20}{2}$ or $2x(x + 20) = 800$ A1 cao following correct working, no need for = 400 *SC B1* $2x \times x + \frac{1}{2} \times 2x(10 - \frac{x}{2}) \times 2$
(b)	$\frac{-20 \pm \sqrt{20^2 - 4 \times 1 \times (-400)}}{2}$ $= \frac{-20 \pm 44.721}{2}$	12.361	3	M1 for correct sub, up to signs, in the quad formula A1 for 44.7 or $\sqrt{2000}$ A1 for 12.3606 – 12.361, ignore negative solution T.I B3 for 12.361 OR Completing the square M1 for $(x+10)^2$ seen A1 for $-10 \pm \sqrt{500}$ A1 for 12.3606 – 12.361 ignore negative solution

Paper 5506

No	Working	Answer	Mark	Notes
14 (a)	$0.5\times 8\times 15\times \sin 70^0$	56.4	2	M1 for correct sub into area formula A1 56.38 – 56.4
(b)	$AB^2 = 8^2 + 15^2 - 2\times 8\times 15\times \cos 70^0 = 206.9$ EITHER $0.5\times AB\times CX$ ='56.38' OR $\frac{\sin B}{8} = \frac{\sin 70}{\sqrt{'206.9'}}$ $B = 31.5$ 15 sin '31.5'	7.84	4	M1 for correct sub into cos rule A1 for 206.9 - 207 or 14.38 – 14.4 EITHER M1 for use of area rule to find CX A1 7.83 – 7.84 OR M1 for correct use of sine rule to find sin B or sin A and then sight of 15sin B *or* 8 sin A A1 7.83 – 7.84

Paper 5506

No	Working	Answer	Mark	Notes
15 (a)	$4a^2 - 4a + 1 - (4b^2 - 4b + 1) =$ $4(a^2 - b^2) - 4(a - b)$ $4(a - b)(a + b - 1)$ OR $((2a - 1) - (2b - 1))((2a - 1) + (2b - 1))$ $(2a - 2b)(2a + 2b - 2)$	AG	3	Expansion Method M1 for a correct expansion of any one of the three terms M1(dep) on an attempt to expand all 3 terms and show LHS = RHS A1 fully correct algebra RHS exp is $4(a^2 + ab - a - ba - b^2 + b)$ OR Factorisation Method M1 for attempt to use difference of 2 squares on LHS M1 for one bracket correctly simplified A1 fully correct
(b)	Any 2 odd square numbers have the above form If a and b are both even or odd then $a - b$ is even, so $4(a - b)$ is a multiple of 8 If one of a,b is odd, then $a + b - 1$ is even, so $4(a + b - 1)$ is a multiple of 8		3	B1 'any 2 square nos have the above form' (may be implied by sight of $(2a - 1)^2 - (2b - 1)^2$ in part (b)) B1 first reason B1 second reason SC B1 for $(2r + 1)^2 - (2r - 1)^2$ B1 for 8r
16 (a)	$g_L = \frac{2 \times 4.495}{1.35^2 \times \sin 30.5}$ $g_u = \frac{2 \times 4.505}{1.25^2 \times \sin 29.5}$	9.719 11.710	4	B2 for any 4 of 4.505, 1.25, 29.5, 4.495, 1.35, 30.5 seen (B1 for any two or three seen) B1 for 11.710 – 11.7103 B1 cao 9.719 – 9.71904
(b)	Round, until lower and upper bounds agree	10	1	B1 for 10 + reason " they agree to this level of accuracy"

Paper 5506

No	Working	Answer	Mark	Notes
17 (a)(i)		xy	3	B1 cao
(ii)		y^2		B1 for y^2 or $y \times y$
(iii)		$\frac{x}{2}$		B1 for $\frac{x}{2}$ or $0.5x$ or $2^{-1}x$
(b)	Divide to get $2y = 1$	$q = -1$	2	M1 for $2y = 1$ or $\frac{x}{2} = 32$ or $p + q = 5$ or $1 + p + 2q = 5$
		$p = 6$		A1 cao
18 (a)	$x^2 - 2mx + m^2 - k$	$k = m^2$	2	M1 for correct exp of $(x - m)^2$ or correct completion of the square eg $\left(x - \frac{2m}{2}\right)^2 - \left(\frac{2m}{2}\right)^2$
				A1 cao
				SC B1 for $k = -m^2$
(b)(i)	Min value is $-m^2$	$-m^2$	3	M1 for recognition that min value occurs when $(x - m)^2 = 0$ (either (b)(i) or (b)(ii) correct implies this M1)
(ii)	$x = m$	m		A1 ft on 'k', " $-k$" gets M1 A0
				A1 cao
19	$0.06 \times 0.05 = 0.003$	No	2	M1 for 0.06×0.05
				A1 correct conclusion based on 0.003 or 0.06 x 0.05 stated as $\neq 0.0011$
				OR M1 for statement that for the two events to be independent P (BL and CL) = P(BL) × P(CL)

Paper 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
20		50 50 4	3	B1 50 or $\frac{100}{2}$ B1 for 50 or "a" B1 4 or $\frac{360}{90}$ oe

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4LN

Telephone 01623 467467
Fax 01623 450481

Order Code UG014129 June 2003

For more information on Edexcel qualifications please contact our
Customer Response Centre on 0870 240 9800
or email: enquiries@edexcel.org.uk
or visit our website: www.edexcel.org.uk

London Qualifications Limited. Registered in England and Wales no.4496750
Registered Office: Stewart House, 32 Russell Square, London WC1B 5DN



edexcel

GCSE

Edexcel GCSE

Mathematics A 1387

July 2004

advancing learning, changing lives

Mark Scheme

Edexcel GCSE

Mathematics A 1387

London Qualifications is one of the leading examining and awarding bodies in the UK and throughout the world. It incorporates all the qualifications previously awarded under the Edexcel and BTEC brand. We provide a wide range of qualifications including general (academic), vocational, occupational and specific programmes for employers.

Through a network of UK and overseas offices, our centres receive the support they need to help them deliver their education and training programmes to learners.

For further information please call Customer Services on 0870 240 9800, or visit our website at www.edexcel.org.uk

July 2004

Publications Code UG015616

All the material in this publication is copyright
© London Qualifications Ltd 2004

CONTENTS

Notes on Marking Principles....2
Paper 5514....4
Paper 5515....8
Paper 5516.... 11
Paper 5517.... 15
Paper 5518.... 19
Paper 5519.... 23

NOTES ON MARKING PRINCIPLES

NOTES ON MARKING PRINCIPLES

1 Three types of mark are available

M marks - awarded for correct working seen or implied.
A marks - conditional accuracy marks which are awarded for accurate working following the award of M marks.
B marks - unconditional accuracy marks (independent of M).

2 Abbreviations

cao - correct answer only.
ft - follow through.
$\surd$ - Denotes a "follow through" answer.

SC - special case.
isw - ignore subsequent working.
oe - or equivalent (and appropriate).
NB: a candidate cannot benefit from both isw and ft.

3 If no working shown, then

correct answers normally score full marks
incorrect (even though nearly correct) answers score no marks.

4 Marking instructions

Misread loses A marks (and sometimes B marks) on that part but ft can be allowed on subsequent parts. M marks can still be earned. If in doubt contact your team leader.
If there is a wrong answer in the answer space DO CHECK the working in the body of the script.

- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.
- If there is a wrong answer in the answer space DO CHECK the working in the body of the script.
- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.

5 Style of marking

Answer correct: tick and write part mark in margin NEXT TO BRACKETED MARK.
Answer incorrect: cross, but show M, A or B marks if any earned in body of script and transfer the total of these to the margin next to the bracket mark.
Total for each double page at bottom right page (except for back if used), FINAL TOTAL IN RELEVANT BOX ON FRONT COVER.
Nought in margin for fully incorrect question or page AND FOR NO ATTEMPT.
Where no attempt has been made a line should be put in the answer space and zero in the margin next to the bracketed mark
CHOICE OF METHOD – No marks unless one answer is in answer space – then mark that.
CROSSED OUT WORK - if not replaced this should be marked (if legible).
There must always be a mark next to bracketed mark in the margin/

6 Follow Through Marks

Follow throughs are guided by two principles:

(a) Follow throughs which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous, do not award.
(b) Follow throughs which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

7 Probability

Probability answers must be given as fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least two decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.

6 Linear Equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

8 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

PAPER 5501					
No		**Working**	**Answer**	**Mark**	**Notes**
1			K: 1020 L: 8.06	2	B1 for 1020 or 1,020 B1 for 8.06 Accept £8.06p and £8,06
2	(a)		28, 33	2	B1, B1 (B1 ft for "28" + 5 if both numbers >25)
	(b)			1	B1 for add 5, +5, for going up in 5's the difference is 5 oe
	(c)			1	B1 for they end in 3 and 8, it ends in 7; or refers to 383 and 388 are in sequence
3	(a)(i)		$\frac{1}{2}$	2	B2 for ½ accept half (B1 for an equivalent unsimplified fraction eg 4/8 or 50% or 0.5)
	(ii)		2 rectangles shaded	1	B1 for correct shading (any 2 rectangles)
	(b)(i)		40	4	B1 for 40 cao
	(ii)		150 000		B1 for 150 000 cao (accept 150,000 not 150.000)
	(iii)		6.55		B1 for 6.55 cao not $6.5^{½}$
	(iv)		$\frac{3}{8}$		B1 for $\frac{3}{8}$ oe accept 0.375
	(c)		Cross 3cm from *A*	1	B1 mark a cross 3 cm (±2 mm) from *A*
4	(a)(i)		metres	2	B1 for metres (m)
	(ii)		grams		B1 for grams (g)
	(b)		miles	1	B1 for miles
5	(a)		(3, 2)	1	B1 for (3, 2)
	(b)(i)		*Q* at (0, 3)	1	B1 for *Q* plotted correctly on *y*-axis at (0, 3) ±2mm
	(ii)		*R* at (−2, −3)	1	B1 for *R* plotted correctly at (−2, −3) ±2mm
6	(a)(i)		30	2	B1 for 30
	(ii)		25		B1 for 25
	(b)(i)		4 shapes	2	B1 for drawing 4 shapes
	(ii)		1½ shapes		B1 for drawing 1½ shapes

PAPER 5501					
	No	Working	Answer	Mark	Notes
7	(a)		30	1	B1 for 30
	(b)	$20 \times 3 + 5$	65	2	M1 for $20 \times 3 + 5$ oe A1 for 65
8	(a)		Draws perp.	1	B1 for correctly drawing perp must touch line or cut line *AB* ± 2mm
	(b)		Sketches a cylinder	1	B1 for sketching cylinder
9	(a)	$\begin{array}{r} 1974 \\ \underline{6580} \\ 8554 \end{array}$	855.4	3	M1 for complete method with relative place value correct, condone 1 error in multiplication A2 cao (A1 for digits 8554 seen or A1 for "855.4" dependent on 1 arithmetic error)
	(b)	$990 \div 69 = 14.3\ldots$ or 14 rem 24	14	4	Method 1 - Everything excluding long division M2 for a valid method with no errors …need to see 966 or 1035 (M1 for a valid method, including estimation, that reaches an answer between 901 and 1099 inclusive. Ignore errors.) A2 for 14 with a fully correct method (A1 (dep on 1st M1) for an answer between 14 and 15 inclusive. Ignore errors. Cannot have used estimation.) Note: Estimation can only score a maximum of M1 unless accompanied by another method or 966 or 1035 see (award M2) Method 2 – long division method M2 for $990 \div 69$ = integer answer between 12 and 19 inclusive and rem 30 seen (M1 for $990 \div 69$ with 1 in tens column.) A2 for 14 with fully correct method (A1 (dep on 1st M1) for an answer between 14 and 15 inclusive.)

PAPER 5501					
	No	**Working**	**Answer**	**Mark**	**Notes**
10	(a)(i)		7	2	B1 for 7
	(ii)		−10		B1 for −10
	(b)(i)		6	2	B1 for 6 (accept −6)
	(ii)		8		B1 for 8 (accept −8)
	(c)		−7	1	B1 for −7 cao
11	(a)		B and D	2	B1, B1 (–1 each extra)
	(b)(i)		A	2	B1 for A
	(ii)		3		B1 for 3
12	(a)	800 − 144	656	2	M1 for at least 1 digit correct and in correct position needs to be 3 digit number A1 for 656
	(b)	144 is less than 200 so Trudy is wrong		2	B1 for 200 B1ft for 'correct' explanation based on cand's "200"
	(c)	$\frac{45\times800}{100}$	360	2	M1 for 45 × 800 ÷ 100 oe A1 for 360
	(d)	$\frac{176}{800}\times100$	22	2	M1 for $\frac{176}{800}\times100$ oe A1 for 22
13	(a)(i)		25	4	B1 for 25
	(ii)		28		B1 for 28
	(iii)		5 and 20		B1 for 5 and 20
	(iv)		26 and 33		B1 for 26 and 33
	(b)	$2^3 = 8$ or $2^3 = 2 \times 2 \times 2$ (which is not 6)		1	B1 for valid 'explanation'
14			10 m^2	2	B1 for 10 B1 indep for m^2.

PAPER 5501					
No		**Working**	**Answer**	**Mark**	**Notes**
15	(a)	$\frac{11}{12}-\frac{10}{12}$	$\frac{1}{12}$	2	M1 for correctly writing both fractions to a common denominator A1 for $\frac{1}{12}$ oe
	(b)	$\frac{70\times400}{200}$	140	2	B2 for 140 (accept 136) (B1 for sight of any two of 70, 400 or 200)
16	(a)		$2y$	1	B1 for $2y$ or $2\times y$, $y2$, $y\times2$
	(b)		$3p^2$.	1	B1 for $3p^2$ or $3\times p^2$ or $p^2\times3$ or $p^2 3$
	(c)		$x(x-3)$	2	B2 for $x(x-3)$ (B1 for x (x…….)) $\frac{25}{60}$ wrongly cancelled gets B1 ISW
17	(a)		2 23 9 34 15 2 9 26 17 25 18 60	3	B3 for all correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
	(b)		$\frac{25}{60}$	1	B1 for $\frac{25}{60}$ or $\frac{5}{12}$ oe $\frac{25}{60}$ wrongly cancelled gets B1 ISW

PAPER 5501					
	No	**Working**	**Answer**	**Mark**	**Notes**
18	(a)(i)		60	2	B1 for 60
	(ii)				B1 for all **angles equal** so equilateral triangle oe
	(b)(i)		130	3	B1 for 130
	(ii)				B1 for isosceles triangle oe or 2 angles equal accept $\angle Q = \angle R$ B1 for angles on a straight **line** add up to **180°**oe (180° could be in working)
	(c)		64	1	B1 for 64
19	(a)		1	1	B1 for 1
	(b)		3	1	B1 for 3
	(c)	$9\times1+3\times2+5\times3+3\times4$ (= 42) "42" ÷ 20	2.1	3	M1 for 9×1, 3×2, 5×3, 3×4 or for 42 seen M1 (dep) for "42" ÷ 20 A1 for 2.1 or $2\frac{1}{10}$ or $2\frac{2}{20}$
20	(a)		09 05	1	B1 for 09 05 oe
	(b)		7	1	B1 for 7
	(c)		10	1	B1 for 10
	(d)	7km in 20 mins	21	3	B1 for 20 (minutes) oe or $\times3$ seen M1 for $\frac{"7"}{"20"}$ A1 cao [SC: "7" × 3 seen gets B1 M1]

PAPER 5501				
No	**Working**	**Answer**	**Mark**	**Notes**
21	Vertices of new triangle at (2, −2) (2, 6) and (6, −2)	Correct triangle drawn	3	B3 cao (B2 for either correct triangle in wrong translated position or for 2 vertices correct) (B1 a right angled triangle with horizontal length 4 or vertical length 8 in the same orientation as the shaded triangle) SC B2 for s + 3 totally correct
22 (a) (b) (c)	 8560 ÷ (10 × 10)	8 Pentagon 85.6	1 1 2	B1 for 8 B1 for pentagon M1 for 8560 ÷ (10 × 10) oe A1 for 85.6
23	$2x + x + 100 + 47 = 360$ $2x + x = 360 - 100 - 47$ $x = 71$ Largest angle = $2x$ =	142	4	M1 for $2x + x + 100 + 47 = 360$ or 360 – 147 or 213 seen M1 dep for correctly separating x-terms and non x terms or "360 – 147" ÷ 3 A1 for $x = 71$provided M2 awarded A1 ft for 142

PAPER 5502					
	No	**Working**	**Answer**	**Mark**	**Notes**
1	(a)		Diagram	1	B1 cao
	(b)		22, 26	1	B1 cao
	(c)		46	1	B1 cao
2	(a)	£5.95 + £1.62 + 25p + 2 × 48p = £8.78	1.22	3	M1 for 3 of £5.95, £1.62, 25p, 48p seen with intention to add or 170 seen A1 for £8.78 A1 ft from " 8.78"
	(b)	160 ÷ 12 = 13.(333…)	14	2	M1 for 160 ÷ 12, or 13 or better or 12 × 13 or 12 × 14 A1 14 cao
	(c)	"14" × £12.20 = £170.8**0**	170.80	2	M1 for "14" × 12.20 A1 for 170.8**0** or 158.6**0** if 13 in (b) NB: 170.8 or 158.6 gets M1 A0
3	(a)(i)		1459	1	B1 cao
	(ii)		9541	1	B1 cao
	(b)		9 + 5 = 14	1	B1 cao
	(c)		0	1	B1 cao
4	(a)		1123	1	B1 cao
	(b)		1125	1	B1 cao
	(c)		43	1	B1 cao
	(d)	67 – "43"	24	2	M1 for 67 – "43" A1 ft from "43"
	(e)(i)		80	2	B1 cao
	(ii)		56 – 58		B1 answer in range 56 to 58 inc
	(f)		Completes graph	2	B2 for (Apr , 70) and (May , 60 < p < 65) plotted and joined (B1 for one point plotted)

PAPER 5502					
No		Working	Answer	Mark	Notes
5	(a)(i)		4	1	B1 cao
	(ii)		10	1	B1 cao
	(b)		28	2	B2 for 28 (B1 for 29 or 14×2)
6	(a)		$\frac{3}{4}$	1	B1 accept 0.75, 75%
	(b)	$\frac{3}{4} \times 28 = 21$	15.54	3	M1 for $\frac{3}{4} \times 28$ or 21 seen M1 for "21" $\times$ 74 or 28×74 or 7×74 A1 cao
	(c)(i)		44 – 46	2	B1 44 – 46 inc
	(ii)		5.2 – 5.4		B1 5.2 – 5.4 inc
7	(a)		Correct shape	1	B1
	(b)		Correct shape	1	B1
8	(a)		Hexagon	1	B1
	(b)		Right	1	B1 cao
	(c)		Drawing	2	B2 for 7 additional hexagons with at least 2 points at which 3 hexagons meet (B1 for one point at which 3 hexagons meet)
9	(a)		$\frac{3}{4}$	2	M1 $\frac{80-20}{80}$ or $\frac{60}{80}$ or 0.75 (oe) A1 cao Do not accept equivalents
	(b)		15	1	B1 cao
	(c)		Iron and Cook set	1	B1 for both Accept mixer and fryer
	(d)		Microwave	1	B1 cao
	(e)		Bar chart	2	B1 one column (mixer): 70, 90 B1 second column (fryer): 70, 85 [SC: B1 columns correct but reversed]

PAPER 5502					
No		**Working**	**Answer**	**Mark**	**Notes**
10	(a)		Acute	1	B1
	(b)		Reflex	1	B1
	(c)		reason	1	B1 reason eg 120 + 230 = 350 ≠ 360
11	(a)		$\frac{1}{2}$	1	B1 for $\frac{1}{2}$ oe
	(b)		reason	1	B1 for reason e.g could get 30 heads
12	(a)	7.5×4	30	2	M1 for 7.5×4 or $7\frac{1}{2} \times 4$ A1 cao
	(b)	$\sqrt{(42.25)}$	6.5	2	B2 for 6.5 (B1 for 42.25)
13	(a)		$6x$	1	B1 accept $6 \times x$, $x6$ oe
	(b)		$x - 4$	1	B1 cao
	(c)		$12(x - 4)$	1	B1 for $12(x - 4)$ or $12x - 48$ or $12 \times x - 48$ oe
	(d)		$18x - 48$	2	M1 for "$6x$" + "$12(x-4)$" or "$6x$" + "$12x - 48$" oe A1 ft $18x - 48$, $2(9x - 24)$, $3(6x - 16)$, $6(3x - 8)$
14	(a)		90	2	B2 for 90 ± 2 (B1 for 9 ± 0.2)
	(b)		317	1	B1 for 317 ± 4
15	(a)	Accurate drawing of triangle		2	B1 cao for 38° (±2°) B1 cao (indep) for BC drawn 7.3 cm (±2mm) and completing the triangle.
	(b)	Measure angle A	63°	1	B1 for 63° (±2°) or ft their diagram (±2°)

PAPER 5502					
	No	Working	Answer	Mark	Notes
16	(a)	0 × 1 = 0 1 × 1 = 1 2 × 4 = 8 3 × 8 = 24 4 × 8 = 32 5 × 7 = 35	100	3	M1 col 1 × col 2 (at least 3 shown) M1 (dep) sum of totals A1 cao SC: M1 M1 A0 for 101
	(b)	Either 35.50 ÷ 1.42 = 25; 26.99 – 25 = 1.99 Cheaper in the USA Or 26.99 × 1.42 = 38.33; 38.33 – 35.50 = 2.83 Cheaper in the USA		3	M1 35.50 ÷ 1.42 A1 25 seen B1 ft (dep on M1) £1.99 with conclusion (must have units) **OR** M1 26.99 × 1.42 A1 38.32 or 38.33… seen B1 ft (dep on M1) $2.83 or $2.82 with conclusion (must have units) must be to 2dp
17	(a)		-1, (1), (3), 5, 7, 9	2	B2 cao (B1 for 2 values)
	(b)		Graph	2	B1 ft for plotting points ±1/2 square B1 cao for line between $x = -2$ and $x = 3$
	(c)(i)		0.4	2	B1 for 0.4 or ft from single straight line with positive gradient
	(ii)		1.2		B1 for 1.2 or ft from single straight line with positive gradient

PAPER 5502					
	No	Working	Answer	Mark	Notes
18	(a)		Plots	1	B1 cao
	(b)		description	1	B1 dynamic relationship or "positive" (correlation)
	(c)		line of best fit	1	Line within overlay region, and to the extent of.
	(d)(i)	280 g →	reading	2	B1 ft from single straight line of positive gradient (±1/2 square)
	(ii)	120 pages →	reading		B1 ft from single straight line of positive gradient (±1/2 square)
19			200 150 225 150 10	3	B3 cao (B2 for three correct, or B1 for one correct)
20	(a)			2	B1 B1 for correct sketch – ignore additional internal lines B1 B0 for rectangle or right-angled triangle or correct shape without line NB 3-D sketch gets B0 B0
	(b)			2	B1 B1 for correct plan – ignore internal lines – accept a rotated plan, not reflected B1 B0 for a single rectangle drawn NB 3-D sketch gets B0 B0
21	(a)	163.25 – 35.50 = 127.75 127.75 ÷ 18.25 = 7	8	3	M1 163.25 – 35.50 (or sight of 127.75) M1 (dep) "127.75" ÷ 18.25 A1 cao SC: M2 for 7 days
	(b)	1.175 × £64 or $\frac{17.5}{100}$ × 64 or £11.20 seen	75.20	2	M1 1.175 × 64, 0.175 × 64 oe or 11.20 or 75.2 seen or 6.40, 3.20 and 1.60 seen A1 cao

PAPER 5502					
	No	Working	Answer	Mark	Notes
22	(a)		6	1	B1 cao
	(b)		$t^2 - 2t$	1	B1 oe
	(c)		$3(y - 4)$	1	B1 Accept $3 \times (y - 4)$ or $3(y - 4$
23	(a)		Reason	1	B1 Makes some mention of bias either directly or making reference to an insufficient or biased range of responses
	(b)		Reason	1	B1 (a) an insufficient range of responses (b) No mention of money (c) No time frame in the question (d) Misunderstanding of "A lot" and "Not much"

PAPER 5503				
No	**Working**	**Answer**	**Mark**	**Notes**
1		10.	1	B1 for 10
2 (a)(i)		$3e + 2f$	2	B1 for $3e + 2f$
(ii)		$3p^2$		B1 for $3p^2$
(b)	$5 \times -3 + 1$	-14	2	M1 for $5 \times -3 + 1$ A1 for -14
3	1974 6580 8554	855.4	3	M1 for complete correct method with relative place value correct, condone 1 error in multiplication. A2 cao (A1 for digits 8554 seen or A1 ft for "855.4" dependent on one arithmetic error only)
4 (a)		2 23 9 34 15 2 9 26 17 25 18 60	3	B3 all correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
(b)		$\frac{25}{60}$	1	B1 for $\frac{25}{60}$ or $\frac{5}{12}$ oe
5 (a)	$\frac{45}{100} \times 800$	360	2	M1 for $\frac{45}{100} \times 800$ oe A1 for 360
(b)	$\frac{176}{800} \times 100$	22	2	M1 for $\frac{176}{800} \times 100$ oe A1 for 22

PAPER 5503					
	No	Working	Answer	Mark	Notes
6	(a)	$\frac{11}{12}-\frac{10}{12}$	$\frac{1}{12}$	2	M1 for correctly writing both fractions to a common denominator A1 for $\frac{1}{12}$ oe
	(b)	$\frac{70\times400}{200}$	140	2	B2 for 140 (accept 136) (B1 for sight of any two of 70, 400 or 200)
7	(a)(i)		60	2	B1 for 60
	(ii)				B1 for all angles equal so equilateral triangle oe
	(b)(i)		130	3	B1 for 130
	(ii)				B1 for isosceles triangle oe B1 for angles on a straight line add up to 180°oe
	(c)		64	1	B1 for 64
8		$9\times1+3\times2+5\times3+3\times4$ (=42) "42" ÷ 20	2.1	3	M1 for 9×1, 3×2, 5×3, 3×4 or for 42 seen M1 (dep) "42" ÷ 20 A1 for 2.1 or $2\frac{1}{10}$ or $2\frac{2}{20}$
9	(a)		09 05	1	B1 for 09 05 oe
	(b)		7	1	B1 for 7
	(c)		10	1	B1 for 10
	(d)	7 km in 20 minutes	21	3	B1 for 20 (minutes) oe or $\times3$ seen M1 for $\frac{"7"}{"20"}$ A1 cao SC: "7" $\times3$ gets B1 M1

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
10		Vertices of new triangle at (2, −2) (2, 6) and (6, −2)	Correct triangle drawn	3	B3 cao (B2 for either correct triangle in wrong translated position or for 2 vertices correct) (B1 for a right-angled triangle with horizontal length 4 or vertical length 8 in the same orientation as shaded triangle) SC B2 for scale factor 3, totally correct
11		$2^2 + 3 =$	7 which is not even	2	B2 (B1 for correctly evaluating $n^2 + 3$ with a prime number value for n.)
12	(a)	360 ÷ 5	72	2	M1 for 360 ÷ 5 oe A1 for 72
	(b)	8560 ÷ (10 × 10)	85.6	2	M1 for 8560 ÷ (10 × 10) oe A1 for 85.6
	(c)(i)	Least length = 100.5	100.5	2	B1 for 100.5
	(ii)	Greatest length = 101.5	101.5		B1 for 101.5 or 101.499 or better
13		$2x + x + 100 + 47 = 360$ $2x + x = 360 - 100 - 47$ $x = 71$ Largest angle = $2x$ =	142	4	M1 for $2x + x + 100 + 47 = 360$ or 360 – 147 or 213 seen M1 (dep) for correctly separating x-terms and non x terms or $\frac{"360-147"}{3}$ A1 for $x = 71$ A1 ft (provided M2 awarded) for "142"
14	(a)(i)		2.21	2	B1 for 2.21
	(ii)		0.013		B1 for 0.013
	(b)	LCM = 3 × 13 × 17 = 3 × 221	663	2	M1 for 3 × 13 × 17 oe A1 for 663

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
15			Tick boxes 1,3 & 6	3	B1 for $\frac{\pi abc}{2d}$; B1 for $2a^2$; B1 for $2\left(c^2+d^2\right)$ (−B1 for each additional expression ticked (>3) to a minimum of 0)
16		200×0.2	40	2	M1 for 200×0.2 or $\frac{40}{200}$ seen A1 for 40
17	(a)	eg 2 | 108 2 | 54 3 | 27 3 | 9 3	$2^2 \times 3^3$	3	M2 for full systematic method of at least 4 divisions by prime numbers oe factor trees; condone 1 calculation error (M1 for 108 written as a correct product(s) with only one non-prime or equivalent division or a full process with 2 calculation errors.) A1 for $2^2 \times 3^3$ (accept $2 \times 2 \times 3 \times 3 \times 3$)
	(b)		12	1	B1 for 12
18		Perpendicular from P to intersecting arcs (within tramlines); perpendicular at least 2cm long		2	M1 relevant pair of arcs crossing within tramlines A1 SC M1 AO for a full construction of a perpendicular to AB not passing through P.
19		15×10	150 cm^3.	3	M1 for 15×10 A1 for 150 B1 for cm^3.

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
20			$y = 2x + 6$	2	B2 for $y = 2x + 6$ (B1 for $y = 2x + k$, $k \neq 1$ or for $y = mx + 6$, m $\neq 0$ or for $2x + 6$)
21		$6\frac{2}{5} = \frac{32}{5}$ Area of triangle = $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ (=2) Length of a side of sq. = $\sqrt{18 \times "2"}$ (=6) Perimeter of square = 4 × 6	24	5	B1 for $6\frac{2}{5} = \frac{32}{5}$ oe or $3\frac{1}{5} = \frac{16}{5}$ or $\frac{30}{8} + \frac{2}{8}$ oe (or implied by area of triangle=2) M1 for $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ oe M1 for area of square = 18 × product of two lengths A1 for $\sqrt{18 \times "2"}$ A1 for 24
22	(a)		$x(x-3)$	2	B2 for $x(x-3)$ (B1 for x (…….))
	(b)		k^3.	1	B1 for k^3.
	(c)(i)	$4x + 20 + 3x - 21$	$7x - 1$	4	M1 for **three** of 4 terms $4x + 20 + 3x - 21$ (or better) A1 for $7x - 1$
	(ii)	$x^2 + 3yx + 2xy + 6y^2$	$x^2 + 5xy + 6y^2$		M1 for **three** of 4 terms $x^2 + 3yx + 2xy + 6y^2$ A1 for $x^2 + 5xy + 6y^2$
	(d)		$(p+q)(p+q+5)$	1	B1 for $(p+q)(p+q+5)$

PAPER 5503					
	No	Working	Answer	Mark	Notes
23	(a)		32	1	B1 for 32 (accept 31.5 to 33.5 inclusive)
	(b)			3	B1 for ends of whiskers at 9 and 57, (with a box) B1 for ends of box at 16 and 45 (± 0.5) B1 for median marked at 32 or a complete box and whisker diagram drawn with a median inside the box
	(c)	Median(B)>Median(G); on average boys take longer IQR(B)>IQR(G); times for boys have a greater spread		2	B1 eg for comparison of medians B1 eg for comparison of (interquartile) ranges
24	(a)	$6y = 15 - 5x$	$y = \frac{15-5x}{6}$	2	M1 for either $6y = 15 - 5x$ or -6 $y = 5x - 15$ or for $\frac{5x}{6} + y = \frac{15}{6}$ or a correct ft on sign error to $y=$ A1 for $y = \frac{15-5x}{6}$ oe
	(b)	$6k + 5(-21) = 15$	20	2	M1 for substitution of $x = -21$ (or $x = 21$) into given equation or candidate's answer to (a) A1 for $k = 20$
	(c)(i)		Region R indicated	3	B2 correct region shaded (accept unshaded if R clear) (B1 shaded or R region satisfies 3 of the 4 given inequalities with same boundaries)
	(ii)		(1,1)		B1 for (1,1)

PAPER 5503					
	No	Working	Answer	Mark	Notes
25	(a)		60	1	B1 for 60 B1 for *BDC* = 25
	(b)	eg Angle *BDC* = 25 *ADB* = 60 − 25	35	2	[Award the mark for equivalent approaches] B1 ft for (a) − 25
	(c)	Ben is correct; angle *DAB* = 65 + 25 = 90 and since angle in a semi-circle is 90°, *BD* must be a diameter		1	B1 for full valid justification

PAPER 5504					
	No	Working	Answer	Mark	Notes
1	(a)	Accurate drawing of triangle		2	B1 cao for 38º (±2º) B1 cao (indep) for BC drawn 7.3 cm (±2mm) and completing the triangle.
	(b)	Measure angle A	63º	1	B1 for 63º (±2º) or ft their diagram (±2º)
2	(a)	0 × 1 = 0 1 × 1 = 1 2 × 4 = 8 3 × 8 = 24 4 × 8 = 32 5 × 7 = 35	100	3	M1 col 1 × col 2 (at least 3 shown) could be implied by answers. M1 (dep) sum of totals A1 cao SC: M1 M1 A0 for 101
	(b)	Either $35.50 ÷ 1.42 = £25; £26.99 - £25 = £1.99 Cheaper in the USA Or £26.99 × 1.42= $38.33; $38.33 - $35.50 = $2.83 Cheaper in the USA		3	M1 35.50 ÷ 1.42 A1 25 seen B1 ft (dep on M1) £1.99 with conclusion; units needed OR: M1 26.99 × 1.42 A1 38.33 or 38.32…seen B1 ft (dep on M1) $2.83 or $2.82 with conclusion; units needed
3	(a)		-1, (1), (3), 5, 7, 9	2	B2 cao (B1 for 2 values)
	(b)		Graph	2	B1 ft for plotting points ±1/2 square B1 cao for line between $x = -2$ and $x = 3$
	(c)(i)		0.4	2	B1 0.4 or ft single straight line with positive gradient
	(ii)		1.2		B1 1.2 or ft single straight line with positive gradient

PAPER 5504					
	No	Working	Answer	Mark	Notes
4	(a)			2	B1 Rectangle drawn B1 Triangle attached Ignore additional internal lines; 3D sketch gets B0
	(b)			2	B1 single Rectangle drawn B1 Attached smaller rectangle drawn Accept rotated plan, Ignore internal lines down; Nets get B0
5	(a)	£163.25 - £35.50 = £127.75 £127.75 ÷ £18.25 = 7	8	3	M1 163.25 – £35.50 (or sight of £127.75) M1 (dep) "127.75" ÷ 18.25 A1 cao SC: M2 for 7 days
	(b)	1.175 × £64 or $\frac{17.5}{100}$ × 64 or £11.20 seen	75.20	2	M1 1.175 × 64.00 0.175 × 64 oe or 11.20 or 75.2 seen OR 6.40, 3.20, and 1.60 seen A1 cao
	(c)	54 × £2.38 =	128.52	2	M1 54 × £2.38 A1 cao
6		Tessellation	Drawing	2	B2 seven additional hexagons, with at least 2 points at which 3 hexagons meet (B1 one point at which 3 hexagons meet).
7			200 150 225 150 10	3	B3 cao (B2 for three correct, or B1 for one correct)
8	(a)(i)	Bearing measured	70	2	B1 70 ± 4
	(ii)	Bearing measured	317		B1 317 ± 4
	(b)	Locus (circle) drawn & shaded		2	B1 circle ±2 mm centre Manchester B1 shading with accurate or approximate circle within tolerance

PAPER 5504					
	No	Working	Answer	Mark	Notes
9	(a)		Plots	1	B1 cao
	(b)		Description	1	B1 dynamic relationship or "positive" (correlation)
	(c)		Line of best fit	1	Line within overlay region, and to the extent of.
	(d)(i)	280 g →	Reading	2	B1 ft from single straight line of positive gradient (±1/2 square) B1 ft from single straight line of positive gradient (±1/2 square)
	(ii)	120 pages →	Reading		
10	(a)	$\frac{1}{6}, \frac{3}{8}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$		2	B2 for all correct (B1 for 1 error or all correct but wrong order, or use of a common denominator decimals).
	(b)	3/5, 65%, 2/3, 0.72, 3/4		2	B2 for all correct (B1 for 1 error or all correct but wrong order or conversions to decimals oe)
11	(a)		182, 178, 180, 184	2	M1 mean of any three consecutive months, eg (147 + 161 + 238) ÷ 3 oe A1 cao
	(b)	Sale price = 80% Fun Friday price = 70% of 80% = 56% (oe)		2	B1 B1 for a fully correct explanation involving a worked example (oe) B1 a partially complete explanation

PAPER 5504					
	No	Working	Answer	Mark	Notes
12	(a)		Reason	1	B1 makes a mention of bias, either directly, or making reference to an insufficient or biased range of responses.
	(b)(i)		Reason	1	B1 make some mention of any one of (a) an insufficient range of responses (b) no mention of money (c) no time frame in the question (d) misunderstanding of "a lot" or "not much"
	(ii)		Question	2	B2 B1 for each of the following upto B2 (a) an improved question eg time frame made clear (b) response boxes (imperfect) (c) response boxes no errors OR For suggesting a generally improved question (a) a question clearly in the context of changes to the canteen (b) at least 3 boxes showing a full range of responses
13	(a)	$20y - 18y = 16 - 9$ oe $2y = 7$	$3\frac{1}{2}$ oe	3	M1 $20y - 18y = 16 - 9$ oe M1 $2y = 7$ A1 cao
	(b)	$40 - x = 3(4 + x)$ $40 - x = 12 + 3x$ $40 - 12 = x + 3x$ $4x = 28$	7	3	M1 multiplying through by 3: $3 \times \frac{40 - x}{3} = 3 \times 4 + 3 \times x$ A1 $40 - 12 = x + 3x$ A1 cao
14	(a)		$12(x\text{-}4)$	1	B1 for $12(x - 4)$ or $12x - 48$ or $12 \times x - 48$ oe $x = 12(x - 4)$ gets B0
	(b)		$18x\text{-}48$	2	M1 $6x +$ "$12(x - 4)$" or $6x +$ "$12x - 48$" A1 ft a linear expression $18x - 48$, $2(9x - 24)$, $3(6x - 16)$, $6(3x - 8)$

PAPER 5504					
No		**Working**	**Answer**	**Mark**	**Notes**
15		x $x^3 - 2x$ 4.1 60.7(21) 4.2 65.6(88) 4.3 70.9(07) Accept answer to 1 dp 4.22 66.7(114) or more 4.23 67.2(269) 4.24 67.7(45) 4.25 68.2(656)	4.2	4	B2 for trial $4.1 \leq x \leq 4.3$ evaluated (B1 for trial $4 < x < 5$ evaluated) B1 for different trial $4.225 \leq x \leq 4.25$ evaluated B1 (dep on at least one previous B1) for 4.2 cao
16	(a)		1.0×10^{-9}	1	B1 accept 1×10^{-9} or just 10^{-9}
	(b)	$1 \div 5 \times 10^{-9}$	2×10^{8}	2	M1 for $1 \div$ ("5×10^{-9}") or digit 2 with zeros only seen Condone omission of bracket for M1. A1 cao
17	(a)	$\frac{6.27 \times 4.52}{4.81 + 9.63} = \frac{28.3404}{14.44} = 1.962631579$	1.9626…	2	B2 for 1.9626… (B1 for 28.34 or 14.44)
	(b)		1.96	1	B1 ft from (a) as rounded to 1dp or 2dp. Do not accept 2, 2.00, but accept 2.0
18			$d = 4n + 6$	2	B2 $d = 4n + 6$ oe (B1 $d = 4n + k$, k an integer or 0, $4n + 6$, $n = 4n + 6$)
19		Vol = $\pi \times 3.8^2 \times 2.5 = \pi \times 14.44 \times 2.5$ = 45.36… × 2.5 = 113.411 Mass = "113" × 1.5 = 170.1165	170	4	M1 for $\pi \times r^2 \times 2.5$ where r = is 3.8 or 7.6 A1 if $r = 3.8$ M1 for "113" × 1.5 A1 for 169.5 – 170.3 cao

PAPER 5504					
	No	Working	Answer	Mark	Notes
20	(a)	$10^2 + 6^2$ or 136 $\sqrt{(100+36)}$ or $\sqrt{136} = 11.66\ldots$	11.7	3	M1 $10^2 + 6^2$ or 136 seen M1 (dep) $\sqrt{100+36}$ or $\sqrt{136}$ A1 11.66 – 11.7
	(b)	$\cos x = \frac{8}{10}$ or 0.8 $x = \cos^{-1} 0.8 = 36.869^\circ$	36.9	3	M1 for $\cos = \frac{8}{10}$, cos = 0.8 (oe) M1 (dep) for $\cos^{-1}$ (oe) A1 for 36.86 – 36.9
21		$18x - 6y = 99$ $\quad 12x - 4y = 66$ $8x + 6y = 18$ $\quad 12x + 9y = 27$ $26x = 117$ $\quad -13y = 39$	$x = 4\frac{1}{2}$ $y = -3$	4	M1 correct process to eliminate either x or y (condone one error) A1 cao for non – eliminated one. M1 (dep on 1st M1) for correct substitution of their found value. A1 cao (need both)
22		$\frac{133}{72} = 1.8472, \frac{160}{82} = 1.9512$ OR $\frac{72}{133} = 0.54135, \frac{82}{160} = 0.5125$ OR $\frac{160}{133} = 1.203...., \frac{82}{72} = 1.1388....$ OR $\frac{133}{160} = 0.83125...., \frac{72}{82} = 0.878$	1.84..≠ 1.95.. 1.20..≠ 1.13..	3	M1 for $\frac{133}{72}$ (= 1.8472…) oe Accept 1.8, 1.85 M1 for $\frac{160}{82}$ (=1.9512…) oe consistent pairing Accept 2.0, 1.9 **OR** M1 for $\frac{160}{133}$ (= 1.203…) oe M1 for $\frac{82}{72}$ (=1.1388) oe A1 for enough decimal places to show that the ratios are not equal; since the scale factors are different the shapes cannot be similar. NB Do Not need conclusion

PAPER 5504					
	No	Working	Answer	Mark	Notes
23	(a)		0.4, 0.6 0.4, 0.6, 0.4	2	B1 for LHS: (0.6), 0.4 B1 for RHS: 0.6, 0.4, 0.6, 0.4
	(b)	(30 × 42) – (25 × 42.8) = 1260 – 1070 = 190 190 ÷ 5 =	38	3	M1 for (30 × 42) – (25 × 42.8) or 1260 – 1070 or 190 seen M1 (dep) for "190" ÷ 5 A1 cao
24	(a)	£12000 × 0.25 = £3000; £12000 – £3000 = £9000 £9000 × 0.25 = £2250; £9000 – £2250 = £6750 £6750 × 0.25 = £1687.50; £6750 – £1687.50 =	£5062.50	3	M1 for 12000 × 0.75 (=9000) oe or £3000 or £23437.50 seen M1 (dep) for at least two further depreciation calculations (complete steps) A1 cao **OR** M2 for $12000 \times (0.75)^3$ or 5062.50 seen (M1 for $12000 \times (0.75)^n$, $n = 2$ or 4)
	(b)	0.8 × 0.8 × 0.8 × 0.8 (oe)	0.4096	2	M1 0.8^4 (oe) A1 cao

PAPER 5505					
	No	Working	Answer	Mark	Notes
1	(a)(i) (ii) (b)	 LCM = 3 × 13 × 17 = 3 × 221	2.21 0.013 663	2 2	B1 for 2.21 B1 for 0.013 M1 for 3 × 13 × 17 oe A1 for 663
2			Tick boxes 1,3 & 6	3	B1 for $\frac{\pi abc}{2d}$; B1 for $2a^2$; B1 for $2(c^2 + d^2)$ (−B1 for each additional expression ticked (>3) to a minimum of 0)
3	(a) (b)	200 × 0.2 0.2 + 0.4	40 0.6	2 2	M1 for 200 × 0.2 or $\frac{40}{200}$ seen A1 for 40 M1 for 0.2 + 0.4 A1 for 0.6
4	(a) (b)	eg 2 | 108 2 | 54 3 | 27 3 | 9 3 12	$2^2 \times 3^3$ 12	3 1	M2 for full systematic method of at least 4 divisions by prime numbers oe factor trees; condone 1 calculation error (M1 for 108 written as a correct product with only one non-prime or equivalent division or a full process with 2 calculation errors.) A1 for $2^2 \times 3^3$ (accept 2 × 2 × 3 × 3 × 3) B1 for 12
5		Perpendicular from P to intersecting arcs (within tramlines); perpendicular at least 2 cm long		2	M1 relevant pair of arcs crossing within tramlines A1 SC M1A0 for full construction of a line perpendicular to AB not through P
6		15 × 10	150 cm^3.	3	M1 for 15 × 10 A1 for 150 B1 for cm^3

PAPER 5505					
	No	Working	Answer	Mark	Notes
7	(a)		k^3.	1	B1 for k^3.
	(b)(i)	$4x + 20 + 3x - 21$	$7x - 1$	4	M1 for **three** of 4 terms $4x + 20 + 3x - 21$ (or better) A1 for $7x - 1$
	(ii)	$x^2 + 3yx + 2xy + 6y^2$	$x^2 + 5xy + 6y^2$		M1 for **three** of 4 terms $x^2 + 3yx + 2xy + 6y^2$ A1 for $x^2 + 5xy + 6y^2$
	(c)		$(p+q)(p+q+5)$	1	B1 for $(p+q)(p+q+5)$
	(d)		m^8	1	B1 for m^8.
	(e)		$6r^3t^6$	2	B2 for $6r^3t^6$ (B1 for $.....r^3t^6$ or for $6....t^6$)
8	(i)	Least length = 100.5	100.5	2	B1 for 100.5
	(ii)	Greatest length = 101.5	101.5		B1 for 101.5; ACCEPT 101.499 or better
9		$6\frac{2}{5} = \frac{32}{5}$ Area of triangle = $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ (= 2) Length of a side of sq. = $\sqrt{18 \times "2"}$ (=6) Perimeter of square = 4 × 6	24	5	B1 for $6\frac{2}{5} = \frac{32}{5}$ oe or $3\frac{1}{5} = \frac{16}{5}$ oe or $\frac{30}{8} + \frac{2}{8}$ oe (or implied by area of triangle=2) M1 for $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ oe M1 for (area of square) = 18 × product of two lengths A1 = $\sqrt{18 \times "2"}$ A1 for 24

PAPER 5505					
	No	Working	Answer	Mark	Notes
10	(a)	$6y = 15 - 5x$	$y = \frac{15-5x}{6}$	2	M1 for either $6y = 15 - 5x$ or for $\frac{5x}{6} + y = \frac{15}{6}$ or $-6y = 5x - 15$ or a correct ft on sign error to $y =$ A1 for $y = \frac{15-5x}{6}$ oe
	(b)	$6k + 5(-21) = 15$	20	2	M1 for subst. of $x = -21$ (or $x = 21$) into given eq^n or answer to (a) A1 for $k = 20$
	(c)(i)		Region R indicated	3	B2 correct region shaded (accept unshaded if R clear) (B1 shaded (R) region satisfies 3 of the 4 given inequalities with same boundaries)
	(ii)		(1,1)		B1 for (1,1)
11	(a)		$y = 2x + 6$	2	B2 for $y = 2x + 6$ (B1 for $y = 2x + k$, $k \neq 1$ or for $y = mx + 6$, $m \neq 0$ or for $2x+6$)
	(b)	Grad of $AB = 2$; Grad of $BC = \frac{-1}{"2"}$	$y = -\frac{1}{2}x + 6$	2	M1 for Grad of $BC = \frac{-1}{"2"}, -\frac{1}{2}$ or grad of $BC = -\frac{1}{\text{grad of AB}}$ A1 ft for $y = -\frac{1}{2}x + 6$ oe ft on wrong coeff. of x in (a)
	(c)	Eg A rectangle is always a cyclic quadrilateral because the opposite angles of a rectangle always add up to 180° (90+90)		1	B1 for valid explanation. (eg lines from the pt of int. of diagonals of rect to all 4 vertices are equal(radii))
12		Vertices of new triangle at $(-1, -4)$ $(-4, 2)$ and $(2, 2)$	Correct triangle drawn	3	B3 cao (B2 for 3 correct vertices no triangle or triangle with 2 correct vertices (B1 for triangle with two of six co-ordinates correct from using P as centre or any isosceles triangle with base 6 and height 6)

PAPER 5505					
	No	Working	Answer	Mark	Notes
13	(a)		32	1	B1 for 32 (accept 31.5 to 33.5 inclusive)
	(b)			3	B1 for ends of whiskers at 9 and 57 (with a box) B1 for ends of box at 16 and 45/46 ($\pm$ 0.5) B1for median marked at "32"or complete box and whisker diagram drawn with a median inside the box
	(c)	Median(B)>Median(G); on average boys take longer IQR(B)>IQR(G); times for boys have a greater spread		2	B1 eg for comparison of medians (ft on diagrams) B1 eg for comparison of (interquartile) ranges (ft on diagram)
14		Reading top to bottom frequencies are 20; 18; 45; 52		2	B2 all correct (B1 for one frequency correct)
15	(a)	$1600 = p\,q^0$.; $400 = pq^2$ $q^2 = 0.25$	$p = 1600$ $q = 0.5$	3	M1 for either $400 = pq^2$ or $1600 = pq^0$ B1 for $p = 1600$ A1 for $q = 0.5$
	(b)	$V = pq^{-2}$	6400	2	M1 for recognition that t = –2 A1 for 6 400

PAPER 5505					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	(I) $AB = AC$ (triangle ABC is isosceles) (II) PB = PC tangents (from a point to a circle are) equal (III) AP = AP (common side) so the 2 triangles are congruent ,SSS.		3	B3 for I, II, III with congruency reason (B2 for any two of I, II or III) (B1 for any one of the I, II or III)
	(b)	$BPC = 20°$ PBC (or PCB) = 90-1/2 "20" (= 80°) $BAC = PBC$ = "80"	50°	4	B4 for 50° (B3 for $BAC = 80°$) (B2 for $PBC = 80°$ or $PCB = 80°$) (B1 for $APC = 10°$ or $BPC = 20°$ or a middle angle = 90°) SC if clear numerical slip seen eg "PBC = 180 – 90 – 10 = 70" then goes on to get correct ft angle $ABC = 55$ deduct 1 from total so this cand would get B4–1 = B3
17	(a)	$\overrightarrow{OP} = \overrightarrow{OA} + \overrightarrow{AP}$ $= \overrightarrow{OA} + \frac{2}{3}(6\mathbf{c} - 6\mathbf{a})$ $= 6\mathbf{a} + 4\mathbf{c} - 4\mathbf{a}$	$2\mathbf{a} + 4\mathbf{c}$	3	M1 for $\overrightarrow{OP} = \overrightarrow{OA} + \overrightarrow{AP}$ or any correct vector journey involving $\overrightarrow{OP}$ M1 for $\overrightarrow{AP} = \frac{2}{3}(6\mathbf{c} - 6\mathbf{a})$ oe or $\overrightarrow{CP} = \frac{1}{3}(-6\mathbf{c} + 6\mathbf{a})$ oe or reverse vectors A1 for $2\mathbf{a} + 4\mathbf{c}$ oe (accept unsimplified)
	(b)	Eg $\overrightarrow{OM} = \overrightarrow{OC} + \overrightarrow{CM} = 6\mathbf{c} + 3\mathbf{a}$ $\overrightarrow{OM} = 1.5\overrightarrow{OP}$	$\overrightarrow{OM} = 1.5\overrightarrow{OP}$ so OPM is a straight line	2	B1 for $\overrightarrow{OM} = 6\mathbf{c} + \frac{1}{2}(6\mathbf{a})$ or $\overrightarrow{PM} = 2\mathbf{c} + \mathbf{a}$ unsimplified or reverse vectors B1 for a fully correct proof.

PAPER 5505					
	No	Working	Answer	Mark	Notes
18	(a)		4	1	B1 for 4 condone $\pm$ 4
	(b)		2	1	B1 for 2 condone ± 2
	(c)	$\sqrt{160} = 4\sqrt{10}$; $\left[\frac{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)-\sqrt{2}\times\sqrt{5}}{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)}\right]\times 100$ $\left[\frac{6\sqrt{10}-\sqrt{10}}{6\sqrt{10}}\right]\times 100$	$\frac{500}{6}$	4	B1 for **either** $\sqrt{160} = 4\sqrt{10}$ or $\sqrt{8} = 2\sqrt{2}$ **or** $\sqrt{20} = 2\sqrt{5}$ M1 for $\left[\frac{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)-\sqrt{2}\times\sqrt{5}}{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)}\right]$ oe $(\times 100)$ B1 for either $6\sqrt{10} - \sqrt{10}$ or $6\sqrt{10}$ A1 for $\frac{500}{6}$ (accept 83.3 if no obvious earlier error)

PAPER 5505					
	No	Working	Answer	Mark	Notes
19	(a)(i)		$(2x-7)(x-14)$	3	M1 x^2 term and constant term (± 98) obtained or $2x(x-14) - 7(x-14)$ or $x(2x-7) - 14(2x-7)$ A1 for $(2x-7)(x-14)$
	(ii)		$x = \frac{7}{2}$; $x = 14$		B1ft ft (i) provided of form $(2x\pm a)(x\pm b)$
	(b)(i)		$\frac{7}{n+7}$	3	B1 for $\frac{7}{n+7}$ oe
	(ii)	$\frac{7}{n+7} = \frac{2}{5} \Rightarrow 2(n+7) = 5 \times 7$ $2n = 21$	$n=10.5$ is not possible since n has to be an integer		M1 for $2(n+7) = 5\times 7$ or $n+7=5\times 3.5$ (can be implied) ft (b)(i) fractional in terms of n and < 1 A1 ft for $n=10.5$ not possible (since n not integer) oe
	(c)	$2\times\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right) = \frac{4}{9}$ $14n\times 9 = 4(n+7)^2$ $14n\times 9 = 4(n^2+14n+49)$ $4n^2+56n+196-126n = 0$	$2n^2 - 35n + 98 = 0$	5	M1 for $\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right)$ seen M1 for $2\times\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right)$ oe $(=\frac{4}{9})$ M1(dep on 1st M) elimination of fractions within an equation B1 3 terms correct in expansion of $(n+7)^2 = n^2 + 7n + 7n + 49$ A1 full valid completion to printed answer

PAPER 5505					
	No	Working	Answer	Mark	Notes
	(d)	$\frac{7}{n+7}\times\frac{7}{n+7}=\frac{7}{21}\times\frac{7}{21}=$	$\frac{1}{9}$	2	M1 for $\frac{7}{n+7}\times\frac{7}{n+7}$ or better or ft [answer (b)(i)]^2 or $1-\frac{4}{9}-(\frac{n}{n+7})^2$ A1 for $\frac{1}{9}$ oe cao
20	(a)(i)		$y=1+\sin x$	2	B1 for $y=1+\sin x$
	(ii)		$y=2\sin x$		B1 for $y=2\sin x$ SC both (i) f(x) + 1, (ii) 2f(x) B1
	(b)	Stretch parallel to y-axis scale factor 3 Stretch parallel to x-axis scale factor $\frac{1}{2}$		3	M1 for 'stretch' A1 for Stretch parallel to y-axis scale factor 3 oe A1 for Stretch parallel to x-axis scale factor $\frac{1}{2}$ oe SC if M0 award BI for "sf 3 vertically" **and** "sf $\frac{1}{2}$ horizon."

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
1		Question	2	B1 for each of the following upto B2 (a) an improved question eg time frame made clear (b) response boxes (imperfect) (c) response boxes no errors OR For suggesting a generally improved question (a) a question clearly in the context of changes to the canteen (b) at least 3 boxes showing a full range of responses
2	Locus (circle) drawn & shaded		2	B1 circle centre Manchester ±2mm B1 shading with accurate or approximate circle within tolerance
3 (a)		182, 178, 180, 184	2	M1 mean of any three consecutive months, eg (147 + 161 + 238) ÷ 3 oe A1 cao
(b)	Sale price = 80% Fun Friday price = 70% of 80% = 56% (oe)		2	B1 B1 for a fully correct explanation involving a worked example (oe) B1 a partially complete explanation
4	x $x^3 - 2x$ 4.1 60.7(21) 4.2 65.6(88) 4.3 70.9(07) 4.22 66.7(114) 4.23 67.2(269) 4.24 67.7(45) 4.25 68.2(656)	4.2	4	B2 for trial $4.1 \leq x \leq 4.3$ evaluated (B1 for trial $4 < x < 5$ evaluated) B1 for different trial $4.225 \leq x \leq 4.25$ evaluated B1 (dep on at least one previous B1) for 4.2 cao

PAPER 5506					
	No	Working	Answer	Mark	Notes
5	(a)		1.0×10^{-9}	1	B1 accept 1×10^{-9} or just 10^{-9}
	(b)	$1 \div (5 \times 10^{-9})$	2×10^{8}	2	M1 for $1 \div$ ("5×10^{-9}") or digit 2 with zeros only seen Condone omission of bracket for M1. A1 cao
6	(a)	$\frac{6.27 \times 4.52}{4.81 + 9.63} = \frac{28.3404}{14.44} = 1.962631579$	1.9626…	2	B2 for 1.9626… (B1 for 28.34… or 14.44)
	(b)		1.96	1	B1 ft from (a) as rounded to 1dp or 2dp. Do not accept 2, 2.00, but accept 2.0
7			$d = 4n + 6$	2	B2 $d = 4n + 6$ oe (B1 $d = 4n + k$, k an integer $\neq 6$, $4n + 6$, $n = 4n + 6$)
8		Vol = $\pi \times 3.8^2 \times 2.5 = \pi \times 14.44 \times 2.5$ $= 45.36\ldots \times 2.5 = 113.411$ Mass = "113" × 1.5 = 170.1165	170	4	M1 for $\pi \times r^2 \times 2.5$ where r = is 3.8 or 7.6 A1 if $r = 3.8$ M1 for "113" × 1.5 A1 for 169.5 – 170.3 cao

PAPER 5506					
	No	Working	Answer	Mark	Notes
9	(a)	$10^2 + 6^2$ or 136 $\sqrt{(100 + 36)}$ or $\sqrt{136} = 11.66\ldots$	11.7	3	M1 for $10^2 + 6^2$ or 136 seen M1 (dep) $\sqrt{100+36}$ or $\sqrt{136}$ A1 11.66 – 11.7
	(b)	Cos x = 8/10 or 0.8 $x = \cos^{-1} 0.8 = 36.869^o$	36.9	3	M1 for cos = $\frac{8}{10}$, cos = 0.8(oe) M1 (dep) for $\cos^{-1}$ (oe) A1 for 36.86 – 36.9 M1 Use of sine rule and x found M1 for $x = 90 - \sin^{-1}$("0.8") A1 for 36.86 – 36.9
10		$18x - 6y = 99$ $12x - 4y = 66$ $8x + 6y = 18$ $12x + 9y = 27$ $26x = 117$ $-13y = 39$	$x = 4\frac{1}{2}$ $y = -3$	4	M1 correct process to eliminate either x or y (condone one error) A1 cao for non – eliminated one. M1 (dep on 1st M1) for correct substitution of their found value. A1 cao (need both)

PAPER 5506					
	No	Working	Answer	Mark	Notes
11		$\frac{133}{72} = 1.8472\,,\ \frac{160}{82} = 1.9512$ OR $\frac{72}{133} = 0.54135, \frac{82}{160} = 0.5125$ OR $\frac{160}{133} = 1.203...., \frac{82}{72} = 1.1388....$ OR $\frac{133}{160} = 0.83125...., \frac{72}{82} = 0.878$	1.84..≠ 1.95.. 1.20..≠ 1.13..	3	M1 for $\frac{133}{72}$ (= 1.8472…) oe Accept 1.8, 1.85 M1 for $\frac{160}{82}$ (=1.9512…) oe consistent pairing Accept 2.0, 1.9 **OR** M1 for $\frac{160}{133}$ (= 1.203…) oe M1 for $\frac{82}{72}$ (=1.1388) oe A1 for enough decimal places to show that the ratios are not equal; since the scale factors are different the shapes cannot be similar. NB Do Not need conclusion
12	(a)	£12000 × 0.25 = £3000; £12000 – £3000 = £9000 £9000 × 0.25 = £2250; £9000 – £2250 = £6750 £6750 × 0.25 = £1687.50; £6750 – £1687.50 =	£5062.50	3	M1 for 12000 × 0.75 (=9000) oe or £3000 or £23437.50 seen M1 (dep) for at least two further depreciation calculations (complete steps) A1 cao **OR** M2 for 12000 × $(0.75)^3$ or 5062.50 seen (M1 for 12000 × $(0.75)^n$, $n = 2$ or 4)
	(b)	0.8 × 0.8 × 0.8 × 0.8 (oe)	0.4096	2	M1 0.8^4 (oe) A1 cao

PAPER 5506					
No		**Working**	**Answer**	**Mark**	**Notes**
13		$r^2 = \frac{3\times10}{\pi h} = \frac{3\times10}{\pi 1.5} = \frac{3\times10}{4.712..} = 6.36, 6.37$ $r = \sqrt{6.366\ldots}$	2.52-2.54	3	M1 for correct rearrangement to give $r^2 = \frac{3V}{\pi h}$ or $30 \div 4.712..$ or $6.36 - 6.37$ *Allow 0.3, 0.33 for* $\frac{1}{3}$ M1 (dep) for $\sqrt{}$ A1 cao 2.52 – 2.54
14	(a)		0.4 0.6,0.4, 0.6,0.4	2	B1 for LHS: (0.6), 0.4 B1 for RHS: 0.6, 0.4, 0.6, 0.4
	(b)	0.6×0.6	0.36	2	M1 $0.6 \times$ "0.6" [0 < "0.6" < 1] A1 cao
	(c)	$(30 \times 42) - (25 \times 42.8) = (1260 - 1070 = 190$ $190 \div 5 =$	38	3	M1 for $(30 \times 42) - (25 \times 42.8)$ or $1260 - 1070$ or 190 seen M1(dep) for "190" ÷ 5 A1 cao 38

PAPER 5506					
	No	Working	Answer	Mark	Notes
15	(a)	$S = \frac{k}{f^2};\ 125 = \frac{k}{8^2};\ k = 8000$	$S = \frac{8000}{f^2}$	3	M1 for $S = \frac{k}{f^2}$ M1 for $125 = \frac{k}{8^2}$ A1 cao These marks can be awarded if the full formula appears in part (b), rather than in part (a). [SC: $S = \frac{125}{64} f^2$ M1 M0 A0, $S = 1.95(3125) f^2$ M1 M0 A0 $S = \frac{1000}{f}$ M1 M0 A0]
	(b)		500	1	B1 cao

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
16	$0.5 \times 3.2 \times 8.4 \times \text{Sin } B = 10$ sin $B = 0.74404\ldots$ 48.077 $AC^2 = 3.2^2 + 8.4^2 - 2 \times 3.2 \times 8.4 \times \cos B$ $AC^2 = 44.8815\ldots..$ $AC = 6.69\ (936\ldots)$ Perimeter = 18.3 Use the altitude AD, $\frac{h \times 8.4}{2} = 10 \Rightarrow h = (2.381)$ $BD = \sqrt{3.2^2 - h^2} = 2.139$ $DC = 6.261$ $AC = \sqrt{2.38^2 + '6.261'^2} = 6.69(936)$ Perimeter = 18.3	18.3	6	M1 for $0.5 \times 3.2 \times 8.4 \times \sin B$ (= 10) A1 for sin B = 0.74(404…) or B = 47.7 – 48.1 M1 for $3.2^2 + 8.4^2 - 2 \times 3.2 \times 8.4 \times \cos$ "48.077" M1(dep) for AC^2 = "44.8(815)"….. with correct order of evaluation A1 $AC = 6.69 - 6.7$ A1 18.29 – 18.3 **for** $\frac{h \times 8.4}{2} = 10 \Rightarrow h = (2.381)$ M1 for $BD^2 = 3.2^2 - "2.381"^2$ A1 $BD = 2.1 - 2.2$ M1 (dep) $AC^2 = "2.381"^2 + "6.261"^2$ A1 $AC = 6.69 - 6.7$ A1 18.29 – 18.3

PAPER 5506					
	No	Working	Answer	Mark	Notes
17	(a)	$(x + 8)^2 = x^2 + (x + 5)^2$ $x^2 + 16x + 64 = 2x^2 + 10x + 25$		4	B1 for angle $OTA = 90°$ (implied by use of Pythagoras with OA as hypotenuse) M1 $(x + 8)^2 = x^2 + (x + 5)^2$ oe M1 for correct squaring of x+8 or x+5 A1 for completion following correct working
	(b)	$(+6 + \sqrt{(6^2 - - 4\times39)})/2$ $= (6 \pm \sqrt{(36 + 156)})/2$ $= (6 \pm \sqrt{192})/2 = (6 + 13.856)/2$	9.93	3	M1 for substitution into quadratic formula, allow sign errors in b and c M1 for $x = (6 \pm \sqrt{192})/2$ [+ alone will do] A1 for 9.92 – 9.93 M1 for $(x-3)^2-9-39$ M1 for $x = 3 \pm \sqrt{48}$ [+ alone will do it] A1 for 9.92 – 9.93 T&I= 9.93 gets M1,M0,A0
18		$EB = 60 \times \tan 30°$ $BD = \sqrt{(60^2 + 60^2)}$ $\tan BDE = 34.64 \div 84.85$ $EB = 60 \times \tan 30°$ (= 34.64) $ED^2 = 60^2 + (\frac{60}{\cos 30})^2$ $ED = \sqrt{8400} = (91.65)$ $\text{Angle} = \sin^{-1}\left(\frac{EB}{\sqrt{8400}}\right) = 22.2$	22.2°	4	M1 for $EB = 60\times\tan30$ M1 for $BD = \sqrt{(60^2 + 60^2)}$ M1 for $\tan BDE$ = "34.64" ÷ "84.85" A1 22.17 – 22.21 M1 for $EB = 60 \times \tan 30°$ oe M1 for fully correct method for ED M1 for $\sin BDE = \left(\frac{'34.84'}{'\sqrt{8400}'}\right)$(oe) A1 22.17 – 22.21

PAPER 5506					
	No	Working	Answer	Mark	Notes
19	(a)	$x^2 + 6^2 = 25$ $x^2 = -11$		2	M1 substitutes y=6 to get x^2+36 = 25 A1 deduces x^2=25-36<0; impossible, (so line does not intersect curve)
	(b)	$y^2 = (2x - 2)^2$ $x^2 + (2x - 2)^2 = 25$ $x^2 + 4x^2 - 8x + 4 = 25$ $5x^2 - 8x + 4 - 25 = 0$ $5x^2 - 8x - 21 = 0$ $(5x + 7)(x - 3) = 0$ or $x = \frac{--8 \pm \sqrt{(-8)^2 - 4 \times 5 \times (-21)}}{10} = \frac{8 \pm \sqrt{484}}{10}$ So $x = 3$, or $x = -1.4$ Subs into either equation gives: $y = 4$, or $y = -4.8$	$x = 3$ $y = 4$ $x = -1.4$ $y = -4.8$	6	M1 $y^2=(2x-2)^2$ seen or implied A1 $x^2 + 4x^2 - 8x + 4 = 25$ (oe expanded form) M1 correct attempt to solve 3 term quadratic equation A1 $x = 3$, $x = -1.4$ M1 (dep on previous Ms) Sub one value of x into either equation gives: A1 $y = 4$, $y = -4.8$ NB: incorrectly matched pairs loses the final A1.

PAPER 5506					
	No	Working	Answer	Mark	Notes
20	(a)	400.005 ÷ 59.95 = 6.672310 6.672310 ÷ 1000 × 3600 = 24.02032 399.995 ÷ 60.05 = 6.661032 6.661032 ÷ 1000 × 3600 = 23.97972	24.020 23.980	5	B1 for 400.005 or 59.95 seen oe M1 for "400.005" ÷ "59.95" where "400.005" ∈ [400.005,400.5] and "59.95" ∈ [59.5,59.95] oe B1 for 399.995 or 60.05 seen oe M1 for "399.995" ÷ "60.05" where "399.995" ∈ [399.5,399.95] and "60.05" ∈ [60.05,60.5] oe A1 23.979-23.980 and 24.020-24.0204
	(b)	24.0 because to 1dp the answers are the same		1	B1cao for 24.0 with reason
	(c)	177 × 50/477 = 18.553 → 19 → 18 111 × 50/477 = 11.635 → 12 86 × 50/477 = 9.0147 → 9 82 × 50/477 = 8.595 → 9 21 × 50/477 = 2.201 → 2	18 12 9 9 2	3	M1 for $\frac{50}{"477"} \times 177$ or 111 or 86 or 82 or 21 A1 for all integers or better answers, at least 3 correct A1 cao
21	(a)	$40 - x = 3(4 + x)$ $40 - x = 12 + 3x$ $40 - 12 = x + 3x$ $4x = 28$	7	3	M1 multiplying through by 3: $3 \times \frac{40 - x}{3} = 3 \times 4 + 3 \times x$ A1 $40 - 12 = x + 3x$ A1 cao
	(b)	$\frac{2x(2x - 3)}{(2x - 3)(2x + 3)} = \frac{2x}{2x + 3}$	$\frac{2x}{2x + 3}$	3	B1 for $(2x-3)(2x+3)$ B1 for $2x(2x-3)$ or $(2x + 0)(2x + 3)$ B1 cao

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
22	Distance from x axis is y. Distance from (0, 2) is $\sqrt{(x^2+(y-2)^2)}$ $y^2 = x^2 + (y-2)^2$ $y^2 = x^2 + y^2 - 4y + 4$ $0 = x^2 - 4y + 4$ $4y = x^2 + 4$ and finish		4	B1 for $(x-0)^2 + (y-2)^2$ or $\sqrt{((x-0)^2+(y-2)^2)}$ oe seen B1 for $y = \sqrt{(x-0)^2+(y-2)^2}$ or $y^2 = (x-0)^2 + (y-2)^2$ oe B1 $(y-2)^2 = y^2 - 4y + 4$ seen B1 for $4y = x^2 + 4$ and finish

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone: 01623 467467
Fax: 01623 450481
Email: publications@linneydirect.com

Order Code UG015616 July 2004

For more information on Edexcel and BTEC qualifications please contact
Customer Services on 0870 240 9800
or http://enquiries.edexcel.org.uk
or visit our website: www.edexcel.org.uk

London Qualifications Limited, trading as Edexcel. Registered in England and Wales No. 4496750
Registered Office: Stewart House, 32 Russell Square, London WC1B 5DN



edexcel

Edexcel GCSE

Mathematics A 1387

June 2007

advancing learning, changing lives

Mark Scheme

Edexcel GCSE

Mathematics A 1387

Table Of Contents

Notes on Marking Principles	3 - 4
5521 / 01 Mark Scheme	5 - 11
5521 / 02 Mark Scheme	12 – 17
5523 / 03 Mark Scheme	18 – 27
5523 / 04 Mark Scheme	28 – 35
5525 / 05 Mark Scheme	36 – 43
5525 / 06 Mark Scheme	44 - 52

NOTES ON MARKING PRINCIPLES

1 **Types of mark**
M marks: method marks
A marks: accuracy marks
B marks: unconditional accuracy marks (independent of M marks)

2 Abbreviations
cao – correct answer only
ft – follow through
isw – ignore subsequent working
SC: special case
oe – or equivalent (and appropriate)
dep – dependent
indep - independent

3 No working
If no working is shown then correct answers normally score full marks
If no working is shown then incorrect (even though nearly correct) answers score no marks.

4 With working
If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks. Discuss each of these situations with your Team Leader.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.
If there is no answer on the answer line then check the working for an obvious answer.

5 Follow through marks
Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

6 Ignoring subsequent work

It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: eg. incorrect cancelling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect eg algebra.
Transcription errors occur when candidates present a correct answer in working, and write it incorrectly on the answer line; mark the correct answer.

7 Probability

Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

8 Linear equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

9 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

Remember: if you are having difficulty making a decision on how you should mark a candidate response contact your Team Leader for advice, or send the item to review.

Paper 5521_01					
No		Working	Answer	Mark	Notes
1		Cat |||| /||| 8 Dog |||| | 6 Fish || 2 Hamster |||| 4	8, 6, 2, 4	3	M1 for attempt to tally or one frequency correct in either column A1 for 1 frequency correct or all tallies correct in correct column A1 for all frequencies correct (accept if /20)
2			27, 35, 42, 67, 118	1	B1 cao
3	(a)		Diameter drawn	1	B1 for a diameter
	(b)		Right angle marked	1	B1 *R* marked correctly
	(c)		Rectangle drawn	1	B1 for a rectangle
4	(a)		40	1	B1 cao
	(b)		50	1	B1 cao
	(c)		3 full loaves 4 full loaves + 1 half loaf	2	B1 for 3 full loaves B1 for 4 full loaves + 1 half loaf
5	(a)		7252	1	B1 cao
	(b)		Three thousand and eighty six	1	B1 accept 3 thousand and eighty six (condone 0 hundred)
	(c)		4600	1	B1 accept 4600
	(d)		200	1	B1 for 200 or 2 hundred or 100 or hundred
6	(i)		Cube	2	B1 for 'cube' (accept 'cuboid') ignore spelling
	(ii)		Cylinder		B1 for 'cylinder' ignore spelling
7		5×100	500	2	B2 for 490 or 500 or 510 (B1 for either 5 or 5.0 or 100 seen)

Paper 5521_01					
No		**Working**	**Answer**	**Mark**	**Notes**
8	(a)		8.4 cm or 84 mm	2	B2 allow ±2mm (B1 for 8.4 or 84, B1 for appropriate unit)
	(b)		37°	1	B1 allow ±2°
9	(a)		Carbon black	1	B1 accept 'black carbon' accept 26%
	(b)		0.1(0)	1	B1 cao
	(c)		0.04	1	B1 cao
	(d)	$\frac{26}{100}$	$\frac{13}{50}$	2	M1 for $\frac{26}{100}$ A1 cao
10	(a)		97	1	B1 cao
	(b)		London Reading	1	B1 cao
	(c)	41 + 57 + 58	156	3	M1 for two of 41, 57, 58 M1(dep) for '41' + '57' + '58' A1 cao
11	(a)		3	1	B1 cao allow ± 0.2
	(b)		–5	1	B1 cao allow ±0.2

Paper 5521_01					
No		**Working**	**Answer**	**Mark**	**Notes**
12	(a)		Centimetres (cm) miles litres (*l*)	3	B3 (B1 for each correct answer) accept abbreviations
	(b)		300	1	B1 cao
	(c)	'1500>1400' or '1.5>1.4'	Reason	1	B1 for No and '1500>1400' or '1.5>1.4'
13	(a)	Height of bars 12, 8, 6 lines drawn between points	Bars drawn	2	B2 for 3 bars correctly drawn (B1 for 2 bars correct)
	(b)		July and August	1	B1 oe
	(c)	24 – 4	20	1	B1 (Accept '4 to 24' oe)
	(d)	The temperatures are rising	Temp's rising oe	1	B1 for reason
14	(a) (i)		$(-4, 3)$	2	B1 cao
	(ii)		$(2, -1)$		B1 cao
	(b) (i)	*D* marked at $(-4, -1)$	Point marked on grid	2	B1 for point marked at $(-4, -1)$ cao
	(ii)		$(-4, -1)$		B1 ft
15	(a)			1	B1 cao
	(b)			1	B1 cao

Paper 5521_01				
No	**Working**	**Answer**	**Mark**	**Notes**
16 (a)		(Pat +) reason	1	B1 correct comment (Pat may be implied)
(b)	21 ÷ 3	7	1	B1 cao
17 (i)		S marked at 1	3	B1 for S within ½ cm of 1
(ii)		P marked at 0		B1 for P marked at 0 cao
(iii)		Q marked at "1/3"		B1 for Q marked at 1/3 ± 1 cm use overlay
18	6 + 6 + 3 or $2\frac{1}{2}\times 6$	15	3	M1 for realizing 6 glasses in one bottle M1 for realizing 3 glasses in ½ a bottle A1 cao (M2 for attempt to find $2\frac{1}{2}\times 6$) oe
19	15 and 16 parts shaded Alternative 1 $\frac{3}{4}=0.75,\ \frac{4}{5}=0.8$ Alternative 2 $\frac{3}{4}=\frac{15}{20},\ \frac{4}{5}=\frac{16}{20}$	$\frac{4}{5}$ + reason	3	M1 for correctly shading 15 parts for 3/4 M1 for correctly shading 16 parts for 4/5 A1 (dependent on M2) for selection of 4/5 Alternative 1 M1 for $\frac{3}{4}=0.75$ M1 for $\frac{4}{5}=0.8$ A1 (dep on M2) for selection of 0.8 or $\frac{4}{5}$ or $\frac{16}{20}$ Alternative 2 M1 for $\frac{3}{4}=\frac{15}{20}$ M1 for $\frac{4}{5}=\frac{16}{20}$ A1(dep on M2) for selection of $\frac{4}{5}$ or $\frac{16}{20}$

Paper 5521_01					
No		**Working**	**Answer**	**Mark**	**Notes**
20	(a)		−5 (−3) (−1) 1 3 5	2	B2 cao (B1 for any 2 or 3 correct)
	(b)	Points plotted	Line	2	B2 for line from (−1, −5) to (4, 5) (B1 ft for plotting at least 5 "points")
21		Shapes shaded on grid	6 tessellating shapes	2	B2 for fully correct with 5 or more additional shapes, no gaps (B1 for 4 shapes tessellating with at least one shape inverted, with or without the given shape ignore extras)
22	(a)		$\frac{7}{20}$	1	B1 for $\frac{7}{20}$ oe
	(b)	7 + 2 (or 20 – 11) are not lime flavour	$\frac{9}{20}$	1	B1 for $\frac{9}{20}$
	(c)		0	1	B1 for 0, zero or nought ($\frac{0}{20}$ gets B0)
23	(a)		$4a$	1	B1 accept $4\times a$, $a \times 4$, $a4$
	(b)		$12b$	1	B1 accept $12\times b$, $b \times 12$, $b12$
	(c)		$2a + 6b$	2	B2 cao (B1 for $2a$ or $6b$ seen)
	(d)		$x(x-6)$	2	B2 cao (B1 for $x(ax+b)$ where a, b are numbers not equal to 0 or $x - 6$ seen on its own, or as part of an expression)
24	(a)		40	1	B1 cao
	(b)		45	1	B1 for 42 – 48 accept ¾ hour
	(c)	40×2 or $\frac{40}{30}\times 60$ or $40\div\frac{1}{2}$	80	2	M1 for 40×2 or $\frac{40}{30}$ or $40\div\frac{1}{2}$ A1 cao NB $\frac{40}{45}\times 60$ gets M0 A0

Paper 5521_01				
No	**Working**	**Answer**	**Mark**	**Notes**
25 (a)		4560	1	B1 cao
(b)		45.6	1	B1 cao
(c)		2.4	1	B1 cao
26	$-7 - 3 = -10$ $2 \times -10 = -20$ $-20 \div 4$	-5	3	M1 for substitution of 2 and -7 into $p(q - 3)$ or sight of -20 or $-14 - 6$ M1dep for '-20' $\div 4$ A1 cao B1 SC for sight of -10 if M0 awarded
27 (a)		Reflection in y-axis	1	B1 cao
(b)		Rotation by half turn about (0,0)	2	B2 cao (B1 for half turn not about (0,0).)
(c)		Enlargement Scale factor 3 Centre (0,0)	3	B1 for 'enlargement' B1 for "scale factor 3" or 3 seen B1 for 'centre (0,0)
28 (a)		Reason	1	B1 for 'The frequencies are nearly equal' oe
(b)	$1\times26+2\times26+3\times23+4\times25 = 247$ 247/100	2.47	3	M1 for fx (attempting at least 2 relevant products) M1 for $\sum fx \div 100$ A1 2.47 cao

Paper 5521_01				
No	**Working**	**Answer**	**Mark**	**Notes**
29	5 × 5 × 6	150	4	M1 for attempt at 1 division (e.g. 40 ÷ 8), may be implied by marks or number on one edge of diagram or by 5 or 6 seen M1 for attempt at 3 divisions (40÷8, 40÷8, 60÷10), may be implied by marks or numbers on diagram or by 5,5 and 6 seen. M1 (dep on 1st M1) for "5" × "5" × "6" A1 cao Alternatively M1 for 40 × 40 × 60 **or** 8 × 8 × 10 **or** 96000 or 640 seen M1 for 40 × 40 × 60 **and** 8 × 8 × 10 or 96000 **and** 640 seen M1 (dep on 1st M1) for "(40 × 40 × 60)" ÷ "(8 × 8 × 10)" A1 cao SC:B1 for dividing area of one carton face by area of corresponding box face if M0

Paper 5521_02					
No		Working	Answer	Mark	Notes
1	(a)	Draw diagram.	Diagram	1	B1 cao
	(b)		13,16	1	B1 cao
	(c)		31	1	B1 cao
2	(a)		8	1	B1 cao
	(b)		14	2	B2 for 14 (B1 for 13 or 15)
	(c)		16	2	B2 for 16 (B1 for 15, 17 or 8)
3	(a)		4,7 drawn	2	B2 for car height 4 and bus height 7, (B1 for one correct)
	(b)		6	1	B1 cao
	(c)		Walk	1	B1
	(d)		27	1	B1 cao
4	(a)		40	1	B1 for 40–41 inclusive
	(b)		12	1	B1 for 11.5 – 12.5 inclusive
5	(a)		Row complete	2	B2 for 1+..+11; 36 (B1 for one of the 2 cells complete)
	(b)		Square	1	B1 "square"
6		One line of symmetry		1	B1 within 2mm of centre of base / 2mm of vertex

Paper 5521_02				
No	**Working**	**Answer**	**Mark**	**Notes**
7 (a) (i)		09 06	2	B1 (accept 9 06 oe)
(ii)		39		B1 cao
(b)		06 55	1	B1 (accept 6 55 oe)
(c)		2h 6min	1	B1 cao
(d)		15 min	2	M1 for 0906 – 0645 – "(c)" or 0906 – 0645 − 2hr 6min or 2hr 21min − "(c)" or 2hr 21min − 2hr 6 min or 141 − 126 or 20 − 5 A1 cao SC: B1 for 55 or 75 or 93 seen
8 (i)		8,10,12,20 or 30	3	B1 at least one of 8, 10, 12, 20, 30 (no extras)
(ii)		8,12 or 20		B1 at least one of 8,12, 20 (no extras)
(iii)		3 or 5		B1 3 or 5 or both (no extras)
9 (a)		C or G	1	B1 at least one of C or G (no extras)
(b)		A and F	1	B1 cao
(c)		2	1	B1 (accept –2)
10 (a)		$\frac{7}{10}$	1	B1 7/10 oe
(b)(i)		4 squares	2	B1 4 squares shaded
(ii)		80%		B1 80% or ft from unshaded part (no ft from 0% or 100%)
(c)(i)		2.5	2	B1 2.4–2.6 inclusive
(ii)		1.7		B1 1.6–1.8 inclusive
11 (a)		2	1	B1 for 2 or –2
(b)		14	1	B1 for 14 or –14

Paper 5521_02					
No		**Working**	**Answer**	**Mark**	**Notes**
12		$2 \times 8.50 = 17.00$ $3 \times 4.50 = 13.50$ Total = 30.50 50.00 – 30.50	19.5(0)(*p*)	3	M1 for adding 5 correct values or $2 \times 8.50 + 3 \times 4.50$ (ignore units) or 30.5(0) or 3050 seen M1 dep for 50 − "30.50" (ignore units) (OR M1for adding at least 1 adult ticket and at least 1 child ticket **and** subtracting from 50) A1 cao SC: B1 for 24 or 37 or 2400 or 3700 seen
13	(a)		Hexagon	1	B1
	(b)(i)		120	2	B1 cao
	(ii)		Str line		B1 reference to a (straight) line and 180°
	(c)		Obtuse	1	B1 Accept "interior"
14	(a)	2, 2, 3, 3, 3, 4, 4, 4, 5, 6	3.5	2	M1 ordering the numbers (condone 1 error or omission) A1 cao
	(b)	36 ÷ 10	3.6	2	M1 sum of numbers ÷ 10 A1 cao SC B1 for 3r 6
	(c)	6 – 2	4	1	B1 cao
15	(a)		Paul	1	B1 cao
	(b)	36 ÷ 2 oe	18	1	B1 cao
	(c)	60/360 =	1/6	2	M1 60/360 oe A1 cao

Paper 5521_02					
No		**Working**	**Answer**	**Mark**	**Notes**
16		4.7 ÷ 5.9 = 0.796610169	0.7966..	2	B2 for 0.7966 or better (B1 for 0.8, 0.80, 0.79, 0.796, 0.797 or digits 59 seen
17		$6x - 7 + 7 = 38 + 7$ $6x = 45$	7.5	2	M1 $6x = 45$ or +7 both sides A1 7.5 oe; accept 45/6 oe
18		**55** 61 74 **190** 33 **17** **10** 60 **88** **78** 84 250	**55** 61 74 **190** 33 **17** **10** 60 **88** **78** 84 250	3	B3 all six entries correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
19	(a)	900 × 1.70 =	1530	2	M1 900 × 1.7(0) or digits 153(0) seen A1 cao
	(b)	160 ÷ 1.70 =	£94.12 or £94.11	2	M1 160 ÷ 1.7(0) or digits 941(....) seen A1 cao
20	(a)(i)	180 – 54 (=126) "126" ÷ 2	63	3	M1 for (180–54) ÷ 2 A1 cao
	(ii)		Reason		B1 (indep) angles in triangle add to 180 OR equal angles in isosceles triangle OR equal angles and 2 sides the same (B0 if any incorrect reasoning given eg parallel, equilateral triangle)
	(b)	180 – "x"	117	1	B1 117 or ft 180 – "x" if $x < 90$
21	(a)	3 × 35 + 50	155	2	M1 for 3 × 35 + 50 or digits 155 seen A1 cao
	(b)	260 – 50 = 210 210 ÷ 35 =	6	3	M1 for 260–50 or 210 seen. M1 for "260-50" ÷ 35 or 210÷35 A1 cao SC B1 for starting at a number between 100 and 170 and adding at least two 35's and showing a total between 230 and 290 OR For adding at least three 35's, perhaps with other numbers, and showing a total between 180 and 240 (or between 230 and 290 if 50 is included in the sum)

Paper 5521_02				
No	**Working**	**Answer**	**Mark**	**Notes**
(c)		P=35h + 50	3	B3 for P=35h+50 or P=35×h+50 oe (B2 for correct RHS or P=h + 50 ×35 or P=35h+k where k is numerical oe) (B1 for P = some other linear expression in h, OR h + 50 ×35 OR 35h seen) NB: P=h scores no marks; ignore £ signs. SC B2 for $h = \frac{P-50}{35}$
22 (a)		Elevation	2	B2 for 4 vertical squares. Accept 4 by 1 rectangle. (B1 for 4 vertical squares with one square added or one parallelogram added at the top, or 3 vertical squares, or 4 horizontal squares)
(b)		Plan	2	B2 for 2 adjacent squares, vertical or horizontal. Accept 2 by 1 rectangle. (B1 for 3 adjacent horizontal or vertical squares or a rectangle with sides in the ratio 2:1)
23 (i)		5	3	B1 cao
(ii)		9		B1 cao
(iii)		6		B1 cao
24	$45.00 + 45.00 \times \frac{15}{100} =$ $45.00 + 6.75 =$	51.75	3	M2 for $45.00 + 45.00 \times \frac{15}{100}$ oe or 45.00×1.15 oe OR $45.00 + 6.75$ OR complete method or 5175 seen. (M1 for $45.00 \times \frac{15}{100}$ oe OR 6.75 seen OR 675 seen OR correct method for calculating 15% of 45) A1 cao SC Award B2 for an answer of 38.25

Paper 5521_02				
No	**Working**	**Answer**	**Mark**	**Notes**
25 (a)		Points	1	B1 all three points ±1 full square
(b)		Negative	1	B1 Negative (ignore additional descriptors unless contradictory)
(c)		lobf	1	B1 A single straight line drawn to cross between (5,30), (5,40) and (40,0), (40,15); accept freehand if considered to be straight.
(d)(i)		18–25	2	B1 18g–25g inclusive OR if not in this range ft ±1 square dep on single straight line with negative gradient.
(ii)		30–40		B1 30–40 min inclusive OR if not in this range ft ±1 square dep on single straight line with negative gradient
26		300 3 75 150	3	B3 for 4 correct answers (B2 for 2 or 3 correct answers) (B1 for 1 correct answer)
27	π × 0.65	2.04–2.05	2	M1 for π × 0.65 or 3.14 x 0.65 or 3.142 x 0.65 A1 for 2.04–2.05 SC Award B1 for 2.0 seen (not 2)
28	5 miles = 8 km 70mph÷5×8 = 112 km/h OR 120km/h ÷ 8 × 5 = 75 mph Faster than 70 mph	70mph (Great Britain) (112 km)	3	M1 5 miles = 8 km; OR 70 mph is about 100 km/h OR 1km=0.6(25) miles OR 1mile=1.6km oe M1 70 ÷ 5 × 8 (=112) or 120 ÷ 8 × 5 (=75) A1 (dep on at least M1) GB or 70 mph Refer to both answer line and working. NB GB or 70 mph without working scores 0 marks

Paper 5523_03				
No	**Working**	**Answer**	**Mark**	**Notes**
1		Cuboid drawn	2	B2 for correct isometric drawing in any orientation (ignore points 'behind', mark 7 vertices only); accept lines drawn near to dots as long as there is no ambiguity. (B1 for one of the three faces drawn correctly **or** for an isometric drawing of any cuboid)
2	Different makes of car Tally Frequency	Make of car Tally Frequency	3	B1 for make of car or list of at least 3 different makes B1 for tally or tally marks B1 for frequency or totals
3		6 tessellating shapes	2	B2 for fully correct with 5 or more additional shapes, no gaps (B1 for 4 or more shapes tessellating, with at least one shape inverted, with or without the given shape, ignore extras)
4	24.90 ÷ 3 or 8.30 24.90 – '8.30' or 2 × 8.30	16.6(0)	3	M1 for 24.90 ÷ 3 or 8.30 M1 (dep) for 24.90 – “8.30” or 2 × “8.30” A1 for 16.60 or 16.6

Paper 5523_03

No	Working	Answer	Mark	Notes
5	315 × 24 24 × 315 1260 6300 7560 7200 7560 **3 1 5** 0 6 | 0 2 | 1 0 — **2** 1 2 | 0 4 | 2 0 — **4** 7 5 6 0 **300 10 5** 6000 200 100 — **20** 1200 40 20 — **4** 6000+200+100+1200+40+20 = 7560 **3 0.1 0.05** 60 2 1 — **20** 12 0.4 0.2 — **4** 60 + 2 + 1 + 12 + 0.4 + 0.2 = 75.6	75.6(0)	3	M1 for a complete method with relative place value correct. Condone 1 multiplication error, addition not necessary. **OR** M1 for a complete grid with not more than 1 multiplication error, addition not necessary. **OR** M1 for sight of a complete partitioning method, condone 1 multiplication error, final addition not necessary. A1 for 7560 or digits 756(0) A1 (dep on M1, but not previous A1) for correct placement of decimal point.

Paper 5523_03				
No	**Working**	**Answer**	**Mark**	**Notes**
6	15 and 16 parts shaded Alternative 1 $\frac{3}{4} = 0.75$ or 75%, $\frac{4}{5} = 0.8$ or 80% Alternative 2 $\frac{3}{4} = \frac{15}{20}$, $\frac{4}{5} = \frac{16}{20}$	$\frac{4}{5}$ + reason	3	M1 for shading 15 parts for $\frac{3}{4}$ M1 for shading 16 parts for $\frac{4}{5}$ A1 (dep on M2) for selection of $\frac{4}{5}$ with correct shading Alternative 1 M1 for $\frac{3}{4} = 0.75$ or 75% M1 for $\frac{4}{5} = 0.8$ or 80% A1 (dep on M2) for selection of 0.8 or 80% or $\frac{4}{5}$ with correct decimals or percentages Alternative 2 M1 for $\frac{3}{4} = \frac{15}{20}$ oe M1 for $\frac{4}{5} = \frac{16}{20}$ oe A1 (dep on M2) for selection of $\frac{4}{5}$ or $\frac{16}{20}$ with equivalent fractions

Paper 5523_03					
No		**Working**	**Answer**	**Mark**	**Notes**
7		$5 \times 5 \times 6$	150	4	M1 for attempt at 1 division (e.g. 40 ÷ 8), may be implied by marks or number on one edge of diagram or by 5 or 6 seen M1 for attempt at 3 divisions (40÷8, 40÷8, 60÷10), may be implied by marks or numbers on diagram or by 5,5 and 6 seen. M1 (dep on 1st M1) for "5" × "5" × "6" A1 cao Alternatively M1 for 40 × 40 × 60 **or** 8 × 8 × 10 **or** 96000 or 640 seen M1 for 40 × 40 × 60 **and** 8 × 8 × 10 or 96000 **and** 640 seen M1 (dep on 1st M1) for "(40 × 40 × 60)" ÷ "(8 × 8 × 10)" A1 cao SC:B1 for dividing area of one carton face by area of corresponding box face if M0
8	(a)		$\frac{7}{20}$	1	B1 for $\frac{7}{20}$ oe
	(b)	7 + 2 (or 20 – 11) are not lime flavour	$\frac{9}{20}$	1	B1 for $\frac{9}{20}$ oe
	(c)		0	1	B1 for 0, zero or nought ($\frac{0}{20}$ gets B0)
9	(a)		$80x$	1	B1 for $80x$ (accept $80 \times x$, $x80$, $x \times 80$) seen
	(b)		$95y$	1	B1 for $95y$ (accept $95 \times y$, $y95$, $y \times 95$) seen
	(c)		$80x + 95y$	2	M1ft for adding "$80x$" and "$95y$" (algebraic expressions only) A1 for $80x + 95y$

Paper 5523_03

No	Working	Answer	Mark	Notes
10 (a)		40	1	B1 cao
(b)		45	1	B1 for 42 to 48 (accept 3/4 hour)
(c)	40×2 or $\frac{40}{30}\times60$ or $40\div\frac{1}{2}$	80	2	M1 for 40×2 or $\frac{40}{30}$ or $40\div\frac{1}{2}$ A1 cao NB $\frac{40}{45}\times 60$ gets M0 A0
11 (a)	$3\times3-4\times2$ or $9-8$	1	2	M1 for substitution of 3 and 2 into expression or 9 and 8 seen A1 cao
(b)	$-7-3=-10$ $2\times-10=-20$ $-20\div4$	-5	3	M1 for substitution of 2 and –7 into p(q – 3) or sight of -20 or –14 – 6 M1 (dep) for "–20" ÷ 4 A1 cao SC: B1 for –10 seen if M0
12 (a)	6 | 8 9 7 7 | 8 5 9 6 3 8 | 1 3 1 7 1 9 | 0 1	6 | 7 8 9 7 | 3 5 6 8 9 8 | 1 1 1 3 7 9 | 0 1	3	M1 for unordered diagram (condone one error) A1 cao B1 for key (eg 6 | 7 = 67)
(b)(i)		Explanation	2	B1 for '(order numbers and) select middle value' oe
(ii)		79		B1 cao

Paper 5523_03					
No		**Working**	**Answer**	**Mark**	**Notes**
13	(a)		Reflection in y-axis	1	B1 for triangle with vertices at (-1, 1) (-3, 1) and (-1,4)
	(b)		Rotation by half turn about (0, 0)	2	B2 for triangle with vertices (-1, -1) (-3, -1) and (-1, -4) (B1 for half turn not about (0,0))
	(c)		Enlargement Scale factor 3 Centre (0, 0)	3	B1 for 'enlargement' B1 for 'scale factor 3' or 3 seen B1 for 'centre (0,0)' B0 for any combination of transformations
14	(a)		4560	1	B1 cao
	(b)		45.6	1	B1 cao
	(c)		2.4	1	B1 cao
15	(a)	$4a-2a+5b+b$	$2a+6b$	2	B2 cao (B1 for $2a$ or $6b$ seen)
	(b)		$x(x-6)$	2	B2 cao (B1 for $x(ax+b)$ where a, b are numbers not equal to zero or $x-6$ seen on its own, or part of an expression)
	(c)		$3x-2x^3$	2	B2 cao (B1 for $3x$ or $2x^3$)
	(d)		$4x(3y+x)$	2	B2 cao (B1 for $2(6xy+2x^2)$ or $4(3xy+x^2)$ or $x(12y+4x)$ or $2x(6y+2x)$ or $4x(\quad)$)

Paper 5523_03					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	$1 - (0.2 + 0.3 + 0.1)$	0.4	2	M1 for $1 - (0.2 + 0.3 + 0.1)$ A1 for 0.4 oe, accept $\frac{0.4}{1}$
	(b)	0.2×200	40	2	M1 for 0.2×200 A1 cao NB $\frac{40}{200}$ is M1 A0, 40 out of 200 is M1 A1
17	(a) (i)	$180 - 2 \times 25$	130	3	M1 for $180 - 2 \times 25$ A1 cao
	(ii)		Reason		B1 for mentioning isosceles and equal (or base) angles or equal sides and equal (or base) angles
	(b)	$180 - 95$	85	1	B1 cao
18	(a) (i)		7^5	3	B1 cao
	(ii)		7^4		B2 cao (B1 for sight of 7^5 or 7^{2+3} or 7×7^3 or $7^1 \times 7^3$ or $7^2 \times 7^2$ or 7^{2+3-1})
	(b)		$\frac{1}{2}$	1	B1 for $\frac{1}{2}$ or 0.5 or 2^{-1}
19	(a)		3×10^7	1	B1 cao
	(b)		0.002	1	B1 cao

Paper 5523_03				
No	**Working**	**Answer**	**Mark**	**Notes**
20		Box plot	2	3 aspects: 1st aspect – vertical line for median 2nd aspect – box using correct quartiles 3rd aspect – whiskers (could be single line) drawn with correct end points B2 for fully correct box plot (B1 for 1 aspect)
21 (a)	e.g. 2 | 126 3 | 63 3 | 21 7	$2\times3\times3\times7$	2	M1 for a systematic method of at least 2 correct divisions by a prime number oe factor trees; can be implied by digits 2, 3, 3, 7 on answer line. A1 for $2\times3^2\times7$ or $2\times3\times3\times7$
(b)	$2\times3\times7$	42	2	B2 cao (B1 for 6, 14, 21 or $2\times3\times7$)
22	$\frac{8}{3}\times\frac{5}{4}=\frac{8\times5}{3\times4}=\frac{40}{12}$	$3\frac{1}{3}$	3	B1 for $\frac{8}{3}$ oe improper fraction or $\frac{5}{4}$ oe improper fraction M1 (dep on B1) for multiplying numerator and denominator of "$\frac{8}{3}$" and "$\frac{5}{4}$" A1 for $3\frac{1}{3}$ oe mixed number or $\frac{10}{3}$ OR B1 for 1.25 and 2.67 or 2.66(…) M1 (dep on B1) for correct method of multiplication A1 for $3.\dot{3}$

Paper 5523_03				
No	**Working**	**Answer**	**Mark**	**Notes**
23			2	M1 for a relevant pair of intersecting arcs A1 for line drawn within guidelines, at least 3cm in length, accept broken line [SC: B1 for line drawn within guidelines if M0]
24 (a)		$-1, 0, 1, 2, 3$	2	B2 cao (-1 each error or omission)
(b)(i)		$x \geq \frac{7}{2}$	3	M1 for $2x \geq 7$, condone use of = sign or wrong equality A1 for $x \geq \frac{7}{2}$ oe as final answer
(ii)		4		SC:B1 for 3.5 or $\frac{7}{2}$ seen if M0 B1 ft from $x \geq$ "$\frac{7}{2}$"
25	$4x + 2y = 8$ $4x - 10y = 20$ $12y = -12$ $y = -1$ $4x + 2(-1) = 8$ $x = 2.5$	$x = 2.5$ $y = -1$	3	M1 for correct process to eliminate either x or y (condone one arithmetical error) M1 (dep) for substituting found value into either equation A1 for $x = 2.5$, $y = -1$ [SC: B1 for $x = 2.5$ or $y = -1$ if M0]

Paper 5523_03					
No		**Working**	**Answer**	**Mark**	**Notes**
26		Interior angle of hexagon = 180 – (360 ÷ 6) = 120 360 – (90 + 120)	150	4	Alternative 1 M1 for 360 ÷ 6 A1 for 60 M1 (dep on M1) for "60" + 90 A1 cao Alternative 2 M1 for 360 ÷ 6 A1 for 60 M1 (dep on M1) for 360 – (2 × "60" + 90) A1 cao Alternative 3 M1 for (6 – 2) × 180 ÷ 6 A1 for 120 M1 (dep on M1) for 360 – (90 + "120") A1 cao
27	(a)		(16), 50, 82, 96, 100	1	B1 cao
	(b)	Cumulative freq. diag. curve/ segments	Cum. freq graph	2	B1 for 4 or 5 points plotted correctly ± 1 full (2mm) square depending on sensible table (condone 1 addition error) B1 (dep) for points joined by curve or line segments provided no gradient is negative - ignore any part of graph outside range of their points. (SC:B1 if 4 or 5 points plotted not at end but consistent within each interval and joined)
	(c)	100 – 42	58	2	M1 (ft dep on graph being cf) for reading from graph at 18 or 19, can be implied by answer in range 40 to 46 A1 for answer in range 56 to 60 or ft for 100 – '42' ±1 full (2mm) square

Paper 5523_04					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	900 × 1.70 =	1530	2	M1 900 × 1.7(0) or digits 153(0) seen A1 cao
	(b)	160 ÷ 1.70 =	£94.12 or £94.11	2	M1 160 ÷ 1.7(0) or digits 941(....) seen A1 cao
2	(a)	4.7 ÷ 5.9 = 0.796610169	0.7966..	2	B2 for 0.7966 or better (B1 for 0.8, 0.80, 0.79, 0.796, 0.797 or digits 59 seen)
	(b)	0.82, 0.8, 0.85, 0.66, 0.875 0.66, 0.8, 0.82, 0.85, 0.875 2/3, 4/5, 0.82, 85%, 7/8	2/3, 4/5, 0.82, 85%, 7/8	2	B2 correct order (oe decimals in order) (B1 correct order reversed, or one error in ordered listing) with or without decimal equivalents. NB Accept 0.67 or 0.66
3		**55** 61 74 **190** 33 **17** **10** 60 **88** **78** 84 250	**55** 61 74 **190** 33 **17** **10** 60 **88** **78** 84 250	3	B3 all 6 correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
4	(a)	–3 (–1) (1) 3 5 7	**–3**, 3, **5**, **7**	2	B2 all correct (B1 2,3 correct)
	(b)	(-2,-3),(-1,-1),(0,1),(1,3),(2,5),(3,7)	line	2	B2 cao for line from $x = -2$ to $x = 3$ (B1 plotting at least 5 points correctly or single line passing through (0, 1) or single line of gradient 2) The six possible points are: (-2,-3), (-1,-1), (0,1), (1,3), (2,5), (3,7)
	(c)(i)		–2	2	B1 $y = -2$ or ft from line segment
	(ii)		2.5		B1 $x = 2.5$ or ft from line segment

Paper 5523_04					
No		**Working**	**Answer**	**Mark**	**Notes**
5	(a) (i)	180 – 54 (=126) "126" ÷ 2	63	3	M1 for (180–54) ÷ 2 A1 cao
	(ii)		Reason		B1 (indep) angles in triangle add to 180 OR equal angles in isosceles triangle OR equal angles and 2 sides the same (B0 if any incorrect reasoning given eg parallel, equilateral triangle)
	(b)	180 – "x"	117	1	B1 117 or ft 180 – "x" if $x < 90$
6		15/120×360 = 45 Plain 40/120×360 = 120 Cheese & Onion 55/120×360 = 165 Salt & Vinegar 10/120 × 360 = 30 Beef	45°, 120°, 165°, 30°	4	M1 evidence of method for at least one angle (could be implied by one correct angle of four on pie chart or in the table) A2 All four angles drawn ±2° tolerance, any order (A1 at least 2 angles correctly drawn ±2°, or all 4 angles in the table) B1 (dep on at least 1 angle drawn correctly, and exactly 4 sectors) for labels (flavour or frequency; initials will do) NB: Ignore the table if the pie chart provides the marks.
7	(a)	260 – 50 = 210 210 ÷ 35 =	6	3	M1 for 260–50 or 210 seen. M1 for "260-50" ÷ 35 or 210÷35 A1 cao
	(b)		P=35h + 50	3	B3 for P=35h+50 or P=35×h+50 oe (B2 for correct RHS or P=h + 50 ×35 or P=35h+k where k is numerical oe) (B1 for P = some other linear expression in h, OR h + 50 ×35 OR 35h seen) NB: P=h scores no marks; ignore £ signs. SC B2 for $h = \frac{P-50}{35}$
8	(a)		Elevation	2	B2 for 4 vertical squares. Accept 4 by 1 rectangle. (B1 for 4 vertical squares with one square added or one parallelogram added at the top, or 3 vertical squares, or 4 horizontal squares)

Paper 5523_04				
No	**Working**	**Answer**	**Mark**	**Notes**
(b)		Plan	2	B2 for 2 adjacent squares, vertical or horizontal. Accept 2 by 1 rectangle. (B1 for 3 adjacent horizontal or vertical squares or a rectangle with sides in the ratio 2:1)
9 (a)		Points	1	B1 all three points ±1 full square.
(b)		Negative	1	B1 Negative. Ignore other descriptors unless contradictory.
(c)		lobf	1	B1 A single straight line drawn to cross between (5,30), (5,40) and (40,0), (40,15); accept freehand if considered to be straight.
(d)(i) (ii)		18–25 30–40	2	B1 18g–25g inclusive OR if not in this range ft ±1 square dep on single straight line with negative gradient. B1 30–40 min inclusive OR if not in this range ft ±1 square dep on single straight line with negative gradient.
10		300, 3, 75, 150	3	B3 for 4 correct (B2 for 2 or 3 correct) (B1 for 1 correct)
11 (a)	$6x - 7 + 7 = 38 + 7$ $6x = 45$	7.5	2	M1 $6x = 45$ or +7 both sides A1 7.5 oe; accept 45/6
(b)	$5y - 2 = 10$ or $20y - 8 = 40$ $5y = 12$ $20y = 48$	$2\frac{2}{5}$	3	M1 $20y–8(=40)$ or $\frac{4(5y-2)}{4} = \frac{40}{4}$ or $5y–2=10$ M1 (indep) for correct rearrangement into the form $ay=b+c$ or better (eg $20y=40+8$ or $5y=10+2$, using own terms) A1 for $2\frac{2}{5}$, 2.4 oe
12	5 miles = 8 km 70mph÷5×8 = 122 km/h OR 120km/h ÷ 8 × 8 = 75 mph Faster than 70 mph	70mph (Great Britain) (112 km)	3	M1 5 miles = 8 km; OR 70 mph is about 100 km/h OR 1km=0.6(25) miles OR 1mile=1.6km oe M1 70 ÷ 5 × 8 (=112) or 120 ÷ 8 × 5 (=75) oe A1 (dep on at least M1) GB or 70 mph Refer to both answer line and working. NB GB or 70 mph without working scores 0 marks.

Paper 5523_04				
No	**Working**	**Answer**	**Mark**	**Notes**
13 (a)	$\pi \times 0.65$	2.04–2.05	2	M1 for $\pi \times 0.65$ or 3.14×0.65 or 3.142×0.65 oe A1 2.04–2.05 SC Award B1 for 2.0 seen (not 2)
(b)	1000 ÷ "(a)"	487–491	2	M1 for 1000 (or 100) ÷ "(a)" A1 for 487–491
14	$45.00 + 45.00 \times \frac{15}{100} =$ $45.00 + 6.75 =$	51.75	3	M2 for $45.00 + 45.00 \times \frac{15}{100}$ oe or 45.00×1.15 oe OR $45.00 + 6.75$ OR complete method or 5175 seen. (M1 for $45.00 \times \frac{15}{100}$ oe OR 6.75 seen OR 675 seen OR correct method for calculating 15% of 45) A1 cao SC Award B2 for an answer of 38.25
15		273	2	M1 for 728 ÷ 8 or 728 ÷ "3+5" or 91 A1 cao SC B1 for 455, or for 273:455
16	3 24 3.7 46.9(53) 4 60 3.8 51.0(72) 3.1 26.6(91) 3.9 55.4(19) 3.2 29.5(68) 3.21 29.8(66…) 3.3 32.6(37) 3.22 30.1(66…) 3.4 35.9(04) 3.23 30.4(68..) 3.5 39.3(75) 3.24 30.7(72...) 3.6 43.0(56) 3.25 31.0(78...) or 31	3.2	4	B2 for trial between 3.2 and 3.3 inclusive (B1 for trial between 3 and 4 inclusive) B1 for different trial between 3.21 and 3.25 inclusive B1 (dep on at least one previous B1) cao for 3.2 as final answer. NB: embedded answers: –B1; award Bs for evaluations rounded or truncated to at least 1 dp or for 31

Paper 5523_04				
No	**Working**	**Answer**	**Mark**	**Notes**
17	$45^2 + 34^2 =$ $2025 + 1156 = 3181$ $\sqrt{3181} = 56.4$	56	4	M1 for $45^2 + 34^2$ M1 (dep) for $\sqrt{(2025 + 1156)}$ A1 for 56.4 … B1 for rounding their diagonal to the nearest integer (dep on evidence from decimal) NB 56 as the final answer gets full marks. NB Scale drawings result in 0 marks.
18	$2000 \times (1.055)^3$ Interest = 2348.48 – 2000 =	348.48	3	M1 for 5.5/100 × 2000 (oe) or 330 or 2330 or 110 or 2110 M1 (dep) for 5.5/100 × (2000 + "110" + "116.05") or 122.4… seen A1 cao (accept only 348.48 or 348.49) **OR** M2 for $2000 \times (1.055)^3$ or 2348.48(…) or 2348.49 seen (M1 for $2000 \times (1.055)^n$, $n \neq 3$) A1 for 348.48 or 348.49 [SC: B2 for 2348.48 - 2348.49]
19		Line	2	B2 line fully within tramlines, crossing AB and CD (B1 a straight line which crosses AB within the tramline, and also crosses CD) NB: Accept dotted or dashed lines, but not curves; accept freehand if considered to be straight. SC B1 for a perpendicular bisector of AB that is at least half way from AB to CD within the tramlines
20 (a)		$90<t\leq100$	1	B1 for $90<t\leq100$; accept 90-100.
(b)	65×12=780 75×22=1650 85×23=1955 95×24=2280 105×19=1995 8660/100=	86.6	4	M1 for use of fx with x consistent within intervals (including end points). Allow one slip. M1 (dep) for use of midpoints M1 (dep on 1st M1) for use of $\sum fx/100$ or $\sum fx/\sum f$ A1 86.6

Paper 5523_04					
No		**Working**	**Answer**	**Mark**	**Notes**
21	(a)	$8 \times \frac{10}{4}$	20	2	M1 $\frac{10}{4}$ or $\frac{4}{10}$ or 0.4 or 2.5 oe seen A1 cao NB ratios get M0 unless of the form 1:*n* OR M1 $\frac{8}{4}, \frac{4}{8}$ oe seen A1 cao
	(b)	$15 \times \frac{4}{10}$	6	2	M1 $15 \times \frac{4}{10}$ oe A1 cao
22	(a)	$x^2 - 4x + 3x - 12 = x^2 - x - 12$	$x^2 - x - 12$	2	M1 for exactly 4 terms correct ignoring signs (eg x^2, $4x$, $3x$, 12) or 3 correct terms out of 4 terms with correct signs (eg 3 out of 4 of x^2, $-4x$, $+3x$, -12) A1 cao
	(b)	$(x+2)(x+5)$	$(x+2)(x+5)$	2	B2 cao (B1 for exactly one of $(x+2)$, $(x+5)$)
	(c)	$6=15+4q-20$ $6-15=4(q-5)$ $p-3t=4q-4t$ $6-3\times5=4(q-5)$	2 ¾	3	M1 for correct substitution of *p* and *t*. M1 for correct expansion of $4(q-t)$ oe (eg $4q-20$, $4q-4t$) A1 11/4 or 2 ¾ or 2.75 OR M1 for correct substitution of *p* and *t*. M1 for $\frac{p-3t}{4} = q - t$ oe A1 11/4 or 2 ¾ or 2.75

Paper 5523_04					
No		**Working**	**Answer**	**Mark**	**Notes**
23	(a)	$9.9\times10^8 - 6.0\times10^7$	9.3×10^8	2	M1 for $99\times10^7 - 6\times10^7$ or $9.9\times10^8 - 0.6\times10^8$ or conversion of either to an ordinary number, or 930000000 or 93×10^7 or 9.3×10^n where n is any positive integer A1 cao
	(b)	$\frac{6.0-4.5}{4.5}\times100 = \frac{1.5}{4.5}\times100 =$ or $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7}\times100$	33.3%	3	M2 $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7}\times100$ oe (M1 for $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7}$ or $\frac{6.0\times10^7 - 4.5\times10^7}{6.0\times10^7}\times100$ oe A1 cao OR M2 $\frac{6.0\times10^7}{4.5\times10^7}\times100$ -100 = (M1 $\frac{6.0\times10^7}{4.5\times10^7}\times100$ or 133.33(%)) A1 cao NB Accept any of the above expressions without any reference to 10^7.
24		LCM (40,24) = 120 Bread buns 120÷40 Burgers 120÷24 OR Bread buns: 40 is $2\times2\times2$ (×5) Burgers: 24 is $2\times2\times2$ (×3)	Bread buns 3 Burgers 5	3	M1 attempt to find LCM by eg lists of multiples, or summing of 40 and 24. A1 identify 120 (as LCM) A1 cao (both) OR M1 expansion of either number into its prime factors in a factor tree or 8×5 or 8×3 A1 both expansions correct A1 cao (both) SC B2 if answers given the wrong way around

Paper 5523_04				
No	**Working**	**Answer**	**Mark**	**Notes**
25	8 × 41 = 328 2 × 29 = 58 328 – 58 = 270 270 ÷ 6 = 45	45	3	M1 for either 8 × 41 (=328) or 2 × 29 (=58) M1 (dep) "328" – "58" (=270) A1 cao NB 328 and/or 58 on the answer line gets M1 (implied); 270 on the answer line gets M2 (implied)

Paper 5525_05				
No	**Working**	**Answer**	**Mark**	**Notes**
1 (a)	$1 - (0.2 + 0.3 + 0.1)$	0.4	2	M1 for $1 - (0.2 + 0.3 + 0.1)$ A1 for 0.4 oe, accept $\frac{0.4}{1}$
(b)	0.2×200	40	2	M1 for 0.2×200 A1 cao NB $\frac{40}{200}$ is M1 A0, 40 out of 200 is M1 A1
2	$650 - 430 = 220$ 1 choc ice costs 110p $650 - 5 \times 110 = 100$p	50	3	M1 for $650 - 430$ or 220 or 110 oe seen M1 for $650 - 5 \times \frac{'220'}{2}$ or $430 - 3 \times \frac{'220'}{2}$ oe A1 for 50p or £0.50 or £0.5 *Alternative scheme* $2x + 5y = 650$ $2x + 3y = 430$ oe M1 for subtracting two simultaneous equations to eliminate x (lollies)(2 or 3 terms correct) M1 for $650 - 5 \times 'y'$ or $430 - 3 \times 'y'$ oe A1 for 50p or £0.50 or £0.5 *Alternative scheme* M1 for $3\times (2x + 5y = 650)$ evaluated and $5 \times (2x + 3y = 430)$ evaluated oe (5 or 6 terms correct) M1 for subtraction of equations to eliminate y (choc ices)(2 or 3 terms correct ft) A1 for 50p or £0.50 or £0.5

Paper 5525_05				
No	**Working**	**Answer**	**Mark**	**Notes**
3		question + response boxes oe	2	1st aspect: One question (eg 'how long does it take you to travel to school?' or 'What time did you leave home to get to school?'); ignore other questions. 2nd aspect: Response list (at least two), not overlapping. 3rd aspect: Some mention of units (eg minutes) in either question or responses B2 for all three aspects, or B1 for just one aspects.
4	2 [(3×1) + (4×1)] + (3×6) + (1×6) + (2×6) + (4×6) + (1×6) + (5×6)	110 cm^2	4	M1 for attempt to find the area of one face M1 for at least 6 faces with intention to add A1 cao B1 (indep) for cm^2 (with or without numerical answer)
5	$\left(\frac{-6+4}{2}\right), \left(\frac{5+3}{2}\right)$	(–1, 4)	2	B2 cao [B1 for (–1,*a*) or (b,4) or (4,-1)]
6		Box plot	2	3 aspects: 1st aspect – vertical line for median 2nd aspect – box using correct quartiles 3rd aspect – whiskers (could be single line) drawn with correct end points B2 for fully correct box plot (B1 for 1 aspect)
7			2	M1 for a relevant pair of intersecting arcs A1 for line drawn within guidelines, at least 3cm in length, accept broken line [SC: B1 for line drawn within guidelines if M0]

Paper 5525_05					
No		**Working**	**Answer**	**Mark**	**Notes**
8	(a)	e.g. 2 | 126 3 | 63 3 | 21 7	$2\times3\times3\times7$	2	M1 for a systematic method of at least 2 correct divisions by a prime number oe factor trees; can be implied by digits 2, 3, 3, 7 on answer line. A1 for $2\times3^2\times7$ or $2\times3\times3\times7$
	(b)	$2\times3\times7$	42	2	B2 cao (B1 for 6, 14, 21 or $2\times3\times7$)
9	(a)		$-1,0,1,2,3$	2	B2 cao (-1 each error or omission)
	(b)(i)		$x\geq\frac{7}{2}$	3	M1 for $2x\geq7$, condone use of = sign or wrong equality A1 for $x\geq\frac{7}{2}$ oe as final answer
	(ii)		4		SC:B1 for 3.5 or $\frac{7}{2}$ seen if M0 B1 ft from $x\geq$ "$\frac{7}{2}$" or $x>$"$\frac{7}{2}$"
10	(a)(i)		7^5	3	B1 cao
	(ii)		7^4		B2 cao (B1 for sight of 7^5 or 7^{2+3} or 7×7^3 or $7^1\times7^3$ or $7^2\times7^2$ or 7^{2+3-1})
	(b)		$\frac{1}{2}$	1	B1 for $\frac{1}{2}$ or 0.5 or 2^{-1}
11	(a)	$5n=m+21$	$n=\frac{m+21}{5}$	2	M1 for $5n=m+21$ or for attempt to divide three terms by 5 A1 $n=\frac{m+21}{5}$ oe

Paper 5525_05				
No	**Working**	**Answer**	**Mark**	**Notes**
(b)	$4p-8q=3p+2$ $p-8q=2$ $p=8q+2$	$p=8q+2$	3	M1 for $4p-aq$ or $\frac{3}{4}p+b$ where a is an integer and b is a number M1 (dep) for taking one term correctly to LHS or RHS of expression A1 $p=8q+2$ oe
12		$y=\frac{1}{2}x+3$	2	B2 for $y = ½x + 3$ oe (B1 for $y = ½x + c$, $c \neq 7$ or $y = mx + 3$ oe or $½x + 3$ or $M = ½x + 3$)
13	$\frac{8}{3}\times\frac{5}{4}=\frac{8\times5}{3\times4}=\frac{40}{12}$	$3\frac{1}{3}$	3	B1 for $\frac{8}{3}$ oe or $\frac{5}{4}$ oe M1 (dep on B1) for multiplying numerator and denominator of "$\frac{8}{3}$" and "$\frac{5}{4}$" A1 for $3\frac{1}{3}$ oe mixed number or $\frac{10}{3}$ *OR* B1 for 1.25 and 2.67 or 2.66(…) M1(dep on B1) for correct method of multiplication A1 for $3.\dot{3}$
14	$4x+2y=8$ $4x-10y=20$ $12y=-12$ $y=-1$ $4x+2(-1)=8$ $x=2.5$	$x=2.5$ $y=-1$	3	M1 for correct process to eliminate either x or y (condone one arithmetical error) M1 (dep) for substituting found value into either equation A1 for $x = 2.5$, $y = -1$ [SC: B1 for $x = 2.5$ or $y = -1$ if M0]

Paper 5525_05					
No		**Working**	**Answer**	**Mark**	**Notes**
15		Interior angle of hexagon = 180 – (360 ÷ 6) = 120 360 – (90 + 120)	150	4	Alternative 1 M1 for 360 ÷ 6 A1 for 60 M1 (dep on M1) for "60" + 90 A1 cao Alternative 2 M1 for 360 ÷ 6 A1 for 60 M1(dep on M1) for 360 – (2 × "60" + 90) A1 cao Alternative 3 M1 for (6 – 2) × 180 ÷ 6 A1 for 120 M1(dep on M1) for 360 – (90 + "120") A1 cao
16	(a)		(16), 50, 82, 96, 100	1	B1 cao
	(b)	Cumulative freq. diag. curve/ segments	Cum. freq graph	2	B1 ft for 4 or 5 points plotted correctly ± 1 full (2mm) square depending on sensible table (condone 1 addition error) B1 (dep) for points joined by curve or line segments provided no gradient is negative - ignore any part of graph outside range of their points. (SC:B1 if 4 or 5 points plotted not at end but consistent within each interval and joined)

Paper 5525_05					
No		Working	Answer	Mark	Notes
	(c)	$100 - 42$	58	2	M1 (ft dep on graph being cf) for reading from graph at 18 or 19, can be implied by answer in range 40 to 46 A1 for answer in range 56 to 60 or ft for 100 –'42' ±1 full (2mm) square
17	(a)		0.6 and 0.7,0.3,0.7	2	B1 for 0.6 on LH branch B1 for 0.7, 0.3 and 0.7 on RH branches
	(b)	0.4×0.3	0.12	2	M1 for 0.4×0.3 A1 0.12 oe
	(c)	$0.4\times0.7+0.6\times0.3$	0.46	3	M1 for '0.4×0.7' or '0.6×0.3' M1 for addition of two products from correct branches A1 0.46 oe Alternative M2 for an attempt to evaluate 1-(0.3×0.4 +'0.6×0.7') A1 cao
18		$x = 0.4545...$ so $100x = 45.4545...$ $99x = 45$ $x = \frac{45}{99} = \frac{15}{33}$	proof	3	M1 for $100x = 45.45\ldots$ or $10000x = 4545.45\ldots$ M1 (dep) for subtraction of both sides A1 for $\frac{15}{33}$ from correct proof
19		$\left(\sqrt{3}\right)^2 + \sqrt{3}\sqrt{2} - \sqrt{3}\sqrt{2} - \left(\sqrt{2}\right)^2$ $= 3 - 2$	1	2	B2 cao (B1 for $\sqrt{3}\sqrt{3} + \sqrt{3}\sqrt{2} - \sqrt{3}\sqrt{2} - \sqrt{2}\sqrt{2}$ oe, $\sqrt{3}\sqrt{3} - \sqrt{2}\sqrt{2}$ oe, or for 2,3, $\sqrt{4}$ $\sqrt{6}$ $\sqrt{9}$ seen)
20	(a)	$\frac{96}{24}$ or 4 $\sqrt{4}$ or 2	8	3	M1 for $\frac{96}{24}$ or $\frac{24}{96}$ or 4 or $\frac{1}{4}$ oe M1 for $\sqrt{\frac{96}{24}}$ or $\sqrt{\frac{24}{96}}$ or $\sqrt{'4'}$ or $\frac{1}{\sqrt{'4'}}$ or 2 or $\frac{1}{2}$ oe A1 cao

Paper 5525_05					
No		**Working**	**Answer**	**Mark**	**Notes**
	(b)	12×2^3	96	2	M1 for '2'^{3} or 8 A1 cao
21	(a)	$x\times3-x\times2x^2$	$3x-2x^3$	2	B2 cao (B1 for a two term expression with either $3x$ or $2x^3$)
	(b)		$4x(3y+x)$	2	M1 for taking out a factor of x, $2x$, 2, 4 or $4x$ A1 cao
	(c)	$\frac{5a}{b^2}$	$\frac{5a}{b^2}$	2	B2 for $\frac{5a}{b^2}$ or $5ab^{-2}$ (accept $\frac{5a}{1b^2}$) (B1 for either dealing with the numbers or dealing with the powers of a)
	(d)	$\frac{\cancel{x-3}}{\cancel{(x-3)}(x+3)}$	$\frac{1}{x+3}$	2	M1 for $(x-3)(x+3)$ A1 cao
22	(a)		$\mathbf{a}+\mathbf{b}$	1	B1 $\mathbf{a}+\mathbf{b}$ oe
	(b)	$ED=\mathbf{a}$ $DX=-2\mathbf{b}+2\ AC=2\mathbf{a}$ (So, $DX=2ED$)	$2\mathbf{a}$	3	M1 for $(DX=)\ DA+AX$ A1 for $(DX=)\ -2\boldsymbol{b}+2$ ("$\boldsymbol{a}+\boldsymbol{b}$") A1 $2\boldsymbol{a}$ from fully correct proof
23		$\pi(2x)^2h=\frac{4}{3}\pi(3x)^3$ $h=\frac{\frac{4}{3}\pi(3x)^3}{\pi(2x)^2}$	$9x$	3	M1 for $\pi(2x)^2h=\frac{4}{3}\pi(3x)^3$ (condone absence of brackets) M1 (dep) for valid algebra that gets to $h=ax$ (condone one error in powers of numerical constants) A1 cao

Paper 5525_05					
No		**Working**	**Answer**	**Mark**	**Notes**
24	(i)	$n^2+(n+1)^2=2(n^2+n)+1$	$2n^2+2n+1$	4	M1 for at least 3 terms correct from $n^2+n+n+1$ A1 for $2n^2+2n+1$ oe
	(ii)		$2(n^2+n)$ is always even so $2(n^2+n)+1$ is always odd		M1 for recognizing $2n^2$ is always even A1ft complete proof for their quadratic *Alternative method* M1 for recognizing that if n^2 is odd then $(n+1)^2$ is even or vice versa A1 for complete proof
25			42 318	2	B1 for answer in range 36 – 48 B1 for answer in range 312 – 324
26	(a)	$(x-3)^2-3^2+15$	$p=3, q=6$	2	B2 for $p=3$ and $q=6$ (B1 for $p=3$ OR $q=6$) SC: award B2 for $(x-3)^2+6$ if p and q are not identified
	(b)		Sketch	2	B1 for U shaped curve B1 ft for TP in first quadrant (ft if TP not in first quadrant)
27	(a)	Graph translated 2 units upwards through points (–4, 2), (–2, 4), (0,2) and (3,5)	Sketch	2	M1 for a vertical translation A1 curve through points (–4, 2), (–2, 4), (0,2) and (3,5) ± ½ square
	(b)	Graph reflected in x-axis through points (–4,0), (–2, –2), (0, 0) and (3, -3)	Sketch	2	M1 for reflection in x-axis or y-axis A1 curve through points (–4,0), (–2, –2), (0, 0) and (3, -3) ± ½ square

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
1		273	2	M1 for 728 ÷ 8 or 728 ÷ "3+5" or 91 A1 cao SC B1 for 455 or 273:455
2		$3n - 1$	2	B2 for $3n - 1$ oe (B1 for $3n + k$ where $k \neq -1$ but k could be 0)
3	3 24 3.7 46.9(53) 4 60 3.8 51.0(72) 3.1 26.6(91) 3.9 55.4(19) 3.2 29.5(68) 3.21 29.8(66…) 3.3 32.6(37) 3.22 30.1(66…) 3.4 35.9(04) 3.23 30.4(68..) 3.5 39.3(75) 3.24 30.7(72...) 3.6 43.0(56) 3.25 31.0(78...) or 31	3.2	4	B2 for trial between 3.2 and 3.3 inclusive (B1 for trial between 3 and 4 inclusive) B1 for different trial between 3.21 and 3.25 inclusive B1 (dep on at least one previous B1) cao for 3.2 NB: embedded answers: –B1; award Bs for evaluations rounded or truncated to at least 1 dp or for 31
4	2 is the only even prime number and the product of 2 odd numbers is odd	Yes	2	B2 for 'yes' and '2 is the only even prime number and the product of two odd numbers is odd' oe (B1 for 'yes' and either '2 is the only even prime number' oe **or** 'the product of two odd numbers is odd' oe)
5	$45^2 + 34^2 =$ $2025 + 1156 = 3181$ $\sqrt{3181} = 56.4$	56	4	M1 for $45^2 + 34^2$ M1 for $\sqrt{(2025 + 1156)}$ A1 for 56.4 … B1 for rounding their diagonal to the nearest integer (dep on evidence from decimal) NB 56 with no incorrect working as the final answer gets full marks. NB Scale drawings result in 0 marks.

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
6	2000 × $(1.055)^3$ Interest = 2348.48 – 2000 =	£348.48	3	M1 for 5.5/100 × 2000 (oe) or 330 or 16.5/100×2000 or 2330 or 110 or 2110 M1 (dep) for 5.5/100 × (2000 + "110" + "116.05") or 122.4… seen A1 cao (accept only 348.48 or 348.49) **OR** M2 for 2000 × $(1.055)^3$ or 2348.48(…) or 2348.49 seen (M1 for 2000 × $(1.055)^n$, $n \neq 3$) A1 for 348.48 or 348.49 [SC: B2 for 2348.48 - 2348.49]
7 (a)		Line	2	B2 line fully within tramlines, crossing AB and CD (B1 a straight line which crosses AB within the tramline, and also crosses CD) NB: Accept dotted or dashed lines, but not curves; accept freehand if considered to be straight. SC B1 for the perpendicular bisector of *AB* reaching halfway or more from *AB*
(b)		Region		B2 correct arc ±2mm and shaded within. Allow dotty or continous arc. (B1 inaccurate arc and shaded or accurate arc unshaded)
8	65×12=780 75×22=1650 85×23=1955 95×24=2280 105×19=1995 8660/100=	86.6	4	M1 for use of fx with x consistent within intervals (including end points). Allow one slip even if outside interval M1 (dep) for use of midpoints M1 (dep on 1st M1) for use of $\sum fx/100$ or $\sum fx/\sum f$ A1 86.6

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
9		Distance ÷ time: 1400 ÷ 2 h 20 min 20 mins is $\frac{1}{3}$ hour 1400 × 3 ÷ 7 =	600 kph	3	B1 20 mins as $\frac{1}{3}$ hour or as 0.33……hour M1 for distance ÷ time eg 1400 ÷ "2h 20 min" A1 cao OR B1 2 hour 20min = 140 (min) M1 Speed = $\frac{1400}{140}$ = (10 km per minute) A1 cao
10	(a)	$(x+18)+2x+(2x+7)=180$	Equation	2	B2 for $(x+18)+2x+(2x+7)=180$ oe (B1 for $(x+18)+2x+(2x+7)$)
	(b)	$5x+25 = 180$ $5x = 155$	31	2	M1 for simplifying to at least $5x+25=180$ or 360 (may be earned in (a)) A1 for $x=31$
11	(a)	(–14) –4 (0) 4 14	–4, 4, 14	2	B2 for all 3 values correct (B1 for 1 or 2 values correct)
	(b)		curve	2	B1 for all 5 points plotted correctly ± ½ square (ft from table if at least B1 awarded in (a)) B1 (indep) ft for any smooth curve through their points

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
12 (a)	$8 \times \frac{10}{4}$	20	2	M1 $\frac{10}{4}$ or $\frac{4}{10}$ or 0.4 or 2.5 oe seen A1 cao NB ratios get M0 unless of the form 1:*n* OR M1 $\frac{8}{4}, \frac{4}{8}$ oe seen A1 cao
(b)	$15 \times \frac{4}{10}$	6	2	M1 $15 \times \frac{4}{10}$ oe A1 cao
13 (a)	$9.9\times10^8 - 6.0\times10^7$	$\pm 9.3\times10^8$	2	M1 for $99\times10^7 - 6.0\times10^7$ or $9.9\times10^8 - 0.60\times10^8$ or correct conversion of either to an ordinary number or 930000000 or 9.3×10^n where *n* is any positive integer A1 cao
(b)	$\frac{6.0-4.5}{4.5} \times 100 = \frac{1.5}{4.5} \times 100 =$ or $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7} \times 100$	33.3%	3	M2 $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7} \times 100$ oe (M1 for $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7}$ or $\frac{6.0\times10^7 - 4.5\times10^7}{6.0\times10^7} \times 100$ oe A1 33.3 – 33.4 OR M2 $\frac{6.0\times10^7}{4.5\times10^7} \times 100$ -100 or 33.3% (M1 $\frac{6.0\times10^7}{4.5\times10^7} \times 100$ or 133.3%) A1 33.3-33.4 NB Accept any of the above expressions without any reference to 10^7.

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
14	LCM (40,24) = 120 Bread buns 120÷40 Burgers 120÷24 OR Bread buns: 40 is 2 × 2 × 2 (×5) Burgers: 24 is 2 × 2 × 2 (×3)	Bread Buns 3 Burgers 5	3	M1 attempt to find LCM by eg lists of multiples, or summing of 40s and summing of 24s, with at least 3 numbers in each list A1 identify 120 as LCM A1 cao (both) **OR** M1 expansion of either number into its prime factors in a factor tree or 8×5 or 8×3 A1 both expansions correct A1 cao (both) SC B2 if answers given the wrong way around
15	$\sin 32 = \frac{AB}{12}$ $AB = 12 \times \sin 32$ $AB = 6.35903\ldots$	6.36	3	M1 $\sin 32 = \frac{AB}{12}$ (accept Sin $\frac{AB}{12}$) M1 $12 \times \sin 32$ or $12 \times 0.5299..$ A1 accept 6.359 – 6.360 SC Gradians 5.78(1…) Radians 6.62 Get M1M1A0 **OR** Use of Sine Rule $\frac{\sin 32}{AB} = \frac{\sin 90}{12}$ or $\frac{AB}{\sin 32} = \frac{12}{\sin 90}$ M1 $AB = \frac{12 \times \sin 32}{\sin 90}$ M1 AB = 6.359 – 6.36 A1 SC Gradians 5.85(…) Radians 7. 40(…) M1M1A0

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
16		$8 \times 41 = 328$ $2 \times 29 = 58$ $328 - 58 = 270$ $270 \div 6 = 45$	45	3	M1 for either 8×41 (=328) or 2×29 (=58) M1 (dep) "328" – "58" (=270) A1 cao NB 328 and /or 58 on the answer line gets M1 (implied); 270 on the answer line gets M2 (implied)
17	(a)	$x^2 - 4x + 3x - 12 = x^2 - x - 12$	$x^2 - x - 12$	2	M1 for exactly 4 terms correct ignoring signs (x^2, $4x$, $3x$, 12) or 3 out of 4 terms with correct signs (x^2, $-4x$, $+3x$, -12) A1 cao
	(b)	$6x^2 - 8x + 15x - 20 = 6x^2 + 7x - 20$	$6x^2 + 7x - 20$	2	M1 for exactly 4 terms correct ignoring signs ($6x^2$, $8x$, $15x$, 20) or 3 out of 4 terms with correct signs ($6x^2$, $-8x$, $+15x$, -20) A1 cao
	(c)	$(x+2)(x+5)$	$(x+2)(x+5)$	2	B2 cao (B1 for exactly one of $(x + 2)$, $(x + 5)$)
	(d)		$12p^8q^3$	2	B2 cao (B1 for any 2 out of 3 terms correct in a product or 3 terms correct in a sum or part product)
	(e)	$6 = 15 + 4(q - 5)$ $6 = 15 + 4q - 20$ $11 = 4q$	$2\frac{3}{4}$	3	M1 for correct substitution of p and t. M1 for correct expansion of $4(q\text{-}t)$ oe (eg $4q$-20, $4q$-$4t$) A1 11/4 or 2 ¾ or 2.75 OR M1 for correct substitution of p and t. M1 for $\frac{p-3t}{4} = q - t$ oe A1 11/4 or 2 ¾ or 2.75
18	(a)	$T=kx$; $150=6k$; $k=25$	$T=25x$	3	M1 for $T=kx$, k algebraic M1 subs $T=150$ and $x=6$ into $T = kx^n$ $(n \neq 0)$ A1 for $T=25x$ oe SC B1 $T \propto 25x$ oe

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
	(b)	$T = 25 \times 15 =$	375	1	B1 ft on k , $k \neq 1$
	(c)	$600 = 25x$; $x = 600 \div 25 =$	24	1	B1 ft on k , $k \neq 1$
19		$\frac{120}{570} \times 50 = 10.5263$ $\frac{250}{570} \times 50 = 21.9298$ $\frac{200}{570} \times 50 = 17.5438$	10 22 18	3	M1 method shown eg $\frac{120}{120+250+200} \times 50$ or one of 10.5(263) 21.9(298), 17.5(438) **OR** 570 ÷ 50 = 11.4 and one of 120 ÷ 11.4 =10.526…) , 270 ÷ 11.4 (=21.9298…) , 200 ÷ 11.4 (=17.5438…) A1 for 10.5(263), 21.9(298), 17.5(438) or 11, 22, 18 B1 correction to add to 50: 10, 22, 18 or 11, 22, 17
20		$x(x+1) + 4(2x–3) = (2x–3)(x+1)$ $x^2 + x + 8x – 12 = 2x^2 + 2x – 3x – 3$ $x^2 – 10x + 9 = 0$ $(x – 9)(x – 1) = 0$	$x = 1, 9$	5	M1 for multiplying through by common denominator $(2x–3)(x+1)$ M1 (dep)for either $x^2 + x + 8x – 12$ or $2x^2 + 2x – 3x – 3$ oe A1 for correct quadratic (= 0) M1 for a correct method to solve 3 term quadratic A1 cao for both solutions
21		$AB^2 = 8^2 + 9^2 – 2\times8\times9\times\cos40$ $AB^2 = 64 + 81 – 144\times\cos40$ $AB^2 = 145 – 144 \times 0.766$ $AB^2 = 145 – 110.31… = 34.6896$ $AB = \sqrt{34.6796} = 5.8897877$	5.89	3	M1 Subs in Cos Rule: $8^2 + 9^2 – 2\times8\times9\times\cos40$ M1 correct order of evaluation of $8^2 + 9^2 – 2\times8\times9\times\cos40$ A1 cao 5.88 – 5.89 SC: Award B2 for one of $AB^2 = 241.03…$ or $AB = 15.525…$ (radians) $AB^2 = 28.50…$ or $AB = 5.33…$ (gradians)
22	(a)		24 30	2	B1 24 cao B1 30 cao
	(b)	Column $60 \leq w < 75$ at 10 Column $75 \leq w < 95$ at 4	10 4	2	B1 10 and correct width (tol $\pm\frac{1}{2}$ small square) B1 4 and correct width (tol $\pm\frac{1}{2}$ small square)

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
23 (a)		100.5	1	B1 cao
(b)		10.515	1	B1 cao
(c)	$\frac{100.5}{10.515}$	9.5577746	2	M1 for greatest distance divided by least time Where 100 < greatest distance ≤ 100.5, 10.51 ≤ least time < 10.52 A1 for 9.555 – 9.56
(d)	$\frac{99.5}{10.525}$	9.45368..	2	M1 for least distance divided by greatest time Where 99.5 ≤ least distance < 100, 10.52 < greatest time ≤10.53 A1 for 9.45 – 9.455
24	$\frac{4}{7}\times\frac{4}{7}\times\frac{3}{7} + \frac{3}{7}\times\frac{3}{7}\times\frac{4}{7} =$ $\frac{48+36}{343} = \frac{84}{343}$ But there are three ways this can be achieved: BBG, BGB, GBB So the probability is $\frac{84}{343}\times 3$ OR $1-\frac{64}{343}-\frac{27}{343}$ NB: 84/343 = 0.244897; 252/343 = 0.73469 $\frac{4}{7} = 0.57(142...)$, $\frac{3}{7} = 0.42(857...)$	$\frac{252}{343}$	3	M1 for $\frac{4}{7}\times\frac{4}{7}\times\frac{3}{7}$ or $\frac{3}{7}\times\frac{3}{7}\times\frac{4}{7}$ oe or $\left(\frac{4}{7}\right)^3$ oe or $\left(\frac{3}{7}\right)^3$ oe or $\frac{91}{343}$ or 0.10(49…) or 0.13(99….) M1 (indep) for identification of all 6 outcomes (M2 for $1-\left[\left(\frac{4}{7}\right)^3+\left(\frac{3}{7}\right)^3\right]$) oe A1 $\frac{252}{343}$, $\frac{36}{49}$, 0.73(469…) oe

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
25	(a)	$\frac{1}{3} \times \pi \times 5^2 \times 8 = \pi \times 25 \times 8 \div 3 =$ 209.4395	209–210	2	M1 for $\frac{1}{3} \times \pi \times 5^2 \times 8$ A1 for 209–210
	(b)	Base radius = $\frac{216}{360} \times 15 = 9$ Height = $\sqrt{(15^2 - 9^2)} =$	12	4	M1 for 216 ÷ 360 A1 for 9 M1 for $\sqrt{(15^2 - \text{“9”}^2)}$, where “9” < 15 A1 cao

PMT

edexcel

Mark Scheme (Results)

March 2013

GCSE Mathematics (2MB01) Higher
5MB3H (Calculator) Paper 01

PMT

Edexcel and BTEC Qualifications

Edexcel and BTEC qualifications come from Pearson, the world's leading learning company. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers. For further information visit our qualifications websites at www.edexcel.com or www.btec.co.uk for our BTEC qualifications.
Alternatively, you can get in touch with us using the details on our contact us page at www.edexcel.com/contactus.

If you have any subject specific questions about this specification that require the help of a subject specialist, you can speak directly to the subject team at Pearson.
Their contact details can be found on this link: www.edexcel.com/teachingservices.

You can also use our online Ask the Expert service at www.edexcel.com/ask. You will need an Edexcel username and password to access this service.

Pearson: helping people progress, everywhere
Our aim is to help everyone progress in their lives through education. We believe in every kind of learning, for all kinds of people, wherever they are in the world. We've been involved in education for over 150 years, and by working across 70 countries, in 100 languages, we have built an international reputation for our commitment to high standards and raising achievement through innovation in education. Find out more about how we can help you and your students at: www.pearson.com/uk

March 2013
Publications Code UG035055
All the material in this publication is copyright
© Pearson Education Ltd 2013

NOTES ON MARKING PRINCIPLES

1 All candidates must receive the same treatment. Examiners must mark the first candidate in exactly the same way as they mark the last.

2 Mark schemes should be applied positively. Candidates must be rewarded for what they have shown they can do rather than penalised for omissions.

3 All the marks on the mark scheme are designed to be awarded. Examiners should always award full marks if deserved, i.e if the answer matches the mark scheme. Examiners should also be prepared to award zero marks if the candidate's response is not worthy of credit according to the mark scheme.

4 Where some judgement is required, mark schemes will provide the principles by which marks will be awarded and exemplification may be limited.

5 Crossed out work should be marked UNLESS the candidate has replaced it with an alternative response.

6 Mark schemes will indicate within the table where, and which strands of QWC, are being assessed. The strands are as follows:

i) *ensure that text is legible and that spelling, punctuation and grammar are accurate so that meaning is clear*
Comprehension and meaning is clear by using correct notation and labeling conventions.

ii) *select and use a form and style of writing appropriate to purpose and to complex subject matter*
Reasoning, explanation or argument is correct and appropriately structured to convey mathematical reasoning.

iii) *organise information clearly and coherently, using specialist vocabulary when appropriate*.
The mathematical methods and processes used are coherently and clearly organised and the appropriate mathematical vocabulary used.

7 With working

If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
If there is no answer on the answer line then check the working for an obvious answer.
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks. Discuss each of these situations with your Team Leader.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.

8 Follow through marks

Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

9 Ignoring subsequent work

It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: e.g. incorrect canceling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect e.g. algebra.
Transcription errors occur when candidates present a correct answer in working, and write it incorrectly on the answer line; mark the correct answer.

10 Probability

Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

11 Linear equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

12 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

13 Range of answers

Unless otherwise stated, when an answer is given as a range (e.g 3.5 – 4.2) then this is inclusive of the end points (e.g 3.5, 4.2) and includes all numbers within the range (e.g 4, 4.1)

Guidance on the use of codes within this mark scheme
M1 – method mark A1 – accuracy mark B1 – Working mark C1 – communication mark QWC – quality of written communication oe – or equivalent cao – correct answer only ft – follow through sc – special case dep – dependent (on a previous mark or conclusion) indep – independent isw – ignore subsequent working

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
*1			small and correct answers	3	M1 for 4.2 ÷ 1.75 (=2.4(0)) **or** 8.68 ÷ 3.5 (=2.48) M1 for 4.2 ÷ 1.75 (=2.4(0)) **and** 8.68 ÷ 3.5 (=2.48) C1 (dep on at least M1) for small and (£)2.4(0) and (£)2.48 **OR** M1 for 1.75 ÷ 4.2 (=0.41(6)) **or** 3.5 ÷ 8.68 (=0.40(3)) M1 for 1.75 ÷ 4.2 (=0.41(6)) **and** 3.5 ÷ 8.68 (=0.40(3)) C1 (dep on at least M1) for small and 0.41(6)(kg) and 0.40(3)(kg) **OR** M1 for 4.2 ÷ 1.75 (=2.4(0)) **or** 8.68 ÷ 3.5 (=2.48) M1 for (4.2 ÷ 1.75) × 3.5 (=8.4(0)) or (8.68 ÷ 3.5) × 1.75 (=4.34) C1 (dep on at least M1) for small and (£)8.4(0) or for small and (£)4.34 **OR** M1 for 1.75 ÷ 4.2 (=0.41(6)) or 3.5 ÷ 8.68 (=0.40(3)) M1 for (1.75 ÷ 4.2) × 8.68 (=3.61(6)) or (3.5 ÷ 8.68) × 4.2 (=1.69(3)) C1 (dep on at least M1) for small and 3.61(6)(kg) or 1.69(3)(kg) **OR** M2 for 8.68 ÷ 2 (=4.34) or 4.20 × 2 (=8.40) C1 (dep on at least M1) for small and (£)4.34 or (£8.40) **OR** Any other method considered equivalent. Figures may be truncated or rounded as long as their method is clear.

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
2		$7 \times 8^2 + 320 = 448 + 320$ 768p = 7.68	£7.68	3	M1 for 7×8^2 or 448 seen A1 for 768 B1 for correct monetary answer written correctly eg £7.68 or 768p
3			correct shaded region	2	B1 for arc of circle, centre oak tree, radius 4cm(±2mm) B1 for shaded region where the tree can be planted, bounded by sides of garden and arc of circle centre oak tree
4	(a)		−3, −2, −1,0,1	2	B2 for all 5 values and no others (B1 for 4 correct values and no others or -4,-3,-2,-1,0,1 or -3,-2,-1,0,1,2
	(b)		$-2 \leq x < 4$	2	B2 for $-2 \leq x < 4$ (B1 for $-2 \leq x$ or $x < 4$ or $-2 < x \leq 4$) [Note: accept the use of any letter other than x throughout and ignore any attempt to list integer values]
5			25.1-25.2	2	M1 for $2 \times 3.142 \times 4$ or 8π oe A1 for 25.1 – 25. 2
6	(a)		5, −4, −3	2	B2 for 5, −4 and −3 (B1 for 5 or −4 or −3)
	(b)		correct curve	2	B2 for fully correct curve (B1 ft for at least 5 points plotted correctly)

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
7			enlargement, scale factor 2, centre (6, −5)	3	B1 for enlargement B1 for (scale) factor 2 or ×2 or sf 2 B1 for (6, −5) NB: award 0 marks for an explanation that includes reference to more than one transformation.
*8		Cost of wages, rent and other expenses last year 92 000+10 800+7000=109 800 Cost of wages, rent and other expenses this year $1.075\times92\,000 + \frac{7}{9} \times 10$ 800 + 7000÷2 = 98 900+8400+3500 = 110 800 Costs are more this year, so she cannot increase the amount she spends on goods	no, with working and reason	4	M1 for an attempt to calculate using 7.5% and 92000 (eg 7.5% of 92000 or increase of 7.5%) eg 92000 + 6900 or 98900 M1 for an attempt to find a fractional amount of 10800 (eg $\frac{7}{9}$ × 10800 or 8400 or $\frac{2}{9}$ × 10800 or 2400) M1 for complete method of increasing 92000 by 7.5%, finding $\frac{7}{9}$ of 10800, and halving 7000, with at least all of these three added together. C1 for statement eg "no" with both 110800 & 109800 seen, OR "no" with "1000 more" OR "no" and compares 181800 with 182800, oe.
9	(a)	$\sqrt{30} = 5.4772255\ldots$ $2.5^2 = 6.25$ 5.4772255...÷ 6.25 =	0.876	2	M1 for $\sqrt{30} \div 6.25$ or $5.4(7\ldots) \div 2.5^2$ A1 for any answer in the range 0.876 to 0.877
	(b)	4.5 × 1000 × 1000	4 500 000	2	M1 for complete method equivalent to 4.5 × 1000 × 1000 A1 for 4 500 000 oe

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
10		3 → 21 4 → 56 3.1 → 23.5(9) 3.2 → 26.3(6) 3.3 → 29.3(3) 3.4 → 32.5(0) 3.5 → 35.8(7) 3.6 → 39.4(5) 3.7 → 43.2(5) 3.8 → 47.2(7) 3.9 → 51.(5) 3.35 → 30.8(9)	3.3	4	B2 for a trial between 3.3 and 3.4 inclusive (B1 for a trial between 3 and 4 inclusive) B1 for a different trial between 3.3 and 3.4 exclusive B1 (dep on at least one previous B1) for 3.3 NB trials should be evaluated to at least 1dp truncated or rounded
11			45	3	M1 for 60000 × 0.75 or ÷1000 or digits 45 or the numbers 60 or 0.00075) M1 for the complete method 60 000 × 0.75 ÷ 1000 oe A1 cao
12	(a)		−7	2	M1 for an attempt to get *x*s on one side or number terms on one side A1 cao
	(b)		8.5	2	M1 for an attempt to divide each side by 4 or an attempt to expand the bracket eg $4 \times x - 4 \times 5$ A1 for 8.5 oe

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
*13		2500×0.04×2 =£200 2500×$(1.039)^2$ = £2698.80 £2698.80 – £2500 = £198.80 Scheme A gives £1.20 more	statement	4	M1 for a correct method to find 4% of 2500 or 3.9% of 2500 A1 for a correctly calculated amount 2700 or 2698.8(0) or 200 or 198.8(0); or percentage rate calculated over the 2 years for comparison: 3.93% or 3.976% oe M1 for a correct compound interest method using 3.9% and 2500 over 2 years C1 for statement of scheme A, with two correct comparable figures.
14		$3x - 2y = 7$ $7x + 2y = 13$ $10x = 20$ $x = 2$ $3\times2 - 2y = 7$ $-2y = 1$ $y = -0.5$	2, −0.5	3	M1 for a correct process to eliminate either x or y (allow one arithmetic error) M1 (dep) for correct substitution of their found variable or an otherwise correct method to eliminate the other variable A1 for 2 and −0.5 oe
15	(a)		3.7×10^{-3}	1	B1 cao
	(b)		49 000	1	B1 cao
	(c)	500 ÷ 250 000 [= 0.002] OR $(5 \times 10^2) \div (2.5 \times 10^5)$ [= $(5\div2.5)\times10^{2-5}$] OR $\frac{500}{250} \times \frac{1}{10^3}$ [= 2×10^{-3}] OR $\frac{500\div100}{250000\div100} = \frac{5}{2500}$ [= 0.002]	2×10^{-3}	2	M1 for an attempt to divide using two numbers that are in consistent form eg following an attempt to convert to ordinary numbers, or standard form numbers. A1 for 2×10^{-3}

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
16			12.7	3	M1 for 3.142 × 5 × 5 oe or 3.142 × 5 × 5 × '*h*' (=78.5 – 78.55) M1 for 1000 ÷ (3.142 × 5 × 5) A1 for 12.7 – 12.8 NB: multiples of π acceptable for M marks
17		$4x - 3 = 2x + 2y$ $2x - 3 = 2y$ $2x = 2y + 3$ $x = y + 1.5$	$x = y + 1.5$	3	M1 for attempt to expand brackets eg $2\times x+2\times y$ or divide through by 2 (each term). M1 for attempt to get x on one side of equation. A1 for $(x =) y + 1.5$, $\frac{2y + 3}{2}$, oe
18			(11, 21)	3	M1 for 5 – 2 or 9 – 3 OR 3 or 6 as long as these are not related to the 3 from *A* or multiple 3 or 9,18 M1 for 2 + 3 × "3" and 3 + 3 × "6" OR for 5 + 2 × "3" and 9 + 2 × "6" OR for 2 + 3 × "3" (=11) and (*y*=) 2 × '11' – 1 A1 cao SC: B1 if no method shown and answer shows *x* coordinate as 11 or *y* coordinate as 21.

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
19			4.6	5	M1 for $AC = \sqrt{(3^2+4^2)}$ (=5) or $DA = \sqrt{(5^2+2^2)}$ M1 for tan BAC = 0.75 oe or (BAC=) 36.8(6) or 36.9 M1 for tan DAC = 0.4 oe or (DAC=) 21.8(0) M1 for $\sqrt{'5'^2+2^2}$ × sin("36.8(6)"+"21.8(0)") or 5.385 × sin 58.7 A1 for 4.59 – 4.61 OR M1 for $AC = \sqrt{3^2+4^2}(=5)$ or $DP = \sqrt{(29 - AP^2)}$ M1 for cos BAC = 0.8 oe or (BAC=) 36.8(6) oe M1 for angle CDP = angle BAC M1 for (DP=) 3 + 2×cos CDP or (AP=) 4 – 2×sin CDP A1 for 4.59 – 4.61
20			0.5, −3	3	M1 for $(2x \pm 1)(x \pm 3)$ M1 for $(2x - 1)(x + 3)$ A1 cao OR M1 for $\frac{-5 \pm \sqrt{5^2 - 4 \times 2 \times -3}}{2 \times 2}$ allow sub. of $c = \pm 3$ M1 for $\frac{-5 \pm \sqrt{49}}{4}$ A1 cao NB: any other method put in review.

PMT

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
21		$1180.5 \div \frac{4}{3}\pi(6.15)^3$	1.21	4	M1 for 1180 ± 0.5 or 6.2 ± 0.05 M1 for 'max. mass' ÷ 'min. volume' where "min volume" is defined as any expression involving 6.15 M1 for $1180.5 \div \frac{4}{3}\pi(6.15)^3$ A1 for 1.21 – 1.22
22			proof	3	B1 for *AD* = *AB* and *AE* = *AG* B1 for angle *EAB* = angle *DAG* (= 90 + angle *DAE*) B1 (dep on previous B marks) for 2 sides and included angle (SAS) oe
23	(a)		$3\boldsymbol{a} + \boldsymbol{b}$	1	B1 oe
	(b)		$3\mathbf{c}$	4	M1 for writing *QB* as a combination of vectors eg $\frac{1}{2}$ ('3**a** + **b**') + **b** or 3**a** + 2**b** – $\frac{1}{2}$ ('3**a** + **b**') or 2**a** + 2**b** − **c** oe M1 for equating **a** + **b** = 2**c** or writing *PQ* in terms of vectors **a** and **b** eg −**a** + $\frac{1}{2}$ ('3**a** + **b**') or 2**a** + **b** – $\frac{1}{2}$ ('3**a** + **b**') A1 for (*PQ*=) $\frac{1}{2}$**a** + $\frac{1}{2}$**b or** (*QB*=) $\frac{3}{2}$**a** + $\frac{3}{2}$**b** or (*QB*=) 2**c**−**a** + **a** + **c** A1 cao NB: accept equivalent expressions throughout

PMT

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone 01623 467467
Fax 01623 450481
Email publication.orders@edexcel.com
Order Code UG035055 March 2013

For more information on Edexcel qualifications, please visit our website
www.edexcel.com

Pearson Education Limited. Registered company number 872828
with its registered office at Edinburgh Gate, Harlow, Essex CM20 2JE

Ofqual
Llywodraeth Cynulliad Cymru
Welsh Assembly Government
Rewarding Learning

PMT

Mark Scheme (Results)

Summer 2016

Pearson Edexcel GCSE
In Mathematics B (2MB01)
Higher (Calculator) Unit 3

PMT

Edexcel and BTEC Qualifications

Edexcel and BTEC qualifications are awarded by Pearson, the UK's largest awarding body. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers. For further information visit our qualifications websites at www.edexcel.com or www.btec.co.uk. Alternatively, you can get in touch with us using the details on our contact us page at www.edexcel.com/contactus.

Pearson: helping people progress, everywhere

Pearson aspires to be the world's leading learning company. Our aim is to help everyone progress in their lives through education. We believe in every kind of learning, for all kinds of people, wherever they are in the world. We've been involved in education for over 150 years, and by working across 70 countries, in 100 languages, we have built an international reputation for our commitment to high standards and raising achievement through innovation in education. Find out more about how we can help you and your students at: www.pearson.com/uk

Summer 2016
Publications Code 5MB3H_01_1606_MS
All the material in this publication is copyright
© Pearson Education Ltd 2016

NOTES ON MARKING PRINCIPLES

1 All candidates must receive the same treatment. Examiners must mark the first candidate in exactly the same way as they mark the last.

2 Mark schemes should be applied positively.

3 All the marks on the mark scheme are designed to be awarded. Examiners should always award full marks if deserved, i.e if the answer matches the mark scheme. Note that in some cases a correct answer alone will not score marks unless supported by working; these situations are made clear in the mark scheme. Examiners should be prepared to award zero marks if the candidate's response is not worthy of credit according to the mark scheme.

4 Where some judgement is required, mark schemes will provide the principles by which marks will be awarded and exemplification may be limited.

5 Crossed out work should be marked UNLESS the candidate has replaced it with an alternative response.

6 Mark schemes will award marks for the quality of written communication (QWC).
The strands are as follows:

i) *ensure that text is legible and that spelling, punctuation and grammar are accurate so that meaning is clear*
Comprehension and meaning is clear by using correct notation and labelling conventions.

ii) *select and use a form and style of writing appropriate to purpose and to complex subject matter*
Reasoning, explanation or argument is correct and appropriately structured to convey mathematical reasoning.

iii) *organise information clearly and coherently, using specialist vocabulary when appropriate*.
The mathematical methods and processes used are coherently and clearly organised and the appropriate mathematical vocabulary used.

7 **With working**

If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
If there is no answer on the answer line then check the working for an obvious answer.
Partial answers shown (usually indicated in the ms by brackets) can be awarded the method mark associated with it (implied).
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks; transcription errors may also gain some credit. Send any such responses to review for the Team Leader to consider.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.

8 **Follow through marks**

Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

9 **Ignoring subsequent work**

It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: e.g. incorrect cancelling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect e.g. algebra.

10 **Probability**

Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

11 Linear equations
Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded (embedded answers).

12 Parts of questions
Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

13 Range of answers
Unless otherwise stated, when an answer is given as a range (e.g 3.5 – 4.2) then this is inclusive of the end points (e.g 3.5, 4.2) and includes all numbers within the range (e.g 4, 4.1)

Guidance on the use of codes within this mark scheme
M1 – method mark A1 – accuracy mark B1 – Working mark C1 – communication mark QWC – quality of written communication oe – or equivalent cao – correct answer only ft – follow through sc – special case dep – dependent (on a previous mark or conclusion) indep – independent isw – ignore subsequent working

PMT

PAPER: 5MB3H/01					
Question		**Working**	**Answer**	**Mark**	**Notes**
1*			Decision (supported)	3	M1 for correct first step e.g. 15 ÷ 3 M1 for complete method C1 for correct decision with accurate figures
2	(a)		Correct diagram	2	B2 cao (B1 for correct orientation)
	(b)		Enlargement, sf 4, centre (0, 1)	3	B1 for enlargement B1 for scale factor 4 B1 for centre (0, 1)
3			$w = \frac{d+5}{2}$	2	M1 for attempt to add 5 to both sides or divide both sides by 2 as a first step, eg $d + 5 = 2w$ oe or $\frac{d}{2} = w - \frac{5}{2}$ oe A1 for $w = \frac{d+5}{2}$ oe

PMT

PAPER: 5MB3H/01					
Question		Working	Answer	Mark	Notes
4			22.5	4	M1 for $4(x - 8) = 2x + 13$ M1 for expansion of bracket or division of all terms by 4, eg $4x - 32 = 2x + 13$, or $x - 8 = \frac{2x}{4} + \frac{13}{4}$ M1 for isolating x and number terms eg $2x = 45$, $\frac{x}{2} = \frac{45}{4}$ A1 for $\frac{45}{2}$ or 22.5 OR M1 for $(180 - 64) \div 2$ (= 58) M1 for $4(x - 8)$ = "58" or $2x + 13$ = "58" or "58" – 13 (= 45) M1 for isolating x and number terms eg $4x = 90$, $2x = 45$ or "45" ÷ 2 A1 for $\frac{45}{2}$ or 22.5 OR M1 for $64 + 4(x - 8) + 2x + 13$ M1 for $64 + 4(x - 8) + 2x + 13 = 180$ M1 for isolating x and number terms eg $6x = 135$ A1 for $\frac{45}{2}$ or 22.5
5			Correct region shaded	3	M1 for a circle centre M or N (accept arc of sufficient length to define the region) M1 for circle centre M radius 5 cm **and** circle centre N radius 3 cm (accept arc of sufficient length to define the region) A1 for correct region shaded

PMT

PAPER: 5MB3H/01					
Question		Working	Answer	Mark	Notes
*6			Conclusion (supported)	4	M1 for $\pi \times 120^2$ (= 45 216 – 45 249) M1 for "$\pi \times 120^2$" ÷ 1800 A1 for 25 – 25.2 C1 ft (dep on M2) for appropriate conclusion from their figures OR M1 for $\pi \times 120^2$ (= 45 216 – 45 249) M1 for 20 × 1800 A1 for 36 000 and 45 216 – 45 249 C1 ft (dep on M2) for appropriate conclusion from their figures OR M1 for $\pi \times 120^2$ (= 45 216 – 45 249) M1 for "$\pi \times 120^2$" ÷ 20 A1 for 2260 – 2263 C1 ft (dep on M2) for appropriate conclusion from their figures OR M1 for 1800 × 20 M1 for 36 000 ÷ π (=11 457 – 11 465) A1 for 107(.0…) C1 ft (dep on M2) for appropriate conclusion from their figures
7			161.50	5	M2 for a correct method to decrease 6720 by 20%, eg 6720 × 0.8 (= 5376) or 6720 × 0.2 (= 1344 and 6720 – 1344 (= 5376)) (M1 for a correct method to find 20% of 6720 eg 6720 × 0.2 or $\frac{20}{100} \times 6720$ (= 1344)) M1 for subtracting 1500 (= 3876) after a percentage calculation M1 "3876" ÷ 24 after the subtraction of 1500 A1 for 161.5(0)

PMT

PAPER: 5MB3H/01					
Question		**Working**	**Answer**	**Mark**	**Notes**
8		3 42 3.1 45.(291) 3.2 48.(768) 3.3 52.(437) 3.4 56.(304) 3.5 60.(375) 3.6 64.(656) 3.7 69.(153) 3.8 73.(872) 3.9 78.(819) 4 84 3.71 69.6(14811) 3.72 70.(078848) 3.73 70.5(45117) 3.74 71.(013624) 3.75 71.4(84375)	3.7	4	B2 for a trial between 3 and 4 exclusive (B1 for a trial at 3 or 4) B1 for a different trial of $3.7 < x \leq 3.75$ B1 (dep on at least one previous B1) for 3.7 NB. Trials should be evaluated to at least 2 sf truncated or rounded for values of x correct to 1 decimal place. Trials should be evaluated to at least 1 dp truncated or rounded for values of x correct to 2dp. **NB** No working scores 0 marks even if answer is correct
9			618	4	M1 for a method to find an area which is part of the cross section M1 (dep) for a complete method to find the total area of the cross section M1 (dep M1) for their cross sectional area × 12 A1 cao **OR** M1 for a method to find the volume of cuboid, 8 × 8 × 12 (= 768) M1 for a method to find the volume of the triangular prism, ½ ×5 × 5 × 12(= 150) M1 (dep M2) for a complete method for the volume of the prism A1 cao

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
10	(a)		15.2	3	M1 for $12.7^2 + 8.3^2$ or 161.29 + 68.89 or 230.18 M1 for √"$(12.7^2 + 8.3^2)$" or √"161.29 + 68.89" or $\sqrt{230.18}$ A1 for 15.2 or 15.17(168…)
	(b)		16.1	3	M1 for $\sin 40° = \frac{DE}{25}$ oe or $\frac{DE}{\sin 40} = \frac{25}{\sin 90}$ oe M1 for 25 sin 40° A1 for 16.1 or 16.06(969…)
11	(a)		4.081	2	M1 for 8.875 or $\frac{71}{8}$ or 2.979…or 4.08 A1 for 4.081 or 4.0809(5…)…
	(b)		4×10^{-3}	2	M1 for 4×10^n, $n \neq -3$ or $a \times 10^{-3}$, $a \neq 4$ or 0.004 or 0.4×10^{-2} or 1/250 A1 cao
12			$x < 2$	2	M1 for an attempt to isolate x and number terms or multiply all terms by 2, or for $\frac{3}{2}x < 3$ or $-\frac{3}{2}x < -3$ or $x = 2$ A1 cao
13	(a)		0, 6, 4, –6	2	B2 for all values correct (B1 for any one value correct)
	(b)		Graph drawn	2	M1 ft (provided B1 in (a) for at least 6 points plotted correctly from their table A1 cao for correct curve drawn from (–4, –6) to (3, –6)
	(c)		1.5 to 1.6 and –2.5 to –2.6	2	M1 for correct use $y = 2$ (may be implied by one correct estimate) or correct use of formula. A1 for 1.5 to 1.6 and –2.5 to –2.6

5MB3H_01					
Question		**Working**	**Answer**	**Mark**	**Notes**
14*		Sher Yas **Old 19300 12560** New 20265 13502 **Inc 965 942**	Correct comparison (supported)	3	M1 for a correct method to calculate the population at the beginning of the 10 year period for at least one place. eg $\frac{20265}{1.05}$ (= 19 300) oe or $\frac{13502}{1.075}$ (= 12 560) oe A1 for 965 (Sherbury) **and** 942(Yaston) C1 (dep on M1) ft for statement comparing increases leading to conclusion based on two comparable amounts eg increase in Sherbury is greater than increase in Yaston
15		$20x + 10y = 35$ $6x - 10y = -48$ $x = -\frac{1}{2}$ $y = \frac{9}{2}$ OR $12x + 6y = 21$ $12x - 20y = -96$ $26y = 117$ $y = \frac{9}{2}$ $x = -\frac{1}{2}$	$-\frac{1}{2}, \frac{9}{2}$	4	M1 for a correct process to eliminate either variable (condone one arithmetic error) A1 cao for either x or y M1 (dep on M1) for correct substitution of found value into one of the equations or appropriate method after starting again (condone one arithmetic error) A1 cao OR M1 for full method to rearrange and substitute to eliminate either variable (condone one arithmetic error) A1 cao for either x or y M1 (dep on M1) for correct substitution of found value into one of the equations or appropriate method after starting again (condone one arithmetic error) A1 cao **NB** Trial and improvement methods score 0 marks unless both x and y are correct
16			226	2	M1 for angle $ABC = 180 - 67$ (= 113) A1 cao OR M1 for obtuse angle $AOC = 2 \times 67$ (= 134) A1 cao

5MB3H_01					
Question		Working	**Answer**	**Mark**	**Notes**
17			– 2.82, 19.82	3	M1 for $\frac{--17 \pm \sqrt{(-17)^2 - 4\times1\times-56}}{2\times1}$ (condone one sign error) or $\left(x - \frac{17}{2}\right)^2$ oe M1 for $\frac{17 \pm \sqrt{513}}{2}$ or for method leading to $\frac{17}{2} \pm \sqrt{\frac{513}{4}}$ oe A1 for answers in the range 19.82 to 19.825; – 2.82 to –2.825
18			21.2	4	M1 for correct use of sine rule to find *AB* or *BC*, eg $\frac{6}{\sin 25} = \frac{AB}{\sin 120}$ or $\frac{6}{\sin 25} = \frac{BC}{\sin(180-120-25)}$ M1 for (*AB* =) $\frac{6}{\sin 25} \times \sin 120$ (= 12.2(951…)) or (*BC* =) $\frac{6}{\sin 25} \times \sin 35$ (= 8.1(431…) M1(dep M2) for method to find area, eg 0.5 × 6 × "*AB*" sin35 or 0.5 × 6 × "*BC*" sin 120 A1 for answer in the range 21.1 – 21.2 OR (with perpendicular from *A* meeting *BC* extended at a point *X*) M1 for method to find *AX* M1 for method to find *BX* M1(dep M2) for 0.5 × "*AX*" × "*BC*" A1 for answer in the range 21.1 – 21.2
*19			0.38 because the LB and UB agree to that number of figures	5	B1 for 10.75 or 10.85 or 10.84999… B1 for 75.055 or 75.065 or 75.064999… M1 for $\sqrt{\frac{10.85}{75.055}}$ as UB **OR** $\sqrt{\frac{10.75}{75.065}}$ as LB A1 (dep on all previous marks) for both 0.3802… and 0.3784 must clearly come from working with correct values C1 for 0.38 from 0.3784… and 0.3802 … **and** "both LB and UB round to 0.38" **NB** An answer of 038(932….) without working scores no marks

5MB3H_01					
Question		Working	**Answer**	**Mark**	**Notes**
20			7.35	3	M1 for $y \propto \frac{1}{\sqrt{x}}$ or $y = \frac{k}{\sqrt{x}}$ or $9 = \frac{k}{\sqrt{4}}$ M1 for $k = 9\sqrt{4}$ (=18) A1 for 7.35 or 7.348…
*21			$\frac{2}{3}$ (7**a** + 3**b**) and correct conclusion	4	M1 for correct vector for $\overrightarrow{OY}$, or $\overrightarrow{AP}$ eg $(\overrightarrow{OY}) = \overrightarrow{OA} + \overrightarrow{AY}$, or $\overrightarrow{OY} = \overrightarrow{OA} + \frac{2}{3}\overrightarrow{AP}$ may include terms in **a** and **b,** eg. 6**a** + $\overrightarrow{AY}$, 4**b** + 4**a** – **b** + $\overrightarrow{PY}$ or $\overrightarrow{AP} = \overrightarrow{AO} + \overrightarrow{OB} + \overrightarrow{BP}$ or –6**a** + 4**b** + 4**a** – **b** or – 2**a** + 3**b** M1 for $(\overrightarrow{AY}) = \frac{2}{3}\overrightarrow{AP}$ or ⅔(–6**a** + 4**b** + 4**a** – **b**) or ⅔(–2**a** + 3**b**) or $(\overrightarrow{PY} = \frac{1}{3}\overrightarrow{PA}$ or ⅓(– 4**a** + **b** – 4**b** + 6**a**) or ⅓(2**a** – 3**b**) M1 for correct expression for $\overrightarrow{OY}$ in terms of **a** and **b,** eg $\frac{14}{3}$ **a** + 2**b** C1 for $\frac{2}{3}$ (7**a** + 3**b**) and "$\overrightarrow{OY}$ is parallel to the vector 7**a** +3**b**" **oe**

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5°
Measurements of length: ±5 mm

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q2	(a)	Grid enlarged. Shading changed to dotty shading. Labels added to shapes. Image labelled shape A. Rotation given and labelled shape B. Question changed to 'Describe fully the single transformation which maps shape A to shape B. One row top and bottom, one column left and right has been removed. Three answer lines given.	2 cao (B1 for correct orientation in third quadrant or correct quarter turn)
Q2	(b)	Grid enlarged. Shading changed to dotty shading. Labels added next to the triangles 'triangle P' and 'triangle Q'. One column removed from the left.	B1 for enlargement B1 for scale factor 4 B1 for centre (0, 1)

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q4		Diagram enlarged. MLP only – x changed to y. Braille only – measurements given in the text.	M1 for $4(x - 8) = 2x + 13$ M1 for expansion of bracket or division of all terms by 4, eg $4x - 32 = 2x + 13$, $x - 8 = 2x/4 + 13/4$ M1 for isolating x and number terms eg $2x = 45$, $x/2 = 45/4$ A1 for 45/2 or 22.5 OR M1 for $(180 - 64) \div 2$ (= 58) M1 for $4(x - 8) = 58$ or $2x + 13 = 58$ M1 for isolating x and number terms eg $4x = 90$, $2x = 45$ A1 for 45/2 or 22.5 OR M1 for $64 + 4(x - 8) + 2x + 13$ M1 for $64 + 4(x - 8) + 2x + 13 = 180$ M1 for isolating x and number terms eg $6x = 135$ A1 for 45/2 or 22.5
Q5		Diagram kept the same size as original. Scale moved above the diagram and also put in the question paper.	B1 for circle centre M radius 5 cm B1 for circle centre N radius 3 cm B1 for correct region shaded

PMT

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q6		Diagram enlarged. Cross changed to a filled in circle. Arrow heads removed.	M1 for $\pi \times 120^2$ (= 45238….) M1 for "$\pi \times 120^2$" ÷ 1800 A1 for 25.0 – 25.2 C1 for "surface is large enough as 25 > 20" oe OR M1 for $\pi \times 120^2$ (= 45238….) M1 for 20 × 1800 A1 for 36000 C1 for "surface is large enough as 36000 < 45238..." oe OR M1 for $\pi \times r^2 = 1800 \times 20$ M1 for 36000 ÷ π (=11459..) A1 for 107.0… C1 for "surface is large enough as 107…< 120" oe
Q9		Model provided for all candidates. Diagram enlarged and provided for MLP.	M1 for a method to find an area which is part of the cross section M1 (dep) for a complete method to find the total area of the cross section M1 (dep M2) for a complete method for the volume of the prism A1 cao OR M1 for a method to find the volume of cuboid, 8 × 8 × 12 M1 for a method to find the volume of the triangular prism M1 (depM2) for a complete method for the volume of the prism A1 cao

PMT

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q10	(a)	Diagram enlarged. Braille only: measurements given in the text.	M1 for $12.7^2 + 8.3^2$ or $161.29 + 68.89$ or 230.18 M1 for $\sqrt{161.29 + 68.89}$ or $\sqrt{230.18}$ A1 for 15.2 or 15.17(168…)
Q10	(b)	Diagram enlarged. Braille only – measurements given in the text.	M1 for $\sin 40° = \frac{DE}{25}$ oe M1 for $25 \sin 40°$ A1 for 16.1 or 16.06(969…)
Q13	(a)	Wording added 'There are four spaces to fill.'	B2 for all values correct (B1 for any one value correct)
Q13	(b)	Grid enlarged.	M1 ft for at least 6 points plotted correctly from their table A1 cao for correct curve drawn from (–4, –6) to (3, –6)
Q16		Diagram enlarged. Dot added at centre.	M1 for angle ABC = 180 – 67 (= 113) A1 cao OR M1 for obtuse angle AOC = 2 × 67 (= 134) A1 cao

PMT

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q18		Diagram enlarged.	M1 for correct use of sine rule to find *AB* or *BC*, eg $\frac{6}{\sin 25} = \frac{AB}{\sin 120}$ M1 for (*AB* =) $\frac{6}{\sin 25} \times \sin 120$ or (*BC* =) $\frac{6}{\sin 25} \times \sin 35$ M1(dep M2) for method to find area, eg 0.5×6×*AB*sin35 or 0.5×6×*BC* sin 120 A1 for answer in the range 21.1 – 21.2 OR (with perpendicular from *A* meeting *BC* extended at a point *X*) M1 for method to find *AX* M1 for method to find *BX* M1(dep M2) for 0.5 × "*AX*" × "*BC*" A1 for answer in the range 21.1 – 21.2
Q21		Diagram enlarged.	M1 for correct vector for $\overrightarrow{OY}$, eg $(\overrightarrow{OY}) = \overrightarrow{OA} + \overrightarrow{AY}$, may include terms in **a** and **b,** eg. 6**a** + $\overrightarrow{AY}$, 4**b** + 4**a** – **b** + $\overrightarrow{PY}$ M1 for ($\overrightarrow{AY}$ =) $\frac{2}{3}\vec{A}P$ or ($\overrightarrow{PY}$ =) $\frac{1}{3}\overrightarrow{PA}$ M1 for correct expression for $\overrightarrow{OY}$ in terms of **a** and **b,** eg $\frac{14}{3}$**a** + 2**b** C1 for $\frac{2}{3}$(7**a** + 3**b)** and "$\overrightarrow{OY}$ is parallel to the vector 7**a** +3**b" oe**

PMT

Pearson Education Limited. Registered company number 872828
with its registered office at 80 Strand, London WC2R 0RL

Question 1

This question provided a good start to the paper. Most students scored at least four of the five marks available and nearly all students gained some credit for their answers.

Part (a) of this question required students to use the index law for multiplication of powers of *n*. Nearly all students applied the law correctly. n^{15} was the most commonly seen incorrect answer.

Part (b) of the question was answered less well but nevertheless the great majority of students gained the two marks available. Examiners condoned answers of the form c^1d^3 and $c \times d^3$. It was not unusual for students who did not give a fully correct answer to get one mark for either c or d^3.

In part (c) students could usually find the critical value giving it as either 2.8 or $\frac{14}{5}$.

These students scored at least one mark. A significant number of students gave their final answer as 2.8 or as $x = 2.8$ instead of the correct $x > 2.8$

Question 13

This question was not generally well answered. However, there were a significant number of the more able students who were able to gain full marks.

In part (a) most students attempted to draw lines on the grid but only a minority of the scripts seen contained diagrams with at least two of the lines $x = 2$, $y = x + 3$, $2x + 3y = 6$ drawn correctly. This was the minimum requirement to gain any credit in this part of the question. The line $x = 2$ was often seen drawn incorrectly as $y = 2$. About one in ten of students obtained full marks in part (a).

Part (b) of the question attracted an encouraging number of responses which examiners could give credit for. To score the mark in part (b), students were expected to state that Geoffrey was not correct and give a reason for their response. Examiners accepted a range of possible reasons equivalent to stating that the point with coordinates (2, 4) was in fact in the region or that it satisfied the inequalities given. There were many excellent responses from students who clearly showed they had a very good understanding of the situation by referring to the equals signs in the inequalities or to the solid lines in the diagram.

Question 17

Many students gained no marks because they were not able to draw two of the three lines correctly. When only two of the three lines were drawn correctly it was most commonly the lines $x = 3$ and $y = 6 – 3x$. The graph of $2y + 4 = x$ caused the most problems. A common error was to draw this line with the correct gradient but the wrong y-axis intercept. Some students confused the line $x = 3$ with the line $y = 3$. Even after gaining the first two marks for drawing all three lines correctly many students failed to give a fully correct solution because they identified the wrong region – often this was the region enclosed by the three lines. Students should check whether points in the region they choose satisfy all three inequalities.

Question 1

Part (a) was answered very well. Almost every candidate was able to extract the correct critical value, and most provided the correct inequality symbol too. It was not uncommon to see $-1 < x$ as an acceptable alternative answer. Those who did drop marks were fairly equally spread between choosing < over > or for including an inclusive inequality.
Part (b) was again very well answered. Almost all students scored at least one mark, either for a line of correct length, or for a closed circle at −3, with a large proportion gaining the second mark also. Those who failed to score typically had their circles the wrong way round, **or** the line stopping at 3 rather than 4.

Question 22

This demanding question required students to solve two quadratic inequalities and then select the correct critical values to satisfy both. The mark scheme has 2 sets of 2 marks, a method and an accuracy, for the solving of each quadratic inequality. Students could gain the accuracy mark for both by drawing a suitable diagram, either inequalities on a number line, or a sketch of the quadratic with the correct regions drawn. However, to score the final mark students needed to state both linear inequalities that satisfy both quadratics inequalities.

A large number of students were able to gain one mark for a method to solve the first quadratic, normally by factorising, but typically didn't correctly state the solutions. The second quadratic proved much more challenging. Many were unable to factorise, and thus chose to use the formula. The problem with this was their substitution was often inaccurate, either with incorrect values or with missing brackets.

Summary

Based on their performance on this paper, students:

- should improve their use of calculators in general, but in particular when completing complex calculations involving powers, or fractions.
- learn correct geometrical terms and use these when giving reasons in geometry questions.
- work on more efficient methods when working with percentages when a calculator is available, and refrain from attempting to use 'non-calculator' methods.
- ensure they do not round prematurely in multistep calculations, as it often leads to answers outside of the acceptable range for the accuracy mark.
- check answers make sense in the context of the question.

Question 16

In this inequalities question candidates had to first find the equations of the 4 lines. There was 1 mark for either of the horizontal or vertical lines, and then 1 mark each for the two diagonal lines. For these marks we could accept use of an equals sign, or any inequality symbol. The final mark was for then applying the correct inequalities to all four correct equations.

Most candidates gained some credit, even if this was just a single mark for $y = 6$ or $x = -3$. Candidates did however sometimes mix these two up, giving answers of $x = 6$ or $y = -3$. The line that caused the most problems was $y = -x2 + 1$ with most being unable to deduce this equation correctly, especially the negative gradient. It was very rare to see a fully correct response, with most candidates using the same symbol for all equations. Candidates who had no access to this question simply gave the points of intersection.

Question 11

There were many fully correct answers to this question. However, a significant minority of candidates could not take into account all the information given and were awarded just one of the two marks available for listing a correct set of integers for x (or y). A small number of candidates tried to use inequality signs, therefore ignoring or not understanding the statement that "x and y are integers".

Question 24

It was pleasing to see so many students attempting the final question on the paper. Higher attaining students usually made a good start by showing a correct method to find the critical values for at least one of the inequalities and often for both. Many factorised $4x^2 - 25$ and gained the first mark for $(2x + 5)(2x - 5)$. Those who rearranged it to $x^2 < 25/4$ often failed to complete the method by finding both the positive and negative square root. Inevitably, some errors (mostly sign errors) were made in the factorisation of $12 - 5x - 3x^2$ and those who

rearranged the inequality to $3x^2 + 5x - 12 < 0$ tended to make fewer mistakes. After finding the critical values many students were not able to use them correctly to solve the inequalities. It was very common to see $x < -2.5$ and $x < 2.5$ for $4x^2 - 25 < 0$ and $x > -3$ and $x > \frac{4}{3}$ for $12 - 5x - 3x^2 > 0$ with students using < or > to match the original inequality. Students were more successful in writing the solution to the first inequality, $-2.5 < x < 2.5$, than the solution to the second inequality. The latter was often given as $x < -3$ and $x > \frac{4}{3}$ rather than as $-3 < x < \frac{4}{3}$. Drawing a sketch of the curve helped some students but there were others who drew a correct sketch and were still unable to identify the relevant region. Furthermore, students who drew sketches often drew $y = 12 - 5x - 3x^2$ as if it were a positive quadratic which led them to deduce an incorrect critical region. Students who solved both inequalities correctly were often able to identify the set of possible values as $-2.5 < x < \frac{4}{3}$ and gain full marks. Some students gave the final answer as –2, –1, 0, 1 or used ≤ instead of < and lost the accuracy mark.

Summary

Based on their performance on this paper, students should:

- practise their arithmetic skills, particularly division and operations with decimals
- take care when carrying out arithmetic operations and use logical checking processes to make sure that their answer is sensible
- become more familiar with the set notation for the complement of a set and how to identify it on a Venn diagram
- know the difference between stating the type of correlation and describing a relationship and should not confuse positive correlation with direct proportion
- practise finding angles using the circle theorems and stating the circle theorems used
- practise algebraic manipulation including rearranging formulae, using index laws and solving equations

Question 4

In part (a) many candidates gained the mark for a correct answer, although some are still unclear on the meaning of the inequality symbols; something that is surprising at Higher level. Part (b) was generally answered well, but we saw the typical error of the shading being the incorrect way round on the circles. In this case candidates gained one of the two marks. A number of candidates drew their line on the number line which made marking trickier. Where partial marks were awarded, in most cases, it was for a correct line drawn with incorrect end points.
In part (c), most were able to gain some credit with many getting at least 2 for finding the critical value. However, the fraction in the inequality caused problems for a significant proportion of learners. Those who attempted to work with the fraction first, typically scored no marks as they failed to multiply or divide all 3 terms or failed to deal with the inverse of multiplying by $\frac{2}{5}$.
Those who started with the -4 first often fared better. It was pleasing however to see fewer candidates losing marks for using '=' rather than '<'.

Question 4

Part (a) of this question was very well answered with the great majority of students giving clear and concise descriptions of the two mistakes on the diagram. On occasion the vagueness of a statement cost students a mark, for example when they said that one of the circles should be shaded but did not specify which circle. Part (b) was also quite well answered and most students worked accurately to find the critical value. This was more than enough to score the first mark. A surprising number of students left their answer as 4.6 so had not addressed the requirement stated in the question to give an integer. Other students solved the inequality and wrote $y < 4.6$ on the answer line. Students are reminded to read questions carefully and take on board any specific requirements. The overwhelming majority of students who did give an integer answer gave the correct integer, 4.

Question 13

Students gained the first mark for at least two correct boundaries, normally, but not always, for $y = -3$ and $x = 2$. The second mark was harder to gain, but again many did. This could be gained for drawing the remaining two boundaries or one more correct boundary **and** shading correct for at least two correct boundaries. The second of these was probably seen more often. A fully correct region identified was needed to gain the C1, and although not scored by a majority, it was scored by a significant minority.

Question 15

Identifying a region that satisfies a set of inequalities is another question that provides a good differentiator. Most were able to gain 1 mark, for drawing $y=1$ and $x=2$, although there were still a few learners who got these the wrong way round. To gain any further credit at least one of the diagonal lines needed to be drawn. The one of these drawn correctly most often was $x+y=5$. A common mistake was to draw $x+y=4$ instead of $x+y=5$.To gain full marks the correct region needed to be correctly identified. What made this question different to ones set previously was that one of the lines, $y=3x-2$, was not actually a boundary to the region. This meant that full marks could be awarded in part (a) and in part (b) if this line was missing from the diagram.
In part (b) learners needed to identify which of the lines was not a boundary and could be awarded without full marks in part (a). To gain it from an incorrect diagram they needed to state a line that was not a boundary for their region, which many were able to do successfully.