Chhetri Academy

chhetriacademy.com

GCSE MATHS

Algebra

Edexcel 1MA1 | Subtopic collection Topic 25

Transforming graphs

Higher tier

Answers and examiner comments

26	2003-2024	Higher
question groups	available papers	tier

Using this booklet

1. Answer numbers match the companion question booklet.
2. Follow the original question number on marking tables.
3. Examiner comments are included where available.

Name _____ **Date** _____

Some entries use full source marking material in an appendix. Any unavailable mark schemes are identified beside the relevant answer.

Original question 24

The full source mark scheme begins on page 81. Use the original paper code, tier and question number shown above.

Original question 20

No matching mark scheme was available in the supplied archive for this question.

Original question 20

The full source mark scheme begins on page 135. Use the original paper code, tier and question number shown above.

Original question 20

The full source mark scheme begins on page 186. Use the original paper code, tier and question number shown above.

Original question 27

The full source mark scheme begins on page 247. Use the original paper code, tier and question number shown above.

Question		Working	Answer	Mark	Notes
26	(a)		opp sides are equal	1	B1 for a correct explanation
	(b)	$4x - 2x = 12 - 1$	5.5	2	M1 for $4x + 1 - 1 - 2x = 2x + 12 - 1 - 2x$ oe A1 for 5.5 or 11/2 or 5½
	(c)	'5.5' $\times 2$ + $4 \times$'5.5'+1 + $2 \times$'5.5'+12	57	2	M1 for correct substitution of x = '5.5' into the four expressions to find the sum of FOUR sides or 8x + 13 seen A1 ft
27	(a)			2	M1 rectangle with either correct width or height or any square A1 cao
	(b)			2	B2 for a correct sketch (B1 any 3-D sketch of no more than 4 faces seen, with a trapezoidal face)
28	(a)			2	B1 'What type of magazine do you read?' B1 for at least 2 magazines identified in response boxes [Note: B0 for any data collection sheet/chart
	(b)		How many magazines have you read in the last week 0 ☐ 1 ☐ 2-3 ☐ >3 ☐	2	B1 Relevant question that refers to a time period. B1 for at least 3 mutually exclusive response boxes (need not be exhaustive)

1380/1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
29	(a)		15.456	1	B1 cao
	(b)		0.15456	1	B1 cao
	(c)		3220	1	B1 cao
30	(a)	$x^2 = 72 \div 2$	6	2	M1 for 72 ÷ 2 or 36 seen A1 6 or -6 or ± 6
	(b)	$72 = 2 \times 36 = 2 \times 2 \times 18$ $= 2 \times 2 \times 2 \times 9$  	$2 \times 2 \times 2 \times 3 \times 3$	2	M1 for a systematic method of at least 2 correct divisions by a prime number oe factor tree or a full process with one calculation error; can be implied by digits 2, 2, 2, 3, 3 on answer line A1 for $2 \times 2 \times 2 \times 3 \times 3$ or $2^3 \times 3^2$ oe [Note 1 × 2 × 2 × 2 × 3 × 3 gets M1 A0]

1380/2F					
Question		Working	Answer	Mark	Notes
1	(a)		3.50	1	B1 for 3.50 cao
	(b)		3.05	1	B1 3.05 cao
	(c)		3510	1	B1 for 3510 or 3510.00
2	(a)		right angle marked	1	B1 for the right angle marked with square or R
	(b)		acute angle marked	1	B1 for either (or both) of the acute angles marked
	(c)		kite drawn	1	B1 for a kite drawn (accept square or rhombus or arrowhead)
3	(a)		circle drawn	1	B1 for a circle drawn within guidelines (see overlay)
	(b)		diameter drawn	1	B1 for line through *C* and touching circle at both ends
4	(a)	5.85 + 4.90	10.75	1	B1 for 10.75 cao
	(b)	60.55 ÷ 8.65	7	2	M1 for 60.55 ÷ 8.65 or 8.65 × 7 = 60.55 or for at least 4 repeated additions or subtractions of 8.65 A1 for 7 cao
	(c)	8.65 + (4.90 + 4.90) 20 – 18.45	1.55	3	M1 for 8.65 + (4.90 + 4.90) M1 (dep) for 20 – '18.45' A1 for 1.55 cao SC: award B1 for sight of 18.45 or 6.45 or 10.20 award B2 for 155

1380/2F					
Question		Working	Answer	Mark	Notes
5	(a)		6	1	B1 for 6 cao
	(b)	I I I I	diagram	1	B1 for correct diagram (4 vertical sticks and 8 horizontal sticks)
	(c)		12, 15	2	B2 for 12 and 15 (B1 for either 12 or 15 or '12'+3
	(d)		reason	1	B1 eg for '100 multiplied by 3' or '100 × 3' or '× 3' or 3*n* (but not 3n + a number) or 'keep adding 3' oe, as long as "3" is mentioned.
6	(a)		Bars at 8 and 5	2	B1 for bar of height 8 (above orange) B1 for bar of height 5 (above green)
	(b)		6	1	B1 for 6 cao
	(c)		yellow	1	B1 ft for yellow or ft from their diagram
	(d)	6 + 10 + 8 + 5	29	1	B1 correct answer or ft by adding the heights of the columns on the graph
7	(i)		cone	1	B1 for cone or alternative spellings only that sound like "cone".
	(ii)		cylinder	1	B1 for cylinder or alternative spellings only that sound like "cylinder". Accept circular based prism.

1380/2F					
Question		Working	Answer	Mark	Notes
8	(a)	$\frac{9}{12}$	$\frac{3}{4}$	2	B2 for $\frac{3}{4}$ cao (B1 for $\frac{9}{12}$ seen)
	(b)		shading	1	B1 for 6 squares (only) shaded
	(c)		0.3	1	B1 for 0.3 oe
	(d)		$\frac{39}{100}$	1	B1 for $\frac{39}{100}$ oe as a fraction
9	(a)		6.4	1	B1 for 6.2 – 6.6 inclusive; accept 62-66 with mm stated.
	(b)		Midpoint marked	1	B1 for midpoint marked at 3 – 3.4 inclusive
10	(a)		7, 4, 2, 1, 2	2	M1 for at least one correct frequency or tally A1 for 7, 4, 2, 1, 2 cao (B2 for correct frequencies without the use of tallies)
	(b)		2	1	B1 for 2 or ft values in table NB: B0 if the 7 is given with the 2
	(c)	6 – 2 =	4	2	M1 for identifying 6 and 2, eg 6-2, as long as 6 and 2 are not identified with any incorrect operation A1 cao

1380/2F					
Question		Working	Answer	Mark	Notes
11	(a)	$6 \times 3 + 4$	22	2	M1 for 6×3 or for '6×3' + 4 or 18 seen A1 for 22, accept 22.00 or 22.0
	(b)	$52 - 4 = 48$ $48 \div 6 =$	8	3	M1 for $52 - 4$ or 48 seen M1 (dep) for '$52 - 4$' $\div 6$ or $48 \div 6$ A1 for 8 cao **Alternative method:** M2 for a systematic attempt using $6 \times d + 4$ at least twice with at least one d greater than 5 with correct answers A1 for 8 cao
12	(a)		33	1	B1 for 33 cao
	(b)		180	1	B1 for 180 cao
	(c)		110 marked	1	B1 for 110 marked cao
	(d)		0.27 marked	1	B1 for 0.27 marked cao
13	(i)		12	1	B1 for 12 cao
	(ii)		3	1	B1 for 3 cao
	(iii)		3 or 11	1	B1 for 3 and/or 11 cao
14	(a)		Shading	1	B1 for one square shaded to get one of 
	(b)		Shading	1	B1 for one square shaded to get 

1380/2F					
Question		Working	Answer	Mark	Notes
15		$\frac{1}{6}\times 36 = 6$ $\frac{2}{9}\times 36 = 8$ 36 – (8 + 6)	22	3	M1 for $\frac{1}{6}\times 36$ or $36\div 6$; $\frac{2}{9}\times 36$ or $36\div 9\times 2$ or 8 seen or 14 seen or $\frac{1}{6}+\frac{2}{9}$ or $\frac{7}{18}$ oe or 6 seen as long as not with incorrect working. M1 (dep) for 36 – '(8+ 6)' or $36-"\left(\frac{2}{9}+\frac{1}{6}\right)"\times 36$ or $\left(1-\frac{"1}{6}+\frac{2"}{9}\right)\times 36$ A1 for 22 cao SC B2 for $\frac{22}{36}$ oe fraction
16		10/72×360=50 perch 23/72×360=115 bream 39/72×360=195 carp	50, 115, 195	4	M1 for evidence of method for at least one angle (could be implied by one correct angle on pie chart or in the table) A2 all three angles drawn ±2° tolerance, any order (A1 at least one angle correctly drawn ±2°, or all three angles in the table) B1 names of fish as labels (dep on at least one angle drawn correctly, and exactly three sectors; initials will do) **NB:** Ignore table if pie chart provides marks
17			87.75	2	M1 for 3 × 4.5 × 6.5 seen or implied eg from answer of 87.7 or 87.8 or 88 (with no other working shown) A1 for 87.75 cao

1380/2F					
Question		Working	Answer	Mark	Notes
18	(a)	$1.8 \times -8 + 32$	17.6	2	M1 for 1.8×-8 or -14.4 or $\frac{-72}{5}$ seen or $32 - $ '1.8×8' or $1.8 \times -8 + 32$ seen A1 for 17.6 or $\frac{88}{5}$ or 17.60 oe
	(b)	$68 = 1.8C + 32$ $1.8C = 68 - 32$ $C = 36 \div 1.8$	20	2	M1 for $68 - 32$ or 36 or $68 = 1.8C + 32$ seen; condone replacement of C by another letter. A1 for 20 cao NB Trial and improvement score 0 or 2
19			construction	2	M1 for a pair of arcs drawn from the same centre on 2 lines at same distance from meeting point; or a single arc crossing both lines; using an arc with a radius which is the length of the shorter line will imply an intersection with the end of that line. ($\pm$ 2mm) A1 for bisector ($\pm 2°$) and correct arcs **SC:** B1 for bisector ($\pm 2°$) with no arcs, or incorrect arcs if M0 awarded. Accept bisectors that are dashed or dotted.
20	(a)	325×1.68	546	2	M1 for 325×1.68 seen or digits 546 A1 for 546, accept 546.00, 546.0
	(b)	$117 \div 1.5$	78	2	M1 for $117 \div 1.5$ seen or digits 78 A1 for 78, accept 78.00, 78.0

1380/2F					
Question		Working	Answer	Mark	Notes
21	(a)		(65, 100), (80, 110) plotted	1	B1 for plotting both points (65, 100), (80, 110) correctly (tolerance one square); ignore any additional plots given.
	(b)		positive (correlation)	1	B1 for positive (correlation) or length increases with height oe
	(c)		105 - 110	2	M1 for a single line segment with positive gradient that could be used as a line of best fit or a vertical line from 76 A1 for given answer in the range 105 – 110
22	(a)		Correct shape	2	B2 for correct shape; any orientation. (B1 for any two sides correct or all correct for scale factor other than 1 or 2), tolerance to within half square
	(b)		Reflection in line $x = 0$	2	B1 for reflection, reflect, reflected. B1 for line $x = 0$ or y-axis NB: more than one transformation should be awarded 0 marks.
23	(a)		$4m$	1	B1 for $4m$ oe
	(b)		$4pq$	1	B1 for $4pq$ or $4qp$ or $p4q$ oe
	(c)	$5 \times 3x - 5 \times 2$	$15x - 10$	1	B1 for $15x - 10$ cao
	(d)	$3y \times y + 3y \times 4$	$3y^2 + 12y$	2	M1 for $3y \times y + 3y \times 4$ or $3y^2 + a$ or $3y^2 + ay$ or $b + 12y$ or $by^2 + 12y$ where a, b are integers, and can be zero A1 for $3y^2 + 12y$ or $3 \times y^2 + 12 \times y$

1380/2F					
Question		Working	Answer	Mark	Notes
24	(a)	$18 \div 6 : 12 \div 6$	3 : 2	2	M1 for 18 : 12 or 12 : 18 or 1.5:1 or 1:0.67 oe or correct ratio reversed eg 2:3 A1 for 3 : 2 or 1 : 0.6 … [recurring]
	(b)	5 + 1 = 6 $54 \div 6 = 9$ 5 × 9	45	2	M1 for $\frac{5}{5+1} \times 54$ or $\frac{1}{5+1} \times 54$ or 54 ÷ '5+1' or 54 × 5 or 270 or 9 : 45 or 9 seen, as long as it is not associated with incorrect working. A1 for 45 cao
25		15 × 3 = 45 15 × 3.5 25 × 9 = 225 25 × 9.5 20 × 15 = 300 20 × 15.5 12 × 21 = 252 12 × 21.5 8 × 27 = 216 8 × 27.5 1038 ÷ 80 = 1078 ÷ 80 =	12.97 - 13.48	4	M1 for *fx* consistently within interval including ends (allow 1 error) M1 (dep) consistently using appropriate midpoints M1 (dep on first M) for $\Sigma fx \div \Sigma f$ A1 for 12.97 - 13.48
26	(a)	t^{6+2}	t^8	1	B1 for t^8 or for t^{6+2}
	(b)	m^{8-3}	m^5	1	B1 for m^5 or for m^{8-3}
27	(a)	4.6 + 3.85 = 8.45 $3.2^2 - 6.51 = 3.73$ 8.45 ÷ 3.73 =	2.26541555	2	M1 for $\frac{169}{20}$ or $\frac{256}{25}$ or $\frac{373}{100}$ or 3.73 or 10.24 or 8.45 seen A1 for 2.265(41555); accept $\frac{845}{373}$
	(b)		2	1	B1 ft for 2 or follow through their answer to part (a) NB: 2.0 gets B0

1380/2F					
Question		Working	Answer	Mark	Notes
28		$(0.5 \times 3.14... \times 8) + 8$	20.56 – 20.58	3	M2 for $(0.5 \times \pi \times 8)$ or $\pi \times 4$ or $(\pi \times 8 + 8)$ or $(0.5 \times \pi \times 8 + 8)$ oe (M1 for $\pi \times 8$ or $2\pi \times 4$; for a value 25.1-25.2 inclusive unless seen with incorrect working eg πr^2) A1 for 20.56 – 20.58 (**SC**: B2 if M0 scored for 12.56 – 12.58)

1380/3H					
Question		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	<table><tr><td>15</td><td>**25**</td><td>14</td><td>54</td></tr><tr><td>**22**</td><td>8</td><td>16</td><td>**46**</td></tr><tr><td>37</td><td>**33**</td><td>**30**</td><td>100</td></tr></table>	Table	3	B3 for all 5 correct (B2 for 3 or 4 correct) (B1 for 1 or 2 correct)
	(b)		$\frac{37}{100}$	1	$\frac{37}{100}$ B1 oe
2	(c)		$2x + 8y$	2	B2 for $2x + 8y$ oe [B1 for $2x$ or $8y$ seen] {Note: $-8y$ seen with no working gets B0 $4x + 2x = 6x$ gets B0}
	(b)		$2c + 4r$	2	B2 for $2c + 4r$ oe [B1 for $2c$ or $4r$ oe seen] Ignore any Left Hand Side = $2c + 4r$ {Note: ignore units or use of 'p'}
3	(a)	<table><tr><td>x</td><td>−2</td><td>−1</td><td>0</td><td>1</td><td>2</td><td>3</td></tr><tr><td>y</td><td>−11</td><td>**−7**</td><td>−3</td><td>**1**</td><td>**5**</td><td>9</td></tr></table>	−7, 1, 5	2	B2 all 3 correct (B1 for 1 or 2 correct)
	(b)		Graph	2	B2 for correct line between $x = -2$ and $x = 3$ (B1ft for plotting 5 of their points correctly or for a straight line with gradient 4 or for a straight line passing through (0, −3))

1380/3H					
Question		Working	Answer	Mark	Notes
4	(a)	$50 = 4k - 10$ $4k = 60$	15	2	M1for $50 = 4k - 10$ oe A1 cao
	(b)	$y = 4\times2 - 3\times5$	-7	2	M1 for $4\times2 - 3\times5$ oe A1 cao
5	(a)		Vertices at (2, -2), (7, -2), (7, -6), (4, -6), (4, -4), (2, -4)	2	B2 for a fully correct rotation [B1 for correct shape with correct orientation **OR** a 90° anticlockwise rotation about *O* **OR** a 180° rotation about *O* **OR** for any 3 correct sides in the correct position]
	(b)		Translation by $\begin{pmatrix}3\\-1\end{pmatrix}$	2	B1 for translation B1 (indep) for $\begin{pmatrix}3\\-1\end{pmatrix}$ or 3 right and 1 down
6	(a)		opp sides are equal	1	B1 for a correct explanation
	(b)	$4x - 2x = 12 - 1$	5.5	2	M1 for $4x + 1 - 1 - 2x = 2x + 12 - 1 - 2x$ oe A1 for 5.5 or 11/2 or 5½
	(c)	'5.5' $\times2$ + 4$\times$'5.5'+1 + 2$\times$'5.5'+12	57	2	M1 for correct substitution of x = '5.5' into the four expressions to find the sum of FOUR sides or 8x + 13 seen A1 ft
7	(a)		15.456	1	B1 cao
	(b)		0.15456	1	B1 cao
	(c)		3220	1	B1 cao

1380/3H					
Question		**Working**	**Answer**	**Mark**	**Notes**
8	(a)	$x^2 = 72 \div 2$	6	2	M1 for 72 ÷ 2 or 36 seen A1 6 or -6 or ± 6
	(b)	$72 = 2 \times 36 = 2 \times 2 \times 18$ $= 2 \times 2 \times 2 \times 9$  	$2 \times 2 \times 2 \times 3 \times 3$	2	M1 for a systematic method of at least 2 correct divisions by a prime number oe factor tree or a full process with one calculation error; can be implied by digits 2, 2, 2, 3, 3 on answer line A1 for $2 \times 2 \times 2 \times 3 \times 3$ or $2^3 \times 3^2$ oe [Note 1 × 2 × 2 × 2 × 3 × 3 gets M1 A0]
9	(a)			2	M1 rectangle with either correct width or height or any square A1 cao
	(b)			2	B2 for a correct sketch (B1 any 3-D sketch of no more than 4 faces seen, with a trapezoidal face)
10		$\frac{40000}{125} = \frac{8000}{25}$ =320 seconds	320	3	M1 for 40 × 1000 or 125 ÷ 1000 or 40000 or 0.125 M1 for $\frac{40000}{125}$ or $\frac{40}{'0.125'}$ A1 cao **OR** M1 for 1000 ÷ 125 M1 for '8' × 40 A1 cao

1380/3H					
Question		Working	Answer	Mark	Notes
11	(a)		62.5	1	B1 cao
	(b)		63.5	1	B1 for 63.5 (accept $63.4\dot{9}$ or 63.49.. or any evidence that the 9 is recurring or 63.499 or better)
12			Diagram	4	M1 arc radius 4 cm centre *B* within the guidelines M1 angle bisector from *A* to *BC* within the guidelines A1 for clear indication that inside of arc is being identified as correct region for the first condition, or that side of straight line nearer to *C* is identified as correct region for the second condition. (Note that only 1 of the Ms need be awarded for this A mark to be awarded) A1 fully correct region Ignore any drawing outside the given triangle
13	(a)			2	B1 'What type of magazine do you read?' B1 for at least 2 magazines identified in response boxes [Note: B0 for any data collection sheet/chart
	(b)		How many magazines have you read in the last week 0 ☐ 1 ☐ 2-3 ☐ >3 ☐	2	B1 Relevant question that refers to a time period. B1 for at least 3 mutually exclusive response boxes (need not be exhaustive)
14		$\frac{7\times200}{0.05} = \frac{1400}{0.05}$	28000	3	B1 for any two of 7, 200 or 0.05 M1 for correct processing of at least two of 7, 200 or 190 and 0.05 or 0.1 A1 26600 - 28000

1380/3H					
Question		Working	Answer	Mark	Notes
15	(a)		6.4×10^4	1	B1 cao
	(b)		1.56×10^{-5}	1	B1 cao
16	(a)		$2x(2x - 3y)$	2	B2 (B1 for $x(4x - 6y)$ or $2(2x^2 - 3xy)$ or $2x$(two terms) or $4x(x - 1.5y)$)
	(b)	$x^2 - x + 6x - 6 =$ $x(x - 1) + 6(x - 1)$	$(x + 6)(x - 1)$	2	B2 cao (B1 $(x - 6)(x + 1)$ or $(x - 6)(x - 1)$ or $x(x - 1) + 6(x - 1)$ or $x(x + 6) - (x + 6)$)
17	(a)		Ogive	2	B1 6 or 7 points plotted correctly ± 1 full (2mm) square B1 (dep) for points joined by curve or line segments provided no gradient is negative - ignore any part of graph outside range of their points (SC: B1 if 6 or 7 points plotted not at end but consistent within each interval and joined)
	(b)		240	2	B2 if answer is in the range 235 - 245 **OR** M1 (dep on graph being cf) for using cf = 60 or 60.5 A1 ft (± 1 square)
	(c)			1	B1ft correct comment comparing money spent by men with money spent by women

1380/3H					
Question		Working	Answer	Mark	Notes
18	(a)	AOD = 90 - 36 or 180 – (90 + 36)	54	2	M1 AOD = 90 − 36 or 180 – (90 + 36) A1 cao
	(b)(i)	$ABC = AOD \div 2$	27	2	M1 $ABC = AOD \div 2$ A1 ft from '54'
	(ii)		Reason	1	B1 Angle at centre = twice angle at circumference
19	(a)		$x = 2, y = 3$	1	B1 cao
	(b)		$y = \frac{1}{2}x + 4$	2	M1 for $y = mx + 4$ or $y = \frac{1}{2}x + c$, $c \neq 2$, or $\frac{1}{2}x + 4$ A1 for $y = \frac{1}{2}x + 4$ oe
20	(a)	$3t + 1 < t + 12$ $3t - t < 12 - 1$ $2t < 11$	$t < 5.5$	2	M1 $3t - t < 12 - 1$ A1 $t < 5.5$ oe (B1 for t = 5.5 or $t > 5.5$ or 5.5 or $t \leq 5.5$ or $t \geq 5.5$ on the answer line)
	(b)		5	1	B1 for 5 or ft (a)
21		$M = kL^3$ $k = \frac{M}{L^3} = \frac{160}{8} = 20$ When $L = 3$, $M = 20 \times 3^3$	540	4	M1 for $M \propto L^3$ or $M = kL^3$ A1 k = 20 M1 for '20'×3^3 A1 for 540 cao

1380/3H					
Question		**Working**	**Answer**	**Mark**	**Notes**
22		<table><tr><td>F</td><td>4</td><td>10</td><td>24</td><td>20</td><td>6</td></tr><tr><td>Fd</td><td>0.8</td><td>1</td><td>1.6</td><td>2</td><td>1.2</td></tr></table> or <table><tr><td>F</td><td>4</td><td>10</td><td>24</td><td>20</td><td>6</td></tr><tr><td>Fd</td><td>4</td><td>5</td><td>8</td><td>10</td><td>6</td></tr></table>	Correct histogram	4	M1 use of frequency density as frequency ÷ width (can be implied by two correct frequency densities or two correct bars with different widths) or area (can be implied by one correct bar) to represent frequency A2 for all 5 histogram bars correct ±½ square (A1 at least 3 correct histogram bars ±½ square) A1 for correct label and scale numbered appropriately **or** for key and consistent scaling
23	(a)		Correct diagram	2	B1 for 0.2 oe seen on bottom left branch B1 for correct probabilities on other branches
	(b)	prob(*WW*) = 0.5×0.5	0.25	2	M1for 0.5 × '0.5' A1ft for 0.25 oe

1380/3H					
Question		Working	Answer	Mark	Notes
24	(a)	*AB* = *AC* (equilateral triangle) *AD* is common *ADC*=*ADB* (= 90° given) $\Delta ADC \equiv \Delta ADB$ (RHS) OR *DAC* = *DAB* (since *ACD* = *ABD* and *ADC* = *ADB*) *AB* = *AC* (equilateral triangle) *AD* is common $\Delta ADC \equiv \Delta ADB$ (SAS) OR *DAC* = *DAB* (since *ACD* = *ABD* and *ADC* = *ADB*) *AD* is common *ACD* = *ABD* (equilateral triangle) $\Delta ADC \equiv \Delta ADB$ (AAS)	Proof	3	M1 for any three correct statements (which do not have to be justified) that together lead to a congruence proof (ignore irrelevant statements) A1 for a full justification of these statements A1 for RHS, SAS, AAS, ASA or SSS as appropriate NB The two A marks are independent
	(b)	*BD* = *DC* (congruent Δs) *BC* = *AB* (equilateral Δs) Hence *BD* = $\frac{1}{2}AB$	Proof	2	B1 for *BD* = *DC* and *BC* = *AB* B1 for justification of these statements and completion of proof

1380/3H					
Question		**Working**	**Answer**	**Mark**	**Notes**
25	(a)	$\frac{1}{2\frac{1}{2}}+\frac{1}{3\frac{1}{3}}=\frac{1}{f}$ $\frac{2}{5}+\frac{3}{10}=\frac{1}{f}$ $\frac{7}{10}=\frac{1}{f}$	$\frac{10}{7}$	3	M1 $\frac{1}{2\frac{1}{2}}+\frac{1}{3\frac{1}{3}}=\frac{1}{f}$ M1 correct addition of the fractions to get $\frac{7}{10}$ oe A1 for $\frac{10}{f}$ oe
	(b)	$\frac{1}{u}=\frac{1}{f}-\frac{1}{v}$ $\frac{1}{u}=\frac{v-f}{fv}$	$u=\frac{fv}{v-f}$	2	M1 $\frac{1}{u}=\frac{v-f}{fv}$ oe or $vf+uf=uv$ oe or $\frac{1}{u}=\frac{f-v}{fv}$ **or** $u=\frac{1}{\frac{v-f}{fv}}$ or $u=\frac{1}{\frac{1}{f}-\frac{1}{v}}$ A1 $u=\frac{fv}{v-f}$ or $u=\frac{-fv}{f-v}$
26	(a)		$y = f(x-4)$	2	B2 cao (B1 for f(x - 4) or $y = f(x + a)$, $a \neq -4$, $a \neq 0$)
	(b)			2	B2 cao (B1 cosine curve with either correct amplitude or correct period, but not both)

22

Examples:


represents 2 calls
Frequency density
4
3
2
1
0
10
20
30
40
50
0
10
20
30
40
50

26.



1380/4H					
Question		Working	Answer	Mark	Notes
1	(a)	325 × 1.68	546	2	M1 for 325 × 1.68 seen or digits 546 A1 for 546, accept 546.00, 546.0
	(b)	117 ÷1.5	78	2	M1 for 117 ÷1.5 seen or digits 78 A1 for 78, accept 78.00, 78.0
2	(a)		Correct shape	2	B2 for correct shape; any orientation. (B1 for any two sides correct or all correct for scale factor other than 1 or 2), tolerance to within half square
	(b)		Reflection in line $x = 0$	2	B1 for reflection, reflect, reflected. B1 for line $x = 0$ or y-axis NB: more than one transformation should be awarded 0 marks.
3		1^2+1 2^2+1 3^2+1	2, 5, 10	2	M1 for 1^2+1 or 2^2+1 or 3^2+1 (but not 1^2+1, 2^2+2, 3^2+3) A1 for 2, 5, 10 SC: B1 for 1, 2, 5 with or without working
4	(a)		(65, 100), (80, 110) plotted	1	B1 for plotting both points (65, 100), (80, 110) correctly (tolerance one square); ignore any additional plots given.
	(b)		positive (correlation)	1	B1 for positive (correlation) or length increases with height oe
	(c)		105 - 110	2	M1 for a single line segment with positive gradient that could be used as a line of best fit or a vertical line from 76 A1 for given answer in the range 105 – 110

1380/4H					
Question		Working	Answer	Mark	Notes
5		143.64 ÷ 19 = 7.56 7.56 × 31 =	234.36	3	M1 for 143.64 ÷ 19 (or 7.56 seen) or 143.64 × 31 (or 4452.84 seen) M1(dep) for '7.56' × 31 or '4452.84' ÷ 19 or 143.64 + 12×'7.56' A1 for 234.36 cao accept 234.36p **Alternative method:** M1 for $\frac{31}{19}$ (or 1.63(1…) seen) M1 (dep) '1.63…' × 143.64 A1 for 234.36 cao accept 234.36p
6	(a)	1.8 × –8 + 32	17.6	2	M1 for 1.8 × -8 or -14.4 or $\frac{-72}{5}$ seen or 32 – '1.8 × 8' or 1.8 × –8 + 32 seen A1 for 17.6 or $\frac{88}{5}$ or 17.60 oe
	(b)	68 = 1.8C + 32 1.8C = 68 – 32 C = 36 ÷1.8	20	2	M1 for 68 – 32 or 36 or 68 = 1.8C + 32 seen; condone replacement of C by another letter. A1 for 20 cao NB Trial and improvement score 0 or 2
7			diagram	3	M1 for line drawn or point marked within guidelines from *P* M1 for line drawn or point marked within guidelines from *Q* up to top guideline from *P* A1 for point indicated within region where guidelines intersect

1380/4H					
Question		Working	Answer	Mark	Notes
8	(a)	$18 \div 6 : 12 \div 6$	3 : 2	2	M1 for 18 : 12 or 12 : 18 or 1.5:1 oe or any correct ratio reversed eg 2:3 A1 for 3 : 2 or 1 : 0.6 … [recurring]
	(b)	5 + 1 = 6 $54 \div 6 = 9$ 5 × 9	45	2	M1 for $\frac{5}{5+1} \times 54$ or $\frac{1}{5+1} \times 54$ or 54 ÷ '5+1' or 54 × 5 or 270 or 9 : 45 or 9 seen, as long as it is not associated with incorrect working. A1 for 45 cao
9		2 48 3 87 2.5 65.(625) 2.6 69.(576) 2.7 73.(683) 2.65 71.6(09) 2.61 69.9(79) 2.62 70.3(84) 2.63 70.7(91) 2.64 71.1(99) 2.66 72.(021) 2.67 72.4(34) 2.68 72.8(48) 2.69 73.2(65)	2.6	4	B2 for trial $2.6 \leq x \leq 2.7$ evaluated (B1 for trial $2 \leq x \leq 3$ evaluated) B1 for different trial $2.6 < x \leq 2.65$ B1(dep on at least one previous B1) for 2.6 Values evaluated can be rounded or truncated, but to at least 2sf when x has 1dp and 3sf when x has 2dp **NB** Allow 72 for evaluation using $x = 2.66$ **NB** No working scores no marks even if answer is correct
10			construction	2	M1 for arcs from same centre on 2 lines at same distance from meeting point (± 2mm) A1 for bisector (± 2°) and correct arcs **SC:** B1 for bisector ($\pm 2°$) with no arcs, or incorrect arcs if M0 awarded. Accept bisectors that are dashed or dotted.

1380/4H					
Question		Working	Answer	Mark	Notes
11			2 + 'prime number' is odd	2	M1 for a counter example showing intent to add 2 and another prime number; ignore incorrect examples A1 for a correctly evaluated counter example with no examples given that involve either non-primes or incorrect evaluation **Alternative method** B2 for fully correct explanation '2 is a prime number, odd + even (or 2) = odd' oe with no accompanying incorrect statements or examples (B1 for '2 is a prime number' **or** recognition that not all prime numbers are odd **or** odd + even (or 2) = odd; ignore incorrect examples or statements)
12		15 × 3 = 45 15 × 3.5 25 × 9 = 225 25 × 9.5 20 × 15 = 300 20 × 15.5 12 × 21 = 252 12 × 21.5 8 × 27 = 216 8 × 27.5 1038 ÷ 80 = 12.975 1078 ÷ 80 = 13.475	12.97 – 13.48	4	M1 for fx consistently within interval including ends (allow 1 error) M1 (dep) consistently using appropriate midpoints M1 (dep on first M) for $\Sigma fx \div \Sigma f$ A1 for 12.97 – 13.48 with no arithmetic errors

1380/4H					
Question		Working	Answer	Mark	Notes
13		(0.5 × 3.14... × 8) + 8	20.56 - 20.58	3	M2 for (0.5 × π × 8) or π × 4 or (π × 8 + 8) or (0.5 x π × 8 + 8) oe (M1 for π × 8 or 2π × 4; for a value 25.1-25.2 inclusive unless seen with incorrect working eg πr^2) A1 for 20.56 – 20.58 (**SC**: B2 if M0 scored for 12.56 - 12.58)
14	(a)		a^3	1	B1 for a^3 cao
	(b)	5 × 3*x* – 5 × 2	15*x* – 10	1	B1 for 15*x* – 10 cao
	(c)	$3y \times y + 3y \times 4$	$3y^2$ +12y	2	M1 for $3y \times y + 3y \times 4$ or $3y^2$ + *a* or $3y^2$+ay or *b* + 12y or by^2+12y where *a* ,*b* are integers, and can be zero A1 for $3y^2$ +12y or $3 \times y^2$ + 12×y NB: If more than 2 terms in expansion MOA0
	(d)	$2x-8+3x+6$	$5x-2$	2	M1 for $2 \times x - 2 \times 4$ or $2x-8$ or $3 \times x + 3 \times 2$ or $3x+6$ A1 for $5x-2$ cao
	(e)	$x^2+4x-3x-12$	x^2+x-12	2	M1 for 4 terms correct with or without signs, or 3 out of no more than 4 terms, with correct signs (the terms may be in an expression or table) or $x(x-3)+4(x-3)$ or $x(x+4)-3(x+4)$ A1 for x^2+x-12 cao
15		4.6 + 3.85 = 8.45 3.2^2 – 6.51 = 3.73 8.45 ÷ 3.73 =	2.26541555	2	M1 for $\frac{169}{20}$ or $\frac{256}{25}$ or $\frac{373}{100}$ or 3.73 or 10.24 or 8.45 seen A1 for 2.265(41555); accept $\frac{845}{373}$

1380/4H					
Question		Working	Answer	Mark	Notes
16	(a)	t^{6+2}	t^8	1	B1 for t^8 or for t^{6+2}
	(b)	m^{8-3}	m^5	1	B1 for m^5 or for m^{8-3}
	(c)	$2^3 \times x^3$	$8x^3$	2	B2 for $8x^3$ cao (B1 for ax^3, $a \neq 8$ or $2x \times 2x \times 2x$ or $8x^n$ $n \neq 0,3$)
	(d)	$3 \times 4 \times a^{2+5} \times h^{1+4}$	$12a^7h^5$	2	B2 for $12a^7h^5$ (B1 for $12a^7h^n$, $n \neq 0,5$ or $12a^mh^5$, $m \neq 0,7$ or ka^7h^5, $k \neq 12$ or $3 \times 4 \times a^{2+5} \times h^{1+4}$)
17		$9^2 - 6^2$ $81 - 36 = 45$ $\sqrt{45}$	6.705 - 6.71	3	M1 for $9^2 - 6^2$ or $81 - 36$ or 45 or $9^2 = AB^2 + 6^2$ oe M1 for $\sqrt{81-36}$ or $\sqrt{45}$ A1 for 6.705 – 6.71 [**SC:** M1 for $\sqrt{81+36}$ or $\sqrt{117}$]
18	(a)		Heaviest bag is 29kg	1	B1 for 23kg is the upper quartile oe, or the heaviest bag is 29kg oe, or 25% of bags are heavier than 23kg or range is 5 - 29 oe
	(b)		17	1	B1 for 17 cao
	(c)	23 – 10	13	1	B1 for 13 cao
	(d)	$\frac{25}{100} \times 240$	60	2	M1 for $\frac{25}{100} \times 240$ oe or $\frac{25}{100} \times 241$ oe A1 for 60 cao (**SC:** B1 for 25% or 0.25 or quarter seen)

1380/4H					
Question		Working	Answer	Mark	Notes
19	(a)	4500×1.04^2	4867.20	3	M1 for 4500 × 1.04 or for 4500 + 0.04 × 4500 or for 4680 or 180 or 360 or 4860 M1 (dep) '4680' × 1.04 or for '4680' + 0.04 × '4680' A1 for 4867.2(0) cao (If correct answer seen then ignore any extra years) **Alternative method** M2 for 4500×1.04^2 or 4500 × 1.04^3 A1 for 4867.2(0) cao [SC: 367.2(0) seen B2]
	(b)	2400×1.075^n 2580 2773.5 2981.5125 3205.12... 3445.51...	5	2	M1 for an attempt to evaluate 2400×1.075^n for at least one value of n (not equal to 1) or 3445.51 ÷ 1.075^n ($n \geq 2$) or $\frac{3445.51}{2400}$ (=1.4356...) and 1.075^n evaluated, $n \geq 2$ A1 for 5 cao

1380/4H					
Question		Working	Answer	Mark	Notes
20	(a)	$\cos x = \frac{5}{8}$	51.3 - 51.35	3	M1 for $\cos(x=)\frac{5}{8}$ M1 for $\cos^{-1}\frac{5}{8}$ or $\cos^{-1}0.625$, or $\cos^{-1}(5\div 8)$ A1 for 51.3 - 51.35 (SC B2 for 0.89 – 0.9 or 57 - 57.1 seen) **Alternative Scheme** $h^2 = 8^2 - 5^2$ (=39) M1 for sin(x=) $\frac{\sqrt{"39"}}{8}$ or tan (x=) $\frac{\sqrt{"39"}}{5}$ or $\frac{\sin x}{\sqrt{"39"}} = \frac{\sin 90}{8}$ oe or $(\sqrt{"39"})^2 = 8^2 + 5^2 - 2\times 8\times 5\times\cos x$ M1 for $\sin^{-1}(\frac{\sqrt{"39"}}{8})$ or $\sin^{-1}(\frac{\sqrt{"39"}\times\sin 90}{8})$ or $\tan^{-1}(\frac{\sqrt{"39"}}{5})$ or $\cos^{-1}(\frac{8^2+5^2-(\sqrt{"39"})^2}{2\times 8\times 5})$ A1 for 51.3 - 51.35

1380/4H					
Question		Working	Answer	Mark	Notes
	(b)	$\tan 40 = \frac{y}{12.5}$ $y = 12.5 \times \tan 40$	10.4 - 10.5	3	M1 for $\tan 40 = \frac{y}{12.5}$ M1 for $12.5 \times \tan 40$ A1 for 10.4 – 10.5 SC: B2 for ±(13.9 – 14.0) or 9 - 9.1 seen **Alternative scheme** M1 for $\frac{y}{\sin 40} = \frac{12.5}{\sin 50}$ oe M1 for $y = \frac{12.5}{\sin 50} \times \sin 40$ A1 for 10.4 – 10.5 SC: B2 for ±(35.4 - 35.5) or 10.39 - 10.396 seen
21	(a)	$\frac{26}{258} \times 50$	5	2	M1 for $\frac{a}{258} \times 50$ or $50 \div \frac{258}{a}$ oe, a < 258 or 5.03(8...) or 26 ÷ 5.16 A1 for 5 cao
	(b)	$\frac{(25+48+62)}{258} \times 50$	26	2	M1 for $\frac{135}{258} \times 50$ or $\frac{(25+48+62)}{258} \times 50$ or $\left(\frac{25}{258} \times 50 + \frac{48}{258} \times 50 + \frac{62}{258} \times 50\right)$ oe or 26.1(6...) or 5 + 9 + 12 or $135 \div 5.16$ A1 for 26 or 27

1380/4H					
Question		Working	Answer	Mark	Notes
22		$(9n^2+6n+1)-$ $(9n^2-6n+1)$ $=12n$	$12n$ correct comment	3	M1 for $(3n)^2+3n+3n+1$ or $(3n)^2-3n-3n+1$ or $((3n+1)-(3n-1))((3n+1)+(3n-1))$ A1 for $12n$ from correct expansion of both brackets A1 for $12n$ is a multiple of 4 or $12n = 3 \times 4n$ or $12n = 4 \times 3n$ or $\frac{12n}{4}=3n$ or $\frac{12n}{3}=4n$ NB: Trials using different values for n score no marks.
23	(a)		**b** – **a**	1	B1 for **b** – **a** or – **a** + **b** oe
	(b)	$\overrightarrow{OP}=\overrightarrow{OA}+\overrightarrow{AP}$ $\overrightarrow{OP} = \mathbf{a} + \frac{3}{5}(\mathbf{b}-\mathbf{a})$ $\overrightarrow{OP} = \frac{1}{5}(2\mathbf{a}+3\mathbf{b})$	proof	3	M1 for $\overrightarrow{OP}=\overrightarrow{OA}+\overrightarrow{AP}$ oe or $\overrightarrow{OP}=\overrightarrow{OB}+\overrightarrow{BP}$ oe M1 for $\overrightarrow{AP}=\frac{3}{5}$ x "(**b** - **a**)" oe or $\overrightarrow{BP}=\frac{2}{5}$ x "(**a** - **b**)" oe A1 for **a** + $\frac{3}{5}$ x (**b** - **a**) oe or **b** + $\frac{2}{5}$ x (**a** - **b**) oe leading to given answer with correct expansion of brackets seen

1380/4H					
Question		Working	Answer	Mark	Notes
24		$\frac{1}{2}\times 6\times 6\times \sin 60$ $-\frac{60}{360}\times \pi \times 3^2$ = 15.588 - 4.712	10.8 - 10.9	4	M1 for $\frac{1}{2}\times 6\times 6\times \sin 60$ or for $0.5\times 6\times \sqrt{6^2-3^2}$ or 15.5 - 15.6 or 14.5 - 14.6 or ±5.48(65...) M1 for $\frac{60}{360}\times \pi \times 3^2$ (= 4.712...) M1(dep on 1 previous M1) for 'area of triangle' – 'area of sector' A1 for 10.8 – 10.9 SC: B3 for 10.1 - 10.2 or 9.84 - 9.85
25		$\frac{(x-3)\cancel{(x-5)}}{(2x+3)\cancel{(x-5)}}$	$\frac{(x-3)}{(2x+3)}$	3	B1 for $(x-3)(x-5)$ or $x(x-5)-3(x-5)$ M1 for $(2x\pm 3)(x\pm 5)$ or $2x(x+5)\pm 3(x+5)$ or $2x(x-5)\pm 3(x-5)$ A1 for $\frac{(x-3)}{(2x+3)}$ cao as final answer

1380/4H					
Question		Working	Answer	Mark	Notes
26		$\frac{5}{20}\times\frac{7}{19}+\frac{5}{20}\times\frac{8}{19}+\frac{7}{20}\times\frac{5}{19}+\frac{7}{20}\times\frac{8}{20}+\frac{8}{20}\times\frac{5}{19}+\frac{8}{20}\times\frac{7}{19}$ **or** $\left(\frac{5}{20}\times\frac{15}{19}+\frac{7}{20}\times\frac{13}{19}+\frac{8}{20}\times\frac{12}{19}\right)$ **or** 1 – $\left(\frac{5}{20}\times\frac{4}{19}+\frac{7}{20}\times\frac{6}{19}+\frac{8}{20}\times\frac{7}{19}\right)$	$\frac{131}{190}$	4	M1 for at least one product of the form $\frac{a}{20}\times\frac{b}{19}$ M1 for identifying all products (condone 2 errors in 6 products, 1 error in 3 products) **Either** $\left(\frac{5}{20}\times\frac{7}{19},\frac{5}{20}\times\frac{8}{19},\frac{7}{20}\times\frac{5}{19},\frac{7}{20}\times\frac{8}{19},\frac{8}{20}\times\frac{5}{19},\frac{8}{20}\times\frac{7}{19}\right)$ **or** $\left(\frac{5}{20}\times\frac{15}{19}, \frac{7}{20}\times\frac{13}{19}, \frac{8}{20}\times\frac{12}{19}\right)$ **or** $\left(\frac{5}{20}\times\frac{4}{19}, \frac{7}{20}\times\frac{6}{19}, \frac{8}{20}\times\frac{7}{19}\right)$ M1 (dep) for $\left(\text{'}\frac{5}{20}\times\frac{7}{19}+\frac{5}{20}\times\frac{8}{19}+\frac{7}{20}\times\frac{5}{19}+\frac{7}{20}\times\frac{8}{19}+\frac{8}{20}\times\frac{5}{19}+\frac{8}{20}\times\frac{7}{19}\text{'}\right)$ oe **or** $\left(\text{'}\frac{5}{20}\times\frac{15}{19}+\frac{7}{20}\times\frac{13}{19}+\frac{8}{20}\times\frac{12}{19}\text{'}\right)$ oe **or** 1 – $\left(\text{'}\frac{5}{20}\times\frac{4}{19}+\frac{7}{20}\times\frac{6}{19}+\frac{8}{20}\times\frac{7}{19}\text{'}\right)$oe A1 for $\frac{131}{190}$ oe or 0.68947... correct to at least 2 decimal places or answer that rounds to 0.69 **NB : If decimals used for products then must be correct to at least 2 decimal places**

					With replacement M0 M1 for identifying all products (condone 2 errors in 6 products, 1 error in 3 products) **either** $\left(\frac{5}{20}\times\frac{7}{20},\frac{5}{20}\times\frac{8}{20},\frac{7}{20}\times\frac{5}{20},\frac{7}{20}\times\frac{8}{20},\frac{8}{20}\times\frac{5}{20},\frac{8}{20}\times\frac{7}{20}\right)$ **or** $\left(\frac{5}{20}\times\frac{5}{20},\frac{7}{20}\times\frac{7}{20},\frac{8}{20}\times\frac{8}{20}\right)$ **or** $\left(\frac{5}{20}\times\frac{15}{20},\frac{7}{20}\times\frac{13}{20},\frac{8}{20}\times\frac{12}{20}\right)$ M1 (dep) for $\left(,\frac{5}{20}\times\frac{7}{20}+\frac{5}{20}\times\frac{8}{20}+\frac{7}{20}\times\frac{5}{20}+\frac{7}{20}\times\frac{8}{20}+\frac{8}{20}\times\frac{5}{20}+\frac{8}{20}\times\frac{7}{20},\right)$ **or** $\left(,\frac{5}{20}\times\frac{15}{20}+\frac{7}{20}\times\frac{13}{20}+\frac{8}{20}\times\frac{12}{20},\right)$ **or** 1 – $\left(,\frac{5}{20}\times\frac{5}{20}+\frac{7}{20}\times\frac{7}{20}+\frac{8}{20}\times\frac{8}{20},\right)$ A0 for $\frac{262}{400}$ oe or 0.655 (NB: $\frac{262}{400}$ oe or 0.655 implies M2) **Partial replacement** SC: B2 for $\frac{141}{200}$ oe or 0.705 **or** $\frac{121}{190}$ oe or 0.6368... correct to at least 2 decimal places

24	(a)		(5,–4)	2	B2 for (5,–4) (B1 for (a,–4) or (5,b) where $a \neq 5$ or 3 and $b \neq -4$).
	(b)		(–2,2)	2	B2 for (–2,2) (B1 for (a,2) or (–2,b) where $a \neq -2$ and $b \neq 2$).

27	(a)		$y = f(x - 5)$	1	B1 cao
	(b)		(4, 3)	2	B2 cao (B1 for one coord. correct (in correct position) or (3,4).)

1380_4H

27	(a)	Graph translated 3 units to the right through points (1, 6), (7, 6), (2, 0), (6, 0), (4, –2.5)	sketch	2	M1 for a horizontal translation with at least three of the points (–1, 0), (3, 0), (1, –2.5) translated by the same amount A1 for a curve through the points (1, 6), (7, 6), (2, 0), (6, 0), (4, –2.5) ± ½ square
	(b)	Graph reflected in the *x*-axis through points (–1, 0), (3, 0), (1, 2.5), (–2, –6), (4, –6)	sketch	2	M1 for a reflection in *x*-axis through (–1, 0), (3, 0) or in *y*-axis through (0, –2) A1 for a curve through the points (–1, 0), (3, 0), (1, 2.5), (–2, –6), (4, –6) ± ½ square

1380_4H

1380/4H

Original question 26

The full source mark scheme begins on page 299. Use the original paper code, tier and question number shown above.

25	(a)		sketch		M1 for inverting the parabola, so maximum is at (–2, 0) A1 for parabola passing through all three of the points (–2, 0), (0, –4), (–4, –4)
	(b)		$y = f(x - 6)$	1	B1 for $y = f(x - 6)$ or $y = (x - 4)^2$ oe

1MA0_1H

25	(i)		(3, −1)	3	B1 cao
	(ii)		(1.5, −4)		B1 for (1.5, −4) accept 1.5 or $1\frac{1}{2}$ or $\frac{3}{2}$ for x coordinate
	(iii)		(−3, −4)		B1 cao

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5°
Measurements of length: ±5 mm

PAPER: 1MA0_1H			
Question		**Modification**	**Notes**
3		Stem and leaf diagram – extra line put in at the bottom	
5		Larger gaps between numbers	
10		Line AB put horizontal Small vertical line at either end of line AB	
12	(c)	*x* changed to *y*	
15	(b)	Table changed 50, 250, 175, 100, 225 Box plots labeled – Box plot (a) and Box plot (b) and both extended to 400 with a 2 cm grid Lines moved to 25, 125, 200, 225, 250	
16		Table changed to 20, 70, 140, 170, 185, 195, 200 Grid 1½ cm for 10 on y axis (this one gives 10 people over 60): x axis is 3cm for 10 years. Age (years) 90 column removed	
18		Shading reversed – AEFG is shaded Question wording altered to reflect this	

22	(a)		(0,−1)	1	B1 cao
	(b)		Straight line drawn	2	M1 for a horizontal translation of 1 unit. A1 for straight line drawn parallel to $y = f(x)$ through O from (–1.5, 3) to (1.5, –3)

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5º
Measurements of length: ±5 mm

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
2		No diagrams	
3		Wording changed to: Work out the length of the side labelled w cm on the first diagram.	
5		Garden enlarged – fountain to bench is 9.5 cm North lines put in from fountain and bench. Line joins fountain to bench. Change 7 metres to 11 metres. Change 12 metres to 14 metres.	

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
6		Model – MLP 2 diagrams as well.	
	(i)	Full diagram given without 3 cm and 2 cm measurements put on.	
	(ii)	End face only with all measurements. Wording inserted 'The length of the prism is 9 cm'	
7	(a)	2 cm grid. Shape A coordinates (1, 1) (3, 1) (4, 3) (2, 3)	
10		Ground labelled at each end.	
16		*q* changed to *y*	
		r changed to e	
17		*y* axis 2 cm for 0.1 *x* axis 2 cm for 1 Right axis labelled – leeway will be needed in plotting of some points.	
22		2 cm grid	

24	(a) (i)		(0, 5)	3	B1 cao
	(ii)		(3, 10)		B1 cao
	(iii)		(1, 5)		B1 cao
	(b)		Translation of $\begin{pmatrix} 0 \\ -4 \end{pmatrix}$ oe	1	B1 for a correct transformation, eg. translation of $\begin{pmatrix} 0 \\ -4 \end{pmatrix}$ or translation of 4 units in the negative y-direction, oe.

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5°
Measurements of length: ±5 mm

PAPER: 1MA0_1H			
Question		**Modification**	**Notes**
Q1	(a)	An extra horizontal line has been added at the bottom of the diagram.	B2 for a correct ordered stem and leaf diagram (B1 for fully correct unordered or ordered with one error or omission) B1 (indep) for key (units not required)
Q1	(b)	An extra horizontal line has been added at the bottom of the diagram.	M1 for a method to find "3" as a percentage of the total number of men, eg $\frac{"3"}{"20"}\times 100$ oe $\frac{"3"\times 5}{100}$ or ft from their diagram A1 for 15 cao
Q2	(b)	MLP only: *x* changed to *y*	M1 for collecting the terms in *y* or the number terms in an equation, eg. $5y - y + 4 = 14$ or $5y = 14 - 4 + y$ A1 for 2.5 oe (accept $\frac{10}{4}$)

PAPER: 1MA0_1H			
Question		**Modification**	**Notes**
Q5		2 models provided for all candidates. MLP also have diagrams. In text, wording is added to give the dimensions of the first cheese.	M1 for a method to find volume of a cuboid, eg. 2 × 10 × 15 (= 300) or 5 × 5 × x (= 25x) M1 (dep) for "300" ÷ "25" oe A1 cao OR M1 for 10 ÷5 (= 2) and 15 ÷ 5 (= 3) or 10 ÷5 (= 2) and 2 ÷ 5 (= 0.4) M1 (dep) for 2 × "2" × "3" or 15 × "2" × "0.4" A1 cao
Q6	(a)	Diagram enlarged. Crosses changed to filled in circles. Label for horizontal axis left aligned. Label for vertical axis placed above the axis. Right axis is labelled.	B1 for a description of a dynamic relationship eg "The older the car the lower the price" or "The newer the car the greater the price" oe (accept negative correlation)
Q6	(b)	Diagram enlarged. Crosses changed to filled in circles. Label for horizontal axis left aligned. Label for vertical axis placed above the axis. Right axis is labelled.	M1 for a single straight line segment with negative gradient that could be used as a line of best fit or vert. line from 3.5 or a point plotted at (3.5, y), where y is in the range 6400 to 7000 A1 for 6400 - 7000
Q7	(a)	Grids enlarged. Triangles A, B and C have dotty shading.	B2 for a triangle with vertices at (–3, 3), (–3, 4), (–1, 4) (B1 for triangle in correct orientation and size or rotated 90° clockwise about centre O or three correct vertices without joinin
Q7	(b)	Grids enlarged. Triangles A, B and C have dotty shading.	B1 for reflection B1 for (in the line) $y = x$ Note: award no marks if more than one transformation is given

PAPER: 1MA0_1H			
Question		**Modification**	**Notes**
Q10		Diagram enlarged. Measurement lines for 1 metre and 2.2 metres are removed. Dashed measurement line for 3.4 metres.	M1 for splitting the shape (or showing recognition of the "absent" triangles) and using a method to find the area of one shape M1 for a complete method to find the total area, (= 9 m^2) M1 (dep on M1) for a method to find the number of packs required from their total area, eg. "9" ÷ 2 = 4.5 rounded up to 5 M1 for a method to find 75% of 24.80 or 75% of the cost of their total number of packs, eg. $24.80 \times$ "5" $\times \frac{75}{100}$ (= 93) or $24.80 \times \frac{75}{100}$ (= 18.6) C1 for a conclusion supported by fully correct answers, eg. showing 9 (m^2), 5 (packs) and 93 or 7 (from 100 – 93) OR M1 for method to find 75% of £24.80, eg. $24.80 \times \frac{75}{100}$ (= 18.6) M1 for method to find total number of packs Mary can buy, eg. 100 ÷ "18.60" = 5.3.... truncated to 5 or 10 (m^2) M1 for finding area of one relevant shape or showing how one pack (2 m^2) can fit in the diagram M1 (dep on previous M1) for complete method to show that 5 packs can cover the floor C1 for a conclusion supported by fully correct answers, showing the capacity (10) greater than total area (9)

PAPER: 1MA0_1H			
Question		**Modification**	**Notes**
Q12		Diagram enlarged. AC, DF and PS made the same length. Angle arc put inside the angle size.	M1 for finding one related angle using parallel lines A1 for $x = 40(^o)$ C2 for full reasons linked to appropriate method eg. alternate angles are equal **and** angles in a triangle add up to 180° eg. angles on a straight line add up to 180° **and** corresponding angles are equal **and** alternate angles are equal eg. co-interior (allied) angles add up to 180° **and** exterior angle of a triangle is equal to sum of interior opposite angles Other solutions may include reasons such as: vertically opposite angles are equal the sum of angles at a point is equal to 360° (C1 (dep on M1) for one appropriate reason linked to parallel lines)
Q13		Diagrams enlarged. 8 cm moved above the diagram. In text, wording gives the dimensions.	M1 for 8 – 2 (= 6) M1 (indep) for $x^2 + 8^2$ (provided $x \leq 8$) M1 (dep on previous M1) fo $\sqrt{"x"^2 + 8^2}$ or $\sqrt{"100"}$ M1 (dep on M2) for 4 × 2 + 4 × "10" A1 cao

PAPER: 1MA0_1H			
Question		**Modification**	**Notes**
Q16	(a)	Frequencies changed to 5, 15, 35, 25, 25, 15, 5.	B1 cao
Q16	(b)	Frequencies changed to 5, 15, 35, 25, 25, 15, 5. Grid enlarged. Both axes 3 cm for 20 with an intermediate line. Label for horizontal axis left aligned. Label for vertical axis placed above the axis. Right axis is labelled.	M1 ft from their table for at least 5 points plotted correctly at the ends of the intervals provided table values are cumulative, condoning one arithmetic error, or if the shape of the graph is correct for 5 or 6 points plotted not at the ends but consistently within each interval and joined A1 cao for correct graph with points joined by curve or straight line segments
Q16	(c)	Frequencies changed to 5, 15, 35, 25, 25, 15, 5.	B1 for 47 to 49 or ft their cf graph at cf = 50
Q16	(d)	Frequencies changed to 5, 15, 35, 25, 25, 15, 5. 63 minutes changed to 65.	M1 for reading a value from their cf graph at time = 63 (85 to 90) A1 for answer in the range 10 to 15 or ft from their graph
Q17		Diagram enlarged.	M1 for a method to find the exterior angle of a pentagon eg. $360 \div 5$ (=72) or the interior angle of a pentagon, eg. $180 - 360 \div 5$ (= 108) A1 for 72 or 108 M1 (dep M1) for a fully complete method to find the required angle, *DCF* A1 for 18 or ft their interior or exterior angle

PAPER: 1MA0_1H			
Question		**Modification**	**Notes**
Q18		Grid enlarged.	M1 for the graph of $x + y = 7$ or $y = 2x$ drawn M1 for the graphs of $x + y = 7$, $y = 2x$ and $y = 3$ drawn M1 for any correct shading (in or out), satisfying at least two correct inequalities where the shading must extend from the appropriate lines. A1 for correct region identified by either shading in, or shading out; the letter R is not required. Accept without shading only with the correct region indicated by R. NB accept lines that are solid or dotted/dashed etc or lines defined by unambiguous shading
Q20		MLP only: a changed to m.	M1 for multiplying both sides by $4 – m$ as the first step M1 (dep) for isolating their two terms in m M1 (dep) for factorising their two term expression in m A1 for $m = \frac{4p-5}{3+p}$ or $m = \frac{5-4p}{-p-3}$
Q23		Model provided for all candidates. Diagram also for MLP.	M1 for correct substitution into a volume formula for a cylinder or a cone, eg. $\frac{1}{3}\times\pi\times3^2\times4$ (= 12π) or $\pi\times3^2\times(6-4)$ (= 18π) or $\pi\times3^2\times h$ (= 9πh) or $\pi\times3^2\times(h-2)$ M1 for method to find volume after 5 hours, eg. "12π" + "18π" (= 30π) M1 (dep on M1) for use of a correct ratio, eg. "30π" × $\frac{9}{5}$ (= 54π) or "30π" × $\frac{4}{5}$ (= 24π) M1 for deriving an equation in h, eg. "54π" = "9πh" + "12π" A1 for $\frac{14}{3}$ or equivalent fraction

PAPER: 1MA0_1H			
Question		**Modification**	**Notes**
Q24	(a) (i)	Diagram enlarged. Cross changed to filled in circle.	B1 cao
Q24	(a)(ii)	Diagram enlarged. Cross changed to filled in circle.	B1 cao
Q24	(a)(iii)	Diagram enlarged. Cross changed to filled in circle.	B1 cao
Q24	(b)	Diagram enlarged. Cross changed to filled in circle.	B1 for a correct transformation, eg. translation of $\begin{pmatrix} 0 \\ -4 \end{pmatrix}$ or translation of 4 units in the negative y-direction, oe.

21	(a)		Correct graph	2	M1 for any translation along x axis A1 correct position
	(b)		$y = -g(x)$	1	B1 for $y = -g(x)$ oe from correct interpretation of diagram

5MB3H/01 June 2015

22	(a)		(0, 1)	1	B1 cao
	(b)	P(−1, 0), Q(1, 0)	2	2	M1 for "a" – "$-a$" or (x =) –1 or (x =) 1 or "8" ÷ 4 A1 cao

Modifications to the mark scheme for Modified Large Print (MLP) papers.

Only mark scheme amendments are shown where the enlargement or modification of the paper requires a change in the mark scheme.

The following tolerances should be accepted on marking MLP papers, unless otherwise stated below:
Angles: ±5°
Measurements of length: ±5 mm

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q02		Harbour to Lighthouse = 10 cm. Harbour and Lighthouse are joined with a dashed line. North line extended.	
Q04	(a)	Grid enlarged.	
Q04	(b)	Question reversed. Triangle W given on grid. Candidates asked to describe the transformation of triangle T to triangle W.	
Q06		AB = 8 cm.	
Q08		Model provided for all candidates. MLP also given an enlarged diagram.	
Q09	(a)	Wording added above the table. There are four spaces to fill.	
Q09	(b)	Grid enlarged.	
Q11	(a)	Diagram enlarged.	

PAPER: 5MB3H_01			
Question		**Modification**	**Notes**
Q14		All candidates, a changed to n.	
Q15		Diagram enlarged.	
Q16		MLP only: x changed to y.	
Q17		Diagram enlarged. Wording added: “Angle BAP is marked x.”	
Q21		Diagram enlarged. Wording added: “BA = 5 cm. AQ = 6 cm. Angle PBQ = $30°$.	
Q22		Diagram enlarged.	

Question	Answer	Mark	Mark scheme	Additional guidance
18 (a)	sketch	B1	for appropriate sketch which crosses the x axis at (2,0) and (4,0), minimum point at (3,−1) and end points at (1,3) and (5,3)	Allow some tolerance on the points if the intention is clear.
(b)	$y = g(-x)$	B1	cao	

Question	Answer	Mark	Mark scheme	Additional guidance
15	(−7, −1)	M1	for a method which shows understanding of the type of transformation eg reflection in the y axis or translation $\begin{pmatrix}0\\-3\end{pmatrix}$ or "(0 units right and) 3 units down" **or** for x coordinate as −7 **or** y coordinate as −1	"Reflection" or "Translation" alone is insufficient. Note that the −7 or the −1 may appear in the working space, not necessarily in the final answer.
		A1	for (−7, −1)	

Question	Answer	Mark	Mark scheme	Additional guidance
20 (a)	graph	C2	for a translation of the graph by the vector $\begin{pmatrix}-1\\-3\end{pmatrix}$	Condone graph of $y = f(-x)$ also being drawn on the grid
		(C1	for a translation of the graph by the vector $\begin{pmatrix}-1\\b\end{pmatrix}$ where $b \neq -3$ or $\begin{pmatrix}a\\-3\end{pmatrix}$ where $a \neq -1$ **or** for a translation by the vector $\begin{pmatrix}-1\\-3\end{pmatrix}$ of 3 or 4 critical points)	Correct vector gets 1 mark
(b)	2, 1	B1	cao	

Paper: 1MA1/2H

Question	Answer	Mark	Mark scheme	Additional guidance
21 (a)	Graph drawn	C2	for graph reflected in the y-axis	Key points: (0, 0), (1, 2), (2, 1), (3, 0), (4, 2) Award C1 if line segments but goes through all key points
		(C1	for a graph reflected in the x-axis **or** for a correct graph through four of the five key points)	
(b)	$y = 5 + 2(x – 3) – (x – 3)^2$	C2	for $y = 5 + 2(x – 3) – (x – 3)^2$ oe eg $y = –x^2 + 8x – 10$, $y = –[(x–4)^2 –6]$	For either C mark accept equivalent expressions
		(C1	for $y = 5 + 2(x + 3) – (x + 3)^2$ **or** $y = 5 + 2(x – a) – (x – a)^2$, $a \neq 3$, $a \neq 0$) **or** $y = f(x – 3)$ **or** $y = (x – 4)^2 + 6$ **or** correct expression missing "$y =$"	If a correct answer for C2 is given and is then incorrectly simplified, award C1 a need not be positive

Paper: 1MA1/2H

18	(a)	37, 143, 397, 503	M1	for any two correct angles within the ranges below **or** for a correct method to find a solution beyond 360, eg. “angle read from 0 to 360” + 360	Accept given as coordinates for M1 only
			A1	for all 4 angles in the range, 35 to 40, 140 to 145, 395 to 400 and 500 to 505	
	(b)	$y = -\sin x^o$	B1	for any acceptable equations, eg. $y = -\sin x^o$ or $y = \sin(-x^o)$ or $-y = \sin x^o$ or $y = \cos(x^o + 360n + 90)$ or for any positive integer n, $y = \sin(x^o - (2n - 1)180)$ or $y = \cos(x^o + 360n)$	Quoted are just the more likely solutions but check all attempts Condone missing degrees sign
	(c)	graph	C1	for correct graph shown translated 2 in the positive x-direction	

Paper: 1MA1/2H

Paper: 1MA1/2H

Question	Answer	Mark	Mark scheme	Additional guidance
21 (a)	Sketch	B1	for an appropriate sketch, ie reflection in y axis	Must go through $(-2, -4)$ $(0, 0)$ $(1, 1)$ $(3, 0)$ $(5, 4)$
(b)	$\tan(x + 270)° - 5$	M1	for describing one part of the translation, eg $360 - 90$ $(= 270)$ or $\tan(x + 270)$ **or** $(y =) \tan(kx + a) - 5$ where k and a are numbers and $k \neq 0$	
		A1	cao	Condone missing degree symbol

23	(a)	Sketch	B1	for appropriate sketch which crosses the x axis at (–3, 0), (–1, 0), (0, 0) and passes through (–2, 2) with end points in the correct square	Allow some tolerance on the points and in drawing the curve if the intention is clear
	(b)	$y = -g(x)$	B1	oe	Accept $-y = g(x)$

Paper: 1MA1/3H

21	(a)	Sketch graph	B1	cao	Allow freehand sketch provided intention is clear. (–3, –4), (–2, –3), (–1, –3), (0, –4)
	(b)	Sketch graph	B1	cao	Allow freehand sketch provided intention is clear. (0, 0), (1, 1), (2, 1), (3, 0)

Paper: 1MA1/2H

Question	Answer	Mark	Mark scheme	Additional guidance
20 (a)	(4, 6)	B1	cao	
(b)	Sketch	B2	for a fully correct sketch including points (2, 6), (–2, –4), (6, –4)	see end of mark scheme
		(B1	for a correct sketch of f(–x) **or** f(x) + 3 including the maximum point and the endpoints)	

Question	Answer	Mark	Mark scheme	Additional guidance
21 (a)	Sketch	B1	for an appropriate sketch, ie reflection in x axis	Allow some tolerance on the points and in drawing the function if the intention is clear
(b)	(90, 3)	M1	for coordinates of $p = (270, -1)$	May see 270 and –1 marked in the correct positions on the axes
		M1	for describing part of the translation, eg "270" – 180, or "−1" + 4 or $[x_p] - 180$, or $[y_p] + 4$ **or** for an answer of (90, b) or an answer of (a, 3)	$[x_p]$, $[y_p]$ must be a numerical value and clearly identified as point P by labelling or on the diagram with no contradiction
		A1	cao	

GCSE

Mark Scheme

Mathematics A (1387)

June 2003

Edexcel
Success through qualifications

Edexcel is one of the leading examining and awarding bodies in the UK and throughout the world. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers.

Through a network of UK and overseas offices, Edexcel's centres receive the support they need to help them deliver their education and training programmes to learners.

For further information please call our Customer Response Centre on 0870 240 9800, or visit our website at www.edexcel.org.uk.

June 2003

Publications Code UG014129

All the material in this publication is copyright
© London Qualifications Ltd 2003

CONTENTS

Notes on Marking Principles 2
Paper 5501 4
Paper 5502 11
Paper 5503 17
Paper 5504 24
Paper 5505 32
Paper 5506 40

NOTES ON MARKING PRINCIPLES

NOTES ON MARKING PRINCIPLES

1 Three types of mark are available

M marks - awarded for correct working seen or implied.
A marks - conditional accuracy marks which are awarded for accurate working following the award of M marks.
B marks - unconditional accuracy marks (independent of M).

2 Abbreviations

cao - correct answer only.
ft - follow through.
√ - Denotes a "follow through" answer.

SC - special case.
isw - ignore subsequent working.
oe - or equivalent (and appropriate).
NB: a candidate cannot benefit from both isw and ft.

3 If no working shown, then

correct answers normally score full marks
incorrect (even though nearly correct) answers score no marks.

4 Marking instructions

Misread loses A marks (and sometimes B marks) on that part but ft can be allowed on subsequent parts. M marks can still be earned. If in doubt contact your team leader.
If there is a wrong answer in the answer space DO CHECK the working in the body of the script.

- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.
- If there is a wrong answer in the answer space DO CHECK the working in the body of the script.
- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.

5 Style of marking

Answer correct: tick and write part mark in margin NEXT TO BRACKETED MARK.
Answer incorrect: cross, but show M, A or B marks if any earned in body of script and transfer the total of these to the margin next to the bracket mark.
Total for each double page at bottom right page (except for back if used), FINAL TOTAL IN RELEVANT BOX ON FRONT COVER.
Nought in margin for fully incorrect question or page AND FOR NO ATTEMPT.
Where no attempt has been made a line should be put in the answer space and zero in the margin next to the bracketed mark
CHOICE OF METHOD – No marks unless one answer is in answer space – then mark that.
CROSSED OUT WORK - if not replaced this should be marked (if legible).
There must always be a mark next to bracketed mark in the margin/

6 Follow Through Marks

Follow throughs are guided by two principles:

(a) Follow throughs which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous, do not award.
(b) Follow throughs which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

7 Probability

Probability answers must be given as fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least two decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.

8 Linear Equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

9 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

Paper 5501

No	Working	Answer	Mark	Notes
1 (a)		46	1	B1 cao
(b)		3.4	1	B1 oe
(c)		Arrow at 430	1	B1 allow ± half graduation
(d)		Arrow at 3.7	1	B1 allow ± half graduation Accept indications other than arrows as long as they are clear
2		1.60 2.05	2	B1) Condone B1) reversal
3 (a)	$\frac{18}{24}$ or $\frac{9}{12}$ or $\frac{6}{8}$	$\frac{3}{4}$	2	B2 for $\frac{3}{4}$ cao (B1 for $\frac{18}{24}$ or $\frac{9}{12}$ or $\frac{6}{8}$) SC B1 for $\frac{1}{4}$ only
(b)		16 squares shaded	1	B1 cao
4 (a)		line	1	B1 within overlay tolerance
(b)		midpoint	1	B1 within overlay tolerance ft from (a) ± 0.2cm
(c)		rectangle	1	B1 for rectangle 6 cm ± 0.2cm by 4 cm ± 0.2cm
5		kilograms, kg litre, *l* or cubic metres, m^3 inches, in	3	B1 B1 B1
6 (a)		parallel lines marked	1	B1
(b)		right angle marked	1	B1
(c)(i)		acute	1	B1
(ii)		reflex	1	B1

Paper 5501

No	Working	Answer	Mark	Notes
7 (i)		sphere	1	B1
(ii)		cylinder	1	B1 Accept circular prism
(iii)		pyramid	1	B1 Condone omission of "triangular" Accept tetrahedron
8 (a)(i)		40	2	B1 cao
(ii)		50		B1 cao
(b)		5 complete symbols	1	B1 cao
(c)		 and oe inc	1	B1
9 (i)		9, 37, 56, 59, 75	5	B1 cao
(ii)		0.067, 0.56, 0.6, 0.605, 0.65		B1 cao Ignore trailing zeros
(iii)		–10, –6, –4, 2, 5		B1 cao
(iv)		$\frac{2}{5}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$		B2 for all 4 correct (B1 for any 3 in correct order) SC B1 for all 4 in reverse order (applies to(iv) only)
10 (a)			1	B1
(b)		Plotting (4, 24)	1	B1 ft from their matchsticks
(c)		60	1	B1 cao
(d)		$m = 6n$	2	B2 for $m = 6n$ oe (B1 for $6n$ oe or m = multiple of n except $m = n$)
11 (i)		6, 12	4	B1 cao
(ii)		4, 16		B1 cao
(iii)		3, 4, 6 or 3, 4, 6, 12		B1 Condone omission of 12
(iv)		8, 27		B1 cao

Paper 5501

No	Working	Answer	Mark	Notes
12		2.43	4	B1 for 36 or 0.36 B1 for 96 or 0.96 B1 for 125 or 1.25 If none of first 3 B1s awarded then SC B1 for four 24s and five 25s seen OR 4 × 24 and 5 × 25 seen B1 for 2.43 cao
13 (a)(i)		Edinburgh and Plymouth	3	B1 for Edinburgh or −7 B1 for Plymouth or 5
(ii)		12		B1ft from (i) if one positive and one negative
(b)		Cardiff and Belfast London and Plymouth	2	B1 for Cardiff and Belfast OR −6 and −4 B1 for London and Plymouth OR 3 and 5
14		5 9 8	3	B1 cao B1 cao B1 cao
15 (a)			2	✓ / × / 2 / 0 / B2 1 / 0 / B1 1 / 1 / B1 2 / 1 / B1
(b)	$2\times2\times2$	8	2	M1 for $2\times2\times2$ A1 for 8 cao
16 (a)		30	1	B1 cao
(b)		3	1	B1 cao
(c)	$2 \times 29 = 58$ $5 \times 30 = 150$ $2 \times 31 = 62$ $1\times32 = 32$ $\frac{302}{10} = 30.2$	30.2	3	M1 for freq × no pins M1 (dep on 1st M1) for totalling and ÷ 10 A1 for 30.2 cao

Paper 5501

No	Working	Answer	Mark	Notes
17		7 5 5 13 33 52 23	3	B3 all correct (B2 for 4, 5 or 6 correct B1 for 2 or 3 correct)
18 (a)(i) (ii) (iii) (iv) (b)		$4c$ p^4 $8g$ $10pr$ OR $10rp$ $10y - 15$	4 1	B1 oe B1 cao B1 oe B1 B1 cao Accept $10y + -15$
19		$\frac{2}{3}$	3	M1 for 3 rows (9 squares) shaded M1 for 2 columns (10 squares) shaded A1 for $\frac{2}{3}$
	$\frac{3}{5} = \frac{9}{15}$ $\frac{2}{3} = \frac{10}{15}$	$\frac{2}{3}$	3	M1 for $\frac{3}{5} = \frac{9}{15}$ M1 for $\frac{2}{3} = \frac{10}{15}$ A1 for $\frac{2}{3}$
	$\frac{3}{5} = 0.6$ $\frac{2}{3} = 0.66$ or 0.67 or better	$\frac{2}{3}$	3	M1 for $\frac{3}{5} = 0.6$) Accept M1 for $\frac{2}{3} = 0.66$ or 0.67 or better) percentages A1 for $\frac{2}{3}$

Paper 5501

No	Working	Answer	Mark	Notes
20 (a)	955 × 48 7640 38200 45840 OR 48 × 955 240 2400 43200 45840	458.40	3	M1 for complete correct method (condone one computational error) A2 for 458.40 cao (A1 for digits 4584 OR ft if M1 awarded)
(b)	14. 5 48 | 696. 0 48 216 192 24 0 24 0	14.50	3	M1 for 1 as first digit in answer and remainder 21 M1 (dep) 4 as second digit in answer A1 for 14.50 (Accept 14.5)
21 (a)		$12x$	1	B1 oe
(b)		$12x + 10y$	2	B2 oe ft from (a) (B1 $12x$ + multiple of y or $10y$ seen) SC B1 for $x = 12x + 10y$ OR $y = 12x + 10y$

Paper 5501

No	Working	Answer	Mark	Notes
22	$\frac{1}{3}+\frac{1}{4}=\frac{4}{12}+\frac{3}{12}=\frac{7}{12}$ $1-\frac{7}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	M1 for $\frac{4}{12}$ **and** $\frac{3}{12}$ oe A2 for $\frac{5}{12}$ oe (A1 for $\frac{7}{12}$) B1 for 1–"$\left(\frac{1}{3}+\frac{1}{4}\right)$" correctly evaluated
	$1-\frac{1}{3}=\frac{2}{3}$, $1-\frac{1}{4}=\frac{3}{4}$ $\frac{8}{12}-\frac{3}{12}=\frac{5}{12}$ or $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	B1 for $\frac{2}{3}$ or $\frac{3}{4}$ seen M1 for $\frac{8}{12}-\frac{3}{12}=\frac{5}{12}$ or $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}$ A1 for $\frac{5}{12}$ oe
		$\frac{5}{12}$	3	M1 for 0.25 and 0.33 or better A1 for 0.58 or better A1 for $0.41\dot{6}$ or recurring
23 (a) (b)(i) (ii)	 180 – (54 + 54)	54 72 Reason	1 3	B1 cao M1 for 180 – (54 + 54) A1 ft from (a) if $x < 90$ B1 for mentioning isosceles and equal or base angles or equal sides and equal or base angles

Paper 5501

No	Working	Answer	Mark	Notes
24 (a)		Bryani	2	M1 for 4×9 or $4 \times 3 \times 3$ or $4 \times x \times x$ or square x first or square 3 first A1 SC 4×3^2 with Bryani scores B2
(b)		64	1	B1 cao
25 (a)		 dotted line may be solid	3	B2 for rectangle base 3 squares and height 4 squares (B1 for rectangle with one correct dimension) B1 for horizontal line 1 cm from top) SC B2 for completely correct elevation on its side
(b)			2	B2 for perspective drawing showing slant face and cutout B1 for perspective drawing with either slant face cutout omitted
26 (a)	20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$	40	2	M1 for 20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$ A1 cao
(b)	$\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes	line from (45, 20) to (65, 0)	2	M1 for $\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen A1 for correct line SC If M0, B1 for line from (45, 20) to (t, 0) where $t > 45$ or B1 for a line of the correct gradient.

Paper 5502

No	Working	Answer	Mark	Notes
1 (a)		$\frac{7}{100}$	1	B1 cao accept 0.07
(b)		0.18	1	B1 cao
(c)	20 in 100 oe	40	2	M1 for sight of 20 in 100 or 20 × 2 A1 cao
2 (a)		6cm	2	B1 for 6 ± 0.2 or 60 ± 2 B1 indep for cm or mm consistent with 1st B1
(b)		At centre	1	B1 within overlay
(c)		Circle drawn	1	B1 all within overlay
3		See diagram	3	B3 all correct – see separate sheet (B2 for 3 correct B1 for 2 correct)
4 (a)		$\frac{1}{4}$ oe	1	B1 cao
(b)		0.75	1	B1 cao
(c)		75%	1	B1 cao
(d)(i)		9	2	B1 accept answer in range 9 - 9.2
(ii)		15 - 16		B1 accept answers in range15 - 16
5 (a)		9:30	1	B1 cao
(b)		2hrs 45 min	2	B2 for 2hr 45 min or 2 $\frac{3}{4}$ hr or 165 minutes B1 2:45 or 2.45 or 165 or 45min + 1hr + 1hr oe
(c)		17	1	B1 cao
6 (a)	96 × 4	3.84	2	M1 for 96 × 4 or digits 384 A1 cao
(b)	3 × 96 + 40 = 328	(0).56	2	M1 for 3 × 96 + 40 or digits 328 or digits 56 A1 cao accept 56p

Paper 5502

No	Working	Answer	Mark	Notes
7 (a)		54 000	1	B1 cao accept 54 thousand
(b)		50 000	1	B1 (accept ten thousand or 10 000) oe
8 (a)		14	1	B1 cao
(b)		6	1	B1 cao
(c)		Correct reflection	2	B2 fully correct (B1 correct reflection in a line parallel to the mirror line or condoning 1 block error in shape or position of shape)
9 (a)		Missing horiz label 1 (and 6) missing on vertical scale	2	B1 B1
(b)		Correct graph	2	B1 for bar up to 4 for yellow B1 for bar up to 2 for green
(c)		Blue	1	B1 cao
(d)	3 + 5 + 4 + 2	14	1	B1 ft from (b)
(e)		$\frac{3}{14}$	1	B1 ft on '14'
10	Barry (8) because you double Kath (7) because you add, 1,2,3		2	B1 oe B1 oe SC: B1 for correct rules only
11 (a)		$2n$	1	B1 for $2n$ or $n + n$ OR $2 \times n$ OR $n \times 2$ OR $n2$
(b)		$2n + 15$	1	B1 for "$2n$" + 15 oe
(c)		20q	1	B1 cao
12 (a)	1 + 3 + 5 + 8 + 5	22	2	M1 add frequencies A1 cao
(b)		No, is>no of cups of coffee in the table	1	B1 'average cannot be bigger than 6' oe OR 'Average must be less than 6 oe'
13 (a)		Trapezium	1	B1 cao ignore spelling
(b)		(2, 3)	1	B1 cao
(c)		Isosceles	1	B1 cao ignore spelling
(d)		Q correct	1	B1 cao

Paper 5502

No	Working	Answer	Mark	Notes
14 (a)		250 000	1	B1 cao
(b)	$\frac{28}{4}$	7	2	M1 for $\frac{28}{4}$ oe or "250000" × 28 A1 cao **SC** B1 for 7 000 000
15 (a)		10	1	B1 cao
(b)		5.5	1	B1 ±0.3 pounds
(c)	$\frac{110}{22}$	50	3	M1 for use of graph at 11 or $\frac{110}{22}$ A1 for 5 A1 cao **SC** B2 for 49.5 – 50.6

Paper 5502

No	Working	Answer	Mark	Notes
16 (a)	$269.30 - 56.80 = 212.50$ $\frac{212.50}{42.50}$	6	2	M1 for $\frac{269.30 - 56.80}{42.50}$ or 5 seen A1 cao
(b)	5% of £269.30 £269.30 – "£13.465" OR $\frac{95}{100} \times 269.30$	255.83 or 255.84	3	M1 for $(5 \div 100) \times 269.30$ M1 for $269.30 - $ "13.465" A1 cao OR M2 for $\frac{95}{100} \times 269.30$ A1 cao **Alternative Method:** M1 for $\frac{5}{100} \times 56.80$ (= 2.84) and $\frac{5}{100} \times 42.50$ (=2.12(5)) (OR 53.96 AND 40.38 (40.375) seen M1 for $56.80 -$ "2.84" (= 53.96) $42.50 -$ "2.12(5)" (= 40.375 or 40.38) "5" × "40.375" + "53.96" A1 cao
17	$4.1^2 \times 1.07 = 16.81 \times 1.07$	17.9867	2	M1 for ("4.1") followed by squaring, or sight of 16.81 A1 cao SC: *B1 for 18 or better with no working*
18 (a)		60	1	B1 cao
(b)	$360 - 60 - 90 - 90$	120	2	M1 for $360 -$ " 60 " $- 90 - 90$ or $180 -$ "60" A1 cao
(c)	6×2	12	2	M1 for 6×2 A1 cao for 12

Paper 5502

No	Working	Answer	Mark	Notes
19 (a)(i)	$240 \times 5 = 1200$	1250	3	B1 cao 1250
(ii)	$\frac{50}{'1250'}$	$\frac{1}{25}$		M1 cao $\frac{50}{'1250'}$ A1 for $\frac{1}{25}$ in its simplest form
(b)	$\frac{60}{100} \times 1000 = 600$	12:5	3	M1 for $\frac{60}{100} \times 1000$ oe A1 for 600 A1 cao
20 (a)		$x + 2$	1	B1 accept $2 + x$ but not $x = x + 2$
(b)	$x + 5 + x + 5 + x + 2 + x + 2$	$4x + 14$	2	M1 adding 4 sides, two of which are '$x + 2$' (all sides to be linear expressions in x) **SC** $x + 5 + x + 2 \times 2$ gets M1 A1 for correct simplified answer or $(20 - 14) \div 4$ oe gets M1
(c)	'$4x + 14$' = 20	1.5 oe	2	M1 for equation A1 cao
21	$\sum f = 90$	Angles drawn, labelled	3	M1 for 1 person = 4°or one angle correct in table or pie chart A1 any 2 correctly drawn angles in pie chart A1 fully correct chart labelled
22 (a)		$2p - q$	2	B1 cao for $2p$ B1 cao for $-q$ accept $(-q + 2p)$, $2p - 1q$ and $2p + -q$
(b)	$5x = 3 + 4$	1.4	2	M1 for either (+3 or sight of 7) or (÷ 5 or sight of 0.8 and 0.6) A1 cao accept $\frac{7}{5}$ or $1\frac{2}{5}$

Paper 5502

No	Working	Answer	Mark	Notes
23 (a)		$\frac{4\times5}{2}$	1	B1 cao
(b)	$1+2+3+4+5+6+7+8$	$\frac{8\times9}{2}$	1	B1 cao
(c)	$\frac{100\times101}{2}$	5050	1	B1 cao
24	0 | 5 7 8 8 1 | 0 0 0 0 2 5 5 5 6 2 | 0 0 0 4 5 3 | 3 5 Key 1 | 2 = 12 (min)	See working	3	B1 for stem 0, 1, 2, 3 or 0, 10, 20, 30 B1 for accurate unordered leaves condone 1 error or omission B1 for key and ordered leaves all correct
25	$3.2\times2.8=8.96$ $2\times4.5\times2.8=25.2$ $2\times4.5\times28.8=28.8$ $\frac{62.96}{2.5}\times2.99$	£75.30	5	M1 for area of any face found correctly M1 for 2 areas found correctly A1 for 62.96 or 54 M1 for $\frac{'62.96'}{2.5}\times2.99$ Al cao Alternate method for candidates who round up $\frac{"62.92"}{2.5}$ M1 for "26" × 2.99 A1 for £77.74 cao **SC**: *for top included B2 for 71.92 m^2 seen or* B3 for £86.02 seen **SC** B4 for £64.58 or £65.78 seen
26	$2.5\times10\,000$	25 000	2	M1 for $2.5\times100\times100$ A1 cao

Paper 5503

No	Working	Answer	Mark	Notes
1 (a)(i)		$8g$	2	B1 oe
(ii)		$10rp$		B1 for $10pr$ or $10\ rp$
(b)		$10y - 15$	1	B1 cao accept $10y$ - + 15
(c)	$6x + 8 - 12x + 15$	$-6x + 23$	2	M1 for 3 correct terms out of 4 A1 cao
2		$m = 6n$	2	B2 for $m = 6n$ oe accept $6 \times n$, n 6 (B1 for $6n$ alone, or $6n$ +1 oe OR m = multiple of n except $m = n$)
3 (i)		0.067, 0.56, 0.6, 0.605, 0.65	1	B1 cao Ignore trailing zeros
(ii)		−10, −6, −4, 2, 5	1	B1 cao
(iii)		$\frac{2}{5}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$	2	B2 all four correct (B1 any three in correct order) SC: B1 all 4 in reverse order
4		7 5 5 13 33 52 23	3	B3 all correct (B2 for 4, 5 or 6 correct entries) (B1 for 2, 3 correct entries)

Paper 5503

No	Working	Answer	Mark	Notes
5		$\frac{2}{3}$	3	M1 for 3 rows (9 squares) shaded M1 for 2 columns (10 squares) shaded A1
	OR $\frac{3}{5}=\frac{9}{15}$ $\frac{2}{3}=\frac{10}{15}$ Therefore $\frac{2}{3}>\frac{3}{5}$	$\frac{2}{3}$		M1 for $\frac{3}{5}=\frac{9}{15}$ M1 for $\frac{2}{3}=\frac{10}{15}$ A1
	OR $\frac{3}{5}=0.6$ or percent $\frac{2}{3}=0.66$ or 0.67 or better Therefore $\frac{2}{3}>\frac{3}{5}$	$\frac{2}{3}$		M1 for $\frac{3}{5}=0.6$ or percent M1 for $\frac{2}{3}=0.66$ or 0.67 or better A1
6	$2\times 29=58$ $5\times 30=150$ $2\times 31=62$ $1\times 32=32$ $\frac{302}{10}=30.2$	30.2	3	M1 for freq × no. pins (at least 3) M1 for totalling and for ÷ 10 (dep on 1st M1) A1 cao
7 (a)			2	B1 for 180° rotation (wrong centre) B1 cao
(b)			3	B1 for any enlargement sf other than 1 B1 for all sides halved B1 for position

Paper 5503

No	Working	Answer	Mark	Notes
8 (a)		$12x$	1	B1 oe
(b)		$12x + 10y$	2	B2 oe or ft from (a) (B1 for $12x$ + a multiple of y or $10y$ seen) **SC** B1 for $x = 12x + 10y$ or $y = 12x + 10y$
9	$\frac{1}{3}+\frac{1}{4}=\frac{4}{12}+\frac{3}{12}=\frac{7}{12}$ $1-\frac{7}{12}=\frac{5}{12}$ OR $1-\frac{1}{3}=\frac{2}{3}, 1-\frac{1}{4}=\frac{3}{4}$ $\frac{9}{12}-\frac{4}{12}=\frac{5}{12}, \frac{8}{12}-\frac{3}{12}=\frac{5}{12}$	$\frac{5}{12}$	3	M1 for $\frac{4}{12}$ and $\frac{3}{12}$ oe A2 for $\frac{5}{12}$ oe (A1 for getting $\frac{7}{12}$) (B1 for $1 - \frac{"1"}{3} + \frac{1"}{4}$ correctly evaluated) OR B1 for $\frac{2}{3}$ or $\frac{3}{4}$ seen M1 for $\frac{3}{4}-\frac{1}{3}=\frac{9}{12}-\frac{4}{12}$ or $\frac{2}{3}-\frac{1}{4}=\frac{8}{12}-\frac{3}{12}$ A1 for $\frac{5}{12}$ oe OR M1 0.25 and 0.33 or better A1 for 0.58 or better A1 for 0.416 *recurring*
10 (a)		54	1	B1 cao
(b)(i)	180 – (54 +54)	72	3	M1 for 180 – (“54” + “54”) A1 for 72° ft from (a) if $x < 90°$
(ii)				B1 for mentioning isosceles and equal or base angles or equal sides and equal or base angles

Paper 5503

No	Working	Answer	Mark	Notes
11 (a)	Bryani was correct $4 \times 3^2 = 4 \times 9 = 36$	Bryani	2	M1 for 4×9 or $4 \times 3 \times 3$ or "square the three/x then multiply by four" A1 Bryani **SC** 4×3^2 with Bryani gets B2
(b)			1	B1 cao
12 (a)			3	B2 for rectangle height 4 squares, base 3 squares (B1 for rectangle with one correct dimension) B1for line 1 square from the top **SC** B2 for completely correct elevation on its side
(b)			2	B2 for perspective drawing showing slant face and cut out (B1 for perspective drawing with either slant face or cut out omitted or one aspect incorrect)
13 (a)	20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$	40	2	M1 for 20×2 or $\frac{20}{30} \times 60$ or $20 \div \frac{1}{2}$ A1 cao
(b)	$\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen	Line from (45, 20) to (65, 0)	2	M1 for $\frac{20}{60}$ or $\frac{1}{3}$ or 20 minutes seen A1 for correct line **SC** If M0, B1 for line from (45, 20) to (t, 0) where $t > 45$ or a line of the correct gradient
14 (i)		119.31	3	B1 cao
(ii)		119 310		B1 cao
(iii)		1.23		B1 cao

Paper 5503

No	Working	Answer	Mark	Notes
15	$\frac{10}{100}\times 12000$ 12 000 – 1200 = 10 800 $\frac{10800}{10}=1080$ 10 800 – 1080 = £9720	£9720	3	M1 for $\frac{10}{100}\times 12000$ or sight of 1200 or 2400 or 10 800 or 9600 M1 (dep) for $\frac{10}{100}\times(12\,000-\frac{10}{100}\times 12000)$ or sight of 1080 A1 cao Alternative mark scheme M2 for $12000\times(1-\frac{10}{100})^2$ (M1 for $12000\times(1-\frac{10}{100})$ A1 cao
16 (a)	$2p = 6$	$p = 3$	2	M1 for $7p - 5p = 8 - 2$ or $2p$ or 6 A1 cao
(b)	$7r - 5r = -20 - 2$	–11	2	M1 for $7r + 2 = 5r - 20$ or $\frac{7r}{5}+\frac{2}{5}=r-4$ or $7r-5r=20-2$ or $\frac{7r}{5}-r=-4-\frac{2}{5}$ A1 cao
17		$5n + 1$	2	B2 oe (B1 for $5n$ seen) NB: n = gets B1 max

Paper 5503

No	Working	Answer	Mark	Notes
18 (a)	–1, 0, 1		2	B2 for –1, 0, 1 (B1 for –1, 0 or 0,1 or –1,1 or –2, -1, 0, 1 only)
(b)	(–1, –1), (0, –1), (1, –1), (0, 0), (1, 0), (1, 1)		3	B3 for 6 points correct B2 for 3 points correct B1 for 1 point correct **NB** –B1 each additional point over six
19 (a)	Triangle with vertices at (0,0) (0,–2) and (3,0)		2	M1 for correct orientation A1 cao
(b)	Rotation, 180°, centre (0,1) Enlargement sf - 1 centre (0,1)		2	B2 for 180° 'rotation' centre (0, 1) B2 for Enlargement sf - 1 centre (0,1) (B1 for any two of the three parts) NB: B0 if additional transformation is included
20	Bisector of $\angle BAC$ Arc around A Region		3	B3 cao (B2 for either two correct boundaries, no shading/ wrong shading or one correct boundary, one incorrect boundary with valid shading) (B1 for either two incorrect boundaries but one drawn from A and one intersection, with valid shading or one correct boundary) Ignore shading outside the triangle
21		Length Volume Area	3	B1 for Length B1 for Volume B1 for Area
22 (a)	Unbiased question with choices		2	B1 for unbiased question B1 for at least 2 choices
(b)			2	Classification 1: A biased question Classification 2: A restricted sample of people Classification 3: Not specifying a range of foods Classification 4: Nothing to do with eating habits B2 reasons which satisfy 2 different classifications (B1 a reason which satisfies one classification)



Paper 5503

No	Working	Answer	Mark	Notes
23 (a)	$6 \times 10^2 \times 8 \times 10^4$ 48×10^6	4.8×10^7	3	M1 for $6 \times 10^a \times 8 \times 10^b$ oe, a and b integers including 0 A1 for 48×10^6 oe A1 cao
(b)	200 000 + 30 000	230000	2	B2 cao (B1 for sight of 200 000 or 30 000 or 2.3×10^5 or 23×10^4)
24 (i)		64	4	B1 cao
(ii)		3		B1 cao
(iii)	$\sqrt{16 \times 9} = \sqrt{144}$	12		B2 cao (B1 for sight of $\sqrt{2^4} \times \sqrt{9}$ or better, or 144 seen)
25 (i)	Tangent 90° to diameter /radius/ line from (through) centre	27°	4	B1 for 27° cao B1 for reason
(ii)	180 –(90+ "27") angle in semicircle (is 90°)/Alternate segments /angle at centre twice at circumference	63°		B1 ft for 90–"27" if not 63° B1 for reason
26 (a)(i)		152	2	B1 cao
(ii)		177		B1 cao
(b)			3	B1 for median marked at 167 B1 ft for postion of box with its ends at "152" and "177" B1 for position of whiskers with ends at 132 and 182 NB: For any points plotted between 141 and 149 give a tolerance of an extra ± 1 square
27	$x^2 + xy + xy + y^2$	$x^2 + 2xy + y^2$	2	M1 for at least 3 of the 4 terms correct A1 cao
		25	2	M1 for recognising 3.47 + 1.53 (= 5) A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
1 (a)	$4.1^2 \times 1.07 = 16.81 \times 1.07$	17.9867	2	M1 for (4.1) followed by squaring, or sight of 16.81 A1 cao SC: B1 for 18 or better with no working
(b)		$(1.6 + 3.8 \times 2.4) \times 4.2$	1	B1 cao Allow additional brackets if they give an expression with value 45.024
2 (a)	$269.30 - 56.80 = 212.50$	6	2	M1 for $\frac{269.30 - 56.80}{42.50}$ or 5 seen A1 cao
(b)	5% of £269.30 £269.30 – "£13.465" OR $\frac{95}{100} \times 269.30$	255.83 or 255.84	3	M1 for $(5 \div 100) \times 269.30$ M1 (dep) for 269.30 – "13.465" A1 cao OR M2 for $\frac{95}{100} \times 269.30$ A1 cao **Alternative Method:** M1 for $\frac{5}{100} \times 56.80$ (= 2.84) and $\frac{5}{100} \times 42.50$ (=2.12(5)) (OR 53.96 AND 40.38 (40.375) seen M1 for 56.80 – "2.84" (= 53.96) 42.50 – "2.12(5)" (= 40.375 or 40.38) "5" × "40.375" + "53.96" A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
3 (a)		60	1	B1 cao
(b)	360 – 60 – 90 – 90	120	2	M1 for 360 – "60" – 90 – 90 or 180 – "60" A1 cao
(c)	6 × 2	12	2	M1 for 6 × 2 A1 cao 12
(d)		Correct drawing	2	B2 for triangle and construction lines (see overlay) (B1 for 1 line of length 4cm and correct arcs crossing OR for correct triangle with either no arcs or incorrect arcs) SC: B1 similar triangle drawn with construction lines
4 a(i)	240 × 5 = 1200	1250	3	B1 cao 1250
(ii)	$\frac{50}{1250}$	$\frac{1}{25}$		M1 $\frac{50}{"1250"}$ A1 oe in its simplest form
(b)	$\frac{60}{100} \times 1000 = 600$ 600: 250	12:5	3	M1 for $\frac{60}{100} \times 1000$ oe A1 for 600 A1 cao
5 (a)		$x + 2$	1	B1
(b)	$x + 5 + x + 5 + x + 2 + x + 2$	$4x + 14$	2	M1 adding 4 sides, two of which must be '$x + 2$' (all sides to be linear expressions in x) A1 for correct simplified answer
(c)	"$4x + 14$" = 20	1.5	2	M1 for equation "$4x + 14$" = 20 OR $\frac{20-14}{4}$ oe A1 cao

Paper 5504

No	Working	Answer	Mark	Notes
6 (a)		$2p - q$	2	B1 cao for $2p$ B1 cao for $-q$ accept $-q + 2p$ and $2p - 1q$
(b)	$5x = 3 + 4$	1.4	2	M1 for either (+3 or sight of 7) or (÷ 5 or sight of 0.8 and 0.6) A1 cao accept $\frac{7}{5}$ or $1\frac{2}{5}$
7 (a)		$\frac{4\times5}{2}$	1	B1 cao
(b)	$1 + 2 + 3 + 4 + 5 + 6 + 7 + 8$	$\frac{8\times9}{2}$	1	B1 cao
(c)	$\frac{100\times101}{2}$	5050	1	B1 cao
(d)		$\frac{n(n+1)}{2}$	2	B2 cao (B1 for any quadratic in n)
8	$3.2 \times 2.8 = 8.96$ $2 \times 4.5 \times 2.8 = 25.2$ $2 \times 4.5 \times 3.2 = 28.8$ $\frac{62.96}{2.5} \times 2.99$	75.30	5	M1 for area of any face found correctly M1 for 2 areas seen A1 for 62.96 or 54 M1 for $\frac{'62.96'}{2.5} \times 2.99$ A1 cao Alternate method for candidates who round up $\frac{"62.96"}{2.5}$ M1 for "26" x 2.99 A1 for £77.74 cao SC: for top included B2 for 71.92 m^2 seen or B3 for £86.02 or £86.71 SC: B4 for £64.58 or £65.78 seen

Paper 5504

No	Working	Answer	Mark	Notes
9	2.5×10000	25000	2	M1 for 2.5×10000 or $2.5 \times 100 \times 100$ A1 cao
10 (a)	$\sum f = 90$ (88), 144, 32, 96	Angles drawn, labelled	3	M1 for 1 person = 4° or one angle correct in table or pie chart A1 any 2 angles correctly drawn in pie chart A1 fully correct chart labelled
(b)	$0.38 + 0.27 + 0.15$	0.20	2	M1 1 – sum A1 cao
11	0 | 5 7 8 8 1 | 0 0 0 0 2 5 5 5 6 2 | 0 0 0 4 5 3 | 3 5 Key 1 | 3 = 13 (min)	See working column	3	B1 for stem 0, 1, 2, 3 or 0, 10, 20, 30 B1 for accurate unordered leaves condone 1 error or omission B1 for key and ordered leaves all correct
12 (a)	$V = \pi \times 4^2 \times 10$	502 – 503	2	M1 for $\pi \times 4^2 \times 10$ A1 502 – 503
(b)	$P^2 = 10^2 + 8^2$ $P = \sqrt{164}$	$\sqrt{164} < 13$	3	M1 for sight of a correct right-angled triangle M1 for $10^2 + 8^2$ A1 for conclusion based on a correct calculation or 12.8 seen
13 (a)	2×30	$2 \times 2 \times 3 \times 5$	4	M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
	2×48	$2^5 \times 3$		M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
(b)		12	1	B1 cao
(c)	$2^5 \times 3 \times 5$	480	2	B2 cao B1 for $2^5 \times 3 \times 5$ or any correct common multiple

Paper 5504

No	Working	Answer	Mark	Notes
14 (a)		$150 < C \leq 200$	2	M1 use of cum freq to find the cost of the 20th or 20.5^{th} car OR $\frac{1}{2}\Sigma f$ or $\frac{1}{2}(\Sigma f + 1)$ A1 eg 150 to 200
(b)		No, because the 21st value is in the same interval	1	B1 20.5^{th} or 21st in same interval or an alternative correct explanation
(c)	80% = 5200 $\frac{5200}{80} \times 100$	6500	3	M1 for (100 – 20) % = 5200 M1 for $\frac{5200}{"80"} \times 100$ A1 cao
15 (a)	$x^2(x + 1) = 230$	AG	2	M1 for $x \times x \times (x+1)$ or $x \times x \times x + 1$ oe A1 cao from $x \times x \times (x+1)$
(b)	'5 – 150 5.1 – 158.7 5.2 – 167.6 5.3 – 177.0 5.4 – 186.6 5.5 – 196.6 5.6 – 207.0 5.7 – 217.7 5.8 – 228.8 5.9 –240.2 5.85 – 234.4	5.8	4	B 2 for trial between 5.8 and 5.9 inclusive (B1 for different trial between 5 and 6 inclusive) B1 for different trial between 5.8 and 5.85 (not including 5.8) B1 (dep on at least one previous B1) cao for 5.8, 5.81, 5.811

Paper 5504

No	Working	Answer	Mark	Notes
16	$\pi \times \left(\frac{15}{2}\right)^2 = 176.715$	88.4cm^2	3	M1 for $\pi \times \left(\frac{15}{2}\right)^2$ A1 88.3 – 88.4 B1(ind) for cm²
17 (a)	$5 = 0.5x + 1$	8	2	M1 for $5 = 0.5x + 1$ A1 cao
(b)		$y = \frac{1}{2}x + c$	1	B1 $y = \frac{1}{2}x + c$, c ≠ 1, oe
(c)		$x = 2y - 2$ OR $x = 2(y - 1)$	2	M1 for correctly multiplying both sides by 2 or correctly isolating $\frac{x}{2}$ A1 for $x = 2(y - 1)$, $x = \frac{y-1}{0.5}$, $x = \frac{y-1}{\frac{1}{2}}$ oe SC: B1 for $x = 2y - 1$
18	$4x - 6y = 22$ $15x + 6y = 54$ $19x = 76$	$x = 4,\ y = -1$	4	M1 for coefficients of x or y the same followed by correct operation , one arithmetical error A1 cao M1(dep on previous M mark) for sub for other variable A1 cao Trial and improvement –0 unless both x and y correct values found

Paper 5504

No	Working	Answer	Mark	Notes
19 (a)	$SF = \frac{10}{6}$ $\frac{10}{6} \times 4.8 = 8$	8	2	M1 for sight of $\frac{10}{6}$ or $\frac{6}{10}$ or 1.67 or better or $\frac{CD}{10} = \frac{4.8}{6}$ A1 cao
(b)	$\frac{10}{6} \times 4.5 - 4.5 = 3$	19.8	2	M1 for use of SF from (a) to find *BC* or *AC* and adding 4 sides A1 cao
20	$\frac{6 \times 10^{15}}{3.2 \times 10^{8}}$ 1.875×10^{7}	4.3×10^{3}	3	B3 for 4.3×10^{3} to 4.34×10^{3} (B2 for 1.875×10^{7} oe or 4300 to 4340 or final answer of 1.9×10^{7}) (B1 for sight of 6×10^{15} oe or 3.2×10^{8} oe)
21	$8.5 \times \tan 38 = 8.5 \times 0.7813$	6.64	3	M1 for correct use of trig, eg $\tan 38 = \frac{opp}{8.5}$ M1 for 8.5 × tan38 A1 6.64 – 6.641

Paper 5504

No	Working	Answer	Mark	Notes
22 (a)		No, as you would expect about 100. Yes, as it is possible to get 200 sixes with a fair dice	1	B1 for a consistent answer
(b)	$\frac{1}{6}, \frac{5}{6}$ + labels		3	B1 for $\frac{5}{6}$ on the red dice, *not six* branch B1 for a fully complete tree diagram with all branches labelled B1 for $\frac{1}{6}$, $\frac{5}{6}$ on all remaining branches as appropriate

Paper 5505

No	Working	Answer	Mark	Notes
1 (i) (ii) (iii)		119.31 119310 1.23	3	B1 cao B1 cao B1 cao
2	$\frac{10}{100}\times 12000 = 1200$ 12 000 – 1200 = 10 800 10 800 ÷ 10 =1080 10 800 – 1080 = £9720	9720	3	M1 for $\frac{10}{100}\times 12\,000$ or sight of 1200 or 2400 or 10 800 or 9600 M1 (dep) for $\frac{10}{100}\times(12\,000 - \frac{10}{100}\times 12\,000)$ or sight of 1080 A1 cao Alternative markscheme M2 for $12000\times\left(1-\frac{10}{100}\right)^2$ (M1 for $12000\times\left(1-\frac{10}{100}\right)$) A1 cao
3	$7r - 5r = -20 - 2$	–11	2	M1 for $7r + 2 = 5r - 20$ or $\frac{7r}{5} + \frac{2}{5} = r - 4$ or $7r - 5r = -20 - 2$ or $\frac{7r}{5} - r = -4 - \frac{2}{5}$ A1 cao

Paper 5505

No	Working	Answer	Mark	Notes
4 (a)		–1, 0, 1	2	B2 for –1, 0, 1 only (B1 for –1, 0 or 0,1 or –1, 1 or –2, -1, 0, 1 only)
(b)		(–1,–1)(0,–1) (1,–1) (0, 0) (1, 0) (1, 1)	3	B3 for 6 points correct (B2 for 3 points correct) (B1 for 1 point correct) *NB: –B1 for each additional point over six*
5		$5n + 1$	2	B2 oe (B1 for $5n$ seen) NB: n = gets B1 max
6 (a)	Triangle with vertices at (0,0) (0,–2) and (3,0)		2	M1 for correct orientation A1 cao
(b)	Rotation, 180°, centre (0,1) Enlargement sf –1 centre (0,1)		2	B2 for 180° 'rotation' centre (0, 1) or for Enlargement sf - 1 centre (0,1) (B1 for any two of the three parts) NB: B0 if additional transformation is included
7	Bisector of $\angle BAC$ Arc around A Region	See overlay	3	B3 cao (B2 for either two correct boundaries, no shading/ wrong shading or one correct boundary, one incorrect boundary with valid shading) (B1 for either two incorrect boundaries but one drawn from A and one intersection, with valid shading or one correct boundary) Ignore shading outside the triangle
8		Length Volume Area	3	B1 for Length B1 for Volume B1 for Area



Paper 5505

No		Working	Answer	Mark	Notes
9	(a)	Unbiased question with choices		2	B1 for unbiased question B1 for at least 2 choices
	(b)	Leading question and a restricted sample		2	Classification 1: A biased question Classification 2: A restricted sample of people Classification 3: Not specifying a range of foods Classification 4: Nothing to do with eating habits B2 reasons which satisfy 2 different classifications (B1 a reason which satisfies one classification)
10	(a)	$6 \times 10^2 \times 8 \times 10^4$ $48 \times 10^6 = 4.8 \times 10^7$	4.8×10^7	3	M1 for $6 \times 10^a \times 8 \times 10^b$ oe, a and b integers including 0 A1 for 48×10^6 oe A1 cao
	(b)	200 000 + 30 000 = 230 000	230 000	2	B2 cao (B1 for sight of 200 000 or 30 000 or 2.3×10^5 or 23×10^4)
11	(a)	$x^2 + xy + xy + y^2$	$x^2 + 2xy + y^2$	2	M1 for at least 3 of the 4 terms correct A1 cao
	(b)		25	2	M1 for recognising 3.47 + 1.53 (= 5) A1 cao
12	(i)	Tangent 90° to diameter /radius/ line from (through) centre	27°	4	B1 for 27° cao B1 for reason
	(ii)	180 –(90+ "27") angle in semicircle (is 90°)/Alternate segments /angle at centre twice at circumference	63°		B1 ft for 90–"27" if not 63° B1 for reason
13	(i)		p^9	1	B1 cao
	(ii)		$6q^6$	2	B2 for $6q^6$ (B1 for sight of $\frac{6q^9}{q^3}$ or $3q \times 2q^5$ or $3q^4 \times 2q^2$ or $6 \times q \times q \times q \times q \times q \times q$ or final answer of the form kq^6, $k > 0$)

Paper 5505

No	Working	Answer	Mark	Notes
14 (a)(i)		152	2	B1 cao
(ii)		177		B1 cao
(b)			3	B1 for median marked at 167 B1 ft for postion of box with its ends at "152" and "177" B1 for position of whiskers with ends at 132 and 182 NB: For any points plotted between 141 and 149 give a tolerance of an extra ± 1 square
15	(arc =) $\frac{40}{360} \times 2\pi \times 9$ $= 2\pi$	$2\pi + 18$	4	M1 for $\frac{40}{360} \times$ M1 for $2\pi \times 9$ M1 (dep) for $\frac{40}{360} \times 2\pi \times 9$ oe A1 for $\frac{18 \times \pi}{9} + 18$ oe exact form
16 (i)		1	1	B1 cao
(ii)		$\frac{1}{16}$	1	B1 cao accept 0.0625
(iii)		64	1	B1 cao condone ± 64

Paper 5505

No	Working	Answer	Mark	Notes
17 (a)	$F \propto 1/x^2$ $F = k/x^2$ $4 = k / 3^2$ $F = 36/x^2$	$F = \frac{36}{x^2}$	3	M1 for $F = k/x^2$ seen or implied. ($k \neq 1$) M1 (dep) for subst. or sight of $k = 36$ A1 for $F = 36/x^2$
(b)		9	1	B1 ft for 9 (ft on $F = kx^n$, $n \neq 0$)
(c)	$64 = \frac{36}{x^2}$ $x^2 = \frac{36}{64}$ $x = \pm\frac{3}{4}$	$\frac{6}{8}$	2	M1 for $x^2 = \frac{"36"}{64}$ A1 for $\frac{6}{8}$ oe (condone $\pm$) *SC: Use of $F = kx^2$ max M1 M1 A0 B1 ft M0 A0* *SC: Use of* $F = \frac{k}{\sqrt{x}}$ *max M1 M1 A0 B0 M1* ($\sqrt{x} = \frac{4\sqrt{3}}{64}$) *A0*
18	$(5+\sqrt{3})(5-\sqrt{3}) = 5\times5 - 5\sqrt{3} + 5\sqrt{3} - \sqrt{3}\sqrt{3}$ $= 5\times5 - 3$ $\frac{22}{\sqrt{22}} = \frac{22\sqrt{22}}{22}$	$\sqrt{22}$	3	B1 for correct expansion $25 - 5\sqrt{3} + 5\sqrt{3} - \sqrt{3}\ \sqrt{3}$ with 1st three terms reducing to 25 **without** any errors seen B1 (indep) for $\sqrt{3}\ \sqrt{3} = 3$ B1 for $\sqrt{22}$ coming from $\frac{22}{\sqrt{22}}$ (S.C $\frac{(5+\sqrt{3})(5-\sqrt{3})\sqrt{22}}{22}$ gets B1)

Paper 5505

No	Working	Answer	Mark	Notes
19 (a)		60 40	2	B1 cao B1 cao
(b)		correct bars	2	B1 for $30 < x \leq 40$ with an area of 2½ squares B1 for $40 < x \leq 70$ with an area of 3 squares *SC:* $\frac{0}{4}$ *give M1 if clearly using area or frequency density*
20 (a)	$6x + 8 - 12x + 15$	$-6x + 23$	2	M1 for 3 of the 4 terms $6x$, $+8$, $-12x$, $+15$ correct A1 cao
(b)		$32x^5y^{15}$	2	B2 cao (B1 for two of 32, x^5, y^{15})
(c)	$\frac{(n+1)(n-1)}{n+1} \times \frac{2}{n-2}$ $\frac{2(n-1)}{n-2}$	$\frac{2(n-1)}{n-2}$	3	M1 for $k(n + 1)(n - 1)$ M1 dep for $\frac{(n+1)(n-1)}{(n+1)} = n - 1$ A1 for $\frac{2(n-1)}{n-2}$
21	Vertices at $(-3, -1\frac{1}{2}), (-4\frac{1}{2}, -1\frac{1}{2}), (-3, -4\frac{1}{2})$		3	B1 for all sides $\times 1\frac{1}{2}$ B1 for correct orientation with 2 vertices almost correct B1 cao

Paper 5505

No	Working	Answer	Mark	Notes
22	Total = 3 + 5 + 2 (=10) $\frac{3}{10}\times\frac{3}{10}\times\frac{5}{10}\left(=\frac{45}{1000}\right), \frac{3}{10}\times\frac{3}{10}\times\frac{2}{10}\left(=\frac{18}{1000}\right)$ $\frac{5}{10}\times\frac{5}{10}\times\frac{3}{10}\left(=\frac{75}{1000}\right), \frac{5}{10}\times\frac{5}{10}\times\frac{2}{10}\left(=\frac{50}{1000}\right)$ $\frac{2}{10}\times\frac{2}{10}\times\frac{3}{10}\left(=\frac{12}{1000}\right), \frac{2}{10}\times\frac{2}{10}\times\frac{5}{10}\left(=\frac{20}{1000}\right)$ $3\times\left(\frac{"45"}{1000}+\frac{"18"}{1000}+\frac{"75"}{1000}+\frac{"50"}{1000}+\frac{"12"}{1000}+\frac{"20"}{1000}\right)$ $\frac{660}{1000}$	$\frac{660}{1000}$ oe	5	M3 for all six expressions seen OR their combined equivalents (M2 for four expressions seen OR their combined equivalents) (M1 for two expressions seen OR their combined equivalents) M1 sum of 18 relevant products condone 1 slip A1 for $\frac{660}{1000}$ oe *SC: without replacement maximum M4 A0* SC: Just 2 beads: Answer either $\frac{38}{100}$ oe OR $\frac{28}{90}$ oe B1

Paper 5505

No	Working	Answer	Mark	Notes
23 (a)(i)		$6\mathbf{b} - 6\mathbf{a}$	2	B1 for $6\mathbf{b} - 6\mathbf{a}$ oe
(ii)		$6\mathbf{a}$		B1 for $6\mathbf{a}$ oe
(b)	$\overrightarrow{EX} = \overrightarrow{EB} + \overrightarrow{BX}$ $= 12\mathbf{b} + \frac{1}{2}\overrightarrow{BC}$	$12\mathbf{b} - 3\mathbf{a}$	2	M1 for $\overrightarrow{EX} = \overrightarrow{EB} + \overrightarrow{BX}$ oe vector journey in a form ready for straightforward substitution A1 for $12\mathbf{b} - 3\mathbf{a}$ oe
(c)	$\overrightarrow{AY} = \frac{5}{3}\overrightarrow{AB}$ or $\overrightarrow{BY} = \frac{2}{3}\overrightarrow{AB}$ $\overrightarrow{EY} = 16\mathbf{b} - 4\mathbf{a}$ or $\overrightarrow{XY} = 4\mathbf{b} - \mathbf{a}$ $\overrightarrow{EY} = 4\overrightarrow{XY}$ or $\overrightarrow{EX} = 3\overrightarrow{XY}$ or $\overrightarrow{EY} = \frac{4}{3}\overrightarrow{EX}$	Printer Answer	3	B1 for either $\overrightarrow{AY} = \frac{5}{3}\overrightarrow{AB}$ or $\overrightarrow{BY} = \frac{2}{3}\overrightarrow{AB}$ oe B1 ft for either $\overrightarrow{EY} = 16\mathbf{b} - 4\mathbf{a}$ or $\overrightarrow{XY} = 4\mathbf{b} - \mathbf{a}$ ft only on parts (*a*) and (*b*) B1 for either $\overrightarrow{EY} = 4\overrightarrow{XY}$ or $\overrightarrow{EX} = 3\overrightarrow{XY}$ or $\overrightarrow{EY} = \frac{4}{3}\overrightarrow{EX}$ oe **plus** conclusion of *E*, *X*, *Y* on the same straight line
24 (a)(i)		$(5, -4)$	4	B1 cao
(ii)		$(2, -9)$		B1 cao
(iii)		$(2, 4)$		B1 cao
(iv)		$(1, -4)$		B1 cao
(b)		$(x-2)^2 - 4$	4	B4 for $(x-2)^2 - 4$ oe eg. $x^2 - 4x$ (B3 for $(x+2)^2 - 4$ or $(x-2)^2 + 4$) (B2 for $x^2 - 4$ or $(x-2)^2$ OR $x^2 + bx$, $b \neq 0$ OR $(x+2)^2 + 4$ OR $f(x-2) - 4$) (B1 for $x^2 + 4$ or $(x+2)^2$ or $ax^2 + bx$ or $x^2 + bx + c$ OR $x - 2 - 4$ or $x^2 - 2 - 4$, $a, b, c \neq 0$)

Paper 5506

No	Working	Answer	Mark	Notes
1 (a)	$V = \pi \times 4^2 \times 10$	502 – 503 cm^3	2	M1 for $\pi \times 4^2 \times 10$ A1 502 – 503
(b)	$P^2 = 10^2 + 8^2$ $P = \sqrt{164}$	$\sqrt{164} < 13$	3	M1 for sight of correct right angled triangle M1 for $10^2 + 8^2$ A1 for conclusion based on a correct calculation Or 12.8 seen
2 (a)(i)	2×30	$2 \times 2 \times 3 \times 5$	4	M1 for systematic method, eg division, factor trees (at least one prime) A1 cao
(ii)	2×48	$2^5 \times 3$		M1 for systematic method, division, factor trees (at least one prime) A1 cao
(b)		12	1	B1 cao
(c)	$2^5 \times 3 \times 5$	480	2	B2 cao B1 for $2^5 \times 3 \times 5$ or any correct common multiple

Paper 5506

No	Working	Answer	Mark	Notes
3 (a)		$150 < C \leq 200$	2	M1 use of cum freq to find the cost of the 20th or 20.5^{th} car OR $\frac{1}{2}\Sigma f$ th or $\frac{1}{2}(\Sigma f + 1)$ th car. A1 eg 150 to 200, 150 – 200
(b)		No, because the 21st value is in the same interval	1	B1 for 20.5^{th} or 21st value in the same internal consistent with 'a' OR Refers to the median value being low in the interval (statement to be mathematically correct) See additional sheet
(c)	80% = 5200 $\frac{5200}{80} \times 100$	6500	3	M1 for (100 – 20)% = 5200 M1 for $\frac{5200}{"80"} \times 100$ A1 cao

Paper 5506

No	Working	Answer	Mark	Notes
4 (a)	$x^2(x+1) = 230$	AG	2	M1 for $x \times x \times (x+1)$ or $x \times x \times x + 1$ oe, $x^2(x+1)$, $x^2 \times x + 1$ A1 cao from $x \times x \times (x+1)$, no need to see 230
(b)	5 – 150 6 – 252 5.1 – 158.7 5.2 – 167.6 5.3 – 177.0 5.4 – 186.6 5.5 – 196.6 5.6 – 207.0 5.7 – 217.7 5.8 – 228.8 5.9 –240.2 5.85 – 234.4	5.8	4	B2 for trial between 5.8 and 5.9 inclusive evaluated (B1 for trial between 5 and 6 inclusive evaluated) B1 for different trial between 5.8 and 5.85 (not including 5.8) B1 dep on at least are previous B1 5.8, 5.81, 5.811
5	$\pi \times \left(\frac{15}{2}\right)^2 = 176.715$	88.4 cm^2	3	M1 for $\pi \times \left(\frac{15}{2}\right)^2$ seen A1 88.3 – 88.4 B1 for cm² (independent)

Paper 5506

No	Working	Answer	Mark	Notes
6 (a)	$5 = 0.5x + 1$	8	2	M1 for $5 = 0.5x + 1$ A1 cao
(b)		$y = \frac{1}{2}x + c$	1	B1for $y = \frac{1}{2}x + c$, $c \neq 1$, oe
(c)		$x = 2y - 2$ OR $x = 2(y - 1)$	2	M1for correctly multiplying both sides by 2 or correctly isolating $\frac{x}{2}$ A1 for $x = 2(y - 1)$, $x = \frac{y-1}{0.5}$, $\frac{y-1}{\frac{1}{2}}$ oe SC B1 for x= 2y -1
7	$4x - 6y = 22$ $15x + 6y = 54$ $19x = 76$	$x = 4,\ y = -1$	4	M1 for coefficients of x or y the same followed by correct operation, allow one arithmetical error A1 cao M1 (dep) for correct sub for other variable A1 cao Trial and improvement 0 marks unless both correct values of x and y found
8 (a)	SF = $\frac{10}{6}$ $\frac{10}{6} \times 4.8 = 8$	8	2	M1 for sight of $\frac{10}{6}$ or $\frac{6}{10}$ or 1.67 or better or $\frac{CD}{10} = \frac{4.8}{6}$ A1 cao
(b)	$\frac{10}{6} \times 4.5 - 4.5 = 3$	19.8	2	M1 for use of SF from "a" to find AC or BC or $\frac{BC}{4.5} = \frac{4}{6}$ and adding 4 sides A1 cao

Paper 5506

No	Working	Answer	Mark	Notes
9	$\frac{6\times10^{15}}{3.2\times10^{8}}$ 1.875×10^{7}	4.3×10^{3}	3	B3 for 4.3×10^{3} to 4.34×10^{3} (B2 for 1.875×10^{7} oe or 4300 to 4340, final answer of 1.9×10^{7} B1 for sight of 6×10^{15} oe or 3.2×10^{8} oe)
10	$8.5\times\tan38$ $=8.5\times0.7813$ $\frac{8.5}{\sin(90-38)}=\frac{AB}{\sin38}$ $AB=\frac{8.5\times\sin38}{\sin(90-38)}$ $=\frac{5.2331}{0.788}=6.64$	6.64	3	M1 for correct use of trig, eg $\tan 38=\frac{opp}{8.5}$ M1 for $8.5\times\tan38$ A1 6.64 – 6.641 OR M1 for correct substitution into the sine rule M1 (dep) for correct rearrangement for AB= A1 6.64 – 6.641
11 (a)		No, as you would expect about 100. Yes, as it is possible to get 200 sixes with a fair dice	1	B1 for a consistent answer See additional sheet

Paper 5506

No	Working	Answer	Mark	Notes
(b)	$\frac{1}{6}, \frac{5}{6}$ + labels		3	B1 for $\frac{5}{6}$ on the red dice, *not six* branch B1 for a fully complete tree diagram with all branches labelled B1 for $\frac{1}{6}$ and $\frac{5}{6}$ on all remaining branches as appropriate
(c)(i)	$\left(\frac{1}{6}\right)^2$	$\frac{1}{36}$	2	M1 $\left(\frac{1}{6}\right)^2$ or $\frac{1}{6}\times\frac{1}{6}$ only or 0.28 A1 $\frac{1}{36}$ or 0.03 or better
(ii)	$1-\left(\frac{5}{6}\right)^2$ OR $\frac{1}{6}\times\frac{5}{6}+\frac{5}{6}\times\frac{1}{6}+\frac{1}{6}\times\frac{1}{6}$	$\frac{11}{36}$	3	M2 for $1-\left(\frac{5}{6}\right)^2$ or $1-\frac{5}{6}\times\frac{5}{6}$ A1 cao OR M1 for $\frac{1}{6}\times\frac{5}{6}$ oe M1 for 2 or 3 only of $\frac{1}{6}\times\frac{5}{6}, \frac{5}{6}\times\frac{1}{6}$, "a" A1 for $\frac{11}{36}$ or 0.31 or better

Paper 5506

No	Working	Answer	Mark	Notes
12 (a)	$\pi \times 30 \times \frac{7.5^2}{3} - \pi \times 10 \times \frac{2.5^2}{3} = 1767 - 65$	1700	3	M1 for either $\pi \times 30 \times \frac{7.5^2}{3}$ or $\pi \times 10 \times \frac{2.5^2}{3}$ M1 (dep) for difference A1 1700 – 1702 **SC** B1 Using d instead of r, 6800 – 6808
(b)	$\frac{S}{2\pi d} = \sqrt{h^2 + d^2}$ $\left(\frac{S}{2\pi d}\right)^2 = h^2 + d^2$	$h = \sqrt{\frac{S^2 - 4\pi^2 d}{4\pi^2 d^2}}$	3	M1 for correctly isolating $\sqrt{h^2 + d^2}$ or $h^2 + d^2$ or $h + d$ or kh^2 or kh M1(indep) squaring both sides A1 $h = \sqrt{\frac{S^2 - 4\pi^2 d^4}{4\pi^2 d^2}}$, $h = \frac{\sqrt{S^2 - 4\pi^2 d^4}}{2\pi d}$ $h = \sqrt{\left(\frac{S}{2\pi d}\right)^2 - d^2}$
(c)	$\left(\frac{30}{20}\right)^2 \times 450$ or $450 \div \left(\frac{20}{30}\right)^2$	1012.5	2	M1 for sight of correct SF^2 including 4:9 A1 1010 to 1013

Paper 5506

No	Working	Answer	Mark	Notes
13 (a)	$\frac{2x(x+20)}{2} = 400$	As given	2	M1 $\frac{2x(x+20)}{2}$ or $\frac{2x \times x + 20}{2}$ or $2x(x + 20) = 800$ A1 cao following correct working, no need for = 400 *SC B1* $2x \times x + \frac{1}{2} \times 2x(10 - \frac{x}{2}) \times 2$
(b)	$\frac{-20 \pm \sqrt{20^2 - 4 \times 1 \times (-400)}}{2}$ $= \frac{-20 \pm 44.721}{2}$	12.361	3	M1 for correct sub, up to signs, in the quad formula A1 for 44.7 or $\sqrt{2000}$ A1 for 12.3606 – 12.361, ignore negative solution T.I B3 for 12.361 OR Completing the square M1 for $(x+10)^2$ seen A1 for $-10 \pm \sqrt{500}$ A1 for 12.3606 – 12.361 ignore negative solution

Paper 5506

No	Working	Answer	Mark	Notes
14 (a)	$0.5\times 8\times 15\times \sin 70^0$	56.4	2	M1 for correct sub into area formula A1 56.38 – 56.4
(b)	$AB^2 = 8^2 + 15^2 - 2\times 8\times 15\times \cos 70^0 = 206.9$ EITHER $0.5\times AB\times CX$ ='56.38' OR $\frac{\sin B}{8} = \frac{\sin 70}{\sqrt{'206.9'}}$ $B = 31.5$ 15 sin '31.5'	7.84	4	M1 for correct sub into cos rule A1 for 206.9 - 207 or 14.38 – 14.4 EITHER M1 for use of area rule to find CX A1 7.83 – 7.84 OR M1 for correct use of sine rule to find sin B or sin A and then sight of 15sin B *or* 8 sin A A1 7.83 – 7.84

Paper 5506

No	Working	Answer	Mark	Notes
15 (a)	$4a^2 - 4a + 1 - (4b^2 - 4b + 1) =$ $4(a^2 - b^2) - 4(a - b)$ $4(a - b)(a + b - 1)$ OR $((2a - 1) - (2b - 1))((2a - 1) + (2b - 1))$ $(2a - 2b)(2a + 2b - 2)$	AG	3	Expansion Method M1 for a correct expansion of any one of the three terms M1(dep) on an attempt to expand all 3 terms and show LHS = RHS A1 fully correct algebra RHS exp is $4\left(a^2 + ab - a - ba - b^2 + b\right)$ OR Factorisation Method M1 for attempt to use difference of 2 squares on LHS M1 for one bracket correctly simplified A1 fully correct
(b)	Any 2 odd square numbers have the above form If a and b are both even or odd then $a - b$ is even, so $4(a - b)$ is a multiple of 8 If one of a,b is odd, then $a + b - 1$ is even, so $4(a + b - 1)$ is a multiple of 8		3	B1 'any 2 square nos have the above form' (may be implied by sight of $(2a - 1)^2 - (2b - 1)^2$ in part (b)) B1 first reason B1 second reason SC B1 for $(2r + 1)^2 - (2r - 1)^2$ B1 for 8r
16 (a)	$g_L = \frac{2 \times 4.495}{1.35^2 \times \sin 30.5}$ $g_u = \frac{2 \times 4.505}{1.25^2 \times \sin 29.5}$	9.719 11.710	4	B2 for any 4 of 4.505, 1.25, 29.5, 4.495, 1.35, 30.5 seen (B1 for any two or three seen) B1 for 11.710 – 11.7103 B1 cao 9.719 – 9.71904
(b)	Round, until lower and upper bounds agree	10	1	B1 for 10 + reason " they agree to this level of accuracy"

Paper 5506

No	Working	Answer	Mark	Notes
17 (a)(i)		xy	3	B1 cao
(ii)		y^2		B1 for y^2 or $y \times y$
(iii)		$\frac{x}{2}$		B1 for $\frac{x}{2}$ or $0.5x$ or $2^{-1}x$
(b)	Divide to get $2y = 1$	$q = -1$	2	M1 for $2y = 1$ or $\frac{x}{2} = 32$ or $p + q = 5$ or $1 + p + 2q = 5$
		$p = 6$		A1 cao
18 (a)	$x^2 - 2mx + m^2 - k$	$k = m^2$	2	M1 for correct exp of $(x - m)^2$ or correct completion of the square eg $\left(x - \frac{2m}{2}\right)^2 - \left(\frac{2m}{2}\right)^2$
				A1 cao
				SC B1 for $k = -m^2$
(b)(i)	Min value is $-m^2$	$-m^2$	3	M1 for recognition that min value occurs when $(x - m)^2 = 0$ (either (b)(i) or (b)(ii) correct implies this M1)
(ii)	$x = m$	m		A1 ft on 'k', " $-k$" gets M1 A0
				A1 cao
19	$0.06 \times 0.05 = 0.003$	No	2	M1 for 0.06×0.05
				A1 correct conclusion based on 0.003 or 0.06 x 0.05 stated as $\neq 0.0011$
				OR M1 for statement that for the two events to be independent P (BL and CL) = P(BL) × P(CL)

Paper 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
20		50 50 4	3	B1 50 or $\frac{100}{2}$ B1 for 50 or "a" B1 4 or $\frac{360}{90}$ oe

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4LN

Telephone 01623 467467
Fax 01623 450481

Order Code UG014129 June 2003

For more information on Edexcel qualifications please contact our
Customer Response Centre on 0870 240 9800
or email: enquiries@edexcel.org.uk
or visit our website: www.edexcel.org.uk

London Qualifications Limited. Registered in England and Wales no.4496750
Registered Office: Stewart House, 32 Russell Square, London WC1B 5DN



edexcel

GCSE
Edexcel GCSE
Mathematics A 1387

July 2004

advancing learning, changing lives

Mark Scheme

Edexcel GCSE
Mathematics A 1387

London Qualifications is one of the leading examining and awarding bodies in the UK and throughout the world. It incorporates all the qualifications previously awarded under the Edexcel and BTEC brand. We provide a wide range of qualifications including general (academic), vocational, occupational and specific programmes for employers.

Through a network of UK and overseas offices, our centres receive the support they need to help them deliver their education and training programmes to learners.

For further information please call Customer Services on 0870 240 9800, or visit our website at www.edexcel.org.uk

July 2004

Publications Code UG015616

All the material in this publication is copyright
© London Qualifications Ltd 2004

CONTENTS

Notes on Marking Principles....2
Paper 5514....4
Paper 5515....8
Paper 5516.... 11
Paper 5517.... 15
Paper 5518.... 19
Paper 5519.... 23

NOTES ON MARKING PRINCIPLES

NOTES ON MARKING PRINCIPLES

1 Three types of mark are available

M marks - awarded for correct working seen or implied.
A marks - conditional accuracy marks which are awarded for accurate working following the award of M marks.
B marks - unconditional accuracy marks (independent of M).

2 Abbreviations

cao - correct answer only.
ft - follow through.
$\surd$ - Denotes a "follow through" answer.

SC - special case.
isw - ignore subsequent working.
oe - or equivalent (and appropriate).
NB: a candidate cannot benefit from both isw and ft.

3 If no working shown, then

correct answers normally score full marks
incorrect (even though nearly correct) answers score no marks.

4 Marking instructions

Misread loses A marks (and sometimes B marks) on that part but ft can be allowed on subsequent parts. M marks can still be earned. If in doubt contact your team leader.
If there is a wrong answer in the answer space DO CHECK the working in the body of the script.

- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.
- If there is a wrong answer in the answer space DO CHECK the working in the body of the script.
- If it is clear from working that the "correct" answer has been obtained from incorrect working, award no marks. If in doubt contact your team leader.

5 Style of marking

Answer correct: tick and write part mark in margin NEXT TO BRACKETED MARK.
Answer incorrect: cross, but show M, A or B marks if any earned in body of script and transfer the total of these to the margin next to the bracket mark.
Total for each double page at bottom right page (except for back if used), FINAL TOTAL IN RELEVANT BOX ON FRONT COVER.
Nought in margin for fully incorrect question or page AND FOR NO ATTEMPT.
Where no attempt has been made a line should be put in the answer space and zero in the margin next to the bracketed mark
CHOICE OF METHOD – No marks unless one answer is in answer space – then mark that.
CROSSED OUT WORK - if not replaced this should be marked (if legible).
There must always be a mark next to bracketed mark in the margin/

6 Follow Through Marks

Follow throughs are guided by two principles:

(a) Follow throughs which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous, do not award.
(b) Follow throughs which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

7 Probability

Probability answers must be given as fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least two decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.

6 Linear Equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

8 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

PAPER 5501					
No		**Working**	**Answer**	**Mark**	**Notes**
1			K: 1020 L: 8.06	2	B1 for 1020 or 1,020 B1 for 8.06 Accept £8.06p and £8,06
2	(a)		28, 33	2	B1, B1 (B1 ft for "28" + 5 if both numbers >25)
	(b)			1	B1 for add 5, +5, for going up in 5's the difference is 5 oe
	(c)			1	B1 for they end in 3 and 8, it ends in 7; or refers to 383 and 388 are in sequence
3	(a)(i)		$\frac{1}{2}$	2	B2 for ½ accept half (B1 for an equivalent unsimplified fraction eg 4/8 or 50% or 0.5)
	(ii)		2 rectangles shaded	1	B1 for correct shading (any 2 rectangles)
	(b)(i)		40	4	B1 for 40 cao
	(ii)		150 000		B1 for 150 000 cao (accept 150,000 not 150.000)
	(iii)		6.55		B1 for 6.55 cao not $6.5^{½}$
	(iv)		$\frac{3}{8}$		B1 for $\frac{3}{8}$ oe accept 0.375
	(c)		Cross 3cm from *A*	1	B1 mark a cross 3 cm (±2 mm) from *A*
4	(a)(i)		metres	2	B1 for metres (m)
	(ii)		grams		B1 for grams (g)
	(b)		miles	1	B1 for miles
5	(a)		(3, 2)	1	B1 for (3, 2)
	(b)(i)		*Q* at (0, 3)	1	B1 for *Q* plotted correctly on *y*-axis at (0, 3) ±2mm
	(ii)		*R* at (−2, −3)	1	B1 for *R* plotted correctly at (−2, −3) ±2mm
6	(a)(i)		30	2	B1 for 30
	(ii)		25		B1 for 25
	(b)(i)		4 shapes	2	B1 for drawing 4 shapes
	(ii)		1½ shapes		B1 for drawing 1½ shapes

PAPER 5501					
	No	Working	Answer	Mark	Notes
7	(a)		30	1	B1 for 30
	(b)	$20 \times 3 + 5$	65	2	M1 for $20 \times 3 + 5$ oe A1 for 65
8	(a)		Draws perp.	1	B1 for correctly drawing perp must touch line or cut line *AB* ± 2mm
	(b)		Sketches a cylinder	1	B1 for sketching cylinder
9	(a)	1974 6580 8554	855.4	3	M1 for complete method with relative place value correct, condone 1 error in multiplication A2 cao (A1 for digits 8554 seen or A1 for "855.4" dependent on 1 arithmetic error)
	(b)	990 ÷ 69 = 14.3…. or 14 rem 24	14	4	Method 1 - Everything excluding long division M2 for a valid method with no errors …need to see 966 or 1035 (M1 for a valid method, including estimation, that reaches an answer between 901 and 1099 inclusive. Ignore errors.) A2 for 14 with a fully correct method (A1 (dep on 1st M1) for an answer between 14 and 15 inclusive. Ignore errors. Cannot have used estimation.) Note: Estimation can only score a maximum of M1 unless accompanied by another method or 966 or 1035 see (award M2) Method 2 – long division method M2 for 990 ÷ 69 = integer answer between 12 and 19 inclusive and rem 30 seen (M1 for 990 ÷ 69 with 1 in tens column.) A2 for 14 with fully correct method (A1 (dep on 1st M1) for an answer between 14 and 15 inclusive.)

PAPER 5501					
	No	**Working**	**Answer**	**Mark**	**Notes**
10	(a)(i)		7	2	B1 for 7
	(ii)		−10		B1 for −10
	(b)(i)		6	2	B1 for 6 (accept −6)
	(ii)		8		B1 for 8 (accept −8)
	(c)		−7	1	B1 for −7 cao
11	(a)		B and D	2	B1, B1 (–1 each extra)
	(b)(i)		A	2	B1 for A
	(ii)		3		B1 for 3
12	(a)	800 − 144	656	2	M1 for at least 1 digit correct and in correct position needs to be 3 digit number A1 for 656
	(b)	144 is less than 200 so Trudy is wrong		2	B1 for 200 B1ft for 'correct' explanation based on cand's "200"
	(c)	$\frac{45\times800}{100}$	360	2	M1 for 45 × 800 ÷ 100 oe A1 for 360
	(d)	$\frac{176}{800}\times100$	22	2	M1 for $\frac{176}{800}\times100$ oe A1 for 22
13	(a)(i)		25	4	B1 for 25
	(ii)		28		B1 for 28
	(iii)		5 and 20		B1 for 5 and 20
	(iv)		26 and 33		B1 for 26 and 33
	(b)	$2^3 = 8$ or $2^3 = 2 \times 2 \times 2$ (which is not 6)		1	B1 for valid 'explanation'
14			10 m^2	2	B1 for 10 B1 indep for m^2.

PAPER 5501					
No		**Working**	**Answer**	**Mark**	**Notes**
15	(a)	$\frac{11}{12}-\frac{10}{12}$	$\frac{1}{12}$	2	M1 for correctly writing both fractions to a common denominator A1 for $\frac{1}{12}$ oe
	(b)	$\frac{70\times400}{200}$	140	2	B2 for 140 (accept 136) (B1 for sight of any two of 70, 400 or 200)
16	(a)		$2y$	1	B1 for $2y$ or $2\times y$, $y2$, $y\times2$
	(b)		$3p^2$.	1	B1 for $3p^2$ or $3\times p^2$ or $p^2\times3$ or $p^2 3$
	(c)		$x(x-3)$	2	B2 for $x(x-3)$ (B1 for x (x…….)) $\frac{25}{60}$ wrongly cancelled gets B1 ISW
17	(a)		2 23 9 34 15 2 9 26 17 25 18 60	3	B3 for all correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
	(b)		$\frac{25}{60}$	1	B1 for $\frac{25}{60}$ or $\frac{5}{12}$ oe $\frac{25}{60}$ wrongly cancelled gets B1 ISW

PAPER 5501					
	No	Working	Answer	Mark	Notes
18	(a)(i)		60	2	B1 for 60
	(ii)				B1 for all **angles equal** so equilateral triangle oe
	(b)(i)		130	3	B1 for 130
	(ii)				B1 for isosceles triangle oe or 2 angles equal accept $\angle Q = \angle R$ B1 for angles on a straight **line** add up to **180°**oe (180° could be in working)
	(c)		64	1	B1 for 64
19	(a)		1	1	B1 for 1
	(b)		3	1	B1 for 3
	(c)	$9\times1+3\times2+5\times3+3\times4$ (= 42) "42" ÷ 20	2.1	3	M1 for 9×1, 3×2, 5×3, 3×4 or for 42 seen M1 (dep) for "42" ÷ 20 A1 for 2.1 or $2\frac{1}{10}$ or $2\frac{2}{20}$
20	(a)		09 05	1	B1 for 09 05 oe
	(b)		7	1	B1 for 7
	(c)		10	1	B1 for 10
	(d)	7km in 20 mins	21	3	B1 for 20 (minutes) oe or $\times3$ seen M1 for $\frac{"7"}{"20"}$ A1 cao [SC: "7" × 3 seen gets B1 M1]

PAPER 5501				
No	**Working**	**Answer**	**Mark**	**Notes**
21	Vertices of new triangle at (2, −2) (2, 6) and (6, −2)	Correct triangle drawn	3	B3 cao (B2 for either correct triangle in wrong translated position or for 2 vertices correct) (B1 a right angled triangle with horizontal length 4 or vertical length 8 in the same orientation as the shaded triangle) SC B2 for s + 3 totally correct
22 (a) (b) (c)	 8560 ÷ (10 × 10)	8 Pentagon 85.6	1 1 2	B1 for 8 B1 for pentagon M1 for 8560 ÷ (10 × 10) oe A1 for 85.6
23	$2x + x + 100 + 47 = 360$ $2x + x = 360 - 100 - 47$ $x = 71$ Largest angle = $2x$ =	142	4	M1 for $2x + x + 100 + 47 = 360$ or 360 – 147 or 213 seen M1 dep for correctly separating x-terms and non x terms or "360 – 147" ÷ 3 A1 for $x = 71$provided M2 awarded A1 ft for 142

PAPER 5502					
	No	**Working**	**Answer**	**Mark**	**Notes**
1	(a)		Diagram	1	B1 cao
	(b)		22, 26	1	B1 cao
	(c)		46	1	B1 cao
2	(a)	£5.95 + £1.62 + 25p + 2 × 48p = £8.78	1.22	3	M1 for 3 of £5.95, £1.62, 25p, 48p seen with intention to add or 170 seen A1 for £8.78 A1 ft from " 8.78"
	(b)	160 ÷ 12 = 13.(333…)	14	2	M1 for 160 ÷ 12, or 13 or better or 12 × 13 or 12 × 14 A1 14 cao
	(c)	"14" × £12.20 = £170.8**0**	170.80	2	M1 for "14" × 12.20 A1 for 170.8**0** or 158.6**0** if 13 in (b) NB: 170.8 or 158.6 gets M1 A0
3	(a)(i)		1459	1	B1 cao
	(ii)		9541	1	B1 cao
	(b)		9 + 5 = 14	1	B1 cao
	(c)		0	1	B1 cao
4	(a)		1123	1	B1 cao
	(b)		1125	1	B1 cao
	(c)		43	1	B1 cao
	(d)	67 – "43"	24	2	M1 for 67 – "43" A1 ft from "43"
	(e)(i)		80	2	B1 cao
	(ii)		56 – 58		B1 answer in range 56 to 58 inc
	(f)		Completes graph	2	B2 for (Apr , 70) and (May , 60 < p < 65) plotted and joined (B1 for one point plotted)

PAPER 5502					
No		Working	Answer	Mark	Notes
5	(a)(i)		4	1	B1 cao
	(ii)		10	1	B1 cao
	(b)		28	2	B2 for 28 (B1 for 29 or 14×2)
6	(a)		$\frac{3}{4}$	1	B1 accept 0.75, 75%
	(b)	$\frac{3}{4} \times 28 = 21$	15.54	3	M1 for $\frac{3}{4} \times 28$ or 21 seen M1 for "21" $\times$ 74 or 28×74 or 7×74 A1 cao
	(c)(i)		44 – 46	2	B1 44 – 46 inc
	(ii)		5.2 – 5.4		B1 5.2 – 5.4 inc
7	(a)		Correct shape	1	B1
	(b)		Correct shape	1	B1
8	(a)		Hexagon	1	B1
	(b)		Right	1	B1 cao
	(c)		Drawing	2	B2 for 7 additional hexagons with at least 2 points at which 3 hexagons meet (B1 for one point at which 3 hexagons meet)
9	(a)		$\frac{3}{4}$	2	M1 $\frac{80-20}{80}$ or $\frac{60}{80}$ or 0.75 (oe) A1 cao Do not accept equivalents
	(b)		15	1	B1 cao
	(c)		Iron and Cook set	1	B1 for both Accept mixer and fryer
	(d)		Microwave	1	B1 cao
	(e)		Bar chart	2	B1 one column (mixer): 70, 90 B1 second column (fryer): 70, 85 [SC: B1 columns correct but reversed]

PAPER 5502					
	No	Working	Answer	Mark	Notes
10	(a)		Acute	1	B1
	(b)		Reflex	1	B1
	(c)		reason	1	B1 reason eg 120 + 230 = 350 ≠ 360
11	(a)		$\frac{1}{2}$	1	B1 for $\frac{1}{2}$ oe
	(b)		reason	1	B1 for reason e.g could get 30 heads
12	(a)	7.5×4	30	2	M1 for 7.5×4 or $7\frac{1}{2} \times 4$ A1 cao
	(b)	$\sqrt{(42.25)}$	6.5	2	B2 for 6.5 (B1 for 42.25)
13	(a)		$6x$	1	B1 accept $6 \times x$, $x6$ oe
	(b)		$x - 4$	1	B1 cao
	(c)		$12(x - 4)$	1	B1 for $12(x - 4)$ or $12x - 48$ or $12 \times x - 48$ oe
	(d)		$18x - 48$	2	M1 for "$6x$" + "$12(x-4)$" or "$6x$" + "$12x - 48$" oe A1 ft $18x - 48$, $2(9x - 24)$, $3(6x - 16)$, $6(3x - 8)$
14	(a)		90	2	B2 for 90 ± 2 (B1 for 9 ± 0.2)
	(b)		317	1	B1 for 317 ± 4
15	(a)	Accurate drawing of triangle		2	B1 cao for 38° (±2°) B1 cao (indep) for BC drawn 7.3 cm (±2mm) and completing the triangle.
	(b)	Measure angle A	63°	1	B1 for 63° (±2°) or ft their diagram (±2°)

PAPER 5502					
	No	Working	Answer	Mark	Notes
16	(a)	0 × 1 = 0 1 × 1 = 1 2 × 4 = 8 3 × 8 = 24 4 × 8 = 32 5 × 7 = 35	100	3	M1 col 1 × col 2 (at least 3 shown) M1 (dep) sum of totals A1 cao SC: M1 M1 A0 for 101
	(b)	Either 35.50 ÷ 1.42 = 25; 26.99 – 25 = 1.99 Cheaper in the USA Or 26.99 × 1.42 = 38.33; 38.33 – 35.50 = 2.83 Cheaper in the USA		3	M1 35.50 ÷ 1.42 A1 25 seen B1 ft (dep on M1) £1.99 with conclusion (must have units) **OR** M1 26.99 × 1.42 A1 38.32 or 38.33… seen B1 ft (dep on M1) $2.83 or $2.82 with conclusion (must have units) must be to 2dp
17	(a)		-1, (1), (3), 5, 7, 9	2	B2 cao (B1 for 2 values)
	(b)		Graph	2	B1 ft for plotting points ±1/2 square B1 cao for line between $x = -2$ and $x = 3$
	(c)(i)		0.4	2	B1 for 0.4 or ft from single straight line with positive gradient
	(ii)		1.2		B1 for 1.2 or ft from single straight line with positive gradient

PAPER 5502					
	No	Working	Answer	Mark	Notes
18	(a)		Plots	1	B1 cao
	(b)		description	1	B1 dynamic relationship or "positive" (correlation)
	(c)		line of best fit	1	Line within overlay region, and to the extent of.
	(d)(i)	280 g →	reading	2	B1 ft from single straight line of positive gradient (±1/2 square)
	(ii)	120 pages →	reading		B1 ft from single straight line of positive gradient (±1/2 square)
19			200 150 225 150 10	3	B3 cao (B2 for three correct, or B1 for one correct)
20	(a)			2	B1 B1 for correct sketch – ignore additional internal lines B1 B0 for rectangle or right-angled triangle or correct shape without line NB 3-D sketch gets B0 B0
	(b)			2	B1 B1 for correct plan – ignore internal lines – accept a rotated plan, not reflected B1 B0 for a single rectangle drawn NB 3-D sketch gets B0 B0
21	(a)	163.25 – 35.50 = 127.75 127.75 ÷ 18.25 = 7	8	3	M1 163.25 – 35.50 (or sight of 127.75) M1 (dep) "127.75" ÷ 18.25 A1 cao SC: M2 for 7 days
	(b)	1.175 × £64 or $\frac{17.5}{100}$ × 64 or £11.20 seen	75.20	2	M1 1.175 × 64, 0.175 × 64 oe or 11.20 or 75.2 seen or 6.40, 3.20 and 1.60 seen A1 cao

PAPER 5502					
	No	Working	Answer	Mark	Notes
22	(a)		6	1	B1 cao
	(b)		$t^2 - 2t$	1	B1 oe
	(c)		$3(y - 4)$	1	B1 Accept $3 \times (y - 4)$ or $3(y - 4$
23	(a)		Reason	1	B1 Makes some mention of bias either directly or making reference to an insufficient or biased range of responses
	(b)		Reason	1	B1 (a) an insufficient range of responses (b) No mention of money (c) No time frame in the question (d) Misunderstanding of "A lot" and "Not much"

PAPER 5503				
No	**Working**	**Answer**	**Mark**	**Notes**
1		10.	1	B1 for 10
2 (a)(i)		$3e + 2f$	2	B1 for $3e + 2f$
(ii)		$3p^2$		B1 for $3p^2$
(b)	$5 \times -3 + 1$	-14	2	M1 for $5 \times -3 + 1$ A1 for -14
3	1974 $\frac{6580}{8554}$	855.4	3	M1 for complete correct method with relative place value correct, condone 1 error in multiplication. A2 cao (A1 for digits 8554 seen or A1 ft for "855.4" dependent on one arithmetic error only)
4 (a)		2 23 9 34 15 2 9 26 17 25 18 60	3	B3 all correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
(b)		$\frac{25}{60}$	1	B1 for $\frac{25}{60}$ or $\frac{5}{12}$ oe
5 (a)	$\frac{45}{100} \times 800$	360	2	M1 for $\frac{45}{100} \times 800$ oe A1 for 360
(b)	$\frac{176}{800} \times 100$	22	2	M1 for $\frac{176}{800} \times 100$ oe A1 for 22

PAPER 5503					
	No	Working	Answer	Mark	Notes
6	(a)	$\frac{11}{12}-\frac{10}{12}$	$\frac{1}{12}$	2	M1 for correctly writing both fractions to a common denominator A1 for $\frac{1}{12}$ oe
	(b)	$\frac{70\times400}{200}$	140	2	B2 for 140 (accept 136) (B1 for sight of any two of 70, 400 or 200)
7	(a)(i)		60	2	B1 for 60
	(ii)				B1 for all angles equal so equilateral triangle oe
	(b)(i)		130	3	B1 for 130
	(ii)				B1 for isosceles triangle oe B1 for angles on a straight line add up to 180°oe
	(c)		64	1	B1 for 64
8		$9\times1+3\times2+5\times3+3\times4$ (=42) "42" ÷ 20	2.1	3	M1 for 9×1, 3×2, 5×3, 3×4 or for 42 seen M1 (dep) "42" ÷ 20 A1 for 2.1 or $2\frac{1}{10}$ or $2\frac{2}{20}$
9	(a)		09 05	1	B1 for 09 05 oe
	(b)		7	1	B1 for 7
	(c)		10	1	B1 for 10
	(d)	7 km in 20 minutes	21	3	B1 for 20 (minutes) oe or $\times3$ seen M1 for $\frac{"7"}{"20"}$ A1 cao SC: "7" $\times3$ gets B1 M1

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
10		Vertices of new triangle at (2, −2) (2, 6) and (6, −2)	Correct triangle drawn	3	B3 cao (B2 for either correct triangle in wrong translated position or for 2 vertices correct) (B1 for a right-angled triangle with horizontal length 4 or vertical length 8 in the same orientation as shaded triangle) SC B2 for scale factor 3, totally correct
11		$2^2 + 3 =$	7 which is not even	2	B2 (B1 for correctly evaluating $n^2 + 3$ with a prime number value for n.)
12	(a)	360 ÷ 5	72	2	M1 for 360 ÷ 5 oe A1 for 72
	(b)	8560 ÷ (10 × 10)	85.6	2	M1 for 8560 ÷ (10 × 10) oe A1 for 85.6
	(c)(i)	Least length = 100.5	100.5	2	B1 for 100.5
	(ii)	Greatest length = 101.5	101.5		B1 for 101.5 or 101.499 or better
13		$2x + x + 100 + 47 = 360$ $2x + x = 360 - 100 - 47$ $x = 71$ Largest angle = $2x$ =	142	4	M1 for $2x + x + 100 + 47 = 360$ or 360 – 147 or 213 seen M1 (dep) for correctly separating x-terms and non x terms or $\frac{"360-147"}{3}$ A1 for $x = 71$ A1 ft (provided M2 awarded) for "142"
14	(a)(i)		2.21	2	B1 for 2.21
	(ii)		0.013		B1 for 0.013
	(b)	LCM = 3 × 13 × 17 = 3 × 221	663	2	M1 for 3 × 13 × 17 oe A1 for 663

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
15			Tick boxes 1,3 & 6	3	B1 for $\frac{\pi abc}{2d}$; B1 for $2a^2$; B1 for $2\left(c^2+d^2\right)$ (−B1 for each additional expression ticked (>3) to a minimum of 0)
16		200×0.2	40	2	M1 for 200×0.2 or $\frac{40}{200}$ seen A1 for 40
17	(a)	eg 2 | 108 2 | 54 3 | 27 3 | 9 3	$2^2 \times 3^3$	3	M2 for full systematic method of at least 4 divisions by prime numbers oe factor trees; condone 1 calculation error (M1 for 108 written as a correct product(s) with only one non-prime or equivalent division or a full process with 2 calculation errors.) A1 for $2^2 \times 3^3$ (accept $2 \times 2 \times 3 \times 3 \times 3$)
	(b)		12	1	B1 for 12
18		Perpendicular from P to intersecting arcs (within tramlines); perpendicular at least 2cm long		2	M1 relevant pair of arcs crossing within tramlines A1 SC M1 AO for a full construction of a perpendicular to AB not passing through P.
19		15×10	150 cm^3.	3	M1 for 15×10 A1 for 150 B1 for cm^3.

PAPER 5503					
No		**Working**	**Answer**	**Mark**	**Notes**
20			$y = 2x + 6$	2	B2 for $y = 2x + 6$ (B1 for $y = 2x + k$, $k \neq 1$ or for $y = mx + 6$, m $\neq 0$ or for $2x + 6$)
21		$6\frac{2}{5} = \frac{32}{5}$ Area of triangle = $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ (=2) Length of a side of sq. = $\sqrt{18 \times "2"}$ (=6) Perimeter of square = 4 × 6	24	5	B1 for $6\frac{2}{5} = \frac{32}{5}$ oe or $3\frac{1}{5} = \frac{16}{5}$ or $\frac{30}{8} + \frac{2}{8}$ oe (or implied by area of triangle=2) M1 for $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ oe M1 for area of square = 18 × product of two lengths A1 for $\sqrt{18 \times "2"}$ A1 for 24
22	(a)		$x(x-3)$	2	B2 for $x(x-3)$ (B1 for x (…….))
	(b)		k^3.	1	B1 for k^3.
	(c)(i)	$4x + 20 + 3x - 21$	$7x - 1$	4	M1 for **three** of 4 terms $4x + 20 + 3x - 21$ (or better) A1 for $7x - 1$
	(ii)	$x^2 + 3yx + 2xy + 6y^2$	$x^2 + 5xy + 6y^2$		M1 for **three** of 4 terms $x^2 + 3yx + 2xy + 6y^2$ A1 for $x^2 + 5xy + 6y^2$
	(d)		$(p+q)(p+q+5)$	1	B1 for $(p+q)(p+q+5)$

PAPER 5503					
	No	Working	Answer	Mark	Notes
23	(a)		32	1	B1 for 32 (accept 31.5 to 33.5 inclusive)
	(b)			3	B1 for ends of whiskers at 9 and 57, (with a box) B1 for ends of box at 16 and 45 (± 0.5) B1 for median marked at 32 or a complete box and whisker diagram drawn with a median inside the box
	(c)	Median(B)>Median(G); on average boys take longer IQR(B)>IQR(G); times for boys have a greater spread		2	B1 eg for comparison of medians B1 eg for comparison of (interquartile) ranges
24	(a)	$6y = 15 - 5x$	$y = \frac{15-5x}{6}$	2	M1 for either $6y = 15 - 5x$ or $-6y = 5x - 15$ or for $\frac{5x}{6} + y = \frac{15}{6}$ or a correct ft on sign error to $y=$ A1 for $y = \frac{15-5x}{6}$ oe
	(b)	$6k + 5(-21) = 15$	20	2	M1 for substitution of $x = -21$ (or $x = 21$) into given equation or candidate's answer to (a) A1 for $k = 20$
	(c)(i)		Region R indicated	3	B2 correct region shaded (accept unshaded if R clear) (B1 shaded or R region satisfies 3 of the 4 given inequalities with same boundaries)
	(ii)		(1,1)		B1 for (1,1)

PAPER 5503					
	No	Working	Answer	Mark	Notes
25	(a)		60	1	B1 for 60 B1 for *BDC* = 25
	(b)	eg Angle *BDC* = 25 *ADB* = 60 − 25	35	2	[Award the mark for equivalent approaches] B1 ft for (a) − 25
	(c)	Ben is correct; angle *DAB* = 65 + 25 = 90 and since angle in a semi-circle is 90°, *BD* must be a diameter		1	B1 for full valid justification

PAPER 5504					
	No	Working	Answer	Mark	Notes
1	(a)	Accurate drawing of triangle		2	B1 cao for 38º (±2º) B1 cao (indep) for BC drawn 7.3 cm (±2mm) and completing the triangle.
	(b)	Measure angle A	63º	1	B1 for 63º (±2º) or ft their diagram (±2º)
2	(a)	0 × 1 = 0 1 × 1 = 1 2 × 4 = 8 3 × 8 = 24 4 × 8 = 32 5 × 7 = 35	100	3	M1 col 1 × col 2 (at least 3 shown) could be implied by answers. M1 (dep) sum of totals A1 cao SC: M1 M1 A0 for 101
	(b)	Either $35.50 ÷ 1.42 = £25; £26.99 - £25 = £1.99 Cheaper in the USA Or £26.99 × 1.42= $38.33; $38.33 - $35.50 = $2.83 Cheaper in the USA		3	M1 35.50 ÷ 1.42 A1 25 seen B1 ft (dep on M1) £1.99 with conclusion; units needed OR: M1 26.99 × 1.42 A1 38.33 or 38.32…seen B1 ft (dep on M1) $2.83 or $2.82 with conclusion; units needed
3	(a)		-1, (1), (3), 5, 7, 9	2	B2 cao (B1 for 2 values)
	(b)		Graph	2	B1 ft for plotting points ±1/2 square B1 cao for line between $x = -2$ and $x = 3$
	(c)(i)		0.4	2	B1 0.4 or ft single straight line with positive gradient
	(ii)		1.2		B1 1.2 or ft single straight line with positive gradient

PAPER 5504					
	No	Working	Answer	Mark	Notes
4	(a)			2	B1 Rectangle drawn B1 Triangle attached Ignore additional internal lines; 3D sketch gets B0
	(b)			2	B1 single Rectangle drawn B1 Attached smaller rectangle drawn Accept rotated plan, Ignore internal lines down; Nets get B0
5	(a)	£163.25 - £35.50 = £127.75 £127.75 ÷ £18.25 = 7	8	3	M1 163.25 – £35.50 (or sight of £127.75) M1 (dep) "127.75" ÷ 18.25 A1 cao SC: M2 for 7 days
	(b)	1.175 × £64 or $\frac{17.5}{100}$ × 64 or £11.20 seen	75.20	2	M1 1.175 × 64.00 0.175 × 64 oe or 11.20 or 75.2 seen OR 6.40, 3.20, and 1.60 seen A1 cao
	(c)	54 × £2.38 =	128.52	2	M1 54 × £2.38 A1 cao
6		Tessellation	Drawing	2	B2 seven additional hexagons, with at least 2 points at which 3 hexagons meet (B1 one point at which 3 hexagons meet).
7			200 150 225 150 10	3	B3 cao (B2 for three correct, or B1 for one correct)
8	(a)(i)	Bearing measured	70	2	B1 70 ± 4
	(ii)	Bearing measured	317		B1 317 ± 4
	(b)	Locus (circle) drawn & shaded		2	B1 circle ±2 mm centre Manchester B1 shading with accurate or approximate circle within tolerance

PAPER 5504					
	No	Working	Answer	Mark	Notes
9	(a)		Plots	1	B1 cao
	(b)		Description	1	B1 dynamic relationship or "positive" (correlation)
	(c)		Line of best fit	1	Line within overlay region, and to the extent of.
	(d)(i)	280 g →	Reading	2	B1 ft from single straight line of positive gradient (±1/2 square) B1 ft from single straight line of positive gradient (±1/2 square)
	(ii)	120 pages →	Reading		
10	(a)	$\frac{1}{6}, \frac{3}{8}, \frac{1}{2}, \frac{2}{3}, \frac{3}{4}$		2	B2 for all correct (B1 for 1 error or all correct but wrong order, or use of a common denominator decimals).
	(b)	3/5, 65%, 2/3, 0.72, 3/4		2	B2 for all correct (B1 for 1 error or all correct but wrong order or conversions to decimals oe)
11	(a)		182, 178, 180, 184	2	M1 mean of any three consecutive months, eg (147 + 161 + 238) ÷ 3 oe A1 cao
	(b)	Sale price = 80% Fun Friday price = 70% of 80% = 56% (oe)		2	B1 B1 for a fully correct explanation involving a worked example (oe) B1 a partially complete explanation

PAPER 5504					
	No	Working	Answer	Mark	Notes
12	(a)		Reason	1	B1 makes a mention of bias, either directly, or making reference to an insufficient or biased range of responses.
	(b)(i)		Reason	1	B1 make some mention of any one of (a) an insufficient range of responses (b) no mention of money (c) no time frame in the question (d) misunderstanding of "a lot" or "not much"
					B2
	(ii)		Question	2	B1 for each of the following upto B2 (a) an improved question eg time frame made clear (b) response boxes (imperfect) (c) response boxes no errors OR For suggesting a generally improved question (a) a question clearly in the context of changes to the canteen (b) at least 3 boxes showing a full range of responses
13	(a)	$20y - 18y = 16 - 9$ oe $2y = 7$	$3\frac{1}{2}$ oe	3	M1 $20y - 18y = 16 - 9$ oe M1 $2y = 7$ A1 cao
	(b)	$40 - x = 3(4 + x)$ $40 - x = 12 + 3x$ $40 - 12 = x + 3x$ $4x = 28$	7	3	M1 multiplying through by 3: $3 \times \frac{40 - x}{3} = 3 \times 4 + 3 \times x$ A1 $40 - 12 = x + 3x$ A1 cao
14	(a)		$12(x\text{-}4)$	1	B1 for $12(x - 4)$ or $12x - 48$ or $12 \times x - 48$ oe $x = 12\ (x - 4)$ gets B0
	(b)		$18x\text{-}48$	2	M1 $6x +$ "$12(x - 4)$" or $6x +$ "$12x - 48$" A1 ft a linear expression $18x - 48$, $2(9x - 24)$, $3(6x - 16)$, $6(3x - 8)$

PAPER 5504					
No		**Working**	**Answer**	**Mark**	**Notes**
15		x $x^3 - 2x$ 4.1 60.7(21) 4.2 65.6(88) 4.3 70.9(07) Accept answer to 1 dp 4.22 66.7(114) or more 4.23 67.2(269) 4.24 67.7(45) 4.25 68.2(656)	4.2	4	B2 for trial $4.1 \leq x \leq 4.3$ evaluated (B1 for trial $4 < x < 5$ evaluated) B1 for different trial $4.225 \leq x \leq 4.25$ evaluated B1 (dep on at least one previous B1) for 4.2 cao
16	(a)		1.0×10^{-9}	1	B1 accept 1×10^{-9} or just 10^{-9}
	(b)	$1 \div 5 \times 10^{-9}$	2×10^{8}	2	M1 for $1 \div$ ("5×10^{-9}") or digit 2 with zeros only seen Condone omission of bracket for M1. A1 cao
17	(a)	$\frac{6.27 \times 4.52}{4.81 + 9.63} = \frac{28.3404}{14.44} = 1.962631579$	1.9626…	2	B2 for 1.9626… (B1 for 28.34 or 14.44)
	(b)		1.96	1	B1 ft from (a) as rounded to 1dp or 2dp. Do not accept 2, 2.00, but accept 2.0
18			$d = 4n + 6$	2	B2 $d = 4n + 6$ oe (B1 $d = 4n + k$, k an integer or 0, $4n + 6$, $n = 4n + 6$)
19		Vol = $\pi \times 3.8^2 \times 2.5 = \pi \times 14.44 \times 2.5$ = 45.36… × 2.5 = 113.411 Mass = "113" × 1.5 = 170.1165	170	4	M1 for $\pi \times r^2 \times 2.5$ where r = is 3.8 or 7.6 A1 if $r = 3.8$ M1 for "113" × 1.5 A1 for 169.5 – 170.3 cao

PAPER 5504					
	No	Working	Answer	Mark	Notes
20	(a)	$10^2 + 6^2$ or 136 $\sqrt{(100+36)}$ or $\sqrt{136} = 11.66\ldots$	11.7	3	M1 $10^2 + 6^2$ or 136 seen M1 (dep) $\sqrt{100+36}$ or $\sqrt{136}$ A1 11.66 – 11.7
	(b)	$\cos x = \frac{8}{10}$ or 0.8 $x = \cos^{-1} 0.8 = 36.869^\circ$	36.9	3	M1 for $\cos = \frac{8}{10}$, cos = 0.8 (oe) M1 (dep) for $\cos^{-1}$ (oe) A1 for 36.86 – 36.9
21		$18x - 6y = 99$ $\quad 12x - 4y = 66$ $8x + 6y = 18$ $\quad 12x + 9y = 27$ $26x = 117$ $\quad -13y = 39$	$x = 4\frac{1}{2}$ $y = -3$	4	M1 correct process to eliminate either x or y (condone one error) A1 cao for non – eliminated one. M1 (dep on 1st M1) for correct substitution of their found value. A1 cao (need both)
22		$\frac{133}{72} = 1.8472, \frac{160}{82} = 1.9512$ OR $\frac{72}{133} = 0.54135, \frac{82}{160} = 0.5125$ OR $\frac{160}{133} = 1.203...., \frac{82}{72} = 1.1388....$ OR $\frac{133}{160} = 0.83125...., \frac{72}{82} = 0.878$	1.84..≠ 1.95.. 1.20..≠ 1.13..	3	M1 for $\frac{133}{72}$ (= 1.8472…) oe Accept 1.8, 1.85 M1 for $\frac{160}{82}$ (=1.9512…) oe consistent pairing Accept 2.0, 1.9 **OR** M1 for $\frac{160}{133}$ (= 1.203…) oe M1 for $\frac{82}{72}$ (=1.1388) oe A1 for enough decimal places to show that the ratios are not equal; since the scale factors are different the shapes cannot be similar. NB Do Not need conclusion

PAPER 5504					
	No	Working	Answer	Mark	Notes
23	(a)		0.4, 0.6 0.4, 0.6, 0.4	2	B1 for LHS: (0.6), 0.4 B1 for RHS: 0.6, 0.4, 0.6, 0.4
	(b)	(30 × 42) – (25 × 42.8) = 1260 – 1070 = 190 190 ÷ 5 =	38	3	M1 for (30 × 42) – (25 × 42.8) or 1260 – 1070 or 190 seen M1 (dep) for "190" ÷ 5 A1 cao
24	(a)	£12000 × 0.25 = £3000; £12000 – £3000 = £9000 £9000 × 0.25 = £2250; £9000 – £2250 = £6750 £6750 × 0.25 = £1687.50; £6750 – £1687.50 =	£5062.50	3	M1 for 12000 × 0.75 (=9000) oe or £3000 or £23437.50 seen M1 (dep) for at least two further depreciation calculations (complete steps) A1 cao **OR** M2 for $12000 \times (0.75)^3$ or 5062.50 seen (M1 for $12000 \times (0.75)^n$, $n = 2$ or 4)
	(b)	0.8 × 0.8 × 0.8 × 0.8 (oe)	0.4096	2	M1 0.8^4 (oe) A1 cao

PAPER 5505					
	No	Working	Answer	Mark	Notes
1	(a)(i) (ii) (b)	 LCM = 3 × 13 × 17 = 3 × 221	2.21 0.013 663	2 2	B1 for 2.21 B1 for 0.013 M1 for 3 × 13 × 17 oe A1 for 663
2			Tick boxes 1,3 & 6	3	B1 for $\frac{\pi abc}{2d}$; B1 for $2a^2$; B1 for $2(c^2 + d^2)$ (−B1 for each additional expression ticked (>3) to a minimum of 0)
3	(a) (b)	200 × 0.2 0.2 + 0.4	40 0.6	2 2	M1 for 200 × 0.2 or $\frac{40}{200}$ seen A1 for 40 M1 for 0.2 + 0.4 A1 for 0.6
4	(a) (b)	eg 2 | 108 2 | 54 3 | 27 3 | 9 3 	$2^2 \times 3^3$ 12	3 1	M2 for full systematic method of at least 4 divisions by prime numbers oe factor trees; condone 1 calculation error (M1 for 108 written as a correct product with only one non-prime or equivalent division or a full process with 2 calculation errors.) A1 for $2^2 \times 3^3$ (accept 2 × 2 × 3 × 3 × 3) B1 for 12
5		Perpendicular from P to intersecting arcs (within tramlines); perpendicular at least 2 cm long		2	M1 relevant pair of arcs crossing within tramlines A1 SC M1A0 for full construction of a line perpendicular to AB not through P
6		15 × 10	150 cm^3.	3	M1 for 15 × 10 A1 for 150 B1 for cm^3

PAPER 5505					
	No	Working	Answer	Mark	Notes
7	(a)		k^3.	1	B1 for k^3.
	(b)(i)	$4x + 20 + 3x - 21$	$7x - 1$	4	M1 for **three** of 4 terms $4x + 20 + 3x - 21$ (or better) A1 for $7x - 1$
	(ii)	$x^2 + 3yx + 2xy + 6y^2$	$x^2 + 5xy + 6y^2$		M1 for **three** of 4 terms $x^2 + 3yx + 2xy + 6y^2$ A1 for $x^2 + 5xy + 6y^2$
	(c)		$(p+q)(p+q+5)$	1	B1 for $(p+q)(p+q+5)$
	(d)		m^8	1	B1 for m^8.
	(e)		$6r^3t^6$	2	B2 for $6r^3t^6$ (B1 for $.....r^3t^6$ or for $6....t^6$)
8	(i)	Least length = 100.5	100.5	2	B1 for 100.5
	(ii)	Greatest length = 101.5	101.5		B1 for 101.5; ACCEPT 101.499 or better
9		$6\frac{2}{5} = \frac{32}{5}$ Area of triangle = $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ (= 2) Length of a side of sq. = $\sqrt{18 \times "2"}$ (=6) Perimeter of square = 4 × 6	24	5	B1 for $6\frac{2}{5} = \frac{32}{5}$ oe or $3\frac{1}{5} = \frac{16}{5}$ oe or $\frac{30}{8} + \frac{2}{8}$ oe (or implied by area of triangle=2) M1 for $\frac{1}{2} \times \frac{5}{8} \times 6\frac{2}{5}$ oe M1 for (area of square) = 18 × product of two lengths A1 = $\sqrt{18 \times "2"}$ A1 for 24

PAPER 5505					
	No	Working	Answer	Mark	Notes
10	(a)	$6y = 15 - 5x$	$y = \frac{15-5x}{6}$	2	M1 for either $6y = 15 - 5x$ or for $\frac{5x}{6} + y = \frac{15}{6}$ or $-6y = 5x - 15$ or a correct ft on sign error to $y =$ A1 for $y = \frac{15-5x}{6}$ oe
	(b)	$6k + 5(-21) = 15$	20	2	M1 for subst. of $x = -21$ (or $x = 21$) into given eq^n or answer to (a) A1 for $k = 20$
	(c)(i)		Region R indicated	3	B2 correct region shaded (accept unshaded if R clear) (B1 shaded (R) region satisfies 3 of the 4 given inequalities with same boundaries)
	(ii)		(1,1)		B1 for (1,1)
11	(a)		$y = 2x + 6$	2	B2 for $y = 2x + 6$ (B1 for $y = 2x + k$, $k \neq 1$ or for $y = mx + 6$, $m \neq 0$ or for $2x+6$)
	(b)	Grad of $AB = 2$; Grad of $BC = \frac{-1}{"2"}$	$y = -\frac{1}{2}x + 6$	2	M1 for Grad of $BC = \frac{-1}{"2"}, -\frac{1}{2}$ or grad of $BC = -\frac{1}{\text{grad of AB}}$ A1 ft for $y = -\frac{1}{2}x + 6$ oe ft on wrong coeff. of x in (a)
	(c)	Eg A rectangle is always a cyclic quadrilateral because the opposite angles of a rectangle always add up to 180° (90+90)		1	B1 for valid explanation. (eg lines from the pt of int. of diagonals of rect to all 4 vertices are equal(radii))
12		Vertices of new triangle at $(-1, -4)$ $(-4, 2)$ and $(2, 2)$	Correct triangle drawn	3	B3 cao (B2 for 3 correct vertices no triangle or triangle with 2 correct vertices (B1 for triangle with two of six co-ordinates correct from using P as centre or any isosceles triangle with base 6 and height 6)

PAPER 5505					
	No	Working	Answer	Mark	Notes
13	(a)		32	1	B1 for 32 (accept 31.5 to 33.5 inclusive)
	(b)			3	B1 for ends of whiskers at 9 and 57 (with a box) B1 for ends of box at 16 and 45/46 ($\pm$ 0.5) B1for median marked at "32"or complete box and whisker diagram drawn with a median inside the box
	(c)	Median(B)>Median(G); on average boys take longer IQR(B)>IQR(G); times for boys have a greater spread		2	B1 eg for comparison of medians (ft on diagrams) B1 eg for comparison of (interquartile) ranges (ft on diagram)
14		Reading top to bottom frequencies are 20; 18; 45; 52		2	B2 all correct (B1 for one frequency correct)
15	(a)	$1600 = p\,q^0$.; $400 = pq^2$ $q^2 = 0.25$	$p = 1600$ $q = 0.5$	3	M1 for either $400 = pq^2$ or $1600 = pq^0$ B1 for $p = 1600$ A1 for $q = 0.5$
	(b)	$V = pq^{-2}$	6400	2	M1 for recognition that t = –2 A1 for 6 400

PAPER 5505					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	(I) $AB = AC$ (triangle ABC is isosceles) (II) PB = PC tangents (from a point to a circle are) equal (III) AP = AP (common side) so the 2 triangles are congruent ,SSS.		3	B3 for I, II, III with congruency reason (B2 for any two of I, II or III) (B1 for any one of the I, II or III)
	(b)	$BPC = 20°$ PBC (or PCB) = 90-1/2 "20" (= 80°) $BAC = PBC$ = "80"	50°	4	B4 for 50° (B3 for $BAC = 80°$) (B2 for $PBC = 80°$ or $PCB = 80°$) (B1 for $APC = 10°$ or $BPC = 20°$ or a middle angle = 90°) SC if clear numerical slip seen eg "PBC = 180 – 90 – 10 = 70" then goes on to get correct ft angle $ABC = 55$ deduct 1 from total so this cand would get B4–1 = B3
17	(a)	$\overrightarrow{OP} = \overrightarrow{OA} + \overrightarrow{AP}$ $= \overrightarrow{OA} + \frac{2}{3}(6\mathbf{c} - 6\mathbf{a})$ $= 6\mathbf{a} + 4\mathbf{c} - 4\mathbf{a}$	$2\mathbf{a} + 4\mathbf{c}$	3	M1 for $\overrightarrow{OP} = \overrightarrow{OA} + \overrightarrow{AP}$ or any correct vector journey involving $\overrightarrow{OP}$ M1 for $\overrightarrow{AP} = \frac{2}{3}(6\mathbf{c} - 6\mathbf{a})$ oe or $\overrightarrow{CP} = \frac{1}{3}(-6\mathbf{c} + 6\mathbf{a})$ oe or reverse vectors A1 for $2\mathbf{a} + 4\mathbf{c}$ oe (accept unsimplified)
	(b)	Eg $\overrightarrow{OM} = \overrightarrow{OC} + \overrightarrow{CM} = 6\mathbf{c} + 3\mathbf{a}$ $\overrightarrow{OM} = 1.5\overrightarrow{OP}$	$\overrightarrow{OM} = 1.5\overrightarrow{OP}$ so OPM is a straight line	2	B1 for $\overrightarrow{OM} = 6\mathbf{c} + \frac{1}{2}(6\mathbf{a})$ or $\overrightarrow{PM} = 2\mathbf{c} + \mathbf{a}$ unsimplified or reverse vectors B1 for a fully correct proof.

PAPER 5505					
	No	Working	Answer	Mark	Notes
18	(a)		4	1	B1 for 4 condone $\pm$ 4
	(b)		2	1	B1 for 2 condone ± 2
	(c)	$\sqrt{160} = 4\sqrt{10}$; $\left[\frac{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)-\sqrt{2}\times\sqrt{5}}{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)}\right]\times 100$ $\left[\frac{6\sqrt{10}-\sqrt{10}}{6\sqrt{10}}\right]\times 100$	$\frac{500}{6}$	4	B1 for **either** $\sqrt{160} = 4\sqrt{10}$ or $\sqrt{8} = 2\sqrt{2}$ **or** $\sqrt{20} = 2\sqrt{5}$ M1 for $\left[\frac{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)-\sqrt{2}\times\sqrt{5}}{\sqrt{8}\left(\sqrt{5}+\sqrt{20}\right)}\right]$ oe $(\times 100)$ B1 for either $6\sqrt{10} - \sqrt{10}$ or $6\sqrt{10}$ A1 for $\frac{500}{6}$ (accept 83.3 if no obvious earlier error)

PAPER 5505					
	No	Working	Answer	Mark	Notes
19	(a)(i)		$(2x-7)(x-14)$	3	M1 x^2 term and constant term (± 98) obtained or $2x(x-14) - 7(x-14)$ or $x(2x-7) - 14(2x-7)$ A1 for $(2x-7)(x-14)$
	(ii)		$x = \frac{7}{2}$; $x = 14$		B1ft ft (i) provided of form $(2x\pm a)(x\pm b)$
	(b)(i)		$\frac{7}{n+7}$	3	B1 for $\frac{7}{n+7}$ oe
	(ii)	$\frac{7}{n+7} = \frac{2}{5} \Rightarrow 2(n+7) = 5 \times 7$ $2n = 21$	n=10.5 is not possible since n has to be an integer		M1 for $2(n+7) = 5\times 7$ or $n+7=5\times 3.5$ (can be implied) ft (b)(i) fractional in terms of n and < 1 A1 ft for n=10.5 not possible (since n not integer) oe
	(c)	$2\times\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right) = \frac{4}{9}$ $14n\times 9 = 4(n+7)^2$ $14n\times 9 = 4(n^2+14n+49)$ $4n^2+56n+196-126n = 0$	$2n^2 - 35n + 98 = 0$	5	M1 for $\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right)$ seen M1 for $2\times\left(\frac{n}{n+7}\right)\times\left(\frac{7}{n+7}\right)$ oe $(=\frac{4}{9})$ M1(dep on 1st M) elimination of fractions within an equation B1 3 terms correct in expansion of $(n+7)^2 = n^2 + 7n + 7n + 49$ A1 full valid completion to printed answer

PAPER 5505					
	No	Working	Answer	Mark	Notes
	(d)	$\frac{7}{n+7}\times\frac{7}{n+7}=\frac{7}{21}\times\frac{7}{21}=$	$\frac{1}{9}$	2	M1 for $\frac{7}{n+7}\times\frac{7}{n+7}$ or better or ft [answer (b)(i)]^2 or $1-\frac{4}{9}-(\frac{n}{n+7})^2$ A1 for $\frac{1}{9}$ oe cao
20	(a)(i)		$y=1+\sin x$	2	B1 for $y=1+\sin x$
	(ii)		$y=2\sin x$		B1 for $y=2\sin x$ SC both (i) f(x) + 1, (ii) 2f(x) B1
	(b)	Stretch parallel to y-axis scale factor 3 Stretch parallel to x-axis scale factor $\frac{1}{2}$		3	M1 for 'stretch' A1 for Stretch parallel to y-axis scale factor 3 oe A1 for Stretch parallel to x-axis scale factor $\frac{1}{2}$ oe SC if M0 award BI for "sf 3 vertically" **and** "sf $\frac{1}{2}$ horizon."

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
1		Question	2	B1 for each of the following upto B2 (a) an improved question eg time frame made clear (b) response boxes (imperfect) (c) response boxes no errors OR For suggesting a generally improved question (a) a question clearly in the context of changes to the canteen (b) at least 3 boxes showing a full range of responses
2	Locus (circle) drawn & shaded		2	B1 circle centre Manchester ±2mm B1 shading with accurate or approximate circle within tolerance
3 (a)		182, 178, 180, 184	2	M1 mean of any three consecutive months, eg (147 + 161 + 238) ÷ 3 oe A1 cao
(b)	Sale price = 80% Fun Friday price = 70% of 80% = 56% (oe)		2	B1 B1 for a fully correct explanation involving a worked example (oe) B1 a partially complete explanation
4	x $x^3 - 2x$ 4.1 60.7(21) 4.2 65.6(88) 4.3 70.9(07) 4.22 66.7(114) 4.23 67.2(269) 4.24 67.7(45) 4.25 68.2(656)	4.2	4	B2 for trial $4.1 \leq x \leq 4.3$ evaluated (B1 for trial $4 < x < 5$ evaluated) B1 for different trial $4.225 \leq x \leq 4.25$ evaluated B1 (dep on at least one previous B1) for 4.2 cao

PAPER 5506					
	No	Working	Answer	Mark	Notes
5	(a)		1.0×10^{-9}	1	B1 accept 1×10^{-9} or just 10^{-9}
	(b)	$1 \div (5 \times 10^{-9})$	2×10^{8}	2	M1 for $1 \div$ ("5×10^{-9}") or digit 2 with zeros only seen Condone omission of bracket for M1. A1 cao
6	(a)	$\frac{6.27 \times 4.52}{4.81 + 9.63} = \frac{28.3404}{14.44} = 1.962631579$	1.9626…	2	B2 for 1.9626… (B1 for 28.34… or 14.44)
	(b)		1.96	1	B1 ft from (a) as rounded to 1dp or 2dp. Do not accept 2, 2.00, but accept 2.0
7			$d = 4n + 6$	2	B2 $d = 4n + 6$ oe (B1 $d = 4n + k$, k an integer $\neq 6$, $4n + 6$, $n = 4n + 6$)
8		Vol = $\pi \times 3.8^2 \times 2.5 = \pi \times 14.44 \times 2.5$ $= 45.36\ldots \times 2.5 = 113.411$ Mass = "113" × 1.5 = 170.1165	170	4	M1 for $\pi \times r^2 \times 2.5$ where r = is 3.8 or 7.6 A1 if $r = 3.8$ M1 for "113" × 1.5 A1 for 169.5 – 170.3 cao

PAPER 5506					
	No	Working	Answer	Mark	Notes
9	(a)	$10^2 + 6^2$ or 136 $\sqrt{(100 + 36)}$ or $\sqrt{136} = 11.66\ldots$	11.7	3	M1 for $10^2 + 6^2$ or 136 seen M1 (dep) $\sqrt{100+36}$ or $\sqrt{136}$ A1 11.66 – 11.7
	(b)	Cos x = 8/10 or 0.8 $x = \cos^{-1} 0.8 = 36.869^o$	36.9	3	M1 for cos = $\frac{8}{10}$, cos = 0.8(oe) M1 (dep) for $\cos^{-1}$ (oe) A1 for 36.86 – 36.9 M1 Use of sine rule and x found M1 for $x = 90 - \sin^{-1}$("0.8") A1 for 36.86 – 36.9
10		$18x - 6y = 99$ $\quad 12x - 4y = 66$ $8x + 6y = 18$ $\quad 12x + 9y = 27$ $26x = 117$ $\quad -13y = 39$	$x = 4\ ½$ $y = –3$	4	M1 correct process to eliminate either x or y (condone one error) A1 cao for non – eliminated one. M1 (dep on 1st M1) for correct substitution of their found value. A1 cao (need both)

PAPER 5506					
	No	Working	Answer	Mark	Notes
11		$\frac{133}{72} = 1.8472\,,\ \frac{160}{82} = 1.9512$ OR $\frac{72}{133} = 0.54135, \frac{82}{160} = 0.5125$ OR $\frac{160}{133} = 1.203...., \frac{82}{72} = 1.1388....$ OR $\frac{133}{160} = 0.83125...., \frac{72}{82} = 0.878$	1.84..≠ 1.95.. 1.20..≠ 1.13..	3	M1 for $\frac{133}{72}$ (= 1.8472…) oe Accept 1.8, 1.85 M1 for $\frac{160}{82}$ (=1.9512…) oe consistent pairing Accept 2.0, 1.9 **OR** M1 for $\frac{160}{133}$ (= 1.203…) oe M1 for $\frac{82}{72}$ (=1.1388) oe A1 for enough decimal places to show that the ratios are not equal; since the scale factors are different the shapes cannot be similar. NB Do Not need conclusion
12	(a)	£12000 × 0.25 = £3000; £12000 – £3000 = £9000 £9000 × 0.25 = £2250; £9000 – £2250 = £6750 £6750 × 0.25 = £1687.50; £6750 – £1687.50 =	£5062.50	3	M1 for 12000 × 0.75 (=9000) oe or £3000 or £23437.50 seen M1 (dep) for at least two further depreciation calculations (complete steps) A1 cao **OR** M2 for 12000 × $(0.75)^3$ or 5062.50 seen (M1 for 12000 × $(0.75)^n$, $n = 2$ or 4)
	(b)	0.8 × 0.8 × 0.8 × 0.8 (oe)	0.4096	2	M1 0.8^4 (oe) A1 cao

PAPER 5506					
No		**Working**	**Answer**	**Mark**	**Notes**
13		$r^2 = \frac{3\times10}{\pi h} = \frac{3\times10}{\pi 1.5} = \frac{3\times10}{4.712..} = 6.36, 6.37$ $r = \sqrt{6.366\ldots}$	2.52-2.54	3	M1 for correct rearrangement to give $r^2 = \frac{3V}{\pi h}$ or $30 \div 4.712..$ or $6.36 - 6.37$ *Allow 0.3, 0.33 for* $\frac{1}{3}$ M1 (dep) for $\sqrt{}$ A1 cao 2.52 – 2.54
14	(a)		0.4 0.6,0.4, 0.6,0.4	2	B1 for LHS: (0.6), 0.4 B1 for RHS: 0.6, 0.4, 0.6, 0.4
	(b)	0.6×0.6	0.36	2	M1 $0.6 \times$ "0.6" [0 < "0.6" < 1] A1 cao
	(c)	$(30 \times 42) - (25 \times 42.8) = (1260 - 1070 = 190$ $190 \div 5 =$	38	3	M1 for $(30 \times 42) - (25 \times 42.8)$ or $1260 - 1070$ or 190 seen M1(dep) for "190" ÷ 5 A1 cao 38

PAPER 5506					
	No	Working	Answer	Mark	Notes
15	(a)	$S = \frac{k}{f^2};\ 125 = \frac{k}{8^2};\ k = 8000$	$S = \frac{8000}{f^2}$	3	M1 for $S = \frac{k}{f^2}$ M1 for $125 = \frac{k}{8^2}$ A1 cao These marks can be awarded if the full formula appears in part (b), rather than in part (a). [SC: $S = \frac{125}{64} f^2$ M1 M0 A0, $S = 1.95(3125) f^2$ M1 M0 A0 $S = \frac{1000}{f}$ M1 M0 A0]
	(b)		500	1	B1 cao

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
16	$0.5 \times 3.2 \times 8.4 \times \text{Sin } B = 10$ $\sin B = 0.74404\ldots$ 48.077 $AC^2 = 3.2^2 + 8.4^2 - 2 \times 3.2 \times 8.4 \times \cos B$ $AC^2 = 44.8815\ldots..$ $AC = 6.69\ (936\ldots)$ Perimeter = 18.3 Use the altitude AD, $\frac{h \times 8.4}{2} = 10 \Rightarrow h = (2.381)$ $BD = \sqrt{3.2^2 - h^2} = 2.139$ $DC = 6.261$ $AC = \sqrt{2.38^2 + '6.261'^2} = 6.69(936)$ Perimeter = 18.3	18.3	6	M1 for $0.5 \times 3.2 \times 8.4 \times \sin B\ (= 10)$ A1 for $\sin B = 0.74(404\ldots)$ or $B = 47.7 - 48.1$ M1 for $3.2^2 + 8.4^2 - 2 \times 3.2 \times 8.4 \times \cos$ "48.077" M1(dep) for AC^2 = "44.8(815)"….. with correct order of evaluation A1 $AC = 6.69 - 6.7$ A1 18.29 – 18.3 **for** $\frac{h \times 8.4}{2} = 10 \Rightarrow h = (2.381)$ M1 for $BD^2 = 3.2^2 - "2.381"^2$ A1 $BD = 2.1 - 2.2$ M1 (dep) $AC^2 = "2.381"^2 + "6.261"^2$ A1 $AC = 6.69 - 6.7$ A1 18.29 – 18.3

PAPER 5506					
	No	Working	Answer	Mark	Notes
17	(a)	$(x + 8)^2 = x^2 + (x + 5)^2$ $x^2 + 16x + 64 = 2x^2 + 10x + 25$		4	B1 for angle $OTA = 90°$ (implied by use of Pythagoras with OA as hypotenuse) M1 $(x + 8)^2 = x^2 + (x + 5)^2$ oe M1 for correct squaring of x+8 or x+5 A1 for completion following correct working
	(b)	$(+6 + \sqrt{(6^2 - - 4\times39)})/2$ $= (6 \pm \sqrt{(36 + 156)})/2$ $= (6 \pm \sqrt{192})/2 = (6 + 13.856)/2$	9.93	3	M1 for substitution into quadratic formula, allow sign errors in b and c M1 for $x = (6 \pm \sqrt{192})/2$ [+ alone will do] A1 for 9.92 – 9.93
					M1 for $(x-3)^2-9-39$ M1 for $x = 3 \pm \sqrt{48}$ [+ alone will do it] A1 for 9.92 – 9.93 T&I= 9.93 gets M1,M0,A0
18		$EB = 60 \times \tan 30°$ $BD = \sqrt{(60^2 + 60^2)}$ $\tan BDE = 34.64 \div 84.85$	22.2°	4	M1 for $EB = 60\times\tan30$ M1 for $BD = \sqrt{(60^2 + 60^2)}$ M1 for $\tan BDE =$ "34.64" ÷ "84.85" A1 22.17 – 22.21
		$EB = 60 \times \tan 30°$ (= 34.64) $ED^2 = 60^2 + \left(\frac{60}{\cos 30}\right)^2$ $ED = \sqrt{8400} = (91.65)$ $\text{Angle} = \sin^{-1}\left(\frac{EB}{\sqrt{8400}}\right) = 22.2$			M1 for $EB = 60 \times \tan 30°$ oe M1 for fully correct method for ED M1 for $\sin BDE = \left(\frac{'34.84'}{'\sqrt{8400}'}\right)$ (oe) A1 22.17 – 22.21

PAPER 5506					
	No	Working	Answer	Mark	Notes
19	(a)	$x^2 + 6^2 = 25$ $x^2 = -11$		2	M1 substitutes y=6 to get x^2+36 = 25 A1 deduces x^2=25-36<0; impossible, (so line does not intersect curve)
	(b)	$y^2 = (2x - 2)^2$ $x^2 + (2x - 2)^2 = 25$ $x^2 + 4x^2 - 8x + 4 = 25$ $5x^2 - 8x + 4 - 25 = 0$ $5x^2 - 8x - 21 = 0$ $(5x + 7)(x - 3) = 0$ or $x = \frac{--8 \pm \sqrt{(-8)^2 - 4 \times 5 \times (-21)}}{10} = \frac{8 \pm \sqrt{484}}{10}$ So $x = 3$, or $x = -1.4$ Subs into either equation gives: $y = 4$, or $y = -4.8$	$x = 3$ $y = 4$ $x = -1.4$ $y = -4.8$	6	M1 $y^2=(2x-2)^2$ seen or implied A1 $x^2 + 4x^2 - 8x + 4 = 25$ (oe expanded form) M1 correct attempt to solve 3 term quadratic equation A1 $x = 3$, $x = -1.4$ M1 (dep on previous Ms) Sub one value of x into either equation gives: A1 $y = 4$, $y = -4.8$ NB: incorrectly matched pairs loses the final A1.

PAPER 5506					
	No	Working	Answer	Mark	Notes
20	(a)	400.005 ÷ 59.95 = 6.672310 6.672310 ÷ 1000 × 3600 = 24.02032 399.995 ÷ 60.05 = 6.661032 6.661032 ÷ 1000 × 3600 = 23.97972	24.020 23.980	5	B1 for 400.005 or 59.95 seen oe M1 for "400.005" ÷ "59.95" where "400.005" ∈ [400.005,400.5] and "59.95" ∈ [59.5,59.95] oe B1 for 399.995 or 60.05 seen oe M1 for "399.995" ÷ "60.05" where "399.995" ∈ [399.5,399.95] and "60.05" ∈ [60.05,60.5] oe A1 23.979-23.980 and 24.020-24.0204
	(b)	24.0 because to 1dp the answers are the same		1	B1cao for 24.0 with reason
	(c)	177 × 50/477 = 18.553 → 19 → 18 111 × 50/477 = 11.635 → 12 86 × 50/477 = 9.0147 → 9 82 × 50/477 = 8.595 → 9 21 × 50/477 = 2.201 → 2	18 12 9 9 2	3	M1 for $\frac{50}{"477"} \times 177$ or 111 or 86 or 82 or 21 A1 for all integers or better answers, at least 3 correct A1 cao
21	(a)	$40 - x = 3(4 + x)$ $40 - x = 12 + 3x$ $40 - 12 = x + 3x$ $4x = 28$	7	3	M1 multiplying through by 3: $3 \times \frac{40 - x}{3} = 3 \times 4 + 3 \times x$ A1 $40 - 12 = x + 3x$ A1 cao
	(b)	$\frac{2x(2x - 3)}{(2x - 3)(2x + 3)} = \frac{2x}{2x + 3}$	$\frac{2x}{2x + 3}$	3	B1 for $(2x-3)(2x+3)$ B1 for $2x(2x-3)$ or $(2x + 0)(2x + 3)$ B1 cao

PAPER 5506				
No	**Working**	**Answer**	**Mark**	**Notes**
22	Distance from x axis is y. Distance from (0, 2) is $\sqrt{(x^2+(y-2)^2)}$ $y^2 = x^2 + (y-2)^2$ $y^2 = x^2 + y^2 - 4y + 4$ $0 = x^2 - 4y + 4$ $4y = x^2 + 4$ and finish		4	B1 for $(x-0)^2 + (y-2)^2$ or $\sqrt{((x-0)^2+(y-2)^2)}$ oe seen B1 for $y = \sqrt{(x-0)^2+(y-2)^2}$ or $y^2 = (x-0)^2 + (y-2)^2$ oe B1 $(y-2)^2 = y^2 - 4y + 4$ seen B1 for $4y = x^2 + 4$ and finish

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone: 01623 467467
Fax: 01623 450481
Email: publications@linneydirect.com

Order Code UG015616 July 2004

For more information on Edexcel and BTEC qualifications please contact
Customer Services on 0870 240 9800
or http://enquiries.edexcel.org.uk
or visit our website: www.edexcel.org.uk

London Qualifications Limited, trading as Edexcel. Registered in England and Wales No. 4496750
Registered Office: Stewart House, 32 Russell Square, London WC1B 5DN



GCSE

Edexcel GCSE

Mathematics A 1387

Summer 2005
Mark scheme

Edexcel GCSE
Mathematics A 1387

Edexcel is one of the leading examining and awarding bodies in the UK and throughout the world. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers.

Through a network of UK and overseas offices, Edexcel's centres receive the support they need to help them deliver their education and training programmes to learners.

For further information please call our Customer Services on 0870 240 9800, or visit our website at www.edexcel.org.uk.

Summer 2005

Publications Code UG016720

All the material in this publication is copyright
© Edexcel Ltd 2005

CONTENTS

Notes on Marking Principles 1

Paper 5521/01 3

Paper 5521/02 12

Paper 5523/03 18

Paper 5523/04 27

Paper 5525/05 37

Paper 5525/06 45

NOTES ON MARKING PRINCIPLES

1 Types of mark

- M marks: method marks
- A marks: accuracy marks
- B marks: unconditional accuracy marks (independent of M marks)

2 Abbreviations

cao – correct answer only
ft – follow through
isw – ignore subsequent working
SC: special case
oe – or equivalent (and appropriate)
dep – dependent
indep - independent

3 No working

If no working is shown then correct answers normally score full marks
If no working is shown then incorrect (even though nearly correct) answers score no marks.

4 With working

If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks. Discuss each of these situations with your Team Leader.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.
If there is no answer on the answer line then check the working for an obvious answer.

5 Follow through marks

Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

6 Ignoring subsequent work

It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: eg. incorrect cancelling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect eg algebra.
Transcription errors occur when candidates present a correct answer in working, and write it incorrectly on the answer line; mark the correct answer.

7 Probability

Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

8 Linear equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

9 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)		17252	1	B1 cao
	(b)		5400	1	B1 cao
	(c)		thousands, 1000, 4000	1	B1
2	(a)		grams, g	3	B1 oe spelling
			centimetres, cm		B1 oe spelling
			millilitres, m*l*, cm^3		B1 oe spelling
	(b)		5	1	B1 cao
3	(a)		106, 102	1	B1 cao ignore extras
	(b)		eg take away 4	1	B1 could be indicated on the diagram
	(c)		46	1	B1 cao

Paper 5521/01

No	Working	Answer	Mark	Notes
4	286 × 43 = 11440 + 12298 = 12298 43 × 286 = 258 + 3440 + 8600 = 12298 286 × 40 = 1140 286 × 3 = 858 1140+858=12298 x | 40 | 3 | 8600 200 | 8000 | 600 80 | 3200 | 240 | 3440 6 | 240 | 18 | 258 12298 Grid: 2 8 6 / 1 | 0 8 | 3 2 | 2 4 | 4 / 2 | 0 6 | 2 4 | 1 8 | 3 / 2 9 8	12298	3	M2 for complete correct method (condone one computational error) (M1 for complete correct method with two computational errors) A1 cao OR B2 inside of grid completed (condone missing zeros and one error) (B1 2 or 3 errors) B1 cao
5 (a)		18, 69	1	B1
(b)(i)		18 or 36	1	B1
(ii)		16 or 36	1	B1
(c)		factor	1	B1
(d)(i)		18	3	B1 cao
(ii)		11 or 88		B1
(iii)		69		B1 cao

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
6	(a)		April & May	1	B1 for both
	(b)		Daffodil	1	B1
	(c)		Feb	1	B1
	(d)		Crocus	1	B1
	(e)(i)		$\frac{1}{5}$	2	B1 for $\frac{1}{5}$ oe
	(ii)		× from 56 mm to 64 mm from 0		B1 A single mark on the line, between 56 mm and 64 mm measured from end 0
7	(a)	$\frac{40}{100}$	$\frac{2}{5}$	2	B2 for $\frac{2}{5}$ B1 for $\frac{40}{100}$ or $\frac{4}{10}$ or $\frac{20}{50}$ or $\frac{8}{20}$
	(b)		0.98	1	B1 cao
	(c)		7 500 000	1	B1 cao
	(d)		25	1	B1 cao
	(e)		60	1	B1 cao

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
8	(a)(i)		(0, 2)	2	B1 cao
	(ii)		(4, 1)		B1 cao
	(b)		$(2, 1\frac{1}{2})$ marked	1	B1 Allow 2mm tolerance from $(2, 1\frac{1}{2})$
9	(a)		2.40	1	B1 cao could be indicated on the diagram
	(b)	1.60 + 0.40	2.00	2	M1 for appropriate sum or product in £ or p or 200 seen eg 1.60 + 0.40, 160 + 40, 0.80 + 0.80 + 0.40, 80 + 80 + 40, 0.08×25, 0.80×2.5, 200 A1 cao
	(c)	$1 \div 0.8$ or $2.50 \div 2$	1.25	2	M1 for $1.00 \div 0.8$ or $2.50 \div 2$ or 125 or appropriate combination eg $1 + \frac{1}{2} \times 0.50$ A1 cao
10	(a)		hexagon	1	B1 Condone spelling error
	(b)		Sum of angles at a point is 360°	2	B1 for 360 seen B1 for "point", "complete turn" or "a circle" or similar unless accompanied by an incorrect angle SC If neither B1 scored, award B1 for a clear indication that the size of an angle, other than *x*, is 90° or a right angle (may be on diagram)
	(c)	$30 \times 4 + 8 \times 2$	136	2	M1 $30 \times 4 + 8 \times 2$ or attempt to sum 5 or 6 lengths A1 cao

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
11	(a)		13, 67, 76, 103, 130	5	B1 cao
	(b)		$-7, -3, -1, 0, 5$		B1 cao
	(c)		0.07, 0.072,0.7, 0.702, 0.72		B1 cao
	(d)		0.6, $\frac{2}{3}$, 70%, $\frac{3}{4}$		B2 (B1 for any 3 in correct order)
12	(a)		16 30	1	B1 Accept 4 30 pm Do not accept 4 30
	(b)(i)	$33.56 \div 4$ oe	8.39	3	M1 for $33.56 \div 4$ oe eg 3356 ÷ 4, division by 2 twice A1 cao
	(ii)		9		B1 ft from "8.39" unless whole number of pounds
13	(a)		6 cm^2	3	B2 for 6 cao for numerical answer (B1 for $5.5 < \text{Area} \leq 7$) then B1 (indep) for cm^2 with or without numerical answer
	(b)	See diagram	Correct shape	2	B2 (B1 for any 2 sides correct or a correct enlargement scale factor $\neq 1$ or 2)

Paper 5521/01				
No	**Working**	**Answer**	**Mark**	**Notes**
14 (a)	$(4+3)\times10$	70	2	M1 for (4 + 3) × 10 A1 cao
(b)	$120\div10-3$	9	2	M1 for $\frac{120}{10}$ or 12 seen eg $12\times10=120$ A1 cao
(c)		$C=10(n+3)$	3	B3 for $C=10(n+3)$ oe such as $C=(n+3)\times10$ (B2 for correct RHS or $C=n+3\times10$, $C=10n+3$ oe B1 for C = some other linear expression in n or for $n+3\times10$, $10n+3$ etc) Note: $C = n$ scores no marks
15		11 13 16 8 21	2	B2 all correct (B1 for 2 correct)

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)		$2p + 4q$	2	B2 for $2p + 4q$ (accept $2 \times p$ etc) (B1 for $2p$ or $4q$)
	(b)		$2y^2$	1	B1 accept $2 \times y^2$ oe inc $2 \times y \times y$
	(c)		$3c + 4d$	2	B2 for $3c + 4d$ (accept $3 \times c$ etc) (B1 for $3c$ or $4d$)
	(d)		$8pq$	1	B1 accept in any order but must not include $\times$ sign
17	(a)(i)		60	2	B1 cao
	(ii)		eg top triangle is equilateral		B1 for reason
	(b)		150	2	M1 for $\frac{180-"60"}{2} + 90$ A1 ft from (a)(i) if $x < 90$ SC B1 for "60" + 90 if $x < 90$
18			40	2	M1 for 60×2 or 120 or $60 \div 3$ or 20 or $\frac{120}{180}$ A1 cao
19			correct drawing	2	B2 Condone hidden detail shown with solid lines and missing lines on front face (B1 for a correct sketch with other incorrect sketch(es) or for prism with correct cross section >1 cube wide or for attempt to draw prism with correct cross section or prism with correct plan and side elevation)

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
20		$\frac{600}{3\times10}$ or $\frac{640}{3.2\times10}$	$20\text{-}21\frac{1}{3}$	2	M1 for rounding at least two of the numbers to 1 sf or for sight of 640, 3.2 or 640, 32 or 600, 32 or 30 seen A1 for $20\text{-}21\frac{1}{3}$ Note: 20.3125 scores M0 A0
21	(a)		Points plotted	1	B1 $\pm$ 1 full (2 mm) square
	(b)		positive	1	B1 cao
	(c)		Line of best fit	1	B1 Must pass through (42.5, 1.45), (42.5, 1.55) AND (67.5, 1.75), (67.5, 1.85)
	(d)		~ 1.65	1	B1 ft from single line segment with positive gradient $\pm$ 1 full (2 mm) square
22	(a)	eg $50\times\frac{2000}{500}$	200	2	M1 for $\frac{2000}{500}$ or 4 seen A1 cao
	(b)	eg $400\times\frac{750}{500}$	600	2	M1 for $\frac{750}{500}$ or 1.5 seen or 400 + 200 A1 cao

Paper 5521/01					
No		**Working**	**Answer**	**Mark**	**Notes**
23	(a)	$4\times3-2\times1$ $12-2$	10	3	M1 for 3×4 (=12) or 1×2 or attempt to divide diagram up into rectangles M1 "12"– "2" or sum of areas of rectangles A1 cao
	(b)(i)	$\frac{10}{100}\times680$ or $680\div10$ 680 + 68	748	5	M1 $\frac{10}{100}\times680$ or 680÷10 or 68 seen M1 (dep) 680 + "68" or M2 for 680×1.10 A1 cao
	(ii)	"748"÷50 or 14.96	15		M1 For "748"÷50 or 14.96 Accept "748" rounded up or down to next 50 followed by $\div50$ A1 ft from (b)(i) rounded up SC B1 for 680 (seen) leading to 14

Paper 5521/02					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	Plain llll lll 8 Chicken lll 3 Bovril llll 5 S & Vin llll 4		3	M1 for attempt to tally A1 for 1 frequency correct or all tallies correct A1 for all frequencies correct (accept for /20)
	(b)		4	1	B1 ft
	(c)		Plain or 8	1	B1 ft
2	(a)(i)		11	2	B1 cao
	(ii)		16		B1 cao
	(b)	See diagram	Correct lines	2	B2 cao for both lines correct (B1 for one line correct)
	(c)		12	2	B2 cao (B1 for 11 or 13)
3	(a)		580	1	B1 for 580 (± 2) could be written on line
	(b)		7.2	1	B1 for 7.2 ± 0.02 could be written on line
	(c)		Arrow at 48	1	B1 allow ± half graduation
	(d)		Arrow at 6.7	1	B1 allow ± half graduation
4	(i)		Cylinder	2	B1 ignore spelling
	(ii)		Cuboid		B1 ignore spelling
5	(a)	£10 – (£2.15 + £2.30)	5.55	4	M1 £2.15 + £2.30 A1 for 4.45 M1 £10 – "4.45" A1 cao
	(b)	£60 ÷ £2.80 = 21.42857	21	2	M1 for £60 ÷ 2.80 or sight of digits 214… A1 for 21
	(c)	$120 \times 25 \div 100$	30	2	M1 ¼ of £120 (oe) A1 cao SC B2 for £90

Paper 5521/02					
No		Working	Answer	Mark	Notes
6	(a)(i)		143^0	2	B1 for 143 ($\pm 2^0$)
	(ii)		Obtuse		B1 for obtuse (ignore spelling)
	(b)	See diagram	Accurate drawing	1	B1 for accurate drawing ± 2mm
7	(a)(i)		5	2	B1 cao
	(ii)		23		B1 cao
	(b)	× 2 – 1		1	B1 for explaining a suitable method
	(c)	See their diagram		1	B1 for a correct diagram
	(d)		14, 17	2	B2 cao for both (B1 for one only ft from their 14)
8	(a)		90	1	B1 accept –90
	(b)		540	1	B1 accept –540
	(c)		Jupiter	1	B1 accept –150
	(d)		- 230	1	B1 cao

Paper 5521/02					
No		Working	Answer	Mark	Notes
9	(a)	2658 – 2430 = 228 "228" × 32	72.96	4	M1 2658 – 2430 A1 228 M1 "228" × 32 or "228" × 0.32 or digits 7296 seen A1 cao **Or** M1 for 2430 × 32 (or digits 77760 seen) or 2658 × 32 (or digits 85056 seen) A1 if 1 correct M1 for "85056" – "77760" or 7296 seen A1 cao
	(b)	$\frac{2}{5} \times 145 = 58$ 145 – "58"	87	3	M1 $\frac{2}{5} \times 145$ (or M1 $\frac{3}{5}$ seen) A1 58 (or M1 $\frac{3}{5} \times 145$) A1 for 87 ft
	(c)(i) (ii)		80 125	2	B1 for 80 (± 1) B1 125 (± 3)

Paper 5521/02					
No		**Working**	**Answer**	**Mark**	**Notes**
10	(a)		1.5 – 2.0	1	B1 for height between 1.5m – 2.0m inclusive
	(b)	Height of man × "2.5"	3 – 6	3	B3 for height between 3m – 6m inclusive (B2 for multiplying (a) by a number between 2 and 3 inclusive) (B1 for multiplying (a) by a number)
11		61 – 19 = 42 42 ÷ 3 = 14	14	2	M1 for – 19 or 42 seen A1 cao
12	(a)		5	1	B1
	(b)	4+5+5+5+4+3+2+1+4+5 = 38 mean = 38 ÷ 10 = 3.8	3.8	2	M1 for attempt to add and ÷ 10 or 3.7 or 3.9 seen A1 for 3.8 SC B1 for 33.5 seen
13	(a)		$3x$	1	B1 cao Accept $3 \times x$, $x3$, $x \times 3$, $x + x + x$
	(b)		x - 9	1	B1 for x – 9 cao
14	(a)	14.44 – 8.660254038	5.77974(…)	2	M1 for 14.44 seen or 8.66(…) or 5.7 or 5.8 or better rounded or truncated
	(b)		6	1	A1 cao B1 ft
15		15 ÷ 24	62.5	2	M1 for 15 ÷ 24 or 1500 ÷ 24 or sight of digits 625 A1 cao
16		2.10 × 450	945	2	M1 for digits 210 × 450 or sight of digits 945 A1 cao
17		See diagram	$2(y + y)$ $2y + 2y$	2	B1 for $2(y + y)$ B1 for $2y + 2y$ (Deduct B1 for each additional tick (>2) to min 0)
18		360° ÷ 18 (=20) Sector angles: G= 60; S= 80; B=220; Correct sectors labelled correctly Use angle measurer	Angles drawn, labelled	4	B4 for fully correct and labelled pie chart (B3 for all angles correct or for a labelled pie chart with 2 correct angles) (B2 for labelled pie chart with 1 correct angle drawn) (B1 for 360° ÷ 18 or 20 seen or implied)

Paper 5521/02					
No		Working	Answer	Mark	Notes
19	(a)		Correct plane	2	B2 for a correct plane defined by showing at least 2 lines. (B1 for a line of symmetry on one face)
	(b)		Correct net	2	B2 cao (B1 for 2 equilateral triangles joined appropriately to at least one rectangle or for 1 equilateral triangle joined appropriately to one of 3 rectangles)
	(c)		Correct drawing	2	B1 for two extra sides of length 6cm (± 2mm) B1 for construction arcs 6cm from each of the ends of the given line.
20	(a)		15	1	B1 for 15 (± 1)
	(b)		15	1	B1 for 15 (± 0.4)
	(c)			2	B1 horiz. line from (2, 20) to (3, 20) B1 line from (3, 20) to (5,0) or horizontal translation of it SC B1 for any journey ending at (5,0)
21	(a)	$x+4+x+x+4+x$	$4x+8$	2	M1 for attempting to add x, $x + 4$, x, $x + 4$ may be implied by $4x + a$ ($a > 0$) A1 for $4x + 8$ or $4(x + 2)$
	(b)	$4x + 8 = 54$ $4x = 46$ $x = 11.5$ Length = "11.5" + 4	15.5	3	M1 for "$4x + 8$" = 54 A1 cao for 11.5 seen B1 ft for "11.5" + 4
22		0.4 + 0.15 1 – "0.55"	0.45	2	M1 for 1 – sum A1 for 0.45 o.e. SC B1 for 0.81
23	(a)		3:1	1	B1 cao
	(b)	$\pi \times 2.45$	7.7	2	M1 for $\pi \times 2.45$ (accept π as 3.1 or better) A1 for 7.59 to 7.70

Paper 5521/02					
No		**Working**	**Answer**	**Mark**	**Notes**
24		7×10000	70 000	2	M1 for 7 X 10 000 or 7 X 100 X 100 A1 cao
25		5.40 ÷ 3 × 7	12.60	3	M1 for 5.40 ÷ 3 or sight of 1.8 M1 dep for "1.80" × 7 A1 for 12.6 or equivalent
26		7.60 x $\frac{17.5}{100}$ = 1.33 7.60 + 1.33 = 8.93 1650 x "8.93"	£14 734.50	4	M1 for 7.60 x $\frac{17.5}{100}$ or 1.33 seen or 7.60 x 1.175 (oe) (Award M1 for 10%, 5% and 2½% correctly calculated) A1 for 8.93 or 893 M1 for 1650 x "8.93" or digits 147345 seen A1 cao Accept 14734.5 **Alternative** M1 for 1650 × 7.6(0) or 12540 seen M1 for "12540" × $\frac{17.5}{100}$ or 2194.5 seen or "12540"× 1.175 (oe) (Award M1 for 10%, 5% and 2½% correctly calculated) M1 for "12540" + "2194.5" (dep on both previous method marks) or digits 147345 seen A1 cao accept 14 734.5

Paper 5523/03				
No	**Working**	**Answer**	**Mark**	**Notes**
1		Correct shape	2	B2 B1 for any 2 sides correct, or a correct enlargement scale factor ≠1 or 2.
2 (a)		11 13 16 8 21	2	B2 all correct (B1 for 2 correct) sign
(b)		$\frac{31}{80}$	1	B1 oe
3 (a)		$2p+3q$	2	B2 for $2p+3q$ (accept $2\times p$ etc) (B1 for $2p$ or $3q$ or $2p3q$)
(b)		$2y^2$	1	B1 accept $2\times y^2$ or $2\times y\times y$
(c)		$3c+4d$	2	B2 for $3c+4d$ (accept $3\times c$ etc) (B1 for $3c$ or $4d$ or $3c4d$)
(d)		$8pq$	1	B1 accept in any order but must not include ×
4 (a)(i)		60	2	B1 cao
(ii)		eg top triangle is equilateral		B1 for reason
(b)		150	2	M1 $\frac{(180-"60")}{2}+90$ A1 ft from (a)(i) if $x < 90°$ SC:B1 for answer from "60" + 90 if $x < 90°$

Paper 5523/03					
No		Working	Answer	Mark	Notes
5	(a)	$4\times3-2\times1$ $12-2$	10	3	M1 for 3×4 (=12) or 1×2 or attempt to divide diagram up into rectangles M1 "12" – "2" A1 cao
	(b)(i)	$\frac{10}{100}\times680$ or $680\div10$ 680 + 68	748	5	M1 $\frac{10}{100}\times680$ or $680\div10$ or 68 seen M1 (dep) 680 +"68" (or M2 for 680×1.10) A1 cao
	(ii)	"748" ÷ 50 or 14.96	15		M1 for "748" $\div50$ or 14.96; accept "748" rounded up or down to next 50 followed by $\div50$ A1 ft from (b)(i) rounded up SC B1 for 680 (seen) leading to 14
6	(a)	$2\times5+5\times-3=10-15=$	-5	2	M1 substitute e.g 2×5 and 5×-3 or 10 and -15 A1 cao
	(b)	$5\times4^2-7$ $5\times16-7$	73	3	M1 substitution e.g $5\times4^2-7$; do not accept 54^2-7 M1 $5\times16-7$ or $5\times4\times4-7$ or $80-7$ (NB 4^2 as 4×4) A1 cao

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
7		679 × 28 = 5432 + 13580 = 19012 or 28 × 679 = 252 + 1960 + 16800 = 19012 or  	190.12	3	M1 for an attempt to multiply the units and tens, or correct partitioning M1 complete correct method (condone one arithmetic error) A1 for 190.12 cao OR M1 for putting the numbers in a grid M1 for multiplying out and addition (condone one error) A1 answer shown with point OR M1 for correct partitioning M1 679×20 and 679×8 calculated oe (condone one error) A1 cao
8	(a)		Points plotted	1	B1 ±1 full (2mm) square
	(b)		positive	1	B1 cao
	(c)		Line of best fit	1	B1 must pass through (42.5, 1.45), (42.5, 1.55) AND (67.5, 1.75), (67.5, 1.85)
	(d)		approx 1.65	1	B1 ft from single line segment with positive gradient ± 1 full (2mm) square

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
9	(a)	eg $50 \times \frac{2000}{500}$	200	2	M1 $2000 \div 500$ or 4 seen A1 cao
	(b)	eg $400 \times \frac{750}{500}$	600	2	M1 $750 \div 500$ or 1.5 seen or 400 + 200 A1 cao
10			$C = 10(n+3)$	3	B3 for $C = 10(n+3)$ oe such as $C = (n+3) \times 10$ (B2 for correct RHS or $C = n + 3 \times 10$, $C = 10n + 3$ etc B1 for C = some other linear expression in n or $n + 3 \times 10$, $10n + 3$ etc) NB: C=n scores no marks
11	(a)		$p(p+6)$	2	B2 for $p(p+6)$ or $p \times (p+6)$ (B1 for $p(ap+b)$ where a,b are numbers or $p+6$ seen on it's own, or part of an expression)
	(b)	$x^2 - 4x + 7x - 28$	$x^2 + 3x - 28$	2	M1 for 4 terms correct ignoring signs (e.g $x^2, 4x, 7x, 28$) or 3 terms with correct signs (e.g $x^2, -4x, 7x, -28$) A1 cao
12			correct drawing	2	B2. Condone hidden detail shown with solid lines, or missing lines on front face. (B1 for : one sketch correct with other sketches incorrect cross-section correct with depth > 1 cube, correct plan and side elevation)

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
13		$\frac{600}{3\times10}$ or $\frac{640}{3.2\times10}$	20 to 21 $\frac{1}{3}$	2	M1 For rounding at least two of the numbers to 1 sf, or for sight of 640, 3.2 or 640, 32 or 600, 32 or 30 seen A1 for 20 to 21 $\frac{1}{3}$ NB: 20.3125 scores M0 A0
14	(a)		correct reflection	2	B2 (B1 reflection in line other than x=3)
	(b)		reflection in $y = x$	2	B2 cao Accept the word "reflected" (B1 any statement including the word "reflection")
15	(a)(i)		5^6	1	B1 accept 15125, 5^{4+2}
	(ii)		5^3	1	B1 accept 125, 5^{9-6}
	(b)	$x + y = 10$ and $x - y = 4$	$x = 7$ $y = 3$	3	M1 for either $x + y = 10$ or $x - y = 4$ A2 for both values correct [(A1 for one value correct) If M0, award B3 for both values correct or B2 for one value correct, otherwise B0] SC B2 for $x = 3$ and $y = 7$

Paper 5523/03				
No	**Working**	**Answer**	**Mark**	**Notes**
16 (a)	$5-3x=2x+2$ $5-2=2x+3x$	$\frac{3}{5}$	3	B1 for $2x+2$ seen OR $2.5-1.5x=x+1$ M1 for correct rearrangement of 4 terms A1 for $\frac{3}{5}$ oe
(b)		$-3,-2,-1,0,1,2$	2	B2 (B1 for 5 correct and not more than one incorrect integers)
17		question + response boxes oe	2	1st aspect: One question with time period (eg each night); ignore other questions. 2nd aspect: Response list (at least two), not overlapping.* 3rd aspect: Some mention of units (eg hours) in either question or responses Award B2 for all three aspects, or B1 for just two aspects. * 0-1, 2-3, 4-5 is OK, but 0-1, 1-2, 2-3 is not OK.

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
18	(a)	$\frac{2}{3}\times\frac{3}{4}=\frac{6}{12}$	$\frac{1}{2}$	2	M1 for $\frac{6}{12}$ or $\frac{3}{6}$ or $\frac{2\times3}{3\times4}$ A1 accept 0.5
	(b)	$1+2+\frac{8}{12}+\frac{9}{12}$	$4\frac{5}{12}$	3	M1 for attempt to convert to fractions with common denominator e.g two fractions, denominator of 12 A1 correct conversion : $\frac{8}{12}$ and $\frac{9}{12}$, or $\frac{20}{12}$ and $\frac{33}{12}$ seen (oe) A1 cao for $4\frac{5}{12}$ OR attempts to convert to decimals: must use at least 2dp M1 0.66+0.75 (or 1.66+2.75) or 0.67+0.75 etc A1 4.41, 4.417, 4.416 A1 4.416 (*recurring*)
19		$2\times\frac{1}{2}\times6\times8$ or 48 $8\times9+6\times9+10\times9$ or 72 +54 + 90	264 cm^2	4	M1 attempt to find the area of one face; $\frac{1}{2}\times6\times8$ or (8×9) or (6×9) or (10×9) or 72 or 54 or 90 or 24 M1 all five faces with an intention to add A1 cao numerical answer of 264 B1 (indep) cm^2 with or without numerical answer

Paper 5523/03					
No		**Working**	**Answer**	**Mark**	**Notes**
20			$\frac{\pi ab^3}{3d}$ $3(c+d)^3$ $3\pi bc^2$	3	B3 (B1 for each one correct) Nb –B1 for each of the 4th,5th,6th tick
21	(a)	$x+0.3+0.2+x=1$	0.25	2	M1 for $x+0.3+0.2+x=1$ oe, or $0.5\div 2$ A1 oe
	(b)	0.3×200	60	2	M1 0.3×200 A1 cao Accept 60 out of 200 (in words) SC B1 for $\frac{60}{200}$
22	(a)		$(-12)-4\quad -2\quad (0)8$	3	B3 for all correct [(B1 for each one correct)
	(b)		points plotted accurately points joined with smooth curve	2	B1 ± 1 full (2mm) square ft table if at least B1 awarded (all 5 points plotted) B1 ft for any smooth curve if previous B1 gained NB: curve must pass within 1 full square of the points
23			$\frac{1}{4}$ on LH branch $\frac{2}{3}$ & $\frac{1}{3}$ & $\frac{2}{3}$ on RH branches	2	B1 B1
24			m=3 n=5	2	B1 for 3 B1 for 5 (B2 for $2^3\times 5$ or $2\times 2\times 2\times 5$) SC: award B1 only if m=5, n=3 or for 8×5 seen

Paper 5523/03					
No		Working	Answer	Mark	Notes
25		$\frac{5--1}{-1-2} = -2$	$y = -2x + 5$	4	M1 for clear attempt to find gradient eg fraction with -1,5 in numerator, 2,-1 in denominator A1 for -2 B2 ft for $y =$"-2"$x + 5$ oe (eg $y = \frac{-6}{3}x + 5$) (B1 for $y = mx + 5$ or , $-2x+5$ or $y =$"-2"$x + c$)
26	(a)(i)		150	2	B1 accept 150 or 210
	(ii)				B1 for angle at the centre is twice the angle at the circumference
	(b)		30	3	B1 identifies angle between radius and tangent as $90°$ (may be in working or on diagram) M1 $360° - 90 - 90 -$"150" A1 ft from (a)(i) excluding a negative answer OR B1 for 90 M1 for $2 \times (180 - 90 -$"$\frac{150}{2}$"$)$ A1 ft from (a)(i) excluding a negative answer OR B3 for $180 -$(a)
		$360 - 90 - 90 -$"150"			

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	14.44 – 8.660254038	5.77974(….)	2	M1 for 14.44 seen or 8.66(……) seen or 5.7 or 5.8 or better, rounded or truncated A1 cao
	(b)		6	1	B1 ft
2		15 ÷ 24	62.5	2	M1 for 15 ÷ 24 or 1500 ÷ 24 or sight of digits 625 A1 cao
3	(a)	2.10 × 450	945	2	M1 for digits 210 × 450 or sight of digits 945 A1 cao
	(b)	63÷2.10	30	2	M1 for 63 ÷ digits 210 A1 cao
4		See diagram	$2(y + y)$ $2y + 2y$	2	B1 for $2(y + y)$ B1 for $2y + 2y$ (Deduct B1 for each additional tick (>2) to min 0)
5		$360^o \div 18$ (=20) Sector angles: G= 60; S= 80; B=220; Correct sectors labelled correctly Use angle measurer	Angles drawn, labelled	4	B4 for fully correct and labelled pie chart (B3 for all angles correct or for a labelled pie chart with two angles correct) (B2 for labelled pie chart with one correct angle drawn) (B1 for $360 \div 18$ or 20 seen or implied)
6	(a)		Correct plane	2	B2 for a correct plane defined by showing at least 2 lines. (B1 for a line of symmetry on one face)
	(b)		Correct net	2	B2 cao (B1 for 2 equilateral triangles joined appropriately to at least one rectangle or for 1 equilateral triangle joined appropriately to one of the three rectangles)
	(c)		Correct drawing	2	B1 for two extra sides of length 6 cm (± 2mm) B1 for construction arcs 6cm from each of the ends of the given line
7		61 – 19 = 42 42 ÷ 3 = 14	14	2	M1 for –19 or 42 seen or $3x + 19$ A1 cao

Paper 5523/04					
No		Working	Answer	Mark	Notes
8	(a) (b) (c)		15 15	1 1 2	B1 cao for $15(\pm 1)$ B1 cao for $15(\pm 0.4)$ B1 horiz. line from (2,20) to (3,20) B1 line from (3,20) to (5,0) or horiz. translation of it SC: B1 for any journey ending at (5,0)
9	(a)	$x+4+x+x+4+x$	$4x+8$	2	M1 for attempting to add $x+4, x, x+4, x$ may be implied by $4x+a$, $a>0$ A1 for $4x+8$ or $4(x+2)$
	(b)	$4x + 8 = 54$ $4x = 46$ $x = 11.5$ Length = "11.5" + 4	15.5	3	M1 for "$4x + 8$" = 54 A1 cao for 11.5 seen B1 ft for "11.5"+ 4
10		0.4 + 0.15 1 – 0.55	0.45	2	M1 for 1 – sum A1 for 0.45 oe SC: B1 for 0.81
11	(a) (b)	 $\pi \times 2.45$	3:1 7.7	1 2	B1 cao M1 for $\pi \times 2.45$ (accept π as 3.1 or better) A1 for 7.59 to 7.70
12		7×10000	70000	2	M1 for 7×10000 or $7 \times 100 \times 100$ A1 cao
13		$5.40 \div 3 \times 7$	12.60	3	M1 for $5.40 \div 3$ or sight of 1.8 M1 (dep) for "1.80" × 7 A1 for 12.6 or equivalent

Paper 5523/04				
No	**Working**	**Answer**	**Mark**	**Notes**
14	$7.60 \times \frac{17.5}{100} = 1.33$ 7.60 + 1.33 = 8.93 1650 × "8.93"	£14734.50	4	M1 for $7.60 \times \frac{17.5}{100}$ or 1.33 seen or 7.60 ×1.175 (oe) (Award M1 for 10%, 5% and 2½% correctly calculated) A1 for 8.93 or 893 M1 for 1650 × "8.93" or digits 147345 seen A1 cao Accept 14734.5 OR M1 for 1650×7.6 or 12540 seen M1 for "12540" $\times \frac{17.5}{100}$ or 2194.5 seen or "12540"×1.175 (oe) (Award M1 for 10%, 5%, and 2½% correctly calculated) M1 for "12540" + "2194.5" (dep on both previous M marks) or digits 147345 seen A1 cao accept 14734.5

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
15		$285 \times 1000/(60 \times 60) = 79.1\dot{6}$		3	M2 for $285 \times 1000 \div 60 \div 60$ or $80 \times 60 \times 60 \div 1000$ or for a correct method to obtain two comparable values e.g $80 \times 60 \times 60$ and 285×1000 (M1 for $285 \div 60 \div 60$ or 0.079(….) seen or $80 \times 60 \times 60$ or 288000 seen or for 285×1000 or 285000 seen or $80 \div 1000$ or 0.08 seen) A1 for 288 or 79.(….) or for two correctly calculated comparable values e.g 288000 and 285000
16	(a)	$4x + 12 = 6$ $4x = -6$	-1.5	3	B1 for $4x + 12$ or $x + 3 = \frac{6}{4}$ M1 for a correct re-arrangement of their 3 terms to isolate $4x$ or x A1 for -1.5 oe
	(b)	$v - u = 5t$	$\frac{v-u}{5}$	2	M1 for isolating $\pm 5t$ or $\pm t$ or for dividing through by 5 A1 oe

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
17		3→15 4→48 3.1→17.3(91) 3.2→19.9(68) 3.3→22.7(37) 3.4→25.7(04) 3.5→28.8(75) 3.4→25.7(04) 3.3→22.7(37) 3.35→24.1(95375)	3.3	4	B2 for trial between 3.3 and 3.4 inclusive (B1 for trial between 3 and 4 inclusive) B1 for different trial between 3.3 and 3.4 exclusive B1 (dep on at least one previous B1) for 3.3 NB trials should be evaluated to at least 1 dp truncated or rounded
18	(a)	36 ÷ (7+3+2) "3" × 7	21	3	M1 for 36 ÷ (7+3+2) M1 (dep) for "3" × 7 or 3 or 2 A1 cao
	(b)	$51.5 \times \frac{8.5}{100} = 4.3775$ 51.5 – 4.3775 = 47.1225	47 or 47.1 or 47.12	4	M1 for 51.5 × $\frac{8.5}{100}$ or 4.37(75) seen M1 (dep) for 51.5 – "4.37(75)" A1 for 47 or better B1 (indep) for rounding their answer correctly to the nearest whole number or 1 or 2 d.p OR M1 for $51.5 \times \frac{100-8.5}{100}$ M1 for $51.5 \times$"0.915" or 0.515 × "91.5" A1 for 47 or better B1 (indep) for rounding their answer correct to the nearest whole number or 1 or 2 d.p

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
19	(a)		Angle in a semicircle	1	B1 oe
	(b)	$12^2 + 16^2 = 400$ $\sqrt{400} = 20$	20	3	M1 for $12^2 + 16^2$ M1 for $\sqrt{144+256}$ A1 cao
	(c)	$\pi \times 10^2$	314	3	M1 for $\pi \times \left(\frac{"20"}{2}\right)^2$ M1 (indep) for correct order of evaluation of $\pi \times r^2$ for any r A1 for 314 – 315 inclusive

Paper 5523/04					
No		Working	Answer	Mark	Notes
20	(a)	$(1 \times 10)+(3 \times 15)+(5 \times 30)+(7 \times 35)+(9 \times 25)+(11 \times 5) = 730$ "730" ÷ 120 = 6.08333	6.08	4	M1 for use of *fx* with *x* consistent within intervals (including end points) M1 (dep) for use of midpoints M1 (dep on 1st M1) for use of $\frac{\sum fx}{\sum f}$ A1 6.08 to 6.085
	(b)		(10),25,55,90,115, 120	1	B1 for all correct
	(c)		graph	2	B1 ft for 5 or 6 points plotted correctly ± 1 full (2mm) square at the end of interval dep on sensible table (condone 1 addition error) B1(dep) for points joined by curve or line segments provided no gradient is negative – ignore any part of graph outside range of their points. (SC: B1 if 5 or 6 points plotted not at end but consistent within each interval and joined)

Paper 5523/04				
No	**Working**	**Answer**	**Mark**	**Notes**
(d)		72–74	2	M1 (ft dep on graph being cf) for reading from graph at 7 A1 ft ±1 full (2 mm) square Or B2 for $72-74$
21 (a) (b) (c) (d)		a^7 $15x^3y^4$ $x-1$ $(x+3)(x-3)$	1 2 1 1	B1 accept a^{4+3} B2 cao (B1 for two of 15, x^3, y^4 in a product) B1 cao B1 cao
22	80% = 220 $220 \div 80 \times 100$	275	3	M1 for recognising that 80% is equivalent to 220 M1 for $220 \div 80 \times 100$ oe A1 cao

Paper 5523/04					
No		**Working**	**Answer**	**Mark**	**Notes**
23			$x = 3$ $y = 0.5$	3	M1 for coefficients of x or y the same followed by correct operation, condone one arithmetical error M1 (dep) for substituting found value in one equation A1 cao SC: B1 for one correct answer only if M's not awarded
24			1.4×10^{10}	2	B2 for 1.4×10^{10} or 1.44×10^{10} (B1 for 14.4×10^{9} or 14400,000,000 or 14000,000,000 or 14×10^{9})
25	(a)	$\tan x = \frac{1.9}{3.2}$ $x = \tan^{-1}\left(\frac{1.9}{3.2}\right) = 30.7$	30.7	3	M1 for $\tan x = \frac{1.9}{3.2}$ or $\tan \frac{1.9}{3.2}$ M1 for $\tan^{-1}\left(\frac{1.9}{3.2}\right)$ A1 for 30.6 – 30.7
	(b)	90 + "30.7"	121	1	B1 (indep) ft for 90 + "30.7" rounded to 3 or 4 s.f

Paper 5523/04				
No	**Working**	**Answer**	**Mark**	**Notes**
26	SF$=\frac{12}{9}$ $\frac{12}{9}\times 6=8$	2	2	M1 for $\frac{12}{9}$ or $\frac{9}{12}$ or 1.33… seen or 0.75 seen or 8 seen or $\frac{6}{9}$ or $\frac{9}{6}$ or 0.66… or 1.5 or $\frac{1}{3}$ or 3 oe seen A1 cao

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	$x^2-4x+7x-28$	$x^2+3x-28$	2	M1 for 4 terms correct ignoring signs (e.g $x^2,4x,7x,28$) or 3 terms with correct signs (e.g $x^2,-4x,7x,-28$) A1 cao
	(b)		y^4+2y^2	2	B2 cao B1 for y^4 or $2y^2$
	(c)		$p(p+6)$	2	B2 for $p(p+6)$ or $p\times(p+6)$ (B1 for $p(ap+b)$ where a,b are numbers or $p+6$ seen on it's own, or part of an expression)
	(d)		$3x(2x-3y)$	2	B2 (B1 for $3(2x^2-3xy)$ or $x(6x-9y)$ or $3x(...)$)
2			question + response boxes oe	2	1st aspect: One question with time period (eg each night); ignore other questions. 2nd aspect: Response list (at least two), not overlapping.* 3rd aspect: Some mention of units (eg hours) in either question or responses Award B2 for all three aspects, or B1 for just two aspects. * 0-1, 2-3, 4-5 is OK, but 0-1, 1-2, 2-3 is not OK.
3	(b)		reflection in $y=x$	2	B2 cao accept the word "reflected" (B1 any statement including the word "reflection")
4	(a)	$5-3x=2x+2$ $5-2=2x+3x$	$\frac{3}{5}$	3	B1 for $2x+2$ seen OR $2.5-1.5x=x+1$ M1 for correct rearrangement of 4 terms A1 for $\frac{3}{5}$ oe
	(b)		$-3,-2,-1,0,1,2$	2	B2 (B1 for 5 correct and not more than one incorrect integers)

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
5	(a)	$\frac{2}{3}\times\frac{3}{4}=\frac{6}{12}$	$\frac{1}{2}$	2	M1 for $\frac{6}{12}$ or $\frac{3}{6}$ or $\frac{2\times3}{3\times4}$ A1 accept 0.5
	(b)	$1+2+\frac{8}{12}+\frac{9}{12}$	$4\frac{5}{12}$	2	M1 for attempt to convert to fractions with common denominator e.g two fractions, denominator of 12 A1 correct conversion : $\frac{8}{12}$ and $\frac{9}{12}$, or $\frac{20}{12}$ and $\frac{33}{12}$ seen (oe) A1 cao for $4\frac{5}{12}$ OR attempts to convert to decimals: must use at least 2dp M1 0.66+0.75 (or 1.66+2.75) or 0.67+0.75 etc A1 4.41, 4.417, 4.416 or 0.41, 0.417, 0.416 or 0.42, 4.42 A1 4.416 (*recurring*)
6	(a)(i)		5^6	1	B1 accept 15625, 5^{4+2}
	(ii)		5^3	1	B1 accept 125, 5^{9-6}
	(b)	$x+y=10$ and $x-y=4$	$x = 7$ $y = 3$	3	M1 for either $x + y = 10$ or $x-y=4$ A2 for both values correct [(A1 for one value correct) If M0, award B3 for both values correct or B2 for one value correct, otherwise B0] SC B2 for $x = 3$ or $y = 7$

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
7		$2\times\frac{1}{2}\times6\times8$ or 48 $8\times9+6\times9+10\times9$ or 72 +54 + 90	264 cm^2	4	M1 attempt to find the area of one face; $\frac{1}{2}\times6\times8$ or (8×9) or (6×9) or (10×9) or 72 or 54 or 90 or 24 or 48 M1 all five faces with an intention to add A1 cao numerical answer of 264 B1 (indep) cm^2 with or without numerical answer
8			$\frac{\pi ab^3}{3d}$ $3(c+d)^3$ $3\pi bc^2$	3	B3 (B1 for each one correct) Nb –B1 for each of the 4th,5th,6th tick
9	(a)	$x+0.3+0.2+x=1$	0.25	2	M1 for $x+0.3+0.2+x=1$ oe, or 0.5 ÷ 2 A1 oe
	(b)	0.3×200	60	2	M1 0.3×200 A1 cao Accept 60 out of 200 (in words) SC B1 for $\frac{60}{200}$
10	(a)		$(-12)-4\quad-2\quad(0)8$	3	B3 for all correct [(B1 for each one correct)
	(b)		5 points plotted accurately points joined with smooth curve	2	B1 ±1 full (2mm) square ft table if at least B1 awarded (all 5 points plotted) B1 ft for any smooth curve if previous B1 gained NB: curve must pass within 1 full square of the points
11			m=3 n=5	2	B1 for 3 B1 for 5 (B2 for $2^3\times5$ or $2\times2\times2\times5$) SC: award B1 only if m=3, n=3, for 8×5 seen

Paper 5525/05				
No	**Working**	**Answer**	**Mark**	**Notes**
12	$\frac{5--1}{-1-2} = -2$	$y = -2x + 5$	4	M1 for clear attempt to find gradient eg fraction with -1,5 in numerator, 2,-1 in denominator A1 for -2 cao B2 ft for $y =$"-2"$x + 5$ oe (eg $y = \frac{-6}{3}x + 5$) (B1 for $y = mx + 5$ or , $-2x+5$ or $y =$"-2"$x + c$)
13 (a)		$\frac{1}{4}$ on LH branch $\frac{2}{3}$ & $\frac{1}{3}$ & $\frac{2}{3}$ on RH branches	2	B1 cao B1
(b)	$\frac{3}{4} \times \frac{2}{3} + \frac{1}{4} \times \frac{1}{3} = \frac{6}{12} + \frac{1}{12}$	$\frac{7}{12}$	3	M1 for $\frac{3}{4} \times \frac{2}{3}$ or $\frac{1}{4} \times \frac{1}{3}$ from their tree diagram M1 for sum of two products A1 for $\frac{7}{12}$ oe
(c)	$n = 21 \times 4$ or $\frac{1}{6} : \frac{1}{4}$ oe $\frac{1}{6} \times 84$ or $21 \times \frac{2}{3}$	14	3	M1 for either $\frac{1}{3} \times \frac{3}{4} \left(= \frac{1}{4}\right)$ or $\frac{2}{3} \times \frac{1}{4} \left(= \frac{1}{6}\right)$ from their tree diagram M1 for 21×4 (=84) or $\frac{21}{3} \times 2$ A1 for 14 cao SC: B2 for 63 seen in fraction or ratio

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
14	(a)(i)		150	2	B1 accept 150 or 210
	(ii)				B1 for angle at the centre is twice the angle at the circumference
	(b)		30	3	B1 identifies angle between radius and tangent as $90°$ (may be in working or on diagram)
		$360 - 90 - 90 - "150"$ or $180 - "150"$			M1 $360^\circ - 90 - 90 - "150"$ A1 ft from (a)(i) excluding a negative answer Or B1 for 90 M1 for $2 \times (180 - 90 - "\frac{150}{2}")$ A1 ft from (a)(i) excluding a negative answer Or B3 for $180 - (a)$ SC: 180 – "210" can get B1 for $90°$ and/or B1 for "cyclic quadrilateral"
15	(a)		0.2727…	1	B1 for 2.27 recurring or 0.2727…. oe or 0.273
	(b)	eg $x = 0.3939…$ so $100x = 39.3939…$ $99x = 39$ so $x = \frac{39}{99} = \frac{13}{33}$		3	M1 for $100x = 39.39…$ M1 dep for subtraction of both sides A1 for $\frac{13}{33}$ from correct proof **Alternative method** M1 for $13.000 \div 33$ M1 for remainders 31 and 13 A1 for 0.39 recurring SC:B1 for $\frac{39}{99}$

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	$d = kt^2$ $80 = k \times 4^2$	$d = 5t^2$	3	M1 for $d = kt^2$ or $d \propto t^2$ M1 sub d=80 and t=4 into their equation A1 for $d = 5t^2$ oe (cao)
	(b)		245	1	B1 ft from (a) using "k"
	(c)	$45 = 5t^2$	3	2	M1 ft from (a) for substituting d=45 into their equation A1 for 3 cao (condone inclusion of -3)
17	(a)(i) (ii)		(0, 9) (8, 25)	3	B1 cao B1 for $x = 8$ cao B1 for $y = 25$ cao SC: B1 for (25, 8)
	(b)	LHS = $\left(\frac{100-(x^2-16x+64)}{4}\right)$ = $\left(\frac{36+16x-x^2}{4}\right)$ RHS = $\left(\frac{36-2x+18x-x^2}{4}\right)$ = LHS		3	M1 for expansion of either set of brackets with at least 3 of 4 terms correct M1 for common denominator of 4 or multiplying through by 4 or reducing each numerator to a single term A1 for fully correct solution **Alternative method** M1 for $(5-\frac{(x-8)}{2})(5+\frac{(x-8)}{2})$ M1 for $(\frac{2\times5-(x-8)}{2})(\frac{2\times5+(x-8)}{2})$ A1 for $\frac{(18-x)(x+2)}{4}$

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
18	(a)	$\frac{810\pi}{90\pi}$ or 9 $\sqrt{9}$ or 3	12	3	M1 for $\frac{810\pi}{90\pi}$ or 9 or $\frac{1}{9}$ or 1:9 oe M1 for $\sqrt{\frac{810\pi}{90\pi}}$ or $\sqrt{9}$ or 3 or $\frac{1}{3}$ or $\sqrt{9}:\sqrt{1}$ oe A1 cao
	(b)	3^3 or 27 or 2700	2700π	2	SC:B1 for answer of 36 M1 for "3"^{3} or 27 or $\left(\sqrt{9}\right)^3 : (\sqrt{81})^3$ oe or 9^3 or 2700– A1 cao
19	(a)(i)		1	1	B1 cao
	(ii)		8	1	B1 cao
	(iii)	$64^{-\frac{2}{3}} = \frac{1}{64^{\frac{2}{3}}}$ or $64^{-\frac{2}{3}} = (4^2)^{-1}$	$\frac{1}{16}$	2	M1 for knowing negative power is a reciprocal or power of $\frac{1}{3}$ root is a cube root A1 cao for $\frac{1}{16}$
	(b)	$\sqrt{27} = \sqrt{9\times3}$ or $\sqrt{27} = 3\sqrt{3}$ or $\sqrt{27} = 3^{3/2}$	$\frac{5}{2}$ oe	2	M1 for $\sqrt{27} = \sqrt{9\times3}$ or $\sqrt{27} = 3^{3/2}$ A1 for $\frac{5}{2}$ oe (cao) **Alternative method** M1 for $9\times27 = 3^{2n}$ A1 for $\frac{5}{2}$ oe (cao)

Paper 5525/05					
No		**Working**	**Answer**	**Mark**	**Notes**
20	(a)(i) (ii) (b)(i) (ii)		(90, 1) (180, 0) (45, 0) (90, -3)	2 2 	B1 cao could be indicated on diagram B1 cao could be indicated on diagram B1 cao could be indicated on diagram B1 cao could be indicated on diagram
21		$\frac{1}{3}\pi x^2 h = \frac{4}{3}\pi(2x)^3$ $x^2 h = 4\times 8x^3$	$32x$	3	M1 for substitution in correct formulae M1 (dep.) for correct unsimplified expression eg $h = \frac{\frac{4}{3}\pi(2x)^3}{\frac{1}{3}\pi x^2}$ oe or $h = 8x$ oe A1 for $32x$ cao
22	(a) (b)	$\left(\overline{OM} =\right)\ \boldsymbol{a} + 2\boldsymbol{b}$ $\left(\overline{ON} =\right) 3\boldsymbol{a}$ or $\frac{6}{2}\boldsymbol{a}$ $\left(\overline{MN} =\right)\ -\boldsymbol{a} - 2\boldsymbol{b} + 3\boldsymbol{a}$ $\left(\overline{OX} =\right)\ 2\boldsymbol{a} + \boldsymbol{b}$ $\left(\overline{OY} =\right) \boldsymbol{b} + 4\boldsymbol{a}$ (½ $\overline{QR}$ =) $2\mathbf{a} - \boldsymbol{b}$ or (½ $\overline{RQ}$ =) $\boldsymbol{b} - 2\boldsymbol{a}$	$2\boldsymbol{a} - 2\boldsymbol{b}$ $\overline{XY} = 2\boldsymbol{a}$ (hence parallel)	2 2	B2 (B1 for either $\overline{OM}$ or $\overline{ON}$ or $-\boldsymbol{a} - 2\boldsymbol{b} + 3\boldsymbol{a}$ SC: B1 for $2\boldsymbol{b} - 2\boldsymbol{a}$ B1 for either $\overline{OX}$ or $\overline{OY}$ or (½ $\overline{QR}$) B1 for $\overline{XY} = 2\boldsymbol{a}$ or $\overline{YX} = -2\boldsymbol{a}$

Paper 5525/06					
No		Working	Answer	Mark	Notes
1	(a)	$v - u = 5t$	$\frac{v-u}{5}$	2	M1 for isolating $\pm 5t$ or $\pm t$ or for dividing through by 5 A1 oe
	(b)	$x - 3 = 5x - 25$ $22 = 4x$	$5\frac{1}{2}$	3	M1 for $x - 3 = 5(x-5)$ or $\frac{x}{5} - \frac{3}{5} = x - 5$ M1 for isolating terms in x correctly from $ax + b = cx + d$ A1 cao accept $5\frac{1}{2}$, $\frac{11}{2}$, 5.5
2	(a)	$36 \div (7+3+2)$ "3" $\times 7$	21	3	M1 for $36 \div (7+3+2)$ M1 (dep) for "3" $\times 7$ or 3 or 2 A1 cao
	(b)	$51.5 \times \frac{8.5}{100} = 4.3775$ $51.5 - 4.3775 = 47.1225$	47 or 47.1 or 47.12	4	M1 for $51.5 \times \frac{8.5}{100}$ or 4.37(75) seen M1 (dep) for $51.5 -$ "4.37(75)" A1 for 47 or better B1 (indep) for rounding their answer correctly to the nearest whole number or 1 or 2 d.p OR M1 for $51.5 \times \frac{100 - 8.5}{100}$ M1 for $51.5 \times$"0.915" or $0.515 \times$"91.5" A1 for 47 or better B1 (indep) for rounding their answer correct to the nearest whole number or 1 or 2 d.p

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
3		3→15 4→48 3.1→17.3(91) 3.2→19.9(68) 3.3→22.7(37) 3.4→25.7(04) 3.5→28.8(75) 3.4→25.7(04) 3.3→22.7(37) 3.35→24.1(95375)	3.3	4	B2 for trial between 3.3 and 3.4 inclusive (B1 for trial between 3 and 4 inclusive) B1 for different trial between 3.3 and 3.4 exclusive B1 (dep on at least one previous B1) for 3.3 NB trials should be evaluated to at least 1 dp truncated or rounded
4	(a)		Angle in a semicircle	1	B1 oe
	(b)	$12^2 + 16^2 = 400$ $\sqrt{400} = 20$	20	3	M1 for $12^2 + 16^2$ M1 for $\sqrt{144+256}$ A1 cao
	(c)	$\pi \times 10^2$	314	3	M1 for $\pi \times \left(\frac{"20"}{2}\right)^2$ M1 (indep) for correct order of evaluation of $\pi \times r^2$ for any r A1 for 314 – 315 inclusive

Paper 5525/06					
No		Working	Answer	Mark	Notes
5	(a)	$(1 \times 10)+(3 \times 15)+(5 \times 30)+(7 \times 35)+$ $(9 \times 25)+(11 \times 5) = 730$ "730" $\div$ 120 = 6.08333	6.08	4	M1 for use of *fx* with *x* consistent within intervals (including end points) M1 (dep) for use of midpoints M1 (dep on 1st M1) for use of $\frac{\sum fx}{\sum f}$ A1 6.08 to 6.085
	(b)		(10),25,55,90, 115,120	1	B1 for all correct
	(c)		graph	2	B1 ft for 5 or 6 points plotted correctly $\pm$ 1 full (2mm) square at the end of interval dep on sensible table (condone 1 addition error) B1(dep) for points joined by curve or line segments provided no gradient is negative – ignore any part of graph outside range of their points. (SC: B1 if 5 or 6 points plotted not at end but consistent within each interval and joined)
	(d)		72 – 74	2	M1 (ft dep on graph being cf) for reading from graph at 7 A1 ft ±1 full (2 mm) square Or B2 for $72-74$

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
6	(a)		a^7	1	B1 accept a^{4+3}
	(b)		$15x^3y^4$	2	B2 cao (B1 for two of 15, x^3, y^4 in a product)
	(c)		$x-1$	1	B1 cao
	(d)		$(a + 3b)(a - 3b)$	2	B2 for $(a + 3b)(a - 3b)$ (B1 for $(a \pm 3b)(a \pm 3b)$
7		80% = 220 $220 \div 80 \times 100$	275	3	M1 for recognising that 80% is equivalent to 220 M1 for $220 \div 80 \times 100$ oe A1 cao
8			$x = 3$ $y = 0.5$	3	M1 for coefficients of x or y the same followed by correct operation, condone one arithmetical error M1 (dep) for substituting found value in one equation A1 cao SC: B1 for one correct answer only if Ms not awarded
9			1.4×10^{10}	2	B2 for 1.4×10^{10} or 1.44×10^{10} (B1 for 14.4×10^9 or 14400,000,000 or 14000,000,000 or 14×10^9)

Paper 5525/06					
No		Working	Answer	Mark	Notes
10	(a)	$\tan x = \frac{1.9}{3.2}$ $x = \tan^{-1}\left(\frac{1.9}{3.2}\right) = 30.7$	30.7	3	M1 for $\tan x = \frac{1.9}{3.2}$ or $\tan \frac{1.9}{3.2}$ M1 for $\tan^{-1}\left(\frac{1.9}{3.2}\right)$ A1 for 30.6 – 30.7
	(b)	90 + "30.7"	121	1	B1 (indep) ft for 90 + "30.7" rounded to 3 or 4 s.f
11	(a)	$SF = \frac{12}{9}$ $\frac{12}{9} \times 6 = 8$	2	2	M1 for $\frac{12}{9}$ or $\frac{9}{12}$ or 1.33… seen or 0.75 seen or 8 seen or $\frac{6}{9}$ or $\frac{9}{6}$ or 0.66… or 1.5 or $\frac{1}{3}$ or 3 oe seen A1 cao
	(b)	$SF = \frac{9}{12}, \frac{9}{12} \times 7 = 5.25$	5.25	2	M1 for $\frac{BE}{7} = \frac{9}{12}$ oe A1 cao

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
12	(a)	$84 = 6.7\pi + 2 \times 6.7 + 2a$ $2a + 13.4 = 62.95\ldots$ or $2a + 34.44 = 84$	24.8	3	M1 for substituting correctly, π may be left M1 for correct rearrangement as far as $\pm 2a$ A1 for $24.7 - 24.8$
	(b)	$P = \pi r + 2r + 2a$ $P - 2a = \pi r + 2r$ $P - 2a = (\pi + 2)r$	$\frac{P-2a}{\pi+2}$	3	M1 subtracting $2a$ from each side M1 for factorising to get $(\pi+2)r$ A1 for $\frac{P-2a}{\pi+2}$ oe S.C $\frac{p-2a}{5.14}$ oe is M1 M1 A0
13		Area $\Delta ABC = \frac{1}{2} \times 14 \times 8 \times \sin 106$ (= 53.8)	53.8	3	M1 for $\frac{1}{2} \times 14 \times 8 \times \sin 106$ M1 (dep) for $56 \times 0.961(26..)$ or $107.6\ldots$ A1 $53.8 - 53.9$ SC 107.6 is B2
14	(a)		4.5	1	B1 cao
	(b)	$500 \times 1.045^{20} = 1205.857\ldots\ldots$	1205.86	2	M1 for 500×1.045^{20} A1 for $1205.85 - 1206$ (SC:B1 for $705.85 - 706$ no working)

Paper 5525/06				
No	**Working**	**Answer**	**Mark**	**Notes**
15 (a)	$6x^2 + 11x - 10 + 6x - 4 = 25$ $6x^2 + 17x - 39 = 0$		3	M1 for an expression for the area involving either $(3x-2)(2x+5)+2(3x-2)$ or $3x(3x-2)+(3x-2)(7-x)$ or $3x(2x+5)-2(7-x)$ or $(3x-2)^2 + 2(3x-2) + (3x-2)(7-x)$ where in each case at least one of 2 or 3 product terms must be correct M1 (indep) for one correct expansion involving x^2 A1 for simplification to final answer

Paper 5525/06					
No		Working	Answer	Mark	Notes
15	(b)(i)	$x = \frac{-17 \pm \sqrt{17^2 - 4\times 6\times(-39)}}{2\times 6}$ $= \frac{-17 \pm \sqrt{289+936}}{12}$ $x = +\frac{18}{12}$ or -4.33	1.5, $-\frac{13}{3}$	4	M1 for $x = \frac{-17 \pm \sqrt{17^2 - 4\times 6\times(-39)}}{2\times 6}$ up to signs in b & c M1 for $x = \frac{-17 \pm \sqrt{1225}}{12}$ A1 $x = 1.5$ or -4.33, or better OR M2 for $(3x+13)(2x-3)$ (M1 for $(3x \pm a)(2x \pm b)$ with ab = ±39 A1 x = 1.5 or – 4.33, or better
		$x^2 + \frac{17}{6}x - \frac{39}{6} = 0$ $\left(x+\frac{17}{12}\right)^2 - \left(\frac{17}{12}\right)^2 - \frac{39}{6} = 0$ $\left(x+\frac{17}{12}\right)^2 = \left(\frac{17}{12}\right)^2 + \frac{39}{6}$			OR M1 for $\left(x+\frac{17}{12}\right)^2$ *seen* M1 $\left(x+\frac{17}{12}\right)^2 = \left(\frac{17}{12}\right)^2 + \frac{39}{6}$ A1 x = 1.5 or – 4.33, or better SC:M1 for answer "1.5" with no working or T & I
	(ii)		8		B1 cao length = 8

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	P(win) = $\frac{2}{5}\times\frac{3}{5}+\frac{2}{5}\times\frac{1}{5}(=\frac{8}{25})$	$\frac{8}{25}$	3	M1 for $\frac{2}{5}\times\frac{3}{5}$ or $\frac{2}{5}\times\frac{1}{5}$ or for clearly identifying in P(R) $\times$P(R) + P(B) $\times$ P(B) M1 for P(win) = " $\frac{2}{5}$ " $\times$ " $\frac{3}{5}$ " + " $\frac{2}{5}$ " $\times$ " $\frac{1}{5}$ " A1 for $\frac{8}{25}$, oe
	(b)	$\frac{8}{25}$ $\times$ 100 (=32) 100 $\times$ 20 – "32" $\times$ 50	£4	2	M1 for (" $\frac{8}{25}$ " $\times$100)$\times$50 or $\times$ 0.5 A1 cao

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
17		Lower bound of 1200 is 1150 Upper bound of 60 is 65 $1150 \div 65$	17	4	B1 for 1150 or 1250 seen B1 for 65 or 55 seen M1 (Lower bound of load) ÷ (Upper bound of weight) Where 1150 ≤ LB load < 1200 and 60 < UB Weight ≤ 65 A1 for 17 requires fully correct working OR B1 for 1150 or 1250 seen B1 for 65 or 55 seen M1 (upper bound of load) ÷(lower bound of weight) Where 1200 ‹ UB load ≤ 1250 and 55 ≤ LB weight < 60 A1 for 22 requires fully correct working OR M2 $1200 \div 55$ A1 21.8 A1 21 requires fully correct working OR M2 $1200 \div 65$ A1 18.4(6) A1 18 requires fully correct working
18	(a)	$3^4 x^4 y^8$	$81x^4y^8$	2	B2 for $81x^4y^8$ (B1 for 2 of 81, x^4, y^8)
	(b)	$\frac{x(x-3)}{(x-5)(x-3)}$	$\frac{x}{x-5}$	3	B1 for $x(x-3)$ B1 for $(x-5)(x-3)$ B1 cao

Paper 5525/06					
No		Working	Answer	Mark	Notes
19	(a)	$6^2 - 2^2 = 32$	5.66	2	M1 for $6^2 - 2^2$ (= 32) A1 5.65 – 5.66
	(b)	V  $DVA = 2 \times \sin^{-1}(\frac{2}{6})$ OR $\cos DVA = \frac{6^2 + 6^2 - 16}{2 \times 6 \times 6}$ $= \frac{56}{72}$ $DVA = \cos^{-1}\left(\frac{56}{72}\right) = 38.94$	38.9	3	M1 $\sin x = \frac{2}{6}$ oe M1 for $DVA = 2 \times \sin^{-1}(\frac{2}{6})$ A1 38.9 – 38.95 OR M1 for $(\cos DVA =) \frac{6^2 + 6^2 - 4^2}{2 \times 6 \times 6}$ M1 for $DVA = \cos^{-1}\left(\frac{56}{72}\right)$ A1 38.9 – 38.95

Paper 5525/06				
No	**Working**	**Answer**	**Mark**	**Notes**
19 (c)	$AC^2 = 2^2 + 2^2 - 2 \times 2 \times 2 \times \cos 120^o$ $AC = \sqrt{12}$ **OR** $AN = 2 \times \sin 60 = \sqrt{3}$ **OR** $VN = \sqrt{"32"+1} = \sqrt{33}$ $\cos AVC = \frac{6^2+6^2-12}{2\times 6\times 6}$ $\cos AVC = \frac{60}{72}$ **OR** $AVC = 2 \times \sin^{-1}\frac{\sqrt{3}}{6}$, using AN **OR** $AVC = 2\times\cos^{-1}\frac{\sqrt{33}}{6}$, using VN	33.6	4	M1 for any valid method for AC or AN or VN where N is the midpoint of AC A1 for $AC^2 = 12$ or $AC = \sqrt{12}$ (= 3.46…) or $AN = \sqrt{3}$ (=1.73…)or $VN = \sqrt{33}$ (=5.74…) M1 (indep) for correct method to find angle AVC A1 33.55 – 33.6

Paper 5525/06					
No		**Working**	**Answer**	**Mark**	**Notes**
20	(a)	Graph translated 1 unit to the right passing through the points (-1,0), (1,2) and (2,0)		2	M1 for translation of $\begin{pmatrix}1\\0\end{pmatrix}$ or $\begin{pmatrix}-1\\0\end{pmatrix}$ A1 for right through the 3 points, $\pm\frac{1}{4}$ sq
	(b)	Graph stretched 2 units parallel to y-axis; passing through the points (-2,0), (0,4) and (1,0)		2	M1 for graph stretched parallel to the y-axis by scale factor 2 A1 through all 3 points; $\pm\frac{1}{4}$ sq not on grid at $x = 2$

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone 01623 467467
Fax 01623 450481

Email publications@linneydirect.com

Order Code UG016720 Summer 2005

For more information on Edexcel qualifications, please visit www.edexcel.org.uk/qualifications
Alternatively, you can contact Customer Services at www.edexcel.org.uk/ask or on 0870 240 9800

Edexcel Limited. Registered in England and Wales no.4496750
Registered Office: One90 High Holborn, London, WC1V 7BH

edexcel

Edexcel GCSE

Mathematics A 1387

June 2007

advancing learning, changing lives

Mark Scheme

Edexcel GCSE
Mathematics A 1387

Table Of Contents

Notes on Marking Principles	3 - 4
5521 / 01 Mark Scheme	5 - 11
5521 / 02 Mark Scheme	12 – 17
5523 / 03 Mark Scheme	18 – 27
5523 / 04 Mark Scheme	28 – 35
5525 / 05 Mark Scheme	36 – 43
5525 / 06 Mark Scheme	44 - 52

NOTES ON MARKING PRINCIPLES

1 **Types of mark**

M marks: method marks
A marks: accuracy marks
B marks: unconditional accuracy marks (independent of M marks)

2 Abbreviations

cao – correct answer only
ft – follow through
isw – ignore subsequent working
SC: special case
oe – or equivalent (and appropriate)
dep – dependent
indep - independent

3 No working

If no working is shown then correct answers normally score full marks
If no working is shown then incorrect (even though nearly correct) answers score no marks.

4 With working

If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks. Discuss each of these situations with your Team Leader.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.
If there is no answer on the answer line then check the working for an obvious answer.

5 Follow through marks

Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

6 Ignoring subsequent work

It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: eg. incorrect cancelling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect eg algebra.
Transcription errors occur when candidates present a correct answer in working, and write it incorrectly on the answer line; mark the correct answer.

7 Probability

Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

8 Linear equations

Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

9 Parts of questions

Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

Remember: if you are having difficulty making a decision on how you should mark a candidate response contact your Team Leader for advice, or send the item to review.

Paper 5521_01					
No		Working	Answer	Mark	Notes
1		Cat |||| /||| 8 Dog |||| | 6 Fish || 2 Hamster |||| 4	8, 6, 2, 4	3	M1 for attempt to tally or one frequency correct in either column A1 for 1 frequency correct or all tallies correct in correct column A1 for all frequencies correct (accept if /20)
2			27, 35, 42, 67, 118	1	B1 cao
3	(a)		Diameter drawn	1	B1 for a diameter
	(b)		Right angle marked	1	B1 *R* marked correctly
	(c)		Rectangle drawn	1	B1 for a rectangle
4	(a)		40	1	B1 cao
	(b)		50	1	B1 cao
	(c)		3 full loaves 4 full loaves + 1 half loaf	2	B1 for 3 full loaves B1 for 4 full loaves + 1 half loaf
5	(a)		7252	1	B1 cao
	(b)		Three thousand and eighty six	1	B1 accept 3 thousand and eighty six (condone 0 hundred)
	(c)		4600	1	B1 accept 4600
	(d)		200	1	B1 for 200 or 2 hundred or 100 or hundred
6	(i)		Cube	2	B1 for 'cube' (accept 'cuboid') ignore spelling
	(ii)		Cylinder		B1 for 'cylinder' ignore spelling
7		5×100	500	2	B2 for 490 or 500 or 510 (B1 for either 5 or 5.0 or 100 seen)

Paper 5521_01					
No		Working	Answer	Mark	Notes
8	(a)		8.4 cm or 84 mm	2	B2 allow ±2mm (B1 for 8.4 or 84, B1 for appropriate unit)
	(b)		37°	1	B1 allow ±2°
9	(a)		Carbon black	1	B1 accept 'black carbon' accept 26%
	(b)		0.1(0)	1	B1 cao
	(c)		0.04	1	B1 cao
	(d)	$\frac{26}{100}$	$\frac{13}{50}$	2	M1 for $\frac{26}{100}$ A1 cao
10	(a)		97	1	B1 cao
	(b)		London Reading	1	B1 cao
	(c)	41 + 57 + 58	156	3	M1 for two of 41, 57, 58 M1(dep) for '41' + '57' + '58' A1 cao
11	(a)		3	1	B1 cao allow ± 0.2
	(b)		–5	1	B1 cao allow ±0.2

Paper 5521_01					
No		**Working**	**Answer**	**Mark**	**Notes**
12	(a)		Centimetres (cm) miles litres (*l*)	3	B3 (B1 for each correct answer) accept abbreviations
	(b)		300	1	B1 cao
	(c)	'1500>1400' or '1.5>1.4'	Reason	1	B1 for No and '1500>1400' or '1.5>1.4'
13	(a)	Height of bars 12, 8, 6 lines drawn between points	Bars drawn	2	B2 for 3 bars correctly drawn (B1 for 2 bars correct)
	(b)		July and August	1	B1 oe
	(c)	24 – 4	20	1	B1 (Accept '4 to 24' oe)
	(d)	The temperatures are rising	Temp's rising oe	1	B1 for reason
14	(a) (i)		$(-4, 3)$	2	B1 cao
	(ii)		$(2, -1)$		B1 cao
	(b) (i)	*D* marked at $(-4, -1)$	Point marked on grid	2	B1 for point marked at $(-4, -1)$ cao
	(ii)		$(-4, -1)$		B1 ft
15	(a)			1	B1 cao
	(b)			1	B1 cao

Paper 5521_01				
No	**Working**	**Answer**	**Mark**	**Notes**
16 (a)		(Pat +) reason	1	B1 correct comment (Pat may be implied)
(b)	21 ÷ 3	7	1	B1 cao
17 (i)		S marked at 1	3	B1 for S within ½ cm of 1
(ii)		P marked at 0		B1 for P marked at 0 cao
(iii)		Q marked at "1/3"		B1 for Q marked at 1/3 ± 1 cm use overlay
18	6 + 6 + 3 or $2\frac{1}{2}\times 6$	15	3	M1 for realizing 6 glasses in one bottle M1 for realizing 3 glasses in ½ a bottle A1 cao (M2 for attempt to find $2\frac{1}{2}\times 6$) oe
19	15 and 16 parts shaded Alternative 1 $\frac{3}{4}=0.75,\ \frac{4}{5}=0.8$ Alternative 2 $\frac{3}{4}=\frac{15}{20},\ \frac{4}{5}=\frac{16}{20}$	$\frac{4}{5}$ + reason	3	M1 for correctly shading 15 parts for 3/4 M1 for correctly shading 16 parts for 4/5 A1 (dependent on M2) for selection of 4/5 Alternative 1 M1 for $\frac{3}{4}=0.75$ M1 for $\frac{4}{5}=0.8$ A1 (dep on M2) for selection of 0.8 or $\frac{4}{5}$ or $\frac{16}{20}$ Alternative 2 M1 for $\frac{3}{4}=\frac{15}{20}$ M1 for $\frac{4}{5}=\frac{16}{20}$ A1(dep on M2) for selection of $\frac{4}{5}$ or $\frac{16}{20}$

Paper 5521_01				
No	**Working**	**Answer**	**Mark**	**Notes**
20 (a)		−5 (−3) (−1) 1 3 5	2	B2 cao (B1 for any 2 or 3 correct)
(b)	Points plotted	Line	2	B2 for line from (−1, −5) to (4, 5) (B1 ft for plotting at least 5 "points")
21	Shapes shaded on grid	6 tessellating shapes	2	B2 for fully correct with 5 or more additional shapes, no gaps (B1 for 4 shapes tessellating with at least one shape inverted, with or without the given shape ignore extras)
22 (a)		$\frac{7}{20}$	1	B1 for $\frac{7}{20}$ oe
(b)	7 + 2 (or 20 – 11) are not lime flavour	$\frac{9}{20}$	1	B1 for $\frac{9}{20}$
(c)		0	1	B1 for 0, zero or nought ($\frac{0}{20}$ gets B0)
23 (a)		$4a$	1	B1 accept $4\times a$, $a \times 4$, $a4$
(b)		$12b$	1	B1 accept $12\times b$, $b \times 12$, $b12$
(c)		$2a + 6b$	2	B2 cao (B1 for $2a$ or $6b$ seen)
(d)		$x(x-6)$	2	B2 cao (B1 for $x(ax+b)$ where a, b are numbers not equal to 0 or $x - 6$ seen on its own, or as part of an expression)
24 (a)		40	1	B1 cao
(b)		45	1	B1 for 42 – 48 accept ¾ hour
(c)	40×2 or $\frac{40}{30}\times 60$ or $40\div\frac{1}{2}$	80	2	M1 for 40×2 or $\frac{40}{30}$ or $40\div\frac{1}{2}$ A1 cao NB $\frac{40}{45}\times 60$ gets M0 A0

Paper 5521_01					
No		**Working**	**Answer**	**Mark**	**Notes**
25	(a)		4560	1	B1 cao
	(b)		45.6	1	B1 cao
	(c)		2.4	1	B1 cao
26		$-7 - 3 = -10$ $2 \times -10 = -20$ $-20 \div 4$	-5	3	M1 for substitution of 2 and –7 into $p(q - 3)$ or sight of -20 or $-14 - 6$ M1dep for '–20' ÷ 4 A1 cao B1 SC for sight of –10 if M0 awarded
27	(a)		Reflection in y-axis	1	B1 cao
	(b)		Rotation by half turn about (0,0)	2	B2 cao (B1 for half turn not about (0,0).)
	(c)		Enlargement Scale factor 3 Centre (0,0)	3	B1 for 'enlargement' B1 for "scale factor 3" or 3 seen B1 for 'centre (0,0)
28	(a)		Reason	1	B1 for 'The frequencies are nearly equal' oe
	(b)	$1\times26+2\times26+3\times23+4\times25 = 247$ 247/100	2.47	3	M1 for fx (attempting at least 2 relevant products) M1 for $\sum fx \div 100$ A1 2.47 cao

Paper 5521_01				
No	**Working**	**Answer**	**Mark**	**Notes**
29	5 × 5 × 6	150	4	M1 for attempt at 1 division (e.g. 40 ÷ 8), may be implied by marks or number on one edge of diagram or by 5 or 6 seen M1 for attempt at 3 divisions (40÷8, 40÷8, 60÷10), may be implied by marks or numbers on diagram or by 5,5 and 6 seen. M1 (dep on 1st M1) for "5" × "5" × "6" A1 cao Alternatively M1 for 40 × 40 × 60 **or** 8 × 8 × 10 **or** 96000 or 640 seen M1 for 40 × 40 × 60 **and** 8 × 8 × 10 or 96000 **and** 640 seen M1 (dep on 1st M1) for "(40 × 40 × 60)" ÷ "(8 × 8 × 10)" A1 cao SC:B1 for dividing area of one carton face by area of corresponding box face if M0

Paper 5521_02					
No		Working	Answer	Mark	Notes
1	(a)	Draw diagram.	Diagram	1	B1 cao
	(b)		13,16	1	B1 cao
	(c)		31	1	B1 cao
2	(a)		8	1	B1 cao
	(b)		14	2	B2 for 14 (B1 for 13 or 15)
	(c)		16	2	B2 for 16 (B1 for 15, 17 or 8)
3	(a)		4,7 drawn	2	B2 for car height 4 and bus height 7, (B1 for one correct)
	(b)		6	1	B1 cao
	(c)		Walk	1	B1
	(d)		27	1	B1 cao
4	(a)		40	1	B1 for 40–41 inclusive
	(b)		12	1	B1 for 11.5 – 12.5 inclusive
5	(a)		Row complete	2	B2 for 1+..+11; 36 (B1 for one of the 2 cells complete)
	(b)		Square	1	B1 "square"
6		One line of symmetry		1	B1 within 2mm of centre of base / 2mm of vertex

Paper 5521_02				
No	**Working**	**Answer**	**Mark**	**Notes**
7 (a) (i)		09 06	2	B1 (accept 9 06 oe)
(ii)		39		B1 cao
(b)		06 55	1	B1 (accept 6 55 oe)
(c)		2h 6min	1	B1 cao
(d)		15 min	2	M1 for 0906 – 0645 – "(c)" or 0906 – 0645 − 2hr 6min or 2hr 21min − "(c)" or 2hr 21min − 2hr 6 min or 141 − 126 or 20 − 5 A1 cao SC: B1 for 55 or 75 or 93 seen
8 (i)		8,10,12,20 or 30	3	B1 at least one of 8, 10, 12, 20, 30 (no extras)
(ii)		8,12 or 20		B1 at least one of 8,12, 20 (no extras)
(iii)		3 or 5		B1 3 or 5 or both (no extras)
9 (a)		C or G	1	B1 at least one of C or G (no extras)
(b)		A and F	1	B1 cao
(c)		2	1	B1 (accept –2)
10 (a)		$\frac{7}{10}$	1	B1 7/10 oe
(b)(i)		4 squares	2	B1 4 squares shaded
(ii)		80%		B1 80% or ft from unshaded part (no ft from 0% or 100%)
(c)(i)		2.5	2	B1 2.4–2.6 inclusive
(ii)		1.7		B1 1.6–1.8 inclusive
11 (a)		2	1	B1 for 2 or –2
(b)		14	1	B1 for 14 or –14

Paper 5521_02					
No		**Working**	**Answer**	**Mark**	**Notes**
12		2 × 8.50 = 17.00 3 × 4.50 = 13.50 Total = 30.50 50.00 – 30.50	19.5(0)(*p*)	3	M1 for adding 5 correct values or 2 × 8.50 + 3 × 4.50 (ignore units) or 30.5(0) or 3050 seen M1 dep for 50 − "30.50" (ignore units) (OR M1for adding at least 1 adult ticket and at least 1 child ticket **and** subtracting from 50) A1 cao SC: B1 for 24 or 37 or 2400 or 3700 seen
13	(a)		Hexagon	1	B1
	(b)(i)		120	2	B1 cao
	(ii)		Str line		B1 reference to a (straight) line and 180°
	(c)		Obtuse	1	B1 Accept "interior"
14	(a)	2, 2, 3, 3, 3, 4, 4, 4, 5, 6	3.5	2	M1 ordering the numbers (condone 1 error or omission) A1 cao
	(b)	36 ÷ 10	3.6	2	M1 sum of numbers ÷ 10 A1 cao SC B1 for 3r 6
	(c)	6 – 2	4	1	B1 cao
15	(a)		Paul	1	B1 cao
	(b)	36 ÷ 2 oe	18	1	B1 cao
	(c)	60/360 =	1/6	2	M1 60/360 oe A1 cao

Paper 5521_02					
No		**Working**	**Answer**	**Mark**	**Notes**
16		4.7 ÷ 5.9 = 0.796610169	0.7966..	2	B2 for 0.7966 or better (B1 for 0.8, 0.80, 0.79, 0.796, 0.797 or digits 59 seen
17		$6x - 7 + 7 = 38 + 7$ $6x = 45$	7.5	2	M1 $6x = 45$ or +7 both sides A1 7.5 oe; accept 45/6 oe
18		**55** 61 74 **190** 33 **17** **10** 60 **88** **78** 84 250	**55** 61 74 **190** 33 **17** **10** 60 **88** **78** 84 250	3	B3 all six entries correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
19	(a)	900 × 1.70 =	1530	2	M1 900 × 1.7(0) or digits 153(0) seen A1 cao
	(b)	160 ÷ 1.70 =	£94.12 or £94.11	2	M1 160 ÷ 1.7(0) or digits 941(....) seen A1 cao
20	(a)(i)	180 – 54 (=126) "126" ÷ 2	63	3	M1 for (180–54) ÷ 2 A1 cao
	(ii)		Reason		B1 (indep) angles in triangle add to 180 OR equal angles in isosceles triangle OR equal angles and 2 sides the same (B0 if any incorrect reasoning given eg parallel, equilateral triangle)
	(b)	180 – "x"	117	1	B1 117 or ft 180 – "x" if $x < 90$
21	(a)	3 × 35 + 50	155	2	M1 for 3 × 35 + 50 or digits 155 seen A1 cao
	(b)	260 – 50 = 210 210 ÷ 35 =	6	3	M1 for 260–50 or 210 seen. M1 for "260-50" ÷ 35 or 210÷35 A1 cao SC B1 for starting at a number between 100 and 170 and adding at least two 35's and showing a total between 230 and 290 OR For adding at least three 35's, perhaps with other numbers, and showing a total between 180 and 240 (or between 230 and 290 if 50 is included in the sum)

Paper 5521_02				
No	**Working**	**Answer**	**Mark**	**Notes**
(c)		P=35h + 50	3	B3 for P=35h+50 or P=35×h+50 oe (B2 for correct RHS or P=h + 50 ×35 or P=35h+k where k is numerical oe) (B1 for P = some other linear expression in h, OR h + 50 ×35 OR 35h seen) NB: P=h scores no marks; ignore £ signs. SC B2 for $h = \frac{P-50}{35}$
22 (a)		Elevation	2	B2 for 4 vertical squares. Accept 4 by 1 rectangle. (B1 for 4 vertical squares with one square added or one parallelogram added at the top, or 3 vertical squares, or 4 horizontal squares)
(b)		Plan	2	B2 for 2 adjacent squares, vertical or horizontal. Accept 2 by 1 rectangle. (B1 for 3 adjacent horizontal or vertical squares or a rectangle with sides in the ratio 2:1)
23 (i) (ii) (iii)		5 9 6	3	B1 cao B1 cao B1 cao
24	$45.00 + 45.00 \times \frac{15}{100} =$ $45.00 + 6.75 =$	51.75	3	M2 for $45.00 + 45.00 \times \frac{15}{100}$ oe or 45.00×1.15 oe OR $45.00 + 6.75$ OR complete method or 5175 seen. (M1 for $45.00 \times \frac{15}{100}$ oe OR 6.75 seen OR 675 seen OR correct method for calculating 15% of 45) A1 cao SC Award B2 for an answer of 38.25

Paper 5521_02				
No	**Working**	**Answer**	**Mark**	**Notes**
25 (a)		Points	1	B1 all three points ±1 full square
(b)		Negative	1	B1 Negative (ignore additional descriptors unless contradictory)
(c)		lobf	1	B1 A single straight line drawn to cross between (5,30), (5,40) and (40,0), (40,15); accept freehand if considered to be straight.
(d)(i)		18–25	2	B1 18g–25g inclusive OR if not in this range ft ±1 square dep on single straight line with negative gradient.
(ii)		30–40		B1 30–40 min inclusive OR if not in this range ft ±1 square dep on single straight line with negative gradient
26		300 3 75 150	3	B3 for 4 correct answers (B2 for 2 or 3 correct answers) (B1 for 1 correct answer)
27	π × 0.65	2.04–2.05	2	M1 for π × 0.65 or 3.14 x 0.65 or 3.142 x 0.65 A1 for 2.04–2.05 SC Award B1 for 2.0 seen (not 2)
28	5 miles = 8 km 70mph÷5×8 = 112 km/h OR 120km/h ÷ 8 × 5 = 75 mph Faster than 70 mph	70mph (Great Britain) (112 km)	3	M1 5 miles = 8 km; OR 70 mph is about 100 km/h OR 1km=0.6(25) miles OR 1mile=1.6km oe M1 70 ÷ 5 × 8 (=112) or 120 ÷ 8 × 5 (=75) A1 (dep on at least M1) GB or 70 mph Refer to both answer line and working. NB GB or 70 mph without working scores 0 marks

Paper 5523_03				
No	**Working**	**Answer**	**Mark**	**Notes**
1		Cuboid drawn	2	B2 for correct isometric drawing in any orientation (ignore points 'behind', mark 7 vertices only); accept lines drawn near to dots as long as there is no ambiguity. (B1 for one of the three faces drawn correctly **or** for an isometric drawing of any cuboid)
2	Different makes of car Tally Frequency	Make of car Tally Frequency	3	B1 for make of car or list of at least 3 different makes B1 for tally or tally marks B1 for frequency or totals
3		6 tessellating shapes	2	B2 for fully correct with 5 or more additional shapes, no gaps (B1 for 4 or more shapes tessellating, with at least one shape inverted, with or without the given shape, ignore extras)
4	24.90 ÷ 3 or 8.30 24.90 – '8.30' or 2 × 8.30	16.6(0)	3	M1 for 24.90 ÷ 3 or 8.30 M1 (dep) for 24.90 – “8.30” or 2 × “8.30” A1 for 16.60 or 16.6

Paper 5523_03

No	Working	Answer	Mark	Notes
5	315 × 24 24 × 315 1260 6300 7560 7200 7560 **3 1 5** 0 6 | 0 2 | 1 0 — **2** 1 2 | 0 4 | 2 0 — **4** 7 5 6 0 **300 10 5** 6000 200 100 — **20** 1200 40 20 — **4** 6000+200+100+1200+40+20 = 7560 **3 0.1 0.05** 60 2 1 — **20** 12 0.4 0.2 — **4** 60 + 2 + 1 + 12 + 0.4 + 0.2 = 75.6	75.6(0)	3	M1 for a complete method with relative place value correct. Condone 1 multiplication error, addition not necessary. **OR** M1 for a complete grid with not more than 1 multiplication error, addition not necessary. **OR** M1 for sight of a complete partitioning method, condone 1 multiplication error, final addition not necessary. A1 for 7560 or digits 756(0) A1 (dep on M1, but not previous A1) for correct placement of decimal point.

Paper 5523_03				
No	**Working**	**Answer**	**Mark**	**Notes**
6	15 and 16 parts shaded Alternative 1 $\frac{3}{4} = 0.75$ or 75%, $\frac{4}{5} = 0.8$ or 80% Alternative 2 $\frac{3}{4} = \frac{15}{20}$, $\frac{4}{5} = \frac{16}{20}$	$\frac{4}{5}$ + reason	3	M1 for shading 15 parts for $\frac{3}{4}$ M1 for shading 16 parts for $\frac{4}{5}$ A1 (dep on M2) for selection of $\frac{4}{5}$ with correct shading Alternative 1 M1 for $\frac{3}{4} = 0.75$ or 75% M1 for $\frac{4}{5} = 0.8$ or 80% A1 (dep on M2) for selection of 0.8 or 80% or $\frac{4}{5}$ with correct decimals or percentages Alternative 2 M1 for $\frac{3}{4} = \frac{15}{20}$ oe M1 for $\frac{4}{5} = \frac{16}{20}$ oe A1 (dep on M2) for selection of $\frac{4}{5}$ or $\frac{16}{20}$ with equivalent fractions

Paper 5523_03					
No		**Working**	**Answer**	**Mark**	**Notes**
7		$5 \times 5 \times 6$	150	4	M1 for attempt at 1 division (e.g. 40 ÷ 8), may be implied by marks or number on one edge of diagram or by 5 or 6 seen M1 for attempt at 3 divisions (40÷8, 40÷8, 60÷10), may be implied by marks or numbers on diagram or by 5,5 and 6 seen. M1 (dep on 1st M1) for "5" × "5" × "6" A1 cao Alternatively M1 for 40 × 40 × 60 **or** 8 × 8 × 10 **or** 96000 or 640 seen M1 for 40 × 40 × 60 **and** 8 × 8 × 10 or 96000 **and** 640 seen M1 (dep on 1st M1) for "(40 × 40 × 60)" ÷ "(8 × 8 × 10)" A1 cao SC:B1 for dividing area of one carton face by area of corresponding box face if M0
8	(a)		$\frac{7}{20}$	1	B1 for $\frac{7}{20}$ oe
	(b)	7 + 2 (or 20 – 11) are not lime flavour	$\frac{9}{20}$	1	B1 for $\frac{9}{20}$ oe
	(c)		0	1	B1 for 0, zero or nought ($\frac{0}{20}$ gets B0)
9	(a)		$80x$	1	B1 for $80x$ (accept $80 \times x$, $x80$, $x \times 80$) seen
	(b)		$95y$	1	B1 for $95y$ (accept $95 \times y$, $y95$, $y \times 95$) seen
	(c)		$80x + 95y$	2	M1ft for adding "$80x$" and "$95y$" (algebraic expressions only) A1 for $80x + 95y$

Paper 5523_03

No	Working	Answer	Mark	Notes
10 (a)		40	1	B1 cao
(b)		45	1	B1 for 42 to 48 (accept 3/4 hour)
(c)	40×2 or $\frac{40}{30}\times60$ or $40\div\frac{1}{2}$	80	2	M1 for 40×2 or $\frac{40}{30}$ or $40\div\frac{1}{2}$ A1 cao NB $\frac{40}{45}\times 60$ gets M0 A0
11 (a)	$3\times3-4\times2$ or $9-8$	1	2	M1 for substitution of 3 and 2 into expression or 9 and 8 seen A1 cao
(b)	$-7-3=-10$ $2\times-10=-20$ $-20\div4$	-5	3	M1 for substitution of 2 and –7 into p(q – 3) or sight of -20 or –14 – 6 M1 (dep) for "–20" ÷ 4 A1 cao SC: B1 for –10 seen if M0
12 (a)	6 | 8 9 7 7 | 8 5 9 6 3 8 | 1 3 1 7 1 9 | 0 1	6 | 7 8 9 7 | 3 5 6 8 9 8 | 1 1 1 3 7 9 | 0 1	3	M1 for unordered diagram (condone one error) A1 cao B1 for key (eg 6 | 7 = 67)
(b)(i)		Explanation	2	B1 for '(order numbers and) select middle value' oe
(ii)		79		B1 cao

Paper 5523_03					
No		**Working**	**Answer**	**Mark**	**Notes**
13	(a)		Reflection in y-axis	1	B1 for triangle with vertices at (-1, 1) (-3, 1) and (-1,4)
	(b)		Rotation by half turn about (0, 0)	2	B2 for triangle with vertices (-1, -1) (-3, -1) and (-1, -4) (B1 for half turn not about (0,0))
	(c)		Enlargement Scale factor 3 Centre (0, 0)	3	B1 for 'enlargement' B1 for 'scale factor 3' or 3 seen B1 for 'centre (0,0)' B0 for any combination of transformations
14	(a)		4560	1	B1 cao
	(b)		45.6	1	B1 cao
	(c)		2.4	1	B1 cao
15	(a)	$4a-2a+5b+b$	$2a+6b$	2	B2 cao (B1 for $2a$ or $6b$ seen)
	(b)		$x(x-6)$	2	B2 cao (B1 for $x(ax+b)$ where a, b are numbers not equal to zero or $x-6$ seen on its own, or part of an expression)
	(c)		$3x-2x^3$	2	B2 cao (B1 for $3x$ or $2x^3$)
	(d)		$4x(3y+x)$	2	B2 cao (B1 for $2(6xy+2x^2)$ or $4(3xy+x^2)$ or $x(12y+4x)$ or $2x(6y+2x)$ or $4x(\quad)$)

Paper 5523_03					
No		**Working**	**Answer**	**Mark**	**Notes**
16	(a)	$1 - (0.2 + 0.3 + 0.1)$	0.4	2	M1 for $1 - (0.2 + 0.3 + 0.1)$ A1 for 0.4 oe, accept $\frac{0.4}{1}$
	(b)	0.2×200	40	2	M1 for 0.2×200 A1 cao NB $\frac{40}{200}$ is M1 A0, 40 out of 200 is M1 A1
17	(a) (i)	$180 - 2 \times 25$	130	3	M1 for $180 - 2 \times 25$ A1 cao
	(ii)		Reason		B1 for mentioning isosceles and equal (or base) angles or equal sides and equal (or base) angles
	(b)	$180 - 95$	85	1	B1 cao
18	(a) (i)		7^5	3	B1 cao
	(ii)		7^4		B2 cao (B1 for sight of 7^5 or 7^{2+3} or 7×7^3 or $7^1 \times 7^3$ or $7^2 \times 7^2$ or 7^{2+3-1})
	(b)		$\frac{1}{2}$	1	B1 for $\frac{1}{2}$ or 0.5 or 2^{-1}
19	(a)		3×10^7	1	B1 cao
	(b)		0.002	1	B1 cao

Paper 5523_03				
No	**Working**	**Answer**	**Mark**	**Notes**
20		Box plot	2	3 aspects: 1st aspect – vertical line for median 2nd aspect – box using correct quartiles 3rd aspect – whiskers (could be single line) drawn with correct end points B2 for fully correct box plot (B1 for 1 aspect)
21 (a)	e.g. 2 | 126 3 | 63 3 | 21 7	$2\times3\times3\times7$	2	M1 for a systematic method of at least 2 correct divisions by a prime number oe factor trees; can be implied by digits 2, 3, 3, 7 on answer line. A1 for $2\times3^2\times7$ or $2\times3\times3\times7$
(b)	$2\times3\times7$	42	2	B2 cao (B1 for 6, 14, 21 or $2\times3\times7$)
22	$\frac{8}{3}\times\frac{5}{4}=\frac{8\times5}{3\times4}=\frac{40}{12}$	$3\frac{1}{3}$	3	B1 for $\frac{8}{3}$ oe improper fraction or $\frac{5}{4}$ oe improper fraction M1 (dep on B1) for multiplying numerator and denominator of "$\frac{8}{3}$" and "$\frac{5}{4}$" A1 for $3\frac{1}{3}$ oe mixed number or $\frac{10}{3}$ OR B1 for 1.25 and 2.67 or 2.66(…) M1 (dep on B1) for correct method of multiplication A1 for $3.\dot{3}$

Paper 5523_03				
No	**Working**	**Answer**	**Mark**	**Notes**
23			2	M1 for a relevant pair of intersecting arcs A1 for line drawn within guidelines, at least 3cm in length, accept broken line [SC: B1 for line drawn within guidelines if M0]
24 (a)		$-1, 0, 1, 2, 3$	2	B2 cao (-1 each error or omission)
(b)(i)		$x \geq \frac{7}{2}$	3	M1 for $2x \geq 7$, condone use of = sign or wrong equality A1 for $x \geq \frac{7}{2}$ oe as final answer
(ii)		4		SC:B1 for 3.5 or $\frac{7}{2}$ seen if M0 B1 ft from $x \geq$ "$\frac{7}{2}$"
25	$4x + 2y = 8$ $4x - 10y = 20$ $12y = -12$ $y = -1$ $4x + 2(-1) = 8$ $x = 2.5$	$x = 2.5$ $y = -1$	3	M1 for correct process to eliminate either x or y (condone one arithmetical error) M1 (dep) for substituting found value into either equation A1 for $x = 2.5$, $y = -1$ [SC: B1 for $x = 2.5$ or $y = -1$ if M0]

Paper 5523_03					
No		**Working**	**Answer**	**Mark**	**Notes**
26		Interior angle of hexagon = 180 – (360 ÷ 6) = 120 360 – (90 + 120)	150	4	Alternative 1 M1 for 360 ÷ 6 A1 for 60 M1 (dep on M1) for "60" + 90 A1 cao Alternative 2 M1 for 360 ÷ 6 A1 for 60 M1 (dep on M1) for 360 – (2 × "60" + 90) A1 cao Alternative 3 M1 for (6 – 2) × 180 ÷ 6 A1 for 120 M1 (dep on M1) for 360 – (90 + "120") A1 cao
27	(a)		(16), 50, 82, 96, 100	1	B1 cao
	(b)	Cumulative freq. diag. curve/ segments	Cum. freq graph	2	B1 for 4 or 5 points plotted correctly ± 1 full (2mm) square depending on sensible table (condone 1 addition error) B1 (dep) for points joined by curve or line segments provided no gradient is negative - ignore any part of graph outside range of their points. (SC:B1 if 4 or 5 points plotted not at end but consistent within each interval and joined)
	(c)	100 – 42	58	2	M1 (ft dep on graph being cf) for reading from graph at 18 or 19, can be implied by answer in range 40 to 46 A1 for answer in range 56 to 60 or ft for 100 – '42' ±1 full (2mm) square

Paper 5523_04					
No		**Working**	**Answer**	**Mark**	**Notes**
1	(a)	900 × 1.70 =	1530	2	M1 900 × 1.7(0) or digits 153(0) seen A1 cao
	(b)	160 ÷ 1.70 =	£94.12 or £94.11	2	M1 160 ÷ 1.7(0) or digits 941(....) seen A1 cao
2	(a)	4.7 ÷ 5.9 = 0.796610169	0.7966..	2	B2 for 0.7966 or better (B1 for 0.8, 0.80, 0.79, 0.796, 0.797 or digits 59 seen)
	(b)	0.82, 0.8, 0.85, 0.66, 0.875 0.66, 0.8, 0.82, 0.85, 0.875 2/3, 4/5, 0.82, 85%, 7/8	2/3, 4/5, 0.82, 85%, 7/8	2	B2 correct order (oe decimals in order) (B1 correct order reversed, or one error in ordered listing) with or without decimal equivalents. NB Accept 0.67 or 0.66
3		**55** 61 74 **190** 33 **17** **10** 60 **88** **78** 84 250	**55** 61 74 **190** 33 **17** **10** 60 **88** **78** 84 250	3	B3 all 6 correct (B2 for 4 or 5 entries correct) (B1 for 2 or 3 entries correct)
4	(a)	–3 (–1) (1) 3 5 7	**–3**, 3, **5**, **7**	2	B2 all correct (B1 2,3 correct)
	(b)	(-2,-3),(-1,-1),(0,1),(1,3),(2,5),(3,7)	line	2	B2 cao for line from $x = -2$ to $x = 3$ (B1 plotting at least 5 points correctly or single line passing through (0, 1) or single line of gradient 2) The six possible points are: (-2,-3), (-1,-1), (0,1), (1,3), (2,5), (3,7)
	(c)(i)		–2	2	B1 $y = -2$ or ft from line segment
	(ii)		2.5		B1 $x = 2.5$ or ft from line segment

Paper 5523_04					
No		**Working**	**Answer**	**Mark**	**Notes**
5	(a) (i)	180 – 54 (=126) "126" ÷ 2	63	3	M1 for (180–54) ÷ 2 A1 cao
	(ii)		Reason		B1 (indep) angles in triangle add to 180 OR equal angles in isosceles triangle OR equal angles and 2 sides the same (B0 if any incorrect reasoning given eg parallel, equilateral triangle)
	(b)	180 – "x"	117	1	B1 117 or ft 180 – "x" if $x < 90$
6		15/120×360 = 45 Plain 40/120×360 = 120 Cheese & Onion 55/120×360 = 165 Salt & Vinegar 10/120 × 360 = 30 Beef	45°, 120°, 165°, 30°	4	M1 evidence of method for at least one angle (could be implied by one correct angle of four on pie chart or in the table) A2 All four angles drawn ±2° tolerance, any order (A1 at least 2 angles correctly drawn ±2°, or all 4 angles in the table) B1 (dep on at least 1 angle drawn correctly, and exactly 4 sectors) for labels (flavour or frequency; initials will do) NB: Ignore the table if the pie chart provides the marks.
7	(a)	260 – 50 = 210 210 ÷ 35 =	6	3	M1 for 260–50 or 210 seen. M1 for "260-50" ÷ 35 or 210÷35 A1 cao
	(b)		P=35h + 50	3	B3 for P=35h+50 or P=35×h+50 oe (B2 for correct RHS or P=h + 50 ×35 or P=35h+k where k is numerical oe) (B1 for P = some other linear expression in h, OR h + 50 ×35 OR 35h seen) NB: P=h scores no marks; ignore £ signs. SC B2 for $h = \frac{P-50}{35}$
8	(a)		Elevation	2	B2 for 4 vertical squares. Accept 4 by 1 rectangle. (B1 for 4 vertical squares with one square added or one parallelogram added at the top, or 3 vertical squares, or 4 horizontal squares)

Paper 5523_04				
No	**Working**	**Answer**	**Mark**	**Notes**
(b)		Plan	2	B2 for 2 adjacent squares, vertical or horizontal. Accept 2 by 1 rectangle. (B1 for 3 adjacent horizontal or vertical squares or a rectangle with sides in the ratio 2:1)
9 (a)		Points	1	B1 all three points ±1 full square.
(b)		Negative	1	B1 Negative. Ignore other descriptors unless contradictory.
(c)		lobf	1	B1 A single straight line drawn to cross between (5,30), (5,40) and (40,0), (40,15); accept freehand if considered to be straight.
(d)(i) (ii)		18–25 30–40	2	B1 18g–25g inclusive OR if not in this range ft ±1 square dep on single straight line with negative gradient. B1 30–40 min inclusive OR if not in this range ft ±1 square dep on single straight line with negative gradient.
10		300, 3, 75, 150	3	B3 for 4 correct (B2 for 2 or 3 correct) (B1 for 1 correct)
11 (a)	$6x - 7 + 7 = 38 + 7$ $6x = 45$	7.5	2	M1 $6x = 45$ or +7 both sides A1 7.5 oe; accept 45/6
(b)	$5y - 2 = 10$ or $20y - 8 = 40$ $5y = 12$ $20y = 48$	$2\frac{2}{5}$	3	M1 $20y–8(=40)$ or $\frac{4(5y-2)}{4} = \frac{40}{4}$ or $5y–2=10$ M1 (indep) for correct rearrangement into the form $ay=b+c$ or better (eg $20y=40+8$ or $5y=10+2$, using own terms) A1 for $2\frac{2}{5}$, 2.4 oe
12	5 miles = 8 km 70mph÷5×8 = 122 km/h OR 120km/h ÷ 8 × 8 = 75 mph Faster than 70 mph	70mph (Great Britain) (112 km)	3	M1 5 miles = 8 km; OR 70 mph is about 100 km/h OR 1km=0.6(25) miles OR 1mile=1.6km oe M1 70 ÷ 5 × 8 (=112) or 120 ÷ 8 × 5 (=75) oe A1 (dep on at least M1) GB or 70 mph Refer to both answer line and working. NB GB or 70 mph without working scores 0 marks.

Paper 5523_04				
No	**Working**	**Answer**	**Mark**	**Notes**
13 (a)	$\pi \times 0.65$	2.04–2.05	2	M1 for $\pi \times 0.65$ or 3.14×0.65 or 3.142×0.65 oe A1 2.04–2.05 SC Award B1 for 2.0 seen (not 2)
(b)	1000 ÷ "(a)"	487–491	2	M1 for 1000 (or 100) ÷ "(a)" A1 for 487–491
14	$45.00 + 45.00 \times \frac{15}{100} =$ $45.00 + 6.75 =$	51.75	3	M2 for $45.00 + 45.00 \times \frac{15}{100}$ oe or 45.00×1.15 oe OR $45.00 + 6.75$ OR complete method or 5175 seen. (M1 for $45.00 \times \frac{15}{100}$ oe OR 6.75 seen OR 675 seen OR correct method for calculating 15% of 45) A1 cao SC Award B2 for an answer of 38.25
15		273	2	M1 for 728 ÷ 8 or 728 ÷ "3+5" or 91 A1 cao SC B1 for 455, or for 273:455
16	3 24 3.7 46.9(53) 4 60 3.8 51.0(72) 3.1 26.6(91) 3.9 55.4(19) 3.2 29.5(68) 3.21 29.8(66…) 3.3 32.6(37) 3.22 30.1(66…) 3.4 35.9(04) 3.23 30.4(68..) 3.5 39.3(75) 3.24 30.7(72...) 3.6 43.0(56) 3.25 31.0(78...) or 31	3.2	4	B2 for trial between 3.2 and 3.3 inclusive (B1 for trial between 3 and 4 inclusive) B1 for different trial between 3.21 and 3.25 inclusive B1 (dep on at least one previous B1) cao for 3.2 as final answer. NB: embedded answers: –B1; award Bs for evaluations rounded or truncated to at least 1 dp or for 31

Paper 5523_04				
No	**Working**	**Answer**	**Mark**	**Notes**
17	$45^2 + 34^2 =$ $2025 + 1156 = 3181$ $\sqrt{3181} = 56.4$	56	4	M1 for $45^2 + 34^2$ M1 (dep) for $\sqrt{(2025 + 1156)}$ A1 for 56.4 … B1 for rounding their diagonal to the nearest integer (dep on evidence from decimal) NB 56 as the final answer gets full marks. NB Scale drawings result in 0 marks.
18	$2000 \times (1.055)^3$ Interest = 2348.48 – 2000 =	348.48	3	M1 for 5.5/100 × 2000 (oe) or 330 or 2330 or 110 or 2110 M1 (dep) for 5.5/100 × (2000 + "110" + "116.05") or 122.4… seen A1 cao (accept only 348.48 or 348.49) **OR** M2 for $2000 \times (1.055)^3$ or 2348.48(…) or 2348.49 seen (M1 for $2000 \times (1.055)^n$, $n \neq 3$) A1 for 348.48 or 348.49 [SC: B2 for 2348.48 - 2348.49]
19		Line	2	B2 line fully within tramlines, crossing AB and CD (B1 a straight line which crosses AB within the tramline, and also crosses CD) NB: Accept dotted or dashed lines, but not curves; accept freehand if considered to be straight. SC B1 for a perpendicular bisector of AB that is at least half way from AB to CD within the tramlines
20 (a)		$90<t\leq100$	1	B1 for $90<t\leq100$; accept 90-100.
(b)	65×12=780 75×22=1650 85×23=1955 95×24=2280 105×19=1995 8660/100=	86.6	4	M1 for use of fx with x consistent within intervals (including end points). Allow one slip. M1 (dep) for use of midpoints M1 (dep on 1st M1) for use of $\sum fx/100$ or $\sum fx/\sum f$ A1 86.6

Paper 5523_04					
No		**Working**	**Answer**	**Mark**	**Notes**
21	(a)	$8 \times \frac{10}{4}$	20	2	M1 $\frac{10}{4}$ or $\frac{4}{10}$ or 0.4 or 2.5 oe seen A1 cao NB ratios get M0 unless of the form 1:*n* OR M1 $\frac{8}{4}, \frac{4}{8}$ oe seen A1 cao
	(b)	$15 \times \frac{4}{10}$	6	2	M1 $15 \times \frac{4}{10}$ oe A1 cao
22	(a)	$x^2 - 4x + 3x - 12 = x^2 - x - 12$	$x^2 - x - 12$	2	M1 for exactly 4 terms correct ignoring signs (eg x^2, 4*x*, 3*x*, 12) or 3 correct terms out of 4 terms with correct signs (eg 3 out of 4 of x^2, –4*x*, +3*x*,–12) A1 cao
	(b)	$(x+2)(x+5)$	$(x+2)(x+5)$	2	B2 cao (B1 for exactly one of $(x+2)$, $(x+5)$)
	(c)	$6=15+4q-20$ $6-15=4(q-5)$ $p-3t=4q-4t$ $6-3\times5=4(q-5)$	2 ¾	3	M1 for correct substitution of *p* and *t*. M1 for correct expansion of $4(q-t)$ oe (eg $4q-20$, $4q-4t$) A1 11/4 or 2 ¾ or 2.75 OR M1 for correct substitution of *p* and *t*. M1 for $\frac{p-3t}{4} = q - t$ oe A1 11/4 or 2 ¾ or 2.75

Paper 5523_04					
No		**Working**	**Answer**	**Mark**	**Notes**
23	(a)	$9.9\times10^8 - 6.0\times10^7$	9.3×10^8	2	M1 for $99\times10^7 - 6\times10^7$ or $9.9\times10^8 - 0.6\times10^8$ or conversion of either to an ordinary number, or 930000000 or 93×10^7 or 9.3×10^n where n is any positive integer A1 cao
	(b)	$\frac{6.0-4.5}{4.5}\times100 = \frac{1.5}{4.5}\times100 =$ or $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7}\times100$	33.3%	3	M2 $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7}\times100$ oe (M1 for $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7}$ or $\frac{6.0\times10^7 - 4.5\times10^7}{6.0\times10^7}\times100$ oe A1 cao OR M2 $\frac{6.0\times10^7}{4.5\times10^7}\times100$ -100 = (M1 $\frac{6.0\times10^7}{4.5\times10^7}\times100$ or 133.33(%)) A1 cao NB Accept any of the above expressions without any reference to 10^7.
24		LCM (40,24) = 120 Bread buns 120÷40 Burgers 120÷24 OR Bread buns: 40 is $2\times2\times2$ (×5) Burgers: 24 is $2\times2\times2$ (×3)	Bread buns 3 Burgers 5	3	M1 attempt to find LCM by eg lists of multiples, or summing of 40 and 24. A1 identify 120 (as LCM) A1 cao (both) OR M1 expansion of either number into its prime factors in a factor tree or 8×5 or 8×3 A1 both expansions correct A1 cao (both) SC B2 if answers given the wrong way around

Paper 5523_04				
No	**Working**	**Answer**	**Mark**	**Notes**
25	8 × 41 = 328 2 × 29 = 58 328 – 58 = 270 270 ÷ 6 = 45	45	3	M1 for either 8 × 41 (=328) or 2 × 29 (=58) M1 (dep) "328" – "58" (=270) A1 cao NB 328 and/or 58 on the answer line gets M1 (implied); 270 on the answer line gets M2 (implied)

Paper 5525_05				
No	**Working**	**Answer**	**Mark**	**Notes**
1 (a)	$1 - (0.2 + 0.3 + 0.1)$	0.4	2	M1 for $1 - (0.2 + 0.3 + 0.1)$ A1 for 0.4 oe, accept $\frac{0.4}{1}$
(b)	0.2×200	40	2	M1 for 0.2×200 A1 cao NB $\frac{40}{200}$ is M1 A0, 40 out of 200 is M1 A1
2	$650 - 430 = 220$ 1 choc ice costs 110p $650 - 5 \times 110 = 100$p	50	3	M1 for $650 - 430$ or 220 or 110 oe seen M1 for $650 - 5 \times \frac{'220'}{2}$ or $430 - 3 \times \frac{'220'}{2}$ oe A1 for 50p or £0.50 or £0.5 *Alternative scheme* $2x + 5y = 650$ $2x + 3y = 430$ oe M1 for subtracting two simultaneous equations to eliminate x (lollies)(2 or 3 terms correct) M1 for $650 - 5 \times 'y'$ or $430 - 3 \times 'y'$ oe A1 for 50p or £0.50 or £0.5 *Alternative scheme* M1 for $3\times (2x + 5y = 650)$ evaluated and $5 \times (2x + 3y = 430)$ evaluated oe (5 or 6 terms correct) M1 for subtraction of equations to eliminate y (choc ices)(2 or 3 terms correct ft) A1 for 50p or £0.50 or £0.5

Paper 5525_05				
No	**Working**	**Answer**	**Mark**	**Notes**
3		question + response boxes oe	2	1st aspect: One question (eg 'how long does it take you to travel to school?' or 'What time did you leave home to get to school?'); ignore other questions. 2nd aspect: Response list (at least two), not overlapping. 3rd aspect: Some mention of units (eg minutes) in either question or responses B2 for all three aspects, or B1 for just one aspects.
4	2 [(3×1) + (4×1)] + (3×6) + (1×6) + (2×6) + (4×6) + (1×6) + (5×6)	110 cm^2	4	M1 for attempt to find the area of one face M1 for at least 6 faces with intention to add A1 cao B1 (indep) for cm^2 (with or without numerical answer)
5	$\left(\frac{-6+4}{2}\right), \left(\frac{5+3}{2}\right)$	(–1, 4)	2	B2 cao [B1 for (–1,*a*) or (b,4) or (4,-1)]
6		Box plot	2	3 aspects: 1st aspect – vertical line for median 2nd aspect – box using correct quartiles 3rd aspect – whiskers (could be single line) drawn with correct end points B2 for fully correct box plot (B1 for 1 aspect)
7			2	M1 for a relevant pair of intersecting arcs A1 for line drawn within guidelines, at least 3cm in length, accept broken line [SC: B1 for line drawn within guidelines if M0]

Paper 5525_05					
No		**Working**	**Answer**	**Mark**	**Notes**
8	(a)	e.g. 2 | 126 3 | 63 3 | 21 7	$2\times3\times3\times7$	2	M1 for a systematic method of at least 2 correct divisions by a prime number oe factor trees; can be implied by digits 2, 3, 3, 7 on answer line. A1 for $2\times3^2\times7$ or $2\times3\times3\times7$
	(b)	$2\times3\times7$	42	2	B2 cao (B1 for 6, 14, 21 or $2\times3\times7$)
9	(a)		$-1,0,1,2,3$	2	B2 cao (-1 each error or omission)
	(b)(i)		$x\geq\frac{7}{2}$	3	M1 for $2x\geq7$, condone use of = sign or wrong equality A1 for $x\geq\frac{7}{2}$ oe as final answer
	(ii)		4		SC:B1 for 3.5 or $\frac{7}{2}$ seen if M0 B1 ft from $x\geq$"$\frac{7}{2}$" or $x>$"$\frac{7}{2}$"
10	(a)(i)		7^5	3	B1 cao
	(ii)		7^4		B2 cao (B1 for sight of 7^5 or 7^{2+3} or 7×7^3 or $7^1\times7^3$ or $7^2\times7^2$ or 7^{2+3-1})
	(b)		$\frac{1}{2}$	1	B1 for $\frac{1}{2}$ or 0.5 or 2^{-1}
11	(a)	$5n=m+21$	$n=\frac{m+21}{5}$	2	M1 for $5n=m+21$ or for attempt to divide three terms by 5 A1 $n=\frac{m+21}{5}$ oe

Paper 5525_05				
No	**Working**	**Answer**	**Mark**	**Notes**
(b)	$4p-8q=3p+2$ $p-8q=2$ $p=8q+2$	$p=8q+2$	3	M1 for $4p-aq$ or $\frac{3}{4}p+b$ where a is an integer and b is a number M1 (dep) for taking one term correctly to LHS or RHS of expression A1 $p=8q+2$ oe
12		$y=\frac{1}{2}x+3$	2	B2 for $y = ½x + 3$ oe (B1 for $y = ½x + c$, $c \neq 7$ or $y = mx + 3$ oe or $½x + 3$ or $M = ½x + 3$)
13	$\frac{8}{3}\times\frac{5}{4}=\frac{8\times5}{3\times4}=\frac{40}{12}$	$3\frac{1}{3}$	3	B1 for $\frac{8}{3}$ oe or $\frac{5}{4}$ oe M1 (dep on B1) for multiplying numerator and denominator of "$\frac{8}{3}$" and "$\frac{5}{4}$" A1 for $3\frac{1}{3}$ oe mixed number or $\frac{10}{3}$ *OR* B1 for 1.25 and 2.67 or 2.66(…) M1(dep on B1) for correct method of multiplication A1 for $3.\dot{3}$
14	$4x+2y=8$ $4x-10y=20$ $12y=-12$ $y=-1$ $4x+2(-1)=8$ $x=2.5$	$x=2.5$ $y=-1$	3	M1 for correct process to eliminate either x or y (condone one arithmetical error) M1 (dep) for substituting found value into either equation A1 for $x = 2.5$, $y = -1$ [SC: B1 for $x = 2.5$ or $y = -1$ if M0]

Paper 5525_05					
No		**Working**	**Answer**	**Mark**	**Notes**
15		Interior angle of hexagon = 180 – (360 ÷ 6) = 120 360 – (90 + 120)	150	4	Alternative 1 M1 for 360 ÷ 6 A1 for 60 M1 (dep on M1) for "60" + 90 A1 cao Alternative 2 M1 for 360 ÷ 6 A1 for 60 M1(dep on M1) for 360 – (2 × "60" + 90) A1 cao Alternative 3 M1 for (6 – 2) × 180 ÷ 6 A1 for 120 M1(dep on M1) for 360 – (90 + "120") A1 cao
16	(a)		(16), 50, 82, 96, 100	1	B1 cao
	(b)	Cumulative freq. diag. curve/ segments	Cum. freq graph	2	B1 ft for 4 or 5 points plotted correctly ± 1 full (2mm) square depending on sensible table (condone 1 addition error) B1 (dep) for points joined by curve or line segments provided no gradient is negative - ignore any part of graph outside range of their points. (SC:B1 if 4 or 5 points plotted not at end but consistent within each interval and joined)

Paper 5525_05					
No		Working	Answer	Mark	Notes
	(c)	$100 - 42$	58	2	M1 (ft dep on graph being cf) for reading from graph at 18 or 19, can be implied by answer in range 40 to 46 A1 for answer in range 56 to 60 or ft for 100 –'42' ±1 full (2mm) square
17	(a)		0.6 and 0.7,0.3,0.7	2	B1 for 0.6 on LH branch B1 for 0.7, 0.3 and 0.7 on RH branches
	(b)	0.4×0.3	0.12	2	M1 for 0.4×0.3 A1 0.12 oe
	(c)	$0.4\times0.7+0.6\times0.3$	0.46	3	M1 for '0.4×0.7' or '0.6×0.3' M1 for addition of two products from correct branches A1 0.46 oe Alternative M2 for an attempt to evaluate 1-(0.3×0.4 +'0.6×0.7') A1 cao
18		$x = 0.4545...$ so $100x = 45.4545...$ $99x = 45$ $x = \frac{45}{99} = \frac{15}{33}$	proof	3	M1 for $100x = 45.45\ldots$ or $10000x = 4545.45\ldots$ M1 (dep) for subtraction of both sides A1 for $\frac{15}{33}$ from correct proof
19		$\left(\sqrt{3}\right)^2 + \sqrt{3}\sqrt{2} - \sqrt{3}\sqrt{2} - \left(\sqrt{2}\right)^2$ $= 3 - 2$	1	2	B2 cao (B1 for $\sqrt{3}\sqrt{3} + \sqrt{3}\sqrt{2} - \sqrt{3}\sqrt{2} - \sqrt{2}\sqrt{2}$ oe, $\sqrt{3}\sqrt{3} - \sqrt{2}\sqrt{2}$ oe, or for 2,3, $\sqrt{4}$ $\sqrt{6}$ $\sqrt{9}$ seen)
20	(a)	$\frac{96}{24}$ or 4 $\sqrt{4}$ or 2	8	3	M1 for $\frac{96}{24}$ or $\frac{24}{96}$ or 4 or $\frac{1}{4}$ oe M1 for $\sqrt{\frac{96}{24}}$ or $\sqrt{\frac{24}{96}}$ or $\sqrt{'4'}$ or $\frac{1}{\sqrt{'4'}}$ or 2 or $\frac{1}{2}$ oe A1 cao

Paper 5525_05					
No		**Working**	**Answer**	**Mark**	**Notes**
	(b)	12×2^3	96	2	M1 for '2'^{3} or 8 A1 cao
21	(a)	$x\times3-x\times2x^2$	$3x-2x^3$	2	B2 cao (B1 for a two term expression with either $3x$ or $2x^3$)
	(b)		$4x(3y+x)$	2	M1 for taking out a factor of x, $2x$, 2, 4 or $4x$ A1 cao
	(c)	$\frac{5a}{b^2}$	$\frac{5a}{b^2}$	2	B2 for $\frac{5a}{b^2}$ or $5ab^{-2}$ (accept $\frac{5a}{1b^2}$) (B1 for either dealing with the numbers or dealing with the powers of a)
	(d)	$\frac{\cancel{x-3}}{\cancel{(x-3)}(x+3)}$	$\frac{1}{x+3}$	2	M1 for $(x-3)(x+3)$ A1 cao
22	(a)		$\mathbf{a}+\mathbf{b}$	1	B1 $\mathbf{a}+\mathbf{b}$ oe
	(b)	$ED=\mathbf{a}$ $DX=-2\mathbf{b}+2\ AC=2\mathbf{a}$ (So, $DX=2ED$)	$2\mathbf{a}$	3	M1 for $(DX=)\ DA+AX$ A1 for $(DX=)\ -2\boldsymbol{b}+2$ ("$\boldsymbol{a}+\boldsymbol{b}$") A1 $2\boldsymbol{a}$ from fully correct proof
23		$\pi(2x)^2h=\frac{4}{3}\pi(3x)^3$ $h=\frac{\frac{4}{3}\pi(3x)^3}{\pi(2x)^2}$	$9x$	3	M1 for $\pi(2x)^2h=\frac{4}{3}\pi(3x)^3$ (condone absence of brackets) M1 (dep) for valid algebra that gets to $h=ax$ (condone one error in powers of numerical constants) A1 cao

Paper 5525_05					
No		**Working**	**Answer**	**Mark**	**Notes**
24	(i)	$n^2+(n+1)^2=2(n^2+n)+1$	$2n^2+2n+1$	4	M1 for at least 3 terms correct from $n^2+n+n+1$ A1 for $2n^2+2n+1$ oe
	(ii)		$2(n^2+n)$ is always even so $2(n^2+n)+1$ is always odd		M1 for recognizing $2n^2$ is always even A1ft complete proof for their quadratic *Alternative method* M1 for recognizing that if n^2 is odd then $(n+1)^2$ is even or vice versa A1 for complete proof
25			42 318	2	B1 for answer in range 36 – 48 B1 for answer in range 312 – 324
26	(a)	$(x-3)^2-3^2+15$	$p=3, q=6$	2	B2 for $p=3$ and $q=6$ (B1 for $p=3$ OR $q=6$) SC: award B2 for $(x-3)^2+6$ if p and q are not identified
	(b)		Sketch	2	B1 for U shaped curve B1 ft for TP in first quadrant (ft if TP not in first quadrant)
27	(a)	Graph translated 2 units upwards through points (–4, 2), (–2, 4), (0,2) and (3,5)	Sketch	2	M1 for a vertical translation A1 curve through points (–4, 2), (–2, 4), (0,2) and (3,5) ± ½ square
	(b)	Graph reflected in x-axis through points (–4,0), (–2, –2), (0, 0) and (3, -3)	Sketch	2	M1 for reflection in x-axis or y-axis A1 curve through points (–4,0), (–2, –2), (0, 0) and (3, -3) ± ½ square

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
1		273	2	M1 for 728 ÷ 8 or 728 ÷ "3+5" or 91 A1 cao SC B1 for 455 or 273:455
2		$3n - 1$	2	B2 for $3n - 1$ oe (B1 for $3n + k$ where $k \neq -1$ but k could be 0)
3	3 24 3.7 46.9(53) 4 60 3.8 51.0(72) 3.1 26.6(91) 3.9 55.4(19) 3.2 29.5(68) 3.21 29.8(66…) 3.3 32.6(37) 3.22 30.1(66…) 3.4 35.9(04) 3.23 30.4(68..) 3.5 39.3(75) 3.24 30.7(72...) 3.6 43.0(56) 3.25 31.0(78...) or 31	3.2	4	B2 for trial between 3.2 and 3.3 inclusive (B1 for trial between 3 and 4 inclusive) B1 for different trial between 3.21 and 3.25 inclusive B1 (dep on at least one previous B1) cao for 3.2 NB: embedded answers: –B1; award Bs for evaluations rounded or truncated to at least 1 dp or for 31
4	2 is the only even prime number and the product of 2 odd numbers is odd	Yes	2	B2 for 'yes' and '2 is the only even prime number and the product of two odd numbers is odd' oe (B1 for 'yes' and either '2 is the only even prime number' oe **or** 'the product of two odd numbers is odd' oe)
5	$45^2 + 34^2 =$ $2025 + 1156 = 3181$ $\sqrt{3181} = 56.4$	56	4	M1 for $45^2 + 34^2$ M1 for $\sqrt{(2025 + 1156)}$ A1 for 56.4 … B1 for rounding their diagonal to the nearest integer (dep on evidence from decimal) NB 56 with no incorrect working as the final answer gets full marks. NB Scale drawings result in 0 marks.

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
6	$2000 \times (1.055)^3$ Interest = 2348.48 – 2000 =	£348.48	3	M1 for 5.5/100 × 2000 (oe) or 330 or 16.5/100×2000 or 2330 or 110 or 2110 M1 (dep) for 5.5/100 × (2000 + "110" + "116.05") or 122.4… seen A1 cao (accept only 348.48 or 348.49) **OR** M2 for $2000 \times (1.055)^3$ or 2348.48(…) or 2348.49 seen (M1 for $2000 \times (1.055)^n$, $n \neq 3$) A1 for 348.48 or 348.49 [SC: B2 for 2348.48 - 2348.49]
7 (a)		Line	2	B2 line fully within tramlines, crossing AB and CD (B1 a straight line which crosses AB within the tramline, and also crosses CD) NB: Accept dotted or dashed lines, but not curves; accept freehand if considered to be straight. SC B1 for the perpendicular bisector of *AB* reaching halfway or more from *AB*
(b)		Region		B2 correct arc ±2mm and shaded within. Allow dotty or continous arc. (B1 inaccurate arc and shaded or accurate arc unshaded)
8	65×12=780 75×22=1650 85×23=1955 95×24=2280 105×19=1995 8660/100=	86.6	4	M1 for use of fx with x consistent within intervals (including end points). Allow one slip even if outside interval M1 (dep) for use of midpoints M1 (dep on 1st M1) for use of $\sum fx/100$ or $\sum fx/\sum f$ A1 86.6

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
9		Distance ÷ time: 1400 ÷ 2 h 20 min 20 mins is $\frac{1}{3}$ hour 1400 × 3 ÷ 7 =	600 kph	3	B1 20 mins as $\frac{1}{3}$ hour or as 0.33……hour M1 for distance ÷ time eg 1400 ÷ "2h 20 min" A1 cao OR B1 2 hour 20min = 140 (min) M1 Speed = $\frac{1400}{140}$ = (10 km per minute) A1 cao
10	(a)	$(x+18)+2x+(2x+7)=180$	Equation	2	B2 for $(x+18)+2x+(2x+7)=180$ oe (B1 for $(x+18)+2x+(2x+7)$)
	(b)	$5x+25 = 180$ $5x = 155$	31	2	M1 for simplifying to at least $5x+25=180$ or 360 (may be earned in (a)) A1 for $x=31$
11	(a)	(–14) –4 (0) 4 14	–4, 4, 14	2	B2 for all 3 values correct (B1 for 1 or 2 values correct)
	(b)		curve	2	B1 for all 5 points plotted correctly ± ½ square (ft from table if at least B1 awarded in (a)) B1 (indep) ft for any smooth curve through their points

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
12	(a)	$8 \times \frac{10}{4}$	20	2	M1 $\frac{10}{4}$ or $\frac{4}{10}$ or 0.4 or 2.5 oe seen A1 cao NB ratios get M0 unless of the form 1:*n* OR M1 $\frac{8}{4}, \frac{4}{8}$ oe seen A1 cao
	(b)	$15 \times \frac{4}{10}$	6	2	M1 $15 \times \frac{4}{10}$ oe A1 cao
13	(a)	$9.9\times10^8 - 6.0\times10^7$	$\pm 9.3\times10^8$	2	M1 for $99\times10^7 - 6.0\times10^7$ or $9.9\times10^8 - 0.60\times10^8$ or correct conversion of either to an ordinary number or 930000000 or 9.3×10^n where *n* is any positive integer A1 cao
	(b)	$\frac{6.0-4.5}{4.5} \times 100 = \frac{1.5}{4.5} \times 100 =$ or $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7} \times 100$	33.3%	3	M2 $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7} \times 100$ oe (M1 for $\frac{6.0\times10^7 - 4.5\times10^7}{4.5\times10^7}$ or $\frac{6.0\times10^7 - 4.5\times10^7}{6.0\times10^7} \times 100$ oe A1 33.3 – 33.4 OR M2 $\frac{6.0\times10^7}{4.5\times10^7} \times 100$ -100 or 33.3% (M1 $\frac{6.0\times10^7}{4.5\times10^7} \times 100$ or 133.3%) A1 33.3-33.4 NB Accept any of the above expressions without any reference to 10^7.

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
14	LCM (40,24) = 120 Bread buns 120÷40 Burgers 120÷24 OR Bread buns: 40 is 2 × 2 × 2 (×5) Burgers: 24 is 2 × 2 × 2 (×3)	Bread Buns 3 Burgers 5	3	M1 attempt to find LCM by eg lists of multiples, or summing of 40s and summing of 24s, with at least 3 numbers in each list A1 identify 120 as LCM A1 cao (both) **OR** M1 expansion of either number into its prime factors in a factor tree or 8×5 or 8×3 A1 both expansions correct A1 cao (both) SC B2 if answers given the wrong way around
15	$\sin 32 = \frac{AB}{12}$ $AB = 12 \times \sin 32$ $AB = 6.35903\ldots$	6.36	3	M1 $\sin 32 = \frac{AB}{12}$ (accept $\text{Sin}\ \frac{AB}{12}$) M1 $12 \times \sin 32$ or $12 \times 0.5299..$ A1 accept 6.359 – 6.360 SC Gradians 5.78(1…) Radians 6.62 Get M1M1A0 **OR** Use of Sine Rule $\frac{\sin 32}{AB} = \frac{\sin 90}{12}$ or $\frac{AB}{\sin 32} = \frac{12}{\sin 90}$ M1 $AB = \frac{12 \times \sin 32}{\sin 90}$ M1 AB = 6.359 – 6.36 A1 SC Gradians 5.85(…) Radians 7. 40(…) M1M1A0

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
16		$8 \times 41 = 328$ $2 \times 29 = 58$ $328 - 58 = 270$ $270 \div 6 = 45$	45	3	M1 for either 8×41 (=328) or 2×29 (=58) M1 (dep) "328" – "58" (=270) A1 cao NB 328 and /or 58 on the answer line gets M1 (implied); 270 on the answer line gets M2 (implied)
17	(a)	$x^2 - 4x + 3x - 12 = x^2 - x - 12$	$x^2 - x - 12$	2	M1 for exactly 4 terms correct ignoring signs (x^2, $4x$, $3x$, 12) or 3 out of 4 terms with correct signs (x^2, $-4x$, $+3x$, -12) A1 cao
	(b)	$6x^2 - 8x + 15x - 20 = 6x^2 + 7x - 20$	$6x^2 + 7x - 20$	2	M1 for exactly 4 terms correct ignoring signs ($6x^2$, $8x$, $15x$, 20) or 3 out of 4 terms with correct signs ($6x^2$, $-8x$, $+15x$, -20) A1 cao
	(c)	$(x+2)(x+5)$	$(x+2)(x+5)$	2	B2 cao (B1 for exactly one of $(x + 2)$, $(x + 5)$)
	(d)		$12p^8q^3$	2	B2 cao (B1 for any 2 out of 3 terms correct in a product or 3 terms correct in a sum or part product)
	(e)	$6 = 15 + 4(q - 5)$ $6 = 15 + 4q - 20$ $11 = 4q$	$2\frac{3}{4}$	3	M1 for correct substitution of p and t. M1 for correct expansion of $4(q\text{-}t)$ oe (eg $4q$-20, $4q$-$4t$) A1 11/4 or 2 ¾ or 2.75 OR M1 for correct substitution of p and t. M1 for $\frac{p-3t}{4} = q - t$ oe A1 11/4 or 2 ¾ or 2.75
18	(a)	$T=kx$; $150=6k$; $k=25$	$T=25x$	3	M1 for $T=kx$, k algebraic M1 subs $T=150$ and $x=6$ into $T = kx^n$ $(n \neq 0)$ A1 for $T=25x$ oe SC B1 $T \propto 25x$ oe

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
	(b)	$T = 25 \times 15 =$	375	1	B1 ft on k , $k \neq 1$
	(c)	$600 = 25x$; $x = 600 \div 25 =$	24	1	B1 ft on k , $k \neq 1$
19		$\frac{120}{570} \times 50 = 10.5263$ $\frac{250}{570} \times 50 = 21.9298$ $\frac{200}{570} \times 50 = 17.5438$	10 22 18	3	M1 method shown eg $\frac{120}{120+250+200} \times 50$ or one of 10.5(263) 21.9(298), 17.5(438) **OR** 570 ÷ 50 = 11.4 and one of 120 ÷ 11.4 =10.526…) , 270 ÷ 11.4 (=21.9298…) , 200 ÷ 11.4 (=17.5438…) A1 for 10.5(263), 21.9(298), 17.5(438) or 11, 22, 18 B1 correction to add to 50: 10, 22, 18 or 11, 22, 17
20		$x(x+1) + 4(2x–3) = (2x–3)(x+1)$ $x^2 + x + 8x – 12 = 2x^2 + 2x – 3x – 3$ $x^2 – 10x + 9 = 0$ $(x – 9)(x – 1) = 0$	$x = 1,9$	5	M1 for multiplying through by common denominator $(2x–3)(x+1)$ M1 (dep)for either $x^2 + x + 8x – 12$ or $2x^2 + 2x – 3x – 3$ oe A1 for correct quadratic (= 0) M1 for a correct method to solve 3 term quadratic A1 cao for both solutions
21		$AB^2 = 8^2 + 9^2 – 2\times8\times9\times\cos40$ $AB^2 = 64 + 81 – 144\times\cos40$ $AB^2 = 145 – 144 \times 0.766$ $AB^2 = 145 – 110.31… = 34.6896$ $AB = \sqrt{34.6796} = 5.8897877$	5.89	3	M1 Subs in Cos Rule: $8^2 + 9^2 – 2\times8\times9\times\cos40$ M1 correct order of evaluation of $8^2 + 9^2 – 2\times8\times9\times\cos40$ A1 cao 5.88 – 5.89 SC: Award B2 for one of $AB^2 = 241.03…$ or $AB = 15.525…$ (radians) $AB^2 = 28.50…$ or $AB = 5.33…$ (gradians)
22	(a)		24 30	2	B1 24 cao B1 30 cao
	(b)	Column $60 \leq w < 75$ at 10 Column $75 \leq w < 95$ at 4	10 4	2	B1 10 and correct width (tol $\pm\frac{1}{2}$ small square) B1 4 and correct width (tol $\pm\frac{1}{2}$ small square)

Paper 5525_06				
No	**Working**	**Answer**	**Mark**	**Notes**
23 (a)		100.5	1	B1 cao
(b)		10.515	1	B1 cao
(c)	$\frac{100.5}{10.515}$	9.5577746	2	M1 for greatest distance divided by least time Where 100 < greatest distance ≤ 100.5, 10.51 ≤ least time < 10.52 A1 for 9.555 – 9.56
(d)	$\frac{99.5}{10.525}$	9.45368..	2	M1 for least distance divided by greatest time Where 99.5 ≤ least distance < 100, 10.52 < greatest time ≤10.53 A1 for 9.45 – 9.455
24	$\frac{4}{7}\times\frac{4}{7}\times\frac{3}{7} + \frac{3}{7}\times\frac{3}{7}\times\frac{4}{7} =$ $\frac{48+36}{343} = \frac{84}{343}$ But there are three ways this can be achieved: BBG, BGB, GBB So the probability is $\frac{84}{343}\times 3$ OR $1-\frac{64}{343}-\frac{27}{343}$ NB: 84/343 = 0.244897; 252/343 = 0.73469 $\frac{4}{7} = 0.57(142...)$, $\frac{3}{7} = 0.42(857...)$	$\frac{252}{343}$	3	M1 for $\frac{4}{7}\times\frac{4}{7}\times\frac{3}{7}$ or $\frac{3}{7}\times\frac{3}{7}\times\frac{4}{7}$ oe or $\left(\frac{4}{7}\right)^3$ oe or $\left(\frac{3}{7}\right)^3$ oe or $\frac{91}{343}$ or 0.10(49…) or 0.13(99….) M1 (indep) for identification of all 6 outcomes (M2 for $1-\left[\left(\frac{4}{7}\right)^3+\left(\frac{3}{7}\right)^3\right]$) oe A1 $\frac{252}{343}$, $\frac{36}{49}$, 0.73(469…) oe

Paper 5525_06					
No		**Working**	**Answer**	**Mark**	**Notes**
25	(a)	$\frac{1}{3} \times \pi \times 5^2 \times 8 = \pi \times 25 \times 8 \div 3 =$ 209.4395	209–210	2	M1 for $\frac{1}{3} \times \pi \times 5^2 \times 8$ A1 for 209–210
	(b)	Base radius = $\frac{216}{360} \times 15 = 9$ Height = $\sqrt{(15^2 - 9^2)} =$	12	4	M1 for 216 ÷ 360 A1 for 9 M1 for $\sqrt{(15^2 - \text{“9”}^2)}$, where “9” < 15 A1 cao

PMT

edexcel

Mark Scheme (Results)

Summer 2012

GCSE Mathematics (Linear) 1MA0
Foundation (Non-Calculator) Paper 1F

PMT

Edexcel and BTEC Qualifications

Edexcel and BTEC qualifications come from Pearson, the world's leading learning company. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers. For further information, please visit our website at www.edexcel.com.

Our website subject pages hold useful resources, support material and live feeds from our subject advisors giving you access to a portal of information. If you have any subject specific questions about this specification that require the help of a subject specialist, you may find our Ask The Expert email service helpful.

www.edexcel.com/contactus

Pearson: helping people progress, everywhere

Our aim is to help everyone progress in their lives through education. We believe in every kind of learning, for all kinds of people, wherever they are in the world. We've been involved in education for over 150 years, and by working across 70 countries, in 100 languages, we have built an international reputation for our commitment to high standards and raising achievement through innovation in education. Find out more about how we can help you and your students at: www.pearson.com/uk

Summer 2012
Publications Code UG032619
All the material in this publication is copyright
© Pearson Education Ltd 2012

NOTES ON MARKING PRINCIPLES

1 All candidates must receive the same treatment. Examiners must mark the first candidate in exactly the same way as they mark the last.

2 Mark schemes should be applied positively. Candidates must be rewarded for what they have shown they can do rather than penalised for omissions.

3 All the marks on the mark scheme are designed to be awarded. Examiners should always award full marks if deserved, i.e if the answer matches the mark scheme. Examiners should also be prepared to award zero marks if the candidate's response is not worthy of credit according to the mark scheme.

4 Where some judgement is required, mark schemes will provide the principles by which marks will be awarded and exemplification may be limited.

5 Crossed out work should be marked UNLESS the candidate has replaced it with an alternative response.

6 Mark schemes will indicate within the table where, and which strands of QWC, are being assessed. The strands are as follows:

i) *ensure that text is legible and that spelling, punctuation and grammar are accurate so that meaning is clear*
Comprehension and meaning is clear by using correct notation and labeling conventions.

ii) *select and use a form and style of writing appropriate to purpose and to complex subject matter*
Reasoning, explanation or argument is correct and appropriately structured to convey mathematical reasoning.

iii) *organise information clearly and coherently, using specialist vocabulary when appropriate*.
The mathematical methods and processes used are coherently and clearly organised and the appropriate mathematical vocabulary used.

7 With working

If there is a wrong answer indicated on the answer line always check the working in the body of the script (and on any diagrams), and award any marks appropriate from the mark scheme.
If working is crossed out and still legible, then it should be given any appropriate marks, as long as it has not been replaced by alternative work.
If it is clear from the working that the "correct" answer has been obtained from incorrect working, award 0 marks. Send the response to review, and discuss each of these situations with your Team Leader.
If there is no answer on the answer line then check the working for an obvious answer.
Any case of suspected misread loses A (and B) marks on that part, but can gain the M marks. Discuss each of these situations with your Team Leader.
If there is a choice of methods shown, then no marks should be awarded, unless the answer on the answer line makes clear the method that has been used.

8 Follow through marks

Follow through marks which involve a single stage calculation can be awarded without working since you can check the answer yourself, but if ambiguous do not award.
Follow through marks which involve more than one stage of calculation can only be awarded on sight of the relevant working, even if it appears obvious that there is only one way you could get the answer given.

9 Ignoring subsequent work

It is appropriate to ignore subsequent work when the additional work does not change the answer in a way that is inappropriate for the question: e.g. incorrect canceling of a fraction that would otherwise be correct
It is not appropriate to ignore subsequent work when the additional work essentially makes the answer incorrect e.g. algebra.
Transcription errors occur when candidates present a correct answer in working, and write it incorrectly on the answer line; mark the correct answer.

10 Probability

Probability answers must be given a fractions, percentages or decimals. If a candidate gives a decimal equivalent to a probability, this should be written to at least 2 decimal places (unless tenths).
Incorrect notation should lose the accuracy marks, but be awarded any implied method marks.
If a probability answer is given on the answer line using both incorrect and correct notation, award the marks.
If a probability fraction is given then cancelled incorrectly, ignore the incorrectly cancelled answer.

11 Linear equations
Full marks can be gained if the solution alone is given on the answer line, or otherwise unambiguously indicated in working (without contradiction elsewhere). Where the correct solution only is shown substituted, but not identified as the solution, the accuracy mark is lost but any method marks can be awarded.

12 Parts of questions
Unless allowed by the mark scheme, the marks allocated to one part of the question CANNOT be awarded in another.

13 Range of answers
Unless otherwise stated, when an answer is given as a range (e.g 3.5 – 4.2) then this is inclusive of the end points (e.g 3.5, 4.2) and includes all numbers within the range (e.g 4, 4.1)

Guidance on the use of codes within this mark scheme
M1 – method mark A1 – accuracy mark B1 – Working mark C1 – communication mark QWC – quality of written communication oe – or equivalent cao – correct answer only ft – follow through sc – special case dep – dependent (on a previous mark or conclusion) indep – independent isw – ignore subsequent working

PMT

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
1	(a)		380	1	B1 cao
	(b)		6.2	1	B1 cao
	(c)		Arrow at 34	1	B1 cao
2	(a)		8	1	B1 for 8 ± 0.2
	(b)		35	1	B1 for 35 ± 2°
	(c)		Circle drawn	1	B1 for all parts within ± 2mm, (use overlay)
3	(a)		4, 7, 4, 3, 2	2	M1 for at least 3 correct tallies **or** at least 3 correct frequencies A1 for all frequencies correct
	(b)		7	1	B1 for 7 **or** ft from frequencies in (a) or tallies if no frequencies
	(c)		Diagram drawn	3	M1 for bar chart or other suitable chart with at least 3 correct heights for their scale (can f.t.) A1 for all 5 bars correctly labelled and vertical axis correctly scaled A1 for fully correct **or** ft frequencies in (a) **OR** M1 for pictogram with at least 3 correct rows (can f.t.) A1 for correct labels on all 5 rows and correctly key A1 for fully correct **or** ft frequencies in (a) **OR** M1 for pie chart with at least 3 correct sectors ± 2° (can f.t.) A1 for all 5 sectors correctly labelled A1 for fully correct **or** ft frequencies in (a)

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
4		£1.18 + 94p = £2.12 £5 – £2.12 – 30p = £2.58 £2.58 ÷ 2 =	1.29	3	M2 for (5 – 1.18 – 0.94 – 0.30) ÷ 2 oe **or** digits 129 (M1 for 1.18 + 0.94 **or** 2.12 seen **or** 1.18 + 0.94 + 0.30 oe **or** 2.42 seen **or** 5 – 1.18 – 0.94 oe **or** 2.88 seen **or** (5 – 1.18 – 0.94) ÷ 2 **or** 1.44 seen **or** 5 – 1.18 – 0.94 – 0.30 oe **or** 2.58 seen) A1 cao **NOTE**: Accept working in £ or pence
5	(a)(i) (ii) (b)		(2, 3) (–3, 1) Point plotted at (3, –4)	2 1	B1 cao B1 cao B1 cao
6	(a) (b) (c)		– 5 6 3	1 1 1	B1 cao B1 for 6 or – 6 B1 cao
7			(P, B), (P, S), (P, L) (M, B), (M, S), (M, L) (H, B), (H, S), (H, L)	2	M1 for any 3 combinations with no incorrect combinations A1 for all 9 combinations with no duplicates or extras
8	(a) (b)	 24 ÷ 4 =	Walk 6	1 2	B1 cao M1 for 24 ÷ 4 oe or ¼ oe seen A1 cao

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
9	(a)		Isosceles triangle	1	B1 for isosceles triangle
	(b)		Rectangle with area 12 cm^2	2	M1 for rectangle drawn A1 cao
10	(a)		A marked at 0	1	B1 for A marked at 0 (within overlay)
	(b)		B marked at 1/4	1	B1 for B marked at 1/4 (within overlay)
11	(a)		9	1	B1 cao
	(b)		33	2	M1 for 5 × 5 **or** 25 seen in the working **or** 2 × 2 × 2 **or** 8 seen in the working A1 cao
12	(a)		20	2	M1 3 × 3 × 3 oe seen or drawn or 27 seen or use of 3 layers A1 cao
	(b)			2	B2 for correct view (B1 for  or )
13	(a)(i)		07 29	2	B1 for 07 29
	(ii)		36		B1 for 36 or ft difference between (i) and 06 53
	(b)		07 51	1	B1 cao
	(c)		09 55	1	B1 for 09 55 or 9 55 or five to ten

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
14		2 + 8 + 2 + 8 = 20 20 ÷ 4 =	5	4	M2 for 2 + 8 + 2 + 8 oe **or** 20 seen **or** (2 + 8) ÷ 2 oe (M1 for the sum of 3 sides of the rectangle) M1 (dep) for the sum of 3 or 4 sides of the rectangle ÷ 4 **or** an attempt to evaluate (2 + 8) ÷ 2 oe to get the length of one side A1 cao **SC**: B1 for an answer of 4 coming from $\sqrt{2\times 8}$ oe
15	(a)		4	1	B1 cao
	(b)	9.5 – 4.75 = **OR** 9.5 ÷ 2 =	4.75	2	M1 for 9.5 – 4.75 **or** 9.5 ÷ 2 **or** 4.75 – 9.5 A1 cao
	(c)		6	1	B1 cao
	(d)	12 × 4 =	48	2	M1 for × 4 seen **or** identifying + 0.5 for every 2 inches **or** 12 + 12 + 12 + 12 oe **or** build up method eg 12, 24, 36, 48 allow one error A1 cao
16	(a)		trapezium	1	B1 for trapezium or isosceles trapezium
	(b)			2	B2 for correct tessellation (at least 5 more shapes) (B1 for at least 4 shapes (including initial shape) correctly tessellating)

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
17*		S: 35 ÷ 100 × 40 = 14 W: 40 ÷ 8 × 3 = 15 **OR** D: 16 ÷ 40 (× 100) = 0.4 (40%) W: 3 ÷ 8 (× 100) = 0.375 (37.5%) **OR** D: $\frac{16}{40} = \frac{80}{200}$ S: $\frac{35}{100} = \frac{70}{200}$ W: $\frac{3}{8} = \frac{75}{200}$	Debbie and correct calculations	4	**Compares Marks out of 40 or fractions with denominator of 40** M1 for 35 ÷ 100 × 40 oe **or** 14 seen (or 14/40 seen) M1 for 40 ÷ 8 × 3 **or** 15 seen (or 15/40 seen) A1 for 14 and 15 **or** $\frac{14}{40}$ and $\frac{15}{40}$ C1 (dep on M1) for correct conclusion for their working QWC with 3 comparable marks: Decision and justification should be clear with working clearly presented and attributable. **OR Decimals (or Percentages)** M1 for 16 ÷ 40 (× 100) oe **or** 0.4 (or 40) seen M1 for 3 ÷ 8 (× 100) oe **or** 0.375 (or 37.5) seen A1 for 0.4 and 0.375 (**or** 40 and 37.5) C1 (dep on M1) for correct conclusion for their working QWC: with 3 comparable decimals (or percentages: Decision and justification should be clear with working clearly presented and attributable. **OR Compares Fractions with denominator other than 40** M1 for attempt to convert all to fractions with a common denominator other than 40 M1 for at least 1 correct A1 for $\frac{80}{200}$ and $\frac{70}{200}$ and $\frac{75}{200}$ oe C1 (dep on M1) for correct conclusion for their working QWC with 3 comparable fractions: Decision and justification should be clear with working clearly presented and attributable.

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
18*	(a)		10	1	B1 cao
	(b)	 **Miles** 0 10 20 30 40 50 **Ed** 0 15 30 45 60 75 **Bill** 10 20 30 40 50 60	Ed is cheaper up to 20 miles, Bill is cheaper for more than 20 miles	3	M1 for correct line for Ed intersecting at (20,30) ±1 sq tolerance **or** $10 + x = 1.5x$ oe C2 (dep on M1) for a correct full statement ft from graph eg. Ed cheaper up to 20 miles **and** Bill cheaper for more than 20 miles (C1 (dep on M1) for a correct conclusion ft from graph eg. cheaper at 10 miles with Ed ; eg. cheaper at 50 miles with Bill eg. same cost at 20 miles; eg for £5 go further with Bill **or** A general statement covering short **and** long distances eg. Ed is cheaper for shorter distances **and** Bill is cheaper for long distances) **OR** (continued on next page)

PMT

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
18 (contd)					**OR** M1 for correct method to work out Ed's delivery cost for at least 2 values of n miles where $0 < n \leq 50$ **or** for correct method to work out Ed and Bill's delivery cost for n miles where $0 < n \leq 50$ C2 (dep on M1) for 20 miles linked with £30 for Ed and Bill with correct full statement eg. Ed cheaper up to 20 miles **and** Bill cheaper for more than 20 miles (C1 (dep on M1) for a correct conclusion eg. cheaper at 10 miles with Ed; eg. cheaper at 50 miles with Bill eg. same cost at 20 miles; eg for £5 go further with Bill **or** A general statement covering short **and** long distances eg. Ed is cheaper for shorter distances **and** Bill is cheaper for long distances) SC: B1 for correct full statement seen with no working eg. Ed cheaper up to 20 miles **and** Bill cheaper for more than 20 miles QWC Decision and justification should be clear with working clearly presented and attributable

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
19		1,96 × 2.25 = 4.41 **OR** 4.23 ÷ 9 = 0.47 1.96 ÷ 4 = 0.49 **OR** 4.23 × 4 = 16.92 1.96 × 9 = 17.64 **OR** 4.23 ÷ 9 = 0.47 0.47 × 4 = 1.88 **OR** 1.96 ÷ 4 = 0.49 0.49 × 9 = 4.41 **OR** 9 ÷ 4.23 = 2.12 4 ÷ 1.96 = 2.04	Pack of 9	3	M2 for a fully correct method to enable a conclusion eg 1.96 × 2¼ **OR** M1 for 4.23 ÷ 9 or 423 ÷ 9 **or** 0.47 seen **or** 47 seen M1 for 1.96 ÷ 4 or 196 ÷ 4 or 0.49 seen or 49 seen **OR** M1 for 4.23 × 4 **or** 423 × 4 **or** 16.92 seen **or** 1692 seen M1 for 1.96 × 9 **or** 196 × 9 **or** 17.64 seen **or** 1764 seen **OR** M1 for 4.23 ÷ 9 **or** 423 ÷ 9 **or** 0.47 seen **or** 47 seen M1 for 0.47 × 4 **or** 47 × 4 **or** 1.88 seen **or** 188 seen **OR** M1 for 1.96 ÷ 4 **or** 196 ÷ 4 **or** 0.49 seen **or** 49 seen M1 for 0.49 × 9 **or** 49 × 9 **or** 4.41 seen **or** 441 seen **OR** M1 for 9 ÷ 4.23 **or** 2.12(...) seen **or** 2.13 seen M1 for 4 ÷ 1.96 **or** 2.04(...) seen A1 for Pack of 9 and fully correct calculations **NOTE:** B0 for an answer of 9 not supported by working.
20	(a)		6	1	B1 cao
	(b)		44	1	B1 cao
	(c)		31	2	M1 for 60 – 29 **or** 29 – 60 **or** any correct method that is attempting to find the difference between 29 and 60 (allow 1 arithmetic error) A1 cao

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
21*		Angle *DBC* = (180 – 50) ÷ 2 Base angles of isosceles triangle are equal Angle *ABD* = 180 – 65 Angles on a straight line add up to 180 *x* = 180 – 20 – 115 Angles in a triangle add up to 180 **OR** Angle *DBC* = (180 – 50) ÷ 2 Base angles of isosceles triangle are equal *x* = 65 – 20 Exterior angle of triangle is equal to sum of interior opposite angles **OR** Angle *DCB* = (180 – 50) ÷ 2 Base angles of isosceles triangle are equal *x* = 180 – 50 – 20 – 65 Angles in a triangle add up to 180	45 with reasons	4	M1 for (180 – 50) ÷ 2 oe **or** 65 seen M1 for 180 – 20 – (180 – "65") **or** "65" – 20 or 180 – 50 – 20 –'65' oe C2 for *x* identified as 45 with full reasons QWC: Reasons clearly laid out with correct geometrical language used (C1 (dep on M1) for one reason QWC: Reasons clearly laid out with correct geometrical language used) NOTE: *x* = 45 with no working or without any correct angles marked on the diagram cannot score.

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
22	(a)	360 ÷ 60 = 6 300 ÷ 60 = 5 6 × 5 =	Yes and 30	3	M1 for dividing side of patio by side of paving slab eg 360 ÷ 60 **or** 300 ÷ 60 **or** 3.6 ÷ 0.6 **or** 3 ÷ 0.6 **or** 6 and 5 seen **or** 6 divisions seen on length of diagram **or** 5 divisions seen on width of diagram M1 for correct method to find number of paving slabs eg (360 ÷ 60) × (300 ÷ 60) oe **or** 6 × 5 **or** 30 squares seen on diagram (units may not be consistent) A1 for Yes **and** 30 (or 2 extra) with correct calculations **OR** M1 for correct method to find area of patio **or** paving slab eg 360 × 300 **or** 108000 seen **or** 60 × 60 **or** 3600 seen **or** 3.6 × 3 **or** 10.8 seen **or** 0.6 × 0.6 **or** 0.36 seen M1 for dividing area of patio by area of a paving slab eg. (3.6 × 3) ÷ (0.6 × 0.6) oe (units may not be consistent) A1 for Yes **and** 30 (or 2 extra) with correct calculations **OR** M1 for method to find area of patio and area of 32 slabs eg. 60 × 60 × 32 **or** 360 × 300 M1 for method to find both areas eg. 60 × 60 × 32 **and** 360 × 300 (units may not be consistent) A1 for Yes **and** 115200 **and** 108000 **OR** Yes **and** 11.52 **and** 10.8 **NB :** Throughout the question, candidates could be working in metres or centimetres

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
22	(b)	1726 25890 27616 **8 6 3** **2** 2 4 1 8 9 **3** **7** 1 6 1 2 6 **2** 6 1 6 800 60 3 30 24000 1800 90 2 1600 120 6 24000 + 1800 + 90 + 1600 + 120 + 6 = 27616	276.16	3	M1 for complete correct method with relative place value correct. Condone 1 multiplication error, addition not necessary. **OR** M1 for a complete grid. Condone 1 multiplication error, addition not necessary. **OR** M1 for sight of a complete partitioning method, condone 1 multiplication error. Final addition not necessary. A1 for digits 27616 A1 ft (dep on M1) for correct placement of decimal point after addition (of appropriate values) (SC: B1 for attempting to add 32 lots of 8.63)
23	(a)		30	2	M1 for 25 ÷ 10 **or** 2.5 seen **or** 10 ÷ 25 **or** 0.4 seen **or** 12+12+6 oe **or** a complete method eg. 25×12÷10 oe A1 cao
	(b)	1000 ÷ 200 × 12	60	2	M1 for 500 ÷ 50 **or** 1000 ÷ 200 **or** 500 ÷ 10 **or** correct scale factor clearly linked with one ingredient eg 10 with sugar or 5 with butter or flour or 50 with milk **or** an answer of 120 or 600 A1 cao

PMT

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
24		Acton after 24, 48, 72, 96, .. Barton after 20, 40, 60, 80, .. LCM of 20 and 24 is 120 9:00 am + 120 minutes **OR** Acton after 24, 48, 1h 12 min... Barton after 20, 40, 1 h LCM is 2 hours 9:00 am + 2 hours **OR** Times from 9:00 am when each service leaves the bus station Acton at 9:24, 9:48, 10:12.. Barton at 9:20, 9:40, 10:00.. **OR** 20 = 2 × 2 × 5 24 = 2 × 2 × 2 × 3 2 × 2 × 2 × 3 × 5 = 120	11:00 am	3	M1 for listing multiples of 20 and 24 with at least 3 numbers in each list ; multiples could be given in minutes or in hours and minutes (condone one addition error in total in first 3 numbers in lists) A1 identify 120 (mins) **or** 2 (hours) as LCM A1 for 11:00 (am) **or** 11(am) **or** 11 o'clock **OR** M1 for listing times after 9am when each bus leaves the bus station, with at least 3 times in each list (condone one addition error in total in first 3 times after 9am in lists) A1 for correct times in each list up to and including 11:00 A1 for 11:00 (am) **or** 11(am) **or** 11 o'clock **OR** M1 for correct method to write 20 and 24 in terms of their prime factors 2, 2, 5 and 2, 2, 2, 3 (condone one error) A1 identify 120 as LCM A1 for 11:00 (am) **or** 11(am) **or** 11 o'clock

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
25	(a)		$6y - 15$	1	B1 cao
	(b)		$4x(2x + y)$	2	B2 cao (B1 for $x(8x + 4y)$ **or** $2x(4x + 2y)$ **or** $4(2x^2 + xy)$ **or** $4x(ax + by)$ where a, b are positive integers **or** $ax(2x + y)$ where a is a positive integer **or** $4x(2x \quad y)$)
	(c)	$10t = gh$ $h = \frac{10t}{g}$	$\frac{10t}{g}$	2	M1 for clear intention to multiply both sides of the equation by 10 (eg. ×10 seen on both sides of equation) **or** clear intention to divide both sides of the equation by g (eg. ÷ g seen on both sides of equation) **or** $10t = gh$ **or** $\frac{t}{g} = \frac{h}{10}$ **or** fully correct reverse flow diagram eg. ← ×10 ← ÷g ← A1 for $\frac{10t}{g}$ oe

1MA0_1F					
Question		**Working**	**Answer**	**Mark**	**Notes**
26	(a)	$2 \times 5 \times 2 = 20$ $300 \div 20 =$	15	3	M2 for $300 \div (2 \times 5 \times 2)$ oe (M1 for $2 \times 5 \times 2$ **or** 20 seen **or** $300 \div (2 \times 5)$ **or** 30 seen A1 cao
	(b)	$c = \frac{30 \times 40}{150}$ =	8	2	M1 for $\frac{30 \times 40}{150}$ **or** 1200 seen A1 cao
27		$3x - 15 = 2x + 24$ $x = 39$ **OR** $2x + 3x - 15 + 2x + 2x + 24 = 360$ $9x + 9 = 360$ $9x = 351$ $x = 39$ **OR** $2x + 2x + 24 = 180$ $4x + 24 = 180$ $4x = 156$ $x = 39$ **OR** $2x + 3x - 15 = 180$ $5x - 15 = 180$ $5x = 195$ $x = 39$	39	3	M1 for forming an appropriate equation eg $3x - 15 = 2x + 24$ **or** $2x + 3x - 15 + 2x + 2x + 24 = 360$ oe **or** $2x + 2x + 24 = 180$ oe **or** $2x + 3x - 15 = 180$ oe **or** $2x + 3x - 15 = 2x + 2x + 24$ M1 (dep) for correct operation(s) to isolate x and non-x terms in an equation to get $ax = b$ A1 cao **OR** M2 for $\frac{351}{9}$ **or** $\frac{195}{5}$ **or** $\frac{156}{4}$ oe A1 cao

PMT

Further copies of this publication are available from
Edexcel Publications, Adamsway, Mansfield, Notts, NG18 4FN

Telephone 01623 467467
Fax 01623 450481
Email publication.orders@edexcel.com

Order Code UG032619 Summer 2012

For more information on Edexcel qualifications, please visit our website
www.edexcel.com

Pearson Education Limited. Registered company number 872828
with its registered office at Edinburgh Gate, Harlow, Essex CM20 2JE

Ofqual
Llywodraeth Cynulliad Cymru
Welsh Assembly Government
Rewarding Learning

Question 20

Both parts of this question were poorly attempted. A translation of the given function was often seen in part (a), but rarely was this a correct one. A correct translation of either, -1 in *y* direction OR -3 in *x* direction obtained 1 mark.

In part (b), it was rare to see a correct reflection of f(*x*) drawn, many students either guessing the coordinates of *B* or using a diagram found in part (a).

Question 21

In part (a) students were awarded two marks for a correct reflection in the *y* axis. A number of students knew this fact, but lost one of the two marks as they failed to take care and ensure that all key points were hit. Other students were able to gain a single mark for reflecting in the *x* axis, again providing all key points were hit. Unfortunately, the most common response was to see a rotation with the graph drawn in the bottom right quadrant.
Part (b) was again a difficult question for the vast majority of students. Typically, some element of substitution, normally of the value 3, into the given quadratic was seen and gained no credit. Very few students understood the effect of the translation on the function and therefore a correct response was rare. Simplification was not required, but some students did attempt this, and got it wrong, and this resulted in them losing a mark.

Question 18

At this stage of the paper many students had no knowledge to help in accessing the marks. If marks were awarded in part (a) it was usually 1 mark, for 2 correct values, rather than both marks. This is because even those who did know to read values off from the graph, then either didn't read the range for solutions, or more commonly, didn't understand how to find the values beyond 360°.
In part (b) it was again quite rare to award the mark for a correct equation as many didn't understand the effect on the function caused by a reflection. Of those who did gain credit, $y = -\sin x$ was the most common response.
More students realised what was needed in part (c), that a translation was required, but to the left or down were more common than the correct direction of right.

Question 21

Part (a) of this question required students to understand the effect of a reflection on a function and then reflect the graph in the correct axis. As is expected by this stage of the paper, this was very challenging for a great number of students. Some clearly did understand a reflection was required but didn't complete it with sufficient accuracy to gain the mark. A free-hand curve was acceptable, but students need to ensure key points are plotted correctly.
Part (b) was more in-depth as it required a thorough understanding of the graph of tan$x$ and its key intercepts. It also required students to understand the effects of a translation on a function. Those who identified a horizontal movement of 270 were able to score one mark, as were those who applied the correct vertical translation to the function. Very few students were able to score both marks.

Question 23

For part (a) of this question, while there were attempts by a majority of candidates, few were correct. There were many more candidates who sketched the graph of $y = f(x - 2)$, that is, translated the graph to the right instead of to the left. Some candidates tried to sketch $y = f(x) + 2$. Those candidates who did identify the correct translation invariably sketched a graph meeting the criteria in the mark scheme and so scored the mark available.
Part (b) also attracted an incorrect response from the majority of candidates who attempted the question. The incorrect response, $y = g(-x)$ was seen more frequently than the correct answer $y = -g(x)$.

Question 21

Transformations of functions is always a topic that candidates find challenging, and although relatively straight forward compared to some recent examples, that proved the case again here. Part (a), dealing with a translation, was typically answered with more success, with a good number gaining the mark. However, part (b), the reflection, was less well answered and it was common to see responses such as a reflection in the x-axis or a rotation of 180° about the origin.

Question 20

Those students aiming to achieve a high grade were usually able to write down the coordinates of the turning point in part (a) of this question. There were many different incorrect pairs of coordinates seen, with perhaps, not surprisingly (–10, 6) being the most common. Some candidates had apparently not read the question carefully and wrote down the coordinates of the graph given for part (b) of the question.
Part (b) was less well done. Those students who appeared to recognise the transformations needed sometimes carried them out with such inaccuracy that it was not possible for examiners to award any credit. Students are advised in questions like this to consider what happens to specific points before trying to sketch the whole graph. In this question examiners wanted to see the image of the maximum point and endpoints of the graph correctly shown as part of the transformed graph. A very common error was for students to reflect the graph in the x-axis instead of the y-axis.

Question 21

In part (a), there were many blank responses, attempts at translations and reflections in the y axis. Those who reflected in the x axis often did so correctly although there were a number that had one incorrect segment.
In part (b), there were various misunderstandings apparent. Some incorrectly identified point P as (90, 1), whilst others added 180 to their y coordinate of point P rather than subtracting 180 and some added both the 180 and the 4 to their y coordinate. Invariably those that obtained one mark usually did so for having (90, b) or (a, 3) rather than for identifying the coordinates of P.



Examiners' Report
Principal Examiner Feedback

Summer 2019

Pearson Edexcel GCSE (9 – 1)
In Mathematics (1MA1)
Higher (Calculator) Paper 3H

Edexcel and BTEC Qualifications

Edexcel and BTEC qualifications are awarded by Pearson, the UK's largest awarding body. We provide a wide range of qualifications including academic, vocational, occupational and specific programmes for employers. For further information visit our qualifications websites at www.edexcel.com or www.btec.co.uk. Alternatively, you can get in touch with us using the details on our contact us page at www.edexcel.com/contactus.

Pearson: helping people progress, everywhere

Pearson aspires to be the world's leading learning company. Our aim is to help everyone progress in their lives through education. We believe in every kind of learning, for all kinds of people, wherever they are in the world. We've been involved in education for over 150 years, and by working across 70 countries, in 100 languages, we have built an international reputation for our commitment to high standards and raising achievement through innovation in education. Find out more about how we can help you and your students at: www.pearson.com/uk

Grade Boundaries

Grade boundaries for all papers can be found on the website at:
https://qualifications.pearson.com/en/support/support-topics/results-certification/grade-boundaries.html

Summer 2019
Publications Code 1MA1_3H_1906_ER
All the material in this publication is copyright
© Pearson Education Ltd 2019

GCSE (9 – 1) Mathematics – 1MA1
Principal Examiner Feedback – Higher Paper 3

Introduction

Most students entered for this examination presented their working in a clear and logical way and worked accurately to demonstrate a good performance overall. Questions where this was not quite so evident included Q6 (surface area) and Q20 (simultaneous equations). Only a small proportion of students presented weak scripts, suggesting that most students who sat this paper were entered appropriately for the higher tier.

The paper gave the opportunity for students of all abilities to demonstrate positive achievement. All questions were accessible to some students but as you would expect there were relatively few students able to work confidently on all questions.
In particular, Q1 (Venn diagram), Q7 (use of a calculator), Q8a (Pythagoras's Theorem), Q11 (speed, distance, time) and Q18a (cubic expansion) were answered well by a large majority of students whereas Q14 (using areas and ratio), Q18b (solution of a quadratic inequality), Q20 (simultaneous equations), Q22 (circle problem) and
Q23 (trigonometry) proved more of a challenge to students.

The time allowed for the examination appears to have been sufficient for most students to complete the paper.

Report on Individual Questions.

Question 1

This question provided a good start to the paper. Nearly all students gained some credit for their answers with most students scoring at least four of the five marks available. Part (a) of this question requiring students to complete the Venn diagram was generally well done though some students did make careless errors when placing the numbers within set A and/or set B. A significant number of students wrote all of the numbers 1
to 9 in the region $(A \cup B)'$.
Part (b) of the question was answered quite well and many students benefited from the mark scheme which allowed a follow through from part (a). It was not unusual for students to gain part marks in part (a) followed by full marks in part (b). Some students reverted to using the sets listed rather than their Venn diagram to answer part (b). A common error was for students to give $\frac{6}{9}$ as their answer to this part presumably because students had confused intersection with union.

Question 2

This question was a good discriminator. About one third of students entered for the examination scored full marks for their responses to this question testing compound interest. Students generally used a multiplier approach though students frequently used an incorrect multiplier, for example 1.15 A very common error was for students to give 212272.71 as their answer, the total value of the savings after 4 years and not the interest earned over the period. This answer was awarded two of the three marks available. A great majority of students got at least one mark for

the interest earned in the first year. Very few students lost the accuracy mark for not using correct money notation, that is for giving an answer to more than 2 decimal places.

Question 3

A majority of students scored full marks on this question. The most common error seen in part (a) was to give $30 < h \leq 40$ as the class in which the median lies. Common errors in drawing the frequency polygon included plotting points at the upper or lower boundary of each interval instead of the midpoint and joining the points with a curve, not straight lines. Points were generally carefully plotted at the correct heights.

Question 4

This question was quite well answered and descriptions of the things wrong with the time series graph were generally well described. There were a variety of possible acceptable answers but students needed to state them clearly and unambiguously. For example, “the axis does not start at 0” would not be worthy of any credit but “the y axis does not start at 0” would score a mark. Similarly, “the scale on the x axis” would not be enough but “it is not clear what the 2, 3, 4 on the x axis means” would get a mark. A number of students stated there should be a line of best fit drawn. This was not an acceptable response.

Question5

A good discriminator, this question attracted many concise and fully correct solutions. Despite there being a number of possible routes that students could take, there were also many incorrect or incomplete solutions. The most common approach was to use the total of the angles in a hexagon together with the relationship between angles BCE and CDE to work out the size of angle AFE. The most commonly seen alternative route was to use the symmetry of the hexagon to form two pentagons and work from there. A minority of students joined the points F and C and found the size of angle BCE. These students did not usually make significant further progress beyond labelling angles BCD and CDE as $2x$ and x respectively. A surprising number of students marked angles BCD and CDE as x and $2x$ respectively. In most cases, however, labelling of the diagram proved to be a help to students and is to be encouraged. About two in every five of students obtained full marks for their solution to this question.

Question 6

This question was also a good discrminator. Unfortunately, a significant proportion of students calculated the volume of the cylinder rather than the surface area and so could not be awarded much credit for their responses. However, there were many fully correct and complete solutions usually comparing the total surface area of the 3 tanks with the total surface area which could be covered with 7 tins of paint but sometimes comparing the number of tins of paint needed to paint the three tanks with the 7 tins of paint available to Jeremy. A good proprtion of students calculated the surface area of only one end of the cylinder or tried to combine the area of one or two ends with a volume or with an incorrect “area” found by calculating 1.6 by 1.8. It was pleasing to see that students often worked with exact expressions in terms of π, thus avoiding the need to round values in intermediate working and minimizing the risk of errors when calculating and writing down decimal values from calculators.

Question 7

This question was done well by the great majority of students who were awarded both marks. Some students gave an answer of 0.32 believing this was correct to 3 significant figures. These students were given full marks provided they had shown a more accurate version of the answer in the working space. The request to give the answer correct to 3 significant figures served as a guide to students and correct answers given to more than 3 significant figures gained full credit. Students are therefore advised to write down their full calculator display before rounding.

Question 8

A large proportion of students were able to score at least one mark for their responses to this question. Responses were usually clearly expressed.
Part (a) was answered well. The most common description of the mistake that Sarah made was to state that the first line should read $BC^2 = AC^2 - AB^2$ or equivalent, for example that she should be subtracting not adding the numbers. A common but unacceptable response was that the mistake was not to show the square root sign over the 100.
Part (b) was also answered well with most students stating that the scale factor is 2.5 and not 1.5 as required and many other students who explained that the length of one side of the enlarged triangle was incorrect together with a statement of what the length should be. The most common unacceptable response referred to C being the wrong centre of enlargement.

Question 9

This question was not well answered in general though there were many clear and concise responses which earned full marks. Many students were able to make a start by stating that 54 (6×9) machine days were needed to make all the boxes. A much smaller proportion of students could make further progress. The most common strategy used by students who successfully solved the problem was to identify that 42 machine days were needed in addition to the first 3 days and then that 42 machine days is equivalent to 7 days with all the machines working. A small number of students who used this approach gave 7 as their final answer instead of the correct 10 days (3 + 7). The most able students were able to identify that 6 machine days were lost in the first 3 days so one extra day in addition to the 9 days would be needed to make all the boxes.

Question 10

Examiners were able to award full marks to about a half of students for their answer to this question involving percentages. Most students showed a good understanding of the problem and calculated that the total interest added to Marie's account was £144. Not all of these students could express this as a percentage interest rate. The most common error was for students to express £144 as a percentage of £8144 instead of £8000. It was noticeable that a large number of students used a multiplier approach, interpreting 0.018 or 1.018 as a 1.8% increase. The most common errors seen were working out 20% of 8000, or using an incorrect reverse percentage process.

Question 11

Questions involving standard form are often well answered and this question was no exception. Students usually expressed their answer to part (a) as an ordinary number (130) with a small minority of students giving their answer in standard form (1.3×10^2). Most students worked in standard form and did not convert the distance and speed to ordinary numbers before dividing one by the other. The most common error seen in the method was for students to multiply the distance by the speed but this was not commonplace. However, there were a significant number of students who identified the correct calculation $(3.9 \times 10^7) \div (1.3 \times 10^5)$ but who expressed it without the brackets. This usually led to the incorrect answer 1.3×10^{12} because students were not careful about the order of operations when they used their calculator to evaluate their answer. These students could usually be awarded one of the two marks available.

Most students were able to gain the mark in part (b) for stating that their answer to part (a) would be increased or equivalent, for example that the signal will take longer to get to Mars.

Question 12

About two thirds of students were able to give an acceptable reason why $64^{\frac{1}{4}}$ is not equal to $\frac{1}{4}$ of 64, usually by explaining that $64^{\frac{1}{4}}$ can be interpreted as the fourth root of 64 or $\sqrt[4]{64}$ or by evaluating the value of $\sqrt[4]{64}$ as 2.828. The reason "$\frac{1}{4}$ of 64 is not the same as 64 to the power $\frac{1}{4}$" was not deemed sufficient to score the mark because it is the same as merely rephrasing the statement in the question.

Question 13

This question was successfully answered by about a half of all students. About two thirds of all students realised the need to multiply the measures of density and volume of both ethanol and propylene and so accessed the first two marks for these processes. Some students changed litres to millilitres before doing this. About a half of all students were able to move on from there to complete the calculation of the density of the antifreeze. The most common error seen by examiners was for students to use division rather than multiplication to work out $188 \div \left(\frac{60}{1.09} + \frac{128}{0.97}\right)$ or equivalent. The answer given, 1.005, was in the range of acceptable values but could not be awarded any credit.

Question 14

A small minority of students scored full marks for their responses to this question. Weaker students often showed little or no working and if they did show working, it was often characterised by assuming that the triangles were right angled and using trigonometry to fit such a situation. More able students often did realise that references to area in the question together with the diagram showing non right angled triangles suggested use of the formula $\frac{1}{2}ab\sin C$. However, some of these students tried to find the length of AE instead of using the ratio $AB : AE$ to express AE as an unknown variable, for example $3x$. Students who used $AB = x$ and $AE = 3x$ scored at least one mark and often went on to write down and solve an equation using the given fact that the sum of the areas of the triangles was equal to the area of the rectangle. Examiners were surprised at the number of students who equated the area of one triangle to the area of the rectangle which led to the incorrect final answer of 18.

Question15

Some students appeared to have little knowledge about the content covered in this question and either did not attempt the question or revealed little understanding through their responses to the question. In general, little working was seen and students may have benefited from writing down the transformations represented by the equations $y = f(-x)$ and $y = f(x) - 3$.
Very few students did this and so some denied themselves the award of a mark for showing an understanding of the types of transformation involved in the question. However, examiners were able to award a good number of students at least one mark for getting an x coordinate as -7 or a y coordinate as -1. Students who gave a final answer of $(-10, -5)$ following on from an intermediate stage of $(-7, -2)$ could not be awarded any marks because they had not discriminated between which coordinates were changed by which transformation. Some students attempted to substitute values for x and y, often 7 and 2 respectively. The best students did show a good understanding of the notation and transformations involved and gave a fully correct answer.

Question 16

This question discriminated well with many students being awarded each of the 0, 1, 2 or 3 marks available. Most students followed the strategy of finding second differences to help them find the term in n^2 and realised that the common differences of 4 meant they should write an expression for the nth term which included the term $2n^2$. Many students went on to give a fully correct expression but a significant minority of students gave $2n^2 - 3n$ as their answer. Students would be wise to check their answers to questions of this type by substitution.

Question 17

Matching the functions to the graphs in this question produced a good spread of marks with about a third of all students scoring each of the marks available. The graph of a trigonometrical function was identified correctly more frequently than the other graphs and the graphs showing one form of proportionality or another were the least well known.

Question 18

Students usually scored well on part (a) of this question requiring the expansion of a product of three linear expressions to give a fully simplified cubic expression. Errors were usually restricted to incorrect terms rather than a flawed strategy although some students omitted terms from their expansion. It was usual for students to earn two or three of the available marks. Less able students lacked a clear strategy and sometimes tried the multiply all three brackets together at once.

Part (b) of the question proved to be more challenging than part (a) and it was relatively rare for examiners to award full marks. Credit awarded to students was often restricted to the mark gained for taking the square root of each side of the inequality or, in the case of students who started by expanding the left hand side, for getting a quadratic equation or inequality with all the terms on one side. Very few students used the expected method of taking the square root of both sides, taking into account both square roots of $\frac{9}{25}$. Students who expanded $(1 - x)^2$ were more likely to gain two or three marks for their responses but only about a third of all students earned one or more marks. The best answers demonstrated a very good understanding of the topic together with the good practice of including a graph sketch with the rest of their working.

Question 19

Part (a) of this question discriminated well between more able students sitting this paper. Some students did not attempt the question and many weaker students restricted their answer to working out the value of D by substituting $u = 26.2$ and $a = 4.3$ This gained no credit. Of those students who did score marks, many of them scored just one mark for writing down at least one of the bounds for u or a. Students who substituted bounds for u and a into the expression for D were split between those who calculated [UB of u]^2 ÷ [2 × LB of a], the correct expression, those who calculated
[UB of u]^2 ÷ [LB of a] and those who calculated [UB of u]^2 ÷ [2 × UB of a].

Part (b) was not answered well and only a small proportion of students gave the correct answer of 80. Even fewer students were able to say why. The most common incorrect approach by far was to add their answer to part (a) to 78.6003 and then divide by 2, accompanied by an explanation of this being the mid-point or the average. Centres may wish to highlight this misconception.

Question20

This question also proved to be a good discriminator between the most able students. Many of the more able students were able to make a good start, realizing the need to make a substitution, usually using $x = \frac{7-4y}{3}$ from the second equation, to eliminate x from the first equation. Fewer students could carry out the substitution and expand $\left(\frac{7-4y}{3}\right)^2$ correctly to score the second method mark. Often the denominator of the fraction was ignored in this process. Students who rearranged $3x + 4y = 7$ often stopped at $4y = 7 – 3x$, then substituted this into $x^2 – 4y^2 = 9$ to give the incorrect equation
$x^2 – (7 – 3x)(7 – 3x) = 9$. A further error seen quite commonly occurred when students multiplied through their equation by 9 but forgot to multiply all the terms by 9.
Only the most able students could obtain a correct quadratic equation in the form $ay^2 + by + c = 0$ (or $ax^2 + bx + c = 0$ in the cases where y had been eliminated). Some students who did not get a correct quadratic equation were able to score a further mark which was given independently for solving a three term quadratic equation. Full marks were scored in this question by only a very small proportion of all students who were entered for the examination. Some students who arrived at the correct 4 values were not awarded the final accuracy mark as the values were not clearly paired.

Question 21

Though a significant number of students did not attempt this question, a good proportion of those students who did attempt it scored full marks for a complete and correct solution. The most common errors made by those students who followed a correct method, that of finding the total number of onions weighing less than 60g or more than 120g, usually involved obtaining an incorrect frequency for the number of onions weighing between 120g and 135g or for the number of onions weighing between 135g and 180g, or both. This usually arose because of using an incorrect class interval . Students who used the strategy of finding that there were 420 onions weighing between 60g and 120g were generally more successful. Some students opted to work with percentages, either giving their final answer as a percentage, or rounding a recurring decimal to 1decimal place and hence introducing a rounding error. In these cases the final accuracy mark was usually lost. There were a significant number of students who used the heights of the bars to represent frequencies. This approach could not be awarded any credit.

Question 22

Fully correct answers to this question were seen only rarely. It was found to be the most challenging question on the paper. Having said that, a significant proportion of students were able to score at least one mark for a successful start by identifying that angle OAB is a right angle or for a correct process to find the radius of the circle. Few students could see how to use the coordinates of P in order to derive an equation by either using the equation of the circle or by using Pythagoras's Theorem. The evidence from students' scripts showed that more students took the former approach, quoting $x^2 + y^2 = r^2$ and then substituting $x = 3p$, $y = p$, $r = 8$ to get an equation in p. Unfortunately, the lack of of use of correct notation, that is a pair of brackets, meant that many students wrote $3p^2 + p^2 = 8^2$ instead of $(3p)^2 + p^2 = 8^2$. These students usually went on to simplify their equation to $4p^2 = 8^2$.

Question 23

This question was accessible to and discriminated well between the most able students sitting this paper. Students who had a good understanding of bearings together with applications of the sine rule and cosine rule were able to produce an accurate and concise solution to the problem. Of those students who gained partial credit for their attempts, many were only able to score either one mark for a correct process to find the size of angle ABC or two marks for getting as far as finding the length of AC. Some students who got as far as finding the size of angle BAC successfully gave this as their final answer. Finding the bearing of A from C instead of the bearing from C from A was also seen quite frequently.

Summary

Based on their performance on this paper, students should:

- check working for careless errors and to see that the answer given was specifically required by the question.
- practise problems involving the surface areas of solids.
- practise expanding brackets and collecting terms especially with quadratic functions involving fractions.
- ensure a good understanding of multipliers in problems concerning percentages
- practise solving quadratic inequalities.

Pearson Education Limited. Registered company number 872828
with its registered office at 80 Strand, London, WC2R 0RL, United Kingdom